

THE 1988* BREVARD COUNTY COMPREHENSIVE PLAN

TABLE OF CONTENTS

Preface

Adopting Ordinance

Part I. Conservation Element

Part II. Surface Water Management Element

Part III. Recreation and Open Space Element

Part IV. Historic Preservation Element

Part V. Housing Element

Part VI. Potable Water Element

Part VII. Sanitary Sewer Element

Part VIII. Solid Waste and Hazardous Materials Element

Part IX. Transportation Element

Part X. Coastal Management Element

Part XI. Future Land Use Element

Part XII. Intergovernmental Coordination Element

Part XIII. Capital Improvements ~~and Programs~~ Element

Part XIV. Public School Facilities Element

Part XV. Property Rights Element

Part XVI. ~~Glossary~~ [Brevard Barrier Island Element](#)

[Part XVII. Glossary](#)

Updated ~~February 2022~~ [June 2025](#)

CHAPTER PART I

CONSERVATION ELEMENT

TABLE OF CONTENTS

Air Quality	1
Energy	2
Surface Water	4
Flood Plain Areas	9
Wetlands	14
Minerals and Soils	21
Soil Erosion	24
Vegetation	26
Wildlife	27
Aquifer Protection	31
Energy Conservation	33
Potable Water Conservation	34
Appendix	36

GOALS, OBJECTIVES, AND POLICIES

GOAL CON

Protect, conserve, enhance, maintain, and appropriately use natural resources and environmental systems, maintaining their quality and contribution to the quality of life and economic well being of Brevard County.

Air Quality

Objective CON 1

Air quality within Brevard County shall meet or exceed the minimum air quality as adopted by the U.S. Environmental Protection Agency and the Florida Department of Environmental Protection (FDEP).

Policy CON 1.1

Brevard County shall cooperate with ~~the Florida Department of Environmental Protection (FDEP)~~ FDEP in monitoring and protecting ambient air quality within the county.

Policy CON 1.2

Developments of Regional Impact, major transportation projects, industrial uses, and power generation projects shall be evaluated for their impacts on air quality. Buffer areas adjacent to industrial uses, power generation projects, or other stationary air pollution sources shall be utilized as required to maintain air quality within accepted standards.

Policy CON 1.3

The County shall reduce the potential for mobile source emissions by the following means:

Criteria:

- A. Promote appropriate Planned Unit Development (PUD) and multi-use developments or use centers.
- ~~B. Vegetative strips along major transportation corridors to buffer residential land uses.~~
- ~~C.~~ B. Promote alternative transportation methods such as car pooling, van pooling, and mass transit.
- ~~D.~~ C. Promote bicycle and pedestrian traffic by constructing and maintaining additional bike and pedestrian paths.
- ~~E. Roadways with adopted Levels of Service should be evaluated in order to~~

CONSERVATION ELEMENT

~~maintain acceptable air quality after the development is completed.~~

Policy CON 1.4

Brevard County shall continue to enforce the noise regulations in the land development code.

Policy CON 1.5

Brevard County shall continue to enforce regulations within the land development code that address the location of facilities that potentially generate noxious emissions.

Policy CON 1.6

~~Alternate energy resources that do not degrade air quality should be given preference over resources which do degrade air quality.~~ In addition, Brevard County ordinances or programs concerning clean-up and disposal of hazardous materials, mass burn facilities, and solid waste disposal shall not result in the degradation of air quality or endangerment of human health.

Policy CON 1.7

~~Conversion of power plant to coal should not cause degradation of air quality below minimum standards. Best available technology should be utilized for all new power plants. Brevard County supports the use of energy resources that do not degrade air quality over those that do.~~

Policy CON 1.8

~~Land use should also be compatible with the maintenance of good air quality. Development should be designed in such a way as to minimize traffic congestion. Urban land uses should be buffered from stationary and linear pollution sources (roadways). Vegetation should be utilized whenever possible to buffer air pollution sources and maintain air quality. Multi-use developments, such as Planned Unit Development, or other innovative land uses should be utilized to reduce the need to travel. Facilities that house the elderly, very young or sick should be located away from emission sources or areas of poor air quality. Brevard County shall continue to coordinate air quality protection through policies in the Future Land Use Element and the Land Development Regulations.~~

Energy

Objective CON 2

Reduce per capita energy consumption and greenhouse gas emissions within Brevard County through land use and transportation planning.

Policy CON 2.1

Brevard County shall address various energy saving methods including:

CONSERVATION ELEMENT

Criteria:

- A. Encouraging appropriate ~~Planned Unit Development PUD~~ and multi-use developments to utilize Leadership in Energy and Environmental Design (LEED) principles;
- B. ~~Regulating subdivisions to address bicycle and pedestrian pathways; and~~
Promoting connectivity between different land uses among alternative transportation modes, such as bicycle, pedestrian, and public transit; or
- C. Regulating land clearing ~~and~~, landscaping, and impervious surfaces ~~regulations~~ to augment passive cooling by trees and mitigate Heat Island Effect.

Policy CON 2.2

~~Brevard County shall continue to implement the Florida Building Code, Energy Conservation for new construction and substantially rehabilitated structures. Brevard County shall site new public facilities serving large numbers of people close to or within population centers to minimize automobile use.~~

Policy CON 2.3

Brevard County should continue to implement waste reduction, reuse, recycling, and conversion of waste to energy as part of its waste management strategies.

Policy CON 2.4

Brevard County shall consider energy conservation and greenhouse gas emissions in the development and implementation of County ordinances.

Policy CON 2.5

Brevard County should coordinate with the Space Coast Transportation Planning Organization to pursue and publicly promote transportation options that would decrease per capita energy consumption and greenhouse gas emissions.

Policy CON 2.6

Brevard County should coordinate with the East Central Florida Regional Planning Council (ECFRPC), the Economic Development Commission of Florida's Space Coast, and the State to encourage development and use of energy efficient and renewable technologies to enhance economic development while conserving energy and reducing greenhouse gas emissions.

Surface Water

Objective CON 3

Improve the quality of surface waters within Brevard County and protect and enhance the natural functions of these waters.

Policy CON 3.1

~~Brevard County shall cooperate with the Florida Department of Environmental Protection (FDEP) to require small package treatment plants adjacent to surface waters to comply with existing federal, state, or regional rules and regulations, and to ensure that the necessary renovations to achieve compliance are completed in a timely manner. Requests to dredge previously dredged areas that have regained natural characteristics due to lack of use, lack of upkeep, or other factors or requests to change the design specification of previously dredged areas shall not be considered as maintenance dredging but shall be considered new dredging and regulated as such.~~

Policy CON 3.2

Brevard County shall continue to prevent negative impacts of development in and adjacent to Class I waters by implementing and revising, as necessary, the Surface Water Protection Ordinance including the following minimum criteria:

Criteria:

- A. Maintain a two hundred (200) foot surface water protection buffer from the ordinary high water line or mean high water line as determined or approved by the FDEP Bureau of Survey and Mapping. In lieu of an approved ordinary high water line, mean high water line, or safe upland line, an alternative buffer establishment line that approximates the land-water interface may be approved administratively as defined in ordinance. The use of the alternative buffer establishment line shall only be applied to shorelines with a clearly defined land-water interface.
- B. Acceptable uses within the surface water protection buffer are passive recreation, hunting, fish and wildlife management, open space and nature trails, and similar uses.
- C. Require discharges of any substances into Class I waters to meet or exceed applicable receiving water quality standards.
- D. Prohibit dredging and filling, except for permitted utility crossings, publicly owned recreational projects which do not degrade water quality, and necessary maintenance of existing projects.
- E. Regulate development and mining operations within the hydrologic basin of Class I waters. Prohibit mining operations within the 10-year floodplain of

CONSERVATION ELEMENT

Class I waters.

- F. Prohibit alteration within the surface water protection buffer unless it is in the public interest and does not adversely impact water quality and natural habitat.

Policy CON 3.3

Brevard County shall continue to make efforts to prevent negative impacts of development in and adjacent to the Indian River Lagoon and its tributaries designated as Class II waters, Aquatic Preserves and Outstanding Florida Waters by implementing and revising as necessary, the Surface Water Protection Ordinance, including the following minimum criteria:

Criteria:

- A. Maintain a fifty (50) foot surface water protection buffer from the ordinary high water line, mean high water line, or safe upland line as determined or approved by the FDEP Bureau of Survey and Mapping. In lieu of an approved ordinary high water line, mean high water line, or safe upland line, an alternative buffer establishment line that approximates the land-water interface may be approved administratively as defined in ordinance. The use of the alternative buffer establishment line shall only be applied to shorelines with a clearly defined land-water interface.
- B. Except as allowable under Policies CON 3.3.C and CON 3.3.D, primary structures shall not be permitted within the surface water protection buffer. The County shall establish allowable uses within the surface water protection buffer. Stormwater management for all alterations associated with allowable uses shall be required to protect water quality of the receiving water body. Provisions for the alteration and/or removal of non-native invasive plants, mitigation projects, and the planting of native species shall be established by the County.
- C. For residential lots platted or established by deed on the official record books of Brevard County prior to September 8, 1988, ~~an alternative to the fifty (50) foot surface water protection buffer described above shall be available for those lots which have insufficient lot depth to construct a primary structure. In the case where there is insufficient lot depth to construct a primary structure, this alternative shall allow the surface water protection buffer to be reduced to a primary structure may be located within the surface water protection buffer at least twenty five (25) feet from the water line as outlined in Criterion A~~ if additional measures are taken to preserve water quality and natural habitat within the adjacent surface water body. These additional measures shall, at a minimum, prevent the first inch of stormwater runoff from entering surface waters; and may include, but not

CONSERVATION ELEMENT

be limited to, a stormwater retention system or native shoreline revegetation. Where applicable, stormwater management measures shall be consistent with ~~DEP 62-25, as amended~~ and FS F.S. 373, as amended.

- D. For residential lots located along areas of the Indian River Lagoon and its tributaries added to the State's designation of Class II Waters as of February 17, 2016, and platted or established by deed on the official record books of Brevard County prior to that date, ~~an alternative to the fifty (50) foot surface water protection buffer described above shall be available for those lots which have insufficient lot depth to construct a primary structure. In the case where there is insufficient lot depth to construct a primary structure, this alternative shall allow the surface water protection buffer to be reduced to a primary structure may be located within the surface water protection buffer at least twenty five (25) feet from the water line as outlined in Criterion A~~ if additional measures are taken to preserve water quality and natural habitat within the adjacent surface water body. These additional measures shall, at a minimum, prevent the first inch of stormwater runoff from entering surface waters; and may include, but not be limited to, a stormwater retention system or native shoreline revegetation. Avoidance and minimization of buffer impacts shall be required. Where applicable, stormwater management measures shall be consistent with ~~DEP 62-25, as amended~~ and FS F.S. 373, as amended. Lots located along areas of Aquatic Preserves and Outstanding Florida Waters shall maintain a fifty (50) foot surface water protection buffer in accordance with Policy CON 3.3.A, B, and C.
- E. Within the surface water protection buffer the maximum amount of impervious surface is thirty (30) percent, inclusive of primary structures as outlined in Criteria C and D.
- F. Prohibit shoreline alteration other than that allowed by ordinance, unless the alteration is in the public interest and does not adversely impact water quality, natural habitat, and adjacent shoreline uses.
- G. Prohibit channelization, dredging and filling, and impoundment of natural waters of the State unless the activity is clearly in the public interest and does not adversely impact water quality, natural habitat, and adjacent shoreline uses. Dredging shall not be permitted in or connected to Class II Waters, Outstanding Florida Waters (OFWs), Aquatic Preserves, areas that contain ten percent (10%) seagrass or more, and conditionally approved shellfish harvesting waters unless the activity is a federal navigation project, in the public interest, such as approved maintenance dredging of existing public or private navigational channels, or where dredging may improve

CONSERVATION ELEMENT

water quality by removing accumulated silt or improving circulation, or for maintenance of existing structures and utility structures and utility crossings, or for shoreline ~~hardening~~ alteration as allowed by this element.

- H. Prohibit discharges of any substances below ambient water quality standards.

Policy CON 3.4

Brevard County shall continue to prevent negative impacts of development in and adjacent to Class III waters (except Outstanding Florida Waters and Aquatic Preserves) along the St. Johns River and Indian River Lagoon and its tributaries by implementing and revising as necessary, the Surface Water Protection Ordinance including the following minimum criteria:

Criteria:

- A. A twenty five (25) foot surface water protection buffer from the ordinary high water line, mean high water line, or the safe upland line as determined or approved by the FDEP Bureau of Survey and Mapping shall be established. In lieu of an approved ordinary high water line, mean high water line, or safe upland line, an alternative buffer establishment line that approximates the land-water interface may be approved ~~by the director~~ administratively as defined in ordinance. The use of the alternative buffer establishment line shall only be applied to shorelines with a clearly defined land-water interface.
- B. Except as allowable under Policies CON 3.4.C and CON 3.4.D, primary structures shall not be permitted within the surface water protection buffer. The County shall establish allowable uses within the surface water protection buffer. Stormwater management for all alterations associated with allowable uses shall be required to protect water quality of the receiving water body. Provisions for the alteration and/or removal of non-native invasive plants, mitigation projects, and the planting of native species shall be established by the County.
- C. For residential lots located along Class III waters and platted or established by deed on the official record books of Brevard County prior to September 8, 1988, ~~an alternative to the twenty five (25) foot surface water protection buffer described above along Class III waters shall be available for those lots which have insufficient lot depth to construct a primary structure. In the case where there is insufficient lot depth to construct a primary structure, this alternative shall allow the surface water protection buffer to be reduced to a primary structure may be located within the surface water protection buffer at least fifteen (15) feet from the water line as outlined in Criterion A if additional measures are taken to preserve water quality and natural habitat~~

CONSERVATION ELEMENT

within the adjacent surface water body. These additional measures shall, at a minimum, prevent the first inch of stormwater runoff from entering surface waters; and may include, but not be limited to, a stormwater retention system or native shoreline revegetation. Where applicable, stormwater management measures shall be consistent with ~~DEP 62-25, as amended and~~ FS F.S. 373, as amended.

- D. Prohibit shoreline alteration other than that allowed by ordinance, unless it is in the public interest or prevents or repairs erosion; and does not adversely impact water quality, natural habitat and adjacent shoreline uses.
- E. Except for properties on existing residential manmade canals, the maximum amount of impervious surface within the surface water protection buffer is thirty (30) percent.
- F. Prohibit discharges of any substances below ambient water quality standards.

Policy CON 3.5

Brevard County shall continue its implementation of a mosquito impoundment management plan, which should address the following criteria, at a minimum:

Criteria:

- A. The primary use of mosquito control impoundments shall be to protect human health through the control of mosquito populations. Secondary uses may include stormwater management, habitat improvement, wildlife management, and other uses as appropriate. Brevard County shall encourage multiple uses of mosquito control impoundments.
- B. Acquisition of impoundments for maintenance and operation.
- C. Appropriate water management system shall be utilized.
- D. Impoundments shall be restored or reconnected with the Indian River Lagoon when a public benefit can be demonstrated.
- E. Proposed alteration of an impoundment should be reviewed by Mosquito Control. Brevard County should compensate property owners for mosquito impoundments when this use precludes all use by the owner or when no alteration would be acceptable to Mosquito Control.
- F. Non-permitted alteration of an impoundment shall be enforced by Brevard County.

CONSERVATION ELEMENT

- G. All mosquito impoundments should be evaluated and those found to be breached or non-functional should be repaired by the appropriate Mosquito Control District.
- H. Those fully functioning impoundments determined to be needed by the Mosquito Control District, should be placed under a rotational impoundment management plan as approved by the Florida Coordinating Council on Mosquito Control.
- I. Any other "source reduction" mosquito control activities that also reduce the natural habitat required by freshwater or marine organisms should be prohibited.
- J. Mosquito control impoundments shall be managed in a manner that avoids adverse impacts to the water quality of receiving water bodies.
- K. Brevard County should develop a program to acquire right-of-way or easements for drainage systems and mosquito control systems which the County maintains, if not already acquired.

Flood Plain Areas

Objective CON 4

Reduce loss of flood storage capacity and reduce risk to life and property by continuing to apply regulations which minimize the impact of development within flood hazard areas.

Policy CON 4.1

Brevard County shall continue to protect the riverine floodplain floodplains in order to protect infrastructure and human life, conserve flood storage capacities, and to improve, where feasible, the quality of water within the watershed. ~~The preferred land use, density and fill footprint of the riverine floodplain, where developed, should function as is~~ in the predevelopment natural state, and Brevard County supports the use of fee simple acquisition, less than fee acquisition, transfer of development rights, appropriate development standards, and other innovative measures to preserve and restore the predevelopment riverine floodplain. At a minimum, the following criteria shall be the basis for the protection of the riverine floodplain:

Criteria:

- A. Within the 100-year riverine floodplain (that is the area that is below the 100-year flood elevation but above the 25-year flood elevation):
 - 1. ~~Residential density shall be limited to no more than two dwelling units per acre.~~
 - 2. ~~Commercial, institutional, and industrial land uses shall be limited to~~

CONSERVATION ELEMENT

~~a filled footprint of no more than 15,000 square feet per acre, except for redevelopment as specified in Policy 4.3.~~

- ~~3. 1.~~ Development shall not adversely impact the drainage of adjoining properties. There shall be no net loss of flood storage capacity of the 100-year riverine floodplain, except undeveloped parcels created prior to ~~the effective date of this policy~~ February 17, 2011 may fill up to 1/3 acre filled footprint for development without providing compensatory storage.
- ~~4. 2.~~ The following uses are not compatible with the resource requirements of the 100-year riverine floodplain and shall not be permitted. These include, but are not limited to:
 - a. Placing, depositing or dumping of solid waste except for treated municipal solid sludge.
 - b. Processing and storing of threshold amounts of hazardous materials.
 - c. Disposal of hazardous materials.

B. Within the 25-year riverine floodplain (that is the area that is at or below the 25-year flood elevation but above the 10-year flood elevation):

- ~~1. Residential density shall be limited to not more than one dwelling unit per two and one-half acres.~~
- ~~2. Commercial land uses shall be limited to a filled footprint of no more than 3,000 square feet per acre and commercial uses shall be no greater than one acre, except for redevelopment as specified in Policy 4.3.~~
- ~~3. 1.~~ Industrial land uses shall be prohibited, unless the activity is in the best public interest, or except for mining where it does not increase the filled footprint within the 25-year floodplain.
- ~~4. 2.~~ Development shall not adversely impact the drainage of adjoining properties. There shall be no net loss of flood storage capacity of the 25-year riverine floodplain.

C. Within the 10-year riverine floodplain (that is the area that is at or below the 10-year flood elevation but above the mean annual flood elevation):

- 1. The 10-year riverine floodplain should be maintained in its natural state unless a project has a special reason or need to be located there. These special reasons and needs are further defined in the land development regulations. These needs may include but are not limited to agriculture and passive recreation.
- ~~2. Residential density shall be limited to not more than one dwelling unit per ten acres; and~~
- ~~3. 2. Commercial, institutional, and Industrial land uses shall be~~

CONSERVATION ELEMENT

prohibited unless they are in the public interest and the location of the use is integral to its operation.

- ~~4. 3.~~ Development shall not adversely impact the drainage of adjoining properties. There shall be no net loss of flood storage capacity of the 10-year riverine floodplain.

- D. Within the mean annual riverine floodplain (that is the area that is at or below the annual flood elevation) residential, commercial, institutional, and industrial land uses shall be prohibited unless the project has a special reason or need to locate within the annual floodplain and it is in the best public interest. The annual riverine floodplains within Brevard County should be left in their natural state, and re-established where feasible.
- E. The best available data shall be utilized to determine appropriate floodplain elevations.

Policy CON 4.2

~~The following criteria~~ Performance-based standards, including the following, shall apply to all riverine floodplains:

Criteria:

- A. There shall be no net change in the rate and volume of floodwater discharged from the pre-development 100-year, 25-year, 10-year, or mean annual riverine floodplain.
- B. Practices shall be encouraged in development of property within the riverine floodplain in order to minimize total imperviousness and runoff within the floodplain and preserve the flood storage capacity in order to minimize cost to life and property. Practices may include clustering of developed area, provisions for open space, low impact design features, and flood proofing.
- C. The County shall provide incentives for transfer of densities and filled footprints within the riverine floodplain to reduce risk.
- D. Brevard County will coordinate with the [St. Johns River Water Management District \(SJRWMD\)](#) or other appropriate agencies in determining the appropriate first floor building elevation within the ~~25- to 100-year~~ floodplains and shall ensure that habitable structures are constructed above base flood elevation.

Policy CON 4.3

To facilitate redevelopment of commercial and industrial land uses, ~~the filled footprint restrictions may be modified if compensatory storage is provided. Noncontiguous~~ noncontiguous compensatory storage, hydrologically connected to the impacted

CONSERVATION ELEMENT

floodplain, may be considered. ~~Redevelopment means the renovation of a previously developed obsolete commercial or industrial parcel of land or building site which suffers from structural vacancy due to the expiration of its former use and requires intervention to achieve a subsequent useful function and come into compliance with all other current environmental and land development regulations.~~

Policy CON 4.4

New dikes, levees or other such structures should not be permitted below the 100-year riverine flood elevation except for temporary earthen structures that have a maximum height of less than the 10-year flood elevation and which will not restrict the flow of the 100-year storm floodwaters. The only potential exceptions to this provision are such structures which are shown to have over-riding public benefit. Replacement or repair of dikes, levees and other such structures are permitted as long as such replacement or repair does not change the status of the floodplain and will maintain the existing ability to utilize the property. Non-structural methods of floodplain management are given priority over structural methods.

Policy CON 4.5

Brevard County shall continue to protect the estuarine floodplains by implementing the following minimum criteria:

Criteria:

- A. Development within the one-hundred year estuarine floodplain shall not adversely impact the drainage of adjacent properties or the quality of the receiving surface water body.
- B. The following specific uses are not compatible with the resource requirements of the one-hundred year estuarine floodplain and shall not be permitted. These include, but are not limited to:
 - 1. Placing, depositing, or dumping of solid wastes.
 - 2. Processing and storing of threshold amounts of hazardous materials.
 - 3. Disposal of hazardous materials.
- G. ~~The annual estuarine floodplains within Brevard County should be left in their natural state, and re-established where feasible.~~

Policy CON 4.6

Brevard County shall continue to ensure that alterations of isolated one-hundred year floodplains do not adversely impact the drainage of adjacent properties or public drainage facilities.

Policy CON 4.7

Brevard County shall continue to protect the coastal floodplain floodplain of the Atlantic Ocean through the implementation of the following minimum criteria:

Criteria:

CONSERVATION ELEMENT

- ~~A. — Prohibit development within the annual coastal floodplain.~~
- B. A. Limit development water-ward of the Brevard County Coastal Construction Setback Line to those structures necessary to protect the natural dune system and to provide beach access.
- ~~C. B.~~ Brevard County shall continue to maintain construction standards for all development within the one-hundred year storm surge zone as established by the Florida Department of Environmental Protection, the ~~U.S. Southern Building Code~~ Florida Building Code, as amended, or other applicable regulations.

Policy CON 4.8

Brevard County shall identify structural controls within the floodplain which degrade natural systems and make recommendations for alternatives to re-establish the natural floodplain, where feasible.

Policy CON 4.9

Brevard County shall continue to participate in the National Flood Insurance Program (NFIP) administered by the Federal Emergency Management Agency (FEMA). Amendments to the County's flood ordinance shall be adopted as necessitated by changes in FEMA regulations.

Policy CON 4.10

Public facilities should not be located within wetland areas or the 100-year riverine or estuarine floodplain unless the following apply:

Criteria:

- A. The facilities are water-dependent, such as mosquito control facilities; or
- B. The facilities are water-related, such as boat ramps, docks or surface water management facilities; or
- C. The facilities are not adversely affected by periodic flooding or standing water, such as highway bridges and some recreational facilities; or
- D. The building structures are flood-proofed and located above the 100-year flood elevation, or removed from the floodplain by appropriately constructed dikes or levees; or
- E. The facilities are found to be in the public interest and there is no feasible alternative.

Wetlands

Objective CON 5

Preserve, protect, restore, and replace wetlands to achieve no net loss of functional wetlands in Brevard County ~~after September, 1990~~. The County shall ensure the protection of wetlands and wetland functional values by prioritizing protective activities with avoidance of impacts as the first priority, minimization of impacts as the second priority, and mitigation for impacts as the third priority.

Policy CON 5.1

Brevard County shall utilize the same methodology, soil types, hydrological requirements and vegetation types as the FDEP and the SJRWMD in delineating wetlands.

Policy CON 5.2

Brevard County shall ~~adopt~~ maintain regulations which promote no net loss of functional wetlands. At a minimum, the following criteria shall be included in the land development regulations:

Criteria:

- A. The basis for no net loss shall be established in ordinance.
- B. Wetlands shall be considered functional unless the applicant demonstrates that the water regime has been permanently altered, either artificially or naturally, in a manner to preclude the area from maintaining surface water or hydroperiodicity necessary to sustain wetland functions.
- C. If an activity is undertaken which degrades or destroys a functional wetland, the person performing such an activity shall be responsible for repairing and maintaining the wetland. If it is not feasible ~~or desirable~~ for the responsible person to perform the repair and maintenance of the wetland, then the responsible person shall mitigate for the wetland loss. Mitigation can include, but not be limited to: wetland restoration, wetland replacement, wetland enhancement, monetary compensation or wetland preservation.
- D. Wetland activity conducted by a public agency may not be utilized for wetland mitigation credit by private persons unless approved by Brevard County.
- E. The following land use and density restrictions within wetlands are established as a maximum density or most intense land use that may be considered only if the other criteria established in Conservation Element Policy CON 5.2 are met:

1. Residential land uses within wetlands, that are a part of a formal subdivision or site plan, on properties containing wetlands shall be limited to the following:
 - a. Residential land uses within wetlands shall be limited to not more than one (1) dwelling unit per five (5) acres unless strict application of this policy renders a legally established parcel as of September 9, 1988, which is less than five (5) acres, as unbuildable. The preceding limitation of one dwelling unit per five (5) acres within wetlands may be applied as a maximum percentage limiting wetland impacts to not more than 1.8% of the total non-commercial and non-industrial acreage on a cumulative basis as set forth in Policy CON 5.2.E (7), for subdivisions and multi-family parcels greater than five acres in area, ~~New Town Overlays~~ development in the West Viera Area, PUDs, and if applicable, mixed-use land development activities as specified in Policy CON 5.2.E (6).
 - b. For development activities on property greater than five (5) acres, density may be transferred to an upland portion of the site if consistent with all county land development regulations and compatible with adjacent uses.
 - c. Except as allowable in Policy CON 5.2.E(1)a, subdivided lots and multi-family parcels shall contain sufficient uplands for the intended use and for any buffering necessary to maintain the function of the wetland(s), and shall be compatible with adjacent uses.
2. Residential land uses within wetlands and created by metes and bounds, which are not part of a formal subdivision, on properties containing wetlands shall be limited to the following:
 - a. Residential land uses within wetlands shall be limited to not more than one (1) dwelling unit per five (5) acres unless strict application of this policy would render a legally established parcel as of September 9, 1988, which is less than five (5) acres, as unbuildable. The preceding limitation of one dwelling unit per five (5) acres within wetlands may be applied as a maximum percentage limiting wetland impacts as described in Policy CON 5.2.E (1)a above. Application of the one-unit-per-five-acres limitation shall limit impacts to wetlands for single family residential development on a cumulative basis, to not more than 1.8% of the total property as defined in Policy CON 5.2.E (7).
 - b. Except as allowable in Policy CON 5.2.E (2)a, properties shall contain sufficient uplands for the intended use and for any buffering necessary to maintain the function of the wetland(s), and shall be compatible with adjacent uses.

CONSERVATION ELEMENT

- c. In addition to impacts allowable in Policy CON 5.2.E (2)a, on properties where sufficient uplands for the intended use and for any buffering necessary to maintain the function of the wetland(s) exist except for access, wetland impacts may be permitted for single access to the uplands.
- 3. Commercial and industrial land development activities shall be prohibited in wetlands contained in properties designated on the Future Land Use Map as commercial or industrial, and in surrounding upland buffers for such wetlands, except as provided below for I-95 interchanges, mitigation qualified roadways, abutting properties, and access to uplands. In no instance shall a proposed land development activity result in increased flooding on adjacent properties. Where the State does not require a buffer, wetland buffers specifications shall be established in land development regulations and be based on peer-reviewed publications to include, but not be limited to, Buffer Zones for Water, Wetlands, and Wildlife in the East Central Florida Region, (1990, Brown, M.T., Schaefer, and K. Brandt, published by the Center for Wetlands, University of Florida). Where impacts are permitted, the applicant is encouraged to propose innovative wetland preservation alternatives.
 - a. Impacts to wetlands are permissible for commercial or industrial land development activities on a property that is designated as commercial or industrial on the Future Land Use map, and is located within one-half mile of the intersection of the off-ramp of the I-95 interchange with the connecting roadway. The one-half mile radius shall extend from the end of the limited access boundary of I-95. This shall not include those interchanges where I-95 intersects a limited access highway as defined by Florida Statute. Where the State does not require mitigation for any wetland impact, mitigation shall be provided to meet the County's no net loss policy as defined in Objective CON 5.
 - b. In mitigation qualified roadways, commercial or industrial land development activities may be permitted in wetlands contained in properties designated for commercial or industrial land uses on the Future Land Use Map. Mitigation qualified roadways are depicted and identified in a table on Map 8 5. An amendment to the Comprehensive Plan shall be required to add a mitigation qualified roadway to Map 8 5 and the associated table. Impacts to high functioning and landscape level wetlands shall be prohibited unless the proposed impacts are found to be in the public interest, or overriding public benefit. Where the State does not require mitigation for any

CONSERVATION ELEMENT

- wetland impact, mitigation shall be provided to meet the County's no net loss policy as defined in Objective CON 5.
- c. Commercial or industrial land development activities may be permitted in wetlands contained in properties designated for commercial or industrial land uses on the Future Land Use Map prior to February 23, 1996, if the property abuts land(s) developed as commercial or industrial as of December 31, 2010, and has sufficient infrastructure available to serve the commercial or industrial use. This shall not apply to properties that are addressed under Policies CON 5.2.E.3.a, b, and d. Impacts to high functioning and landscape level wetlands shall be prohibited unless the proposed impacts are found to be in the public interest, or overriding public benefit. Where the State does not require mitigation for any wetland impact, mitigation shall be provided to meet the County's no net loss policy as defined in Objective CON 5.
 - d. Impacts to wetlands for commercial or industrial land development activities limited solely to providing access to uplands, and for no other purpose than providing access as required by Brevard County land development regulations may be permitted in wetlands contained in properties designated on the Future Land Use Map as commercial or industrial of February 23, 1996, only if all of the following criteria are met:
 - (i) Sufficient uplands exist for the intended use except for access to uplands.
 - (ii) The property was not subdivided from a larger property after December 31, 2010. This shall not preclude a single shared access through wetlands for properties subdivided after December 31, 2010.
 - (iii) Where the State does not require mitigation for any wetland impact, mitigation shall be provided to meet the County's no net loss policy as defined in Objective CON 5.
4. Institutional and Residential Professional development activities within wetlands shall be limited to the following:
- a. Institutional or Residential Professional land development on properties which contain wetlands and which are designated on the Future Land Use Map as Neighborhood Commercial or Community Commercial shall be considered commercial as set forth in Policy CON 5.2.E.3. The property shall have sufficient infrastructure available to serve the use.
 - b. Institutional or Residential Professional land development on properties which contain wetlands and which are designated on the Future Land Use Map as residential shall be limited to

CONSERVATION ELEMENT

properties of at least 5 acres unless strict application of this policy renders a legally established parcel as of September 9, 1988, which is less than 5 acres, as unbuildable.

5. In the event that the denial of commercial or industrial development activities in wetlands results in an inordinate burden under the Bert Harris Property Rights Act or a taking under state or federal law, an affected property owner may appeal such denial to the Board of County Commissioners in the manner provided in Section 62-507(b)(2), Code of Ordinances of Brevard County, Florida.
6. ~~Beginning on January 1, 2010; mixed~~ Mixed-use land development activities may be permitted in wetlands only if all of the following are met:
 - a. The land development activities that impact wetlands must be part of a mixed use development that includes a minimum of three of the following land uses: residential, commercial (retail services and/or office), recreation/open space and institutional uses. Industrial land uses shall be prohibited in mixed use land development activities within wetlands. For purposes of this policy mixed use land development activities shall be consistent with the following criteria:
 - (i) The mixed use land development activity includes a variety of densities, intensities and types designed to promote walking between uses and utilizes a variety of transportation modes such as bicycles, transit and automobiles; and
 - (ii) The residential component of the land development activity is an integrated part of the project and comprises not less than 30% of the gross square footage of land uses within the development as shown on a site plan or a Sketch Plan complying with the standards set forth in ~~Chapter 11;~~ Future Land Use Element Objective FLU 9.
 - (iii) The development is in conformance with an integrated site plan or commercial subdivision which includes both vertical and horizontal mix of uses within a defined area.
 - b. Impacts to wetlands from mixed-use development activities (including without limitation impacts resulting from associated improvements such as sidewalks, parking areas and driveways) do not exceed the limitation set forth in Policy CON 5.2 E(7); and
 - c. To the extent direct impacts to wetlands are caused by a particular building or buildings within a mixed-use development, not less than 30% of the gross square footage of such building or buildings must be for residential use; or such building or buildings shall be physically attached to a building having not

CONSERVATION ELEMENT

less than 30% of its gross square footage permitted for residential use.

7. Impacts to wetlands from residential and mixed-use land development activities, on a cumulative basis, shall not exceed 1.8% of the non-commercial and non-industrial acreage of a DRI, PUD, parcel acreage or, if the project is within ~~a New Town Overlay (as defined in Chapter 11, Objective 9)~~ the West Viera Area, 1.8% of the non-commercial and non-industrial acreage within the ~~applicable New Town Overlay~~ West Viera Area.
8. Allowable wetland impacts shall be kept to a minimum and related to structural building area requirements, on-site disposal system requirements, the 100-year flood elevation requirement for first floor elevations, required stormwater management and parking, and required access to the on site structures. Minimization shall include application for available land development regulation waivers that would result in reduced wetland impacts.
9. Dumping of solid or liquid wastes shall be prohibited.
10. Applying or storing pesticides and herbicides should be prohibited unless such application is required for protection of the public health or removal of invasive, exotic, or nuisance plant species for management and mitigation or conservation purposes approved by Brevard County or removal of invasive, exotic, or nuisance plant species for management and mitigation or conservation purposes approved by Brevard County.
11. The County shall develop incentives to minimize impacts to highly functional and landscape level wetlands.

F. Agricultural Activities

1. An exemption for agricultural pursuits, utilizing best management practices which do not result in permanent degradation or destruction of wetlands, shall be included within the land development regulation.
2. Wetland impacts for activities listed in agricultural zoning classifications as permitted, permitted with conditions, or approved by the Board of County Commissioners as a Conditional Use on properties designated as bona fide agricultural lands per F.S. 193.461 and 823.14, may be allowed subject to the following criteria:
 - a. The property shall be classified as bona fide agricultural per F.S. 193.461 and 823.14 for not less than ten consecutive years as of the date of the proposed impact;
 - b. The property shall have Agriculture Future Land Use designation or DRI Future Land Use designation and the proposed use is

CONSERVATION ELEMENT

consistent with the defined agricultural uses under an approved DRI Development Order.

- c. Upon approval of the impact, no less than 50 percent of the property area shall retain bona fide agricultural use pursuant to F.2.a above;
- d. Impacts to high functioning or landscape level wetlands shall be prohibited unless the proposed impacts are found to be in the public interest, or overriding public benefit; and
- e. The property shall have an agricultural zoning classification or be zoned PUD and the proposed use is consistent with the defined agricultural uses in the PUD zoning resolution or approved Preliminary Development Plan.

Where the allowable use is residential, residential policies shall apply. Sufficient buffer setbacks of the activity from incompatible land uses shall be provided. Buffer setbacks shall be established through the land development regulations. The property shall meet all other State regulatory criteria.

Policy CON 5.3

Wetland regulations adopted by Brevard County should avoid duplication of wetland regulation unless regulated activities will result in the destruction and/or degradation of functional wetlands. Where the wetland degradation or destruction has been permitted by FDEP or SJRWMD based on FDEP and SJRWMD professional staff application of criteria and evaluation the County shall apply the land use and density requirements of Policy CON 5.2 and the avoidance, minimization of impacts, and mitigation priorities established by Objective CON 5. Any permitted wetland degradation or destruction shall provide for mitigation as designated in the Conservation Element.

Policy CON 5.4

Wetlands artificially created for wastewater treatment or disposal or for wetland stock nurseries shall not be subject to these regulations and shall not be used to fulfill the requirements of this objective (~~Objective 5~~).

Policy CON 5.5

Natural, isolated wetlands should be incorporated into water management systems where practical and appropriate, as an alternative to destruction of wetlands. Whenever wetlands are utilized within water management systems, quality of the water discharged to the wetlands, hydroperiods and stage elevations should be designed to maintain or enhance the wetland.

Policy CON 5.6

Wetlands policy should provide allowances to promote redevelopment, and urban

CONSERVATION ELEMENT

and industrial infill.

Policy CON 5.7

High Functioning and Landscape Level Wetlands analyses shall be prepared by a Recognized Knowledgeable Environmental Professional.

Policy CON 5.8

In considering the functional value of wetlands, the degree of alteration, uniqueness~~s~~, landscape diversity, and ~~proximity~~ proximity to water bodies should be considered.

Minerals and Soils

Objective CON 6

Brevard County shall continue to implement regulations regarding land alteration, including, but not limited to, mining, borrow operations and private lakes which protect environmental systems and permit appropriate utilization of the mineral resources.

Policy CON 6.1

Mining regulations shall continue to include, at a minimum, the following provisions to prevent adverse effects on water quality and quantity.

Criteria:

- A. Mining operations are not permitted within Type 1 aquifer recharge areas, as defined by this Comprehensive Plan.
- B. Mining operations are not permitted within Type 2 aquifer recharge areas which are being used for a drinking water supply or where there is potential for private drinking water supply systems.
- C. Mining operations are not permitted within the 10-year floodplain of the St. Johns River or freshwater tributaries of the Indian River Lagoon or wetlands as protected within this Plan.
- D. Mining operations located within the watersheds of Class I surface waters shall not have adverse impacts on water quality and quantity of potable surface water sources.

Policy CON 6.2

The County's mining regulations shall continue to include, at a minimum, the following provisions to minimize adverse impacts to environmental resources.

Criteria:

- A. Mining operations should not adversely impact protected wetlands or other

water dependent systems, and shall be set back a minimum of 100 feet from such wetlands, except as allowable per Policy CON 5.2.F.

- B. Mining operations shall not cause salt water intrusion. Monitoring by the mining operator shall be required to insure this requirement.

Policy CON 6.3

The County's mining regulations shall continue to include, at a minimum, the following provisions.

Criteria:

- A. ~~Mining~~ Commercial mining operations within any zoning classification shall require a Conditional Use Permit.
- B. Reclaimed mines shall have a minimum five (5) feet horizontally to one (1) foot vertically (5:1) side slopes to a normal water depth of at least five (5) feet below the water surface; subaqueous side slopes deeper than five (5) feet shall be no steeper than 2:1, and a littoral zone.
- C. When the borrow pit (lake) is to be utilized in conjunction with residential development, stormwater shall not be released directly into lakes with depths greater than eight (8) feet. Pretreatment of stormwater, for example via swales, shall be required.

Policy CON 6.4

A reclamation plan and proof of financial responsibility must be submitted and approved prior to the commencement of the mining operation. The reclamation plan shall address the following concerns, at a minimum.

Criteria:

- A. Average depth;
- B. Bottom contours and littoral zones;
- C. Revegetation plan, showing plant materials;
- D. Control of stormwater runoff and drainage;
- E. Recreational amenities, if any;
- F. Stocking with fish, if any; and
- G. Maintenance plan.

Policy CON 6.5

A concept plan to bind the operational scope and other physical features of the

CONSERVATION ELEMENT

operation shall be submitted and approved prior to the commencement of the mining operation. The concept plan shall address the following criteria, at a minimum.

Criteria:

- A. Size and location of operation;
- B. Location of equipment and equipment storage;
- C. Extent of buffering and setbacks;
- D. Side slopes;
- E. Points of ingress and egress; and
- F. A vicinity map depicting removal routes that trucks and other vehicles will use to haul to sites or areas external to the borrow site.
- G. The required reclamation plan shall also be included.

Policy CON 6.6

Brevard County shall continue to implement regulations for land excavation operations in addition to those for commercial borrow operations. These regulations shall include, at a minimum, the following:

Criteria:

- A. Definition of regulated land excavation operations. The construction of a private lake will not be used or constructed as a commercial borrow operation by virtue of its intended use, and maximum size.
- B. Exemptions, including the construction of swimming pools, and water retention areas required in conjunction with an approved development order, including, but not limited to, building permit, site plan, or subdivision plat.
- C. The minimum size to be regulated.
- D. Setbacks shall continue to be established in the private lake regulations from property lines and rights-of-way lines of a publicly owned road, street, highway, drainage, or public or private utility easements, and cable TV easements.
- E. Regulated excavations shall not be permitted within:
 - 1. Type 1 aquifer recharge areas as identified within this Plan or within;
 - 2. Type 2 aquifer recharge areas being utilized as sources for public drinking water supplies.
 - 3. Below the ten-year floodplain of freshwater tributaries of the Indian

CONSERVATION ELEMENT

River Lagoon or the St. Johns River.

- F. Limitations shall be adopted on length of time that excavations may occur and hours of operation.
- G. Requirements for side slopes of the completed excavation.
- H. Maximum permitted depths.
- I. Reclamation requirements.

Policy CON 6.7

The County should, in coordination with the Future Land Use Element, consider [NRCS Natural Resources Conservation Service \(NRCS\)](#) Unique Farmland status for lands with agricultural land use or zoning designation during land use amendment, rezoning, or development review. The County should seek to preserve farmlands of unique importance, as identified by NRCS, in agricultural use.

Soil Erosion

Objective CON 7

Eliminate inappropriate land use practices causing soil erosion and reduce sediment accumulation in the Indian River Lagoon, St. Johns River, and other large surface water bodies.

Policy CON 7.1

Brevard County shall continue to implement its adopted land clearing, tree protection, and landscaping ordinances to address revegetation and premature land clearing.

Criteria:

- A. Require permitting prior to land clearing unless exempt by ordinance.
- B. Require phased clearing in conjunction with phased construction.
- C. Require permits for the removal of trees or vegetation in conjunction with land surveying unless exempt by ordinance.
- D. Require areas cleared of vegetation to be revegetated with biologically appropriate vegetation, to prevent wind or water erosion, within ninety (90) days of initial land clearing activity where no approved landscape plan exists or no active development order has been issued. Native vegetation should be utilized to the maximum extent possible.

CONSERVATION ELEMENT

- E. Exempt single-family residential lots of two and one-half (2 1/2) acres or less in size from the requirement of written notification to clear land, if the activity complies with ordinance, after the issuance of a Certificate of Occupancy for the single-family residential lot.
- F. Exempt land clearing in conjunction with agricultural purposes or normal silviculture conducted in accordance with F.S. 193.461, as amended.

Policy 7.2

~~Where localized soil erosion is noted by Code Enforcement, the Natural Resources Management Department, or other County agency, the Land Conservation Assistance Program (LANDCAN) will be contacted and their recommendations shall be incorporated into a program instituted to assist the landowner to renourish and stabilize such areas.~~

Policy 7.3 CON 7.2

In those cases where soil erosion is of concern, especially properties along the Atlantic Ridge, ~~Brevard County shall request review by the LANDCAN. Brevard County shall consider their recommendations in the design, review and development of projects.~~ Projects should minimize impervious surfaces by using pervious surfaces where ever feasible, such as for overflow parking.

Policy 7.4 CON 7.3

Brevard County will ~~participate~~ consult with the LANDCAN relevant agencies to educate the public about the causes of soil erosion, as well as methods for preventing or repairing such erosion.

Policy 7.5 CON 7.4

Brevard County should employ Best Management Practices for control of erosion and sedimentation for road construction and other County projects.

Policy 7.6 CON 7.5

Brevard County shall utilize techniques in the installation of new facilities or improvement of existing facilities to minimize sediment accumulation within surface water bodies and wetlands.

Criteria:

- A. Turbidity screens shall be utilized for all projects which have the potential to release sediments.
- B. All runoff shall be detained prior to release to allow pollutants, soil, particulates and organic materials to settle out.
- C. Phased projects should be cleared in conjunction with construction of each phase.

- D. Areas cleared of vegetation should be revegetated with appropriate vegetation, to prevent wind or water erosion, within ninety (90) days of initial land clearing activity where no approved landscape plan exists or no active development order has been issued. Native vegetation should be utilized to the maximum extent possible.

Vegetation

Objective CON 8

Conserve, appropriately use and protect native vegetative communities, including forests as appropriate, by regulating land clearing and landscaping practices within Brevard County.

Policy CON 8.1

Brevard County shall continue to implement and improve the land clearing and tree protection ordinance, and the landscaping ordinance, as amended.

Policy CON 8.2

Brevard County shall continue to utilize information from the East Central Florida Regional Planning Council and other agencies in undertaking a program to inventory and identify vegetative communities within the County, and to determine loss rates and rarity of such communities.

Policy CON 8.3

Brevard County shall continue to review all development plans for compliance with vegetative protection regulations developed by ordinance and adopted in Chapter 62, Article XIII, Division 2 of the Land Development Regulations that meet the objectives of F.S. 163.3177 and F.S. 163.3178. Brevard County shall continue to encourage the use of community green space and clustering developments through the ~~open space ordinance ordinances related to open space principles~~, and shall coordinate with the Building and Construction Advisory Committee, the Brevard County Home Builders Association and other appropriate groups to continuously improve environmental design incentive program.

Policy CON 8.4

Brevard County should continue to utilize scientific advisory groups to investigate preservation of vegetation, particularly of upland communities. These groups are ad hoc based upon the Board direction. The Environmentally Endangered Lands Program, Selection and Management Committee (SMC) may also be used to support these investigations when consistent with policy.

Policy CON 8.5

Brevard County shall conserve, appropriately use and protect vegetative communities, including forests, from inappropriate development through the continued implementation of the Landscaping, Land Clearing and Tree Protection ordinance using the following minimum criteria:

Criteria:

- A. Heat Island Mitigation.
- B. Vegetative Buffering.
- C. Vegetative Loss Replacement.

Policy CON 8.6

Brevard County should continue to develop programs for county-wide acquisition of unique vegetative communities which have been identified for protection. This acquisition shall be voluntary, and shall not include the use of eminent domain.

Policy CON 8.7

Brevard County should contact the municipalities within the county and pursue developing a county-wide vegetation protection ordinance to standardize existing landscaping ordinances.

~~Policy 8.8~~ — ~~Reserved~~**Policy ~~8.9~~ CON 8.8**

Brevard County shall continue to incentivize continued use of agricultural and silvicultural lands which are unique to Brevard County. These programs should include, but not be limited to, regulatory incentives and assistance for agriculture landowners, voluntary agricultural or silvicultural districts, time-certain dedications, purchase or transfer of development rights, and voluntary fee simple purchase of agricultural or silvicultural lands.

Policy ~~8.10~~ CON 8.9

Brevard County shall develop a county-wide program for invasive exotic removal on public lands and shall educate private property owners on reasons to remove invasive exotics from private lands. This program should emphasize replacement of invasive exotics with native vegetation where feasible.

Wildlife**Objective CON 9****CONSERVATION ELEMENT**

Protect endangered and threatened wildlife species and species of special concern from adverse impacts due to loss of crucial habitat.

Policy CON 9.1

Brevard County shall continue to obtain and utilize information from the U.S. Fish and Wildlife Service, Florida Fish and Wildlife Conservation Commission, Florida Department of Environmental Protection, Florida Natural Areas Inventory, East Central Florida Regional Planning Council and other agencies to inventory and identify crucial habitat for endangered or threatened wildlife species and species of special concern within the County, and to determine loss rates and rarity of such habitat.

Policy CON 9.2

Brevard County shall continue to make available state and federal maps at the pre-application stage of all projects requiring site-plan or subdivision approval to guide future development away from crucial habitats.

Policy CON 9.3

Brevard County should coordinate a scientific advisory group to investigate preservation of wildlife habitat, particularly of upland communities.

Policy CON 9.4

Brevard County shall continue the Environmentally Endangered Lands Program (EEL), as authorized by the voter-approved public referendums in September 1990 and 2004. This program shall remain committed to acquiring, protecting, and maintaining environmentally endangered lands and making improvements as appropriate for passive recreation and environmental education.

Policy CON 9.5

Development of Brevard County owned conservation areas shall be in accordance with the intent of the original acquisition.

Policy CON 9.6

Prior to development of any county-owned property, an environmental assessment should be completed which would analyze the impact of the proposed development on the natural resources and wildlife habitat of the property.

Policy CON 9.7

Brevard County shall continue to rely upon the Environmentally Endangered Lands (EEL) Program, Selection and Management Committee (SMC) land acquisition analysis and the Florida Fish and Wildlife Conservation Commission (FWC) adopted in 1994, revised in 2006, wildlife corridor studies to determine the appropriateness of wildlife corridors, how extensive they should be, and the location of potential corridors. Brevard County should explore what fiscal resources, including the EELs program, are available for

CONSERVATION ELEMENT

implementation and possible economic incentives for property owners to voluntarily participate in formation of a wildlife corridor program.

Policy CON 9.8

Brevard County shall delineate and protect linkages between natural systems and the open space systems.

Policy CON 9.9

On February 7, 2003, the Florida Fish and Wildlife Conservation Commission approved the Brevard County Manatee Protection Plan (MPP). The MPP includes the following major components: habitat protection, education, boat facility siting, State of Florida manatee protection boat speed zones, manatee mortality, law enforcement, and boating safety. Boat facility siting and shoreline development shall comply with the criteria established in the MPP, as amended. In coordination with FWC, the ~~The~~ County shall continue to monitor manatee protection measures to determine their effectiveness. In addition to the criteria established in the MPP and incorporated into the Coastal Element, the following criteria shall also apply:

Criteria:

- ~~A. All existing and new marinas shall erect manatee education and awareness signs, which will be posted and maintained in a prominent location. Each marina operator shall establish and maintain a permanent manatee educational display at a prominent location at their marina. Brevard County shall establish and maintain a display at public boat launch facilities and license tag agencies.~~
- ~~B. Those involved in the sale of boats and motors should provide manatee information to the buyer at the time of delivery of boats or motors.~~
- ~~C. Brevard County shall maintain well-marked speed limit signs, in accordance with the uniform waterway marker program, for manatee protection and boating safety speed zones established by local ordinance only.~~
- ~~D. Brevard County, or other appropriate agencies, shall develop standardized information packet containing information regarding manatees and regulations protecting manatees for distribution by the U.S. Fish and Wildlife Service, Florida Department of Environmental Protection, Brevard Marine Association, and other agencies or groups as appropriate. This will include information concerning the existing manatee slow speed or idle zones, and any additional zones which may be deemed necessary within areas frequented by manatees.~~
- ~~E. Brevard County shall continue to monitor manatee protection measures to determine their effectiveness.~~

CONSERVATION ELEMENT

~~F. Brevard County shall identify areas containing significant manatee habitat features. Marinas with powerboat slips should not be sited within these areas.~~

Policy CON 9.10

Brevard County should continue to enforce its ordinances related to sea turtle protection ordinance, encompassing lighting and coastal setback regulations, in order to protect sea turtles along the County's beaches. Efforts shall be made to make beachfront lighting ordinances within the County uniform. This may be accomplished through interlocal agreements.

Policy CON 9.11

Beach renourishment and dune restoration plans shall continue to be designed and implemented so that sea turtle nesting is not disrupted.

Policy CON 9.12

Brevard County Natural Resources Management Department shall continue to comply with the county-wide scrub-jay Habitat Conservation Plan as approved by the US Fish and Wildlife Service. ~~Management plans shall be developed for other species, as deemed necessary.~~

Policy CON 9.13

~~The Brevard County Natural Resources Management Department shall make available to the development community, State prepared model management plans for other endangered and threatened species and species of special concern dependent upon habitat rarity and loss rates as described in Policies 9.2, 9.7, and 9.12, in this element. Wildlife management plans shall be developed for other species, as deemed necessary.~~

Policy CON 9.14

Brevard County shall continue to assist in the application of, and compliance with, all state and federal regulations which pertain to endangered, or threatened species and species of special concern.

Policy CON 9.15

The County shall continue to implement education programs to promote the preservation of endangered and threatened species and species of special concern as well as their habitat, with the assistance of the Florida Department of Environmental Protection, the Florida Fish and Wildlife Conservation Commission, and the U.S. Fish and Wildlife Service, and other agencies or groups as appropriate. Brevard County encourages the development of post-development wildlife management plans which would enhance the wildlife potential of existing developments.

CONSERVATION ELEMENT

Policy CON 9.16

Brevard County supports the use of Turtle Excluder Devices (TEDs) or other devices to protect wildlife from shrimp and other fishing nets.

Aquifer Protection

Objective CON 10

Maintain and protect the surficial and Floridan aquifer systems for reasonable and beneficial uses.

Policy CON 10.1

Brevard County shall continue to ~~implement the aquifer protection ordinance~~ maintain regulations that minimize impacts to, alteration of, and loss of aquifer recharge areas and recharge soils during development.

Policy CON 10.2

At a minimum, the following criteria shall be incorporated into the land development regulations to protect the aquifer.

Criteria:

- A. In Type 1, 2, and 3 aquifer recharge areas, post-development groundwater recharge volume shall equal pre-development recharge volume.
 - 1. ~~The maximum allowable impervious surfaces in these areas shall be: For single-family residential development, the following maximum allowable impervious surface area ratios shall be presumed to maintain recharge volumes as required above: Type 1 - 25%; Type 2 - 35%; and Type 3 – 45% unless the developer can demonstrate that post-development recharge volume shall equal pre-development recharge volume and dependent upon additional regulations and local conditions. Citrus, improved pasture, row crop agricultural operations, and normal silvicultural operations using Best Management Practices shall be exempt.~~
 - 2. For all other development, including new residential subdivisions, the applicant shall demonstrate that post-development recharge volume will equal pre-development recharge volume.
- B. For water quality purposes, stormwater run-off in Type 1, 2, and 3 aquifer recharge areas should be directed through a vegetated stormwater management system which at a minimum has a soil depth of at least two feet above the seasonal high water table. ~~Citrus, improved pasture, row crop agricultural operations, and normal silvicultural operations using Best Management Practices shall be exempt.~~ If alternative methods can be shown to meet an equal or greater degree of stormwater treatment these methods may be considered.

CONSERVATION ELEMENT

- C. Within Type 1 aquifer recharge areas, the following are prohibited:
- ~~1. New septic tanks. However, residential lots platted or established by deed on the official record books of the County prior to September 10, 1990 that are (1) outside of the Indian River Lagoon Basin Management Action Plan area as established by FDEP and (2) within the Titusville Area of Critical Concern, where centralized sewer service is unavailable, may construct an OSTDS pursuant to FDEP permitting requirements. No more than one (1) black water septic tank shall be permitted per acre. An OSTDS constructed according to this provision shall not exceed 1,200 gallon capacity and shall be an enhanced nutrient-reducing OSTDS as defined by section 381.0065, F.S., achieving at least sixty-five (65) percent total nitrogen reduction. Properties developed with OSTDS according to this provision shall be required to connect to an available centralized sewer system within three hundred sixty five (365) days after written notification by the owner of the centralized sewer system that the system is available for connection.~~
 - ~~2. 1.~~ New underground chemical or fuel storage tanks.
 - ~~3. 2.~~ Storage of threshold amounts of hazardous materials.
 - ~~4. 3.~~ Disposal of hazardous materials.
- D. Within Type 2 aquifer recharge areas, the following are prohibited:
1. Storage of threshold amounts of hazardous materials.
 2. Disposal of hazardous materials.
- E. Within Type 3 aquifer recharge areas, the disposal of hazardous materials is prohibited.
- F. ~~Groundwater withdrawals shall be managed to prevent salt water intrusion and adverse affects to existing wells.~~ Anyone proposing a new public water supply well must own or control all areas within 500 feet of the proposed well.
- G. An applicant can show that the area does not function as a recharge area by providing additional information about hydrogeologic conditions on site ~~which may include vertical permeability as found including the absence of soils defined as highly permeable soils in the Aquifer Protection ordinance Glossary.~~
- H. ~~Bona-fide agricultural operations using Best Management Practices shall be exempt from aquifer protection requirements.~~

CONSERVATION ELEMENT

Policy 10.3

~~Brevard County shall support the City of Titusville's efforts to obtain G-1 sole source aquifer designation.~~

Policy 10.4 CON 10.3

~~Brevard County shall continue cooperation with the City of Titusville through Ordinance No. 99-010E and pre-annexation agreements for properties within the City's Area of Critical Concern in order to carry out Titusville's aquifer protection policies and the provision of potable water.~~

Policy 10.5 CON 10.4

~~Brevard County shall develop a coordinate with SJRWMD in public education program efforts concerning the importance and methods of protecting the County's surficial and Floridan aquifers.~~

Policy 10.6 CON 10.5

Brevard County shall continue to regulate land uses which involve the storage, production, use and disposal of threshold amounts of regulated substances identified as priority pollutants by the Environmental Protection Agency in 40 CFR 401.15, as amended, within Type 1, Type 2, and Type 3 aquifer recharge areas. These regulations shall meet the state criteria for protecting wellfields.

Policy 10.7 CON 10.6

~~Brevard County should include LID and GSI design principles in public capital projects and prioritize stormwater retention projects that seek to recharge the aquifer where feasible and fiscally prudent. Brevard County shall consider incorporating in the aquifer protection code requirements for the use of LID and GSI standards, including provisions for maintenance and upkeep, in aquifer recharge areas.~~

Policy 10.8 CON 10.7

~~Brevard County shall review its public facilities infrastructure and operations for potable water conservation opportunities. The County shall strengthen and enforce the provisions found in the Brevard County Water Source Heat Pump Ordinance in an effort to protect water resources.~~

Energy Conservation**Objective 11**

~~Brevard County shall develop strategies through transportation decisions and planning to address the reduction of greenhouse gas emissions, energy conservation and energy efficient design.~~

Policy 11.1

~~Sites for new public facilities serving large numbers of people shall be close to or within population centers to minimize automobile use.~~

Policy 11.2

~~The County shall promote car pooling opportunities for commuters with the same destination.~~

Policy 11.3

~~The County shall encourage the use of transit opportunities and other alternate modes of transportation throughout the County.~~

Policy 11.4

~~The County shall continue its education program to promote bicycle, pedestrian and other non-motorized transportation options to reduce vehicle miles traveled.~~

Potable Water Conservation**Objective CON 11**

Brevard County shall conserve and appropriately use potable water resources to ensure sufficient water quality and quantity to meet future demand.

Policy CON 11.1

Brevard County shall review its public facilities infrastructure and operations for potable water conservation opportunities.

Policy CON 11.2

The County shall include provisions within the Land Development Regulations in an effort to reduce per capita consumption:

Criteria:

- A. New irrigation systems should be designed to use non-potable water or reclaimed water as the source when a non-potable water or reclaimed water supply source is available.
- B. New industrial or commercial development that does not require water meeting potable water quality standards should be designed to use non-potable water or ~~reclaiamed~~ reclaimed water when a non-potable water or reclaimed water supply source is available.
- C. New irrigation systems should utilize micro-irrigation techniques to the greatest extent practicable.

CONSERVATION ELEMENT

- D. Landscaping for new development should utilize waterwise landscaping principles including limits on the use of landscaping that requires irrigation.

Policy CON 11.3

The County shall cooperate with SJRWMD during declared water shortage emergencies by conserving water resources and assisting SJWRMD with enforcement of water shortage emergency declarations, orders, and plans.


Policy CON 11.4

The County shall continue to implement its Water Conservation Plan submitted to SJRWMD as part of the consumptive use permitting process.


APPENDIX

LIST OF MAPS

Map	Title
1	General Soils
2	Vegetation
3	Floodplains
4	Surface Water - Classification
5 <u>4</u>	Wetlands
6 <u>5</u>	Mitigation Qualified Roadways Map and Table
7 <u>6</u>	Landscape Level Polygon




CONSERVATION ELEMENT





Conservation Element Vegetation

0 5 10 20 Miles

Brevard County Information Technology Department
Data Source: St Johns River Water Management District (SJRWMD)
Source Date: 2020








**Conservation Element
Surface Water - Classification**




9/28/2017

CONSERVATION ELEMENT




Conservation Element Wetlands

0 5 10 20 Miles



Brevard County Information Technology Department
Data Source: National Wetlands Inventory (NWI)
Source Date: 2024

Brevard County - Comprehensive Plan




Mitigation Qualified Roadways/I-95 Interchange Areas

CONSERVATION ELEMENT

MQR SEGMENT NAME (Segments apply ONLY in unincorporated areas of Brevard County)	FROM	TO
Stuck Way Rd (CR 5A)	I-95 interchange area*	U.S. Highway 1
U.S. Highway 1	County Line Rd	Kingman Rd (Titusville City Northern Boundary)
SR 46 / Main St	I-95 interchange area*	Approx. 300' west of Turpentine Rd
SR 46 / Main St	I-95 interchange area*	U.S. Highway 1
Parrish Rd	Singleton Ave	U.S. Highway 1
Cheney Hwy (SR 50)	I-95 interchange area*	Approx. 3,800' west of I-95 interchange area*
South Street	Cheney Hwy (SR 50)	Fox Lake Rd
Columbia Blvd (SR 405)	Woodland Hills Dr	U.S. Highway 1
U.S. Highway 1	Titusville City Boundary	Cocoa City Boundary
Grissom Pkwy	Titusville City Boundary	Cocoa City Boundary
Port St. John Pkwy	I-95 interchange area*	Grissom Pkwy
Kings Hwy	U.S. Highway 1	Approx. 325' west of Koesaw
Curtis Blvd	Fay Blvd	Approx. 210' east of Song Dr
Fay Blvd	Carole Ave	Adobe Ave
Canaveral Groves Blvd	U.S. Highway 1	Approx. 330' west of Morris Ave
SR 520	I-95 interchange area*	Penny Ln
SR 524	SR 520	Cocoa City Boundary
Friday Rd	SR 520	Cocoa City Boundary
Lake Dr	SR 520	Cocoa City Boundary
School St	Clearlake Rd	Pineda St
King St (SR 520)	I-95 interchange area*	Cocoa City Boundary
Peachtree St	Clearlake Rd	Pineda St
Pineda St	Peachtree St	School St
Burnett Rd	Lake Dr	Pluckebaum Rd
Range Rd	Lake Dr	Pluckebaum Rd
Pluckebaum Rd	Burnett Rd	Approx. 700' east of Range Rd
Clearlake Rd	SR 520	Tate St
Fiske Blvd	I-95 interchange area*	Eyster Blvd
U.S. Highway 1	Rockledge City Boundary	Post Rd (Melbourne City Boundary)
Murrell Rd	Wickham Rd	Rockledge City Boundary
Viera Blvd	Stadium Pkwy	U.S. Highway 1
Spyglass Hill Rd	Murrell Rd	Pinehurst Ave
Wickham Rd	I-95 interchange area*	New Haven Ave (SR 192)
Suntree Blvd	Wickham Rd	U.S. Highway 1
Pineda Cswy	Wickham Rd	RR Crossing
Aurora Rd	Citrus St	Melbourne City Boundary (Approx. 235' east of Alpha Dr)
Croton Rd	Carlton Dr	Melbourne City Boundary (Approx. 100' north of Leewood Blvd)
John Rodes Blvd	Melbourne City Boundary (N end of Lamplighter Village)	New Haven Ave (SR 192)
Ellis Rd	John Rhodes Blvd	Distribution Dr
New Haven Ave (SR 192)	I-95 interchange area*	Minton Road
Babcock St	Micco Rd	Approx. 680' north of Micco Rd
Micco Rd	Babcock Road	Approx. 1,310' east of Babcock St
US 1/SR 5/Dixie Hwy	Senne St (Grant - Valkaria City Boundary)	Sebastian Inlet Bridge (South Brevard County Line)
Micco Rd	US 1/SR 5/Dixie Hwy	Approx. 340' west of Pine Ridge Trail
N Courtenay Pkwy	Pine Island Rd	SR 520
Courtenay Pkwy	SR 520	Approx. 470' south of Island Beach Blvd.
Sea Ray Dr	N Courtenay Parkway	Banana River Dr
Marine Harbor Dr	N Courtenay Parkway	Tropical Tr
Tropical Tr	Marine Harbor Dr	Barge Canal
N Banana River Dr	Barge Canal	Stafford Ave
Merritt Island Cswy (SR 520)	Indian River Lagoon (east shore)	New Found Harbor (west shore)
Merritt Island Cswy (SR 520)	Newfound Harbor (east shore)	Banana River (west shore)
Milford Point Dr	Merritt Island Cswy	Approx. 625' north of Merritt Island Cswy
Banana River Dr	Merritt Island Cswy	Approx. 1,200' south of Merritt Island Cswy
Newfound Harbor Dr	Merritt Island Cswy	Approx. 175' south of Kessler Dr
Atlantic Ave	Grant	Barlow
Orlando Ave (SR A1A)	11th St (Cocoa Beach City Boundary)	Atlantic Ave (SR A1A)
Atlantic Ave/SR A1A	Indian Village Trail (Cocoa Beach City Boundary)	Grosse Pointe Ave (Indianalantic City Boundary)
SR 513/5 Patrick Dr	Pineda Cswy	Satellite Beach City Boundary (Approx. 185' north of Siena Ct)
Eau Gallie Blvd	Harbor City Parkway	SR A1A

* - Please refer to Policy 5.2.E.3.a

CONSERVATION ELEMENT



Conservation Element Landscape-Level Polygon Map



11/7/2024

CONSERVATION ELEMENT

LPA Adoption June 16, 2025

CHAPTER PART II

SURFACE WATER MANAGEMENT ELEMENT

TABLE OF CONTENTS

Stormwater Management Plan Implementation	1
Meeting Future Needs	5
Concurrency Management	5
Natural Drainage Functions	7

GOALS, OBJECTIVES, AND POLICIES

GOAL SF

A safe, efficient, environmentally sound, and comprehensive surface water management system in Brevard County.

Stormwater Management Plan Implementation

Objective SF 1

~~Correct~~ Identify existing stormwater system deficiencies to ensure preservation and improvement of surface water quality, enhance existing stormwater systems, and implement new stormwater systems according to priorities established within the County's Stormwater Management Plans stormwater area studies to ensure preservation and improvement of surface water quality.

Policy SF 1.1

Brevard County shall continue to implement and update ~~Stormwater Management Plans~~ stormwater area studies which establish criteria and methodologies for drainage basin analysis and Level of Service standards. Drainage basins will be prioritized and analyzed based on severity of problems and available funding. The analysis shall identify the following information, at a minimum:

Criteria:

- A. Surface water drainage basins and sub-basins.
- B. Public and private stormwater treatment facilities, including detention/retention facilities, and the entity having operations responsibility.
 - 1. For shared facilities, the proportional capacity allocated to each entity shall be identified.
 - 2. The geographic service area of each facility and the predominant types of land use served by the facility.
 - 3. The design capacity of the facility.
 - 4. The current demand on the facility.
 - 5. The impact of the drainage facility on adjacent natural resources, including water quality of receiving waters.
- C. Estimated timeframe and costs of correcting deficiencies.

Policy SF 1.2

Priorities for basin analysis and retrofitting shall be established using a matrix approach and the following criteria, at a minimum:

Criteria:

- A. Health and safety.

SURFACE WATER MANAGEMENT

- B. Flooding potential.
- C. Impact of stormwater on the water quality of the receiving water bodies.

Policy SF 1.3

The Natural Resources Management Department shall be the lead agency for the development and implementation of the Stormwater Management Plans and shall coordinate its efforts with the Florida Department of Environmental Protection (FDEP) and St. Johns River Water Management District (SJRWMD) on the Basin Management Action Plan (BMAP), Total Maximum Daily Loads (TMDL²s), and the National Pollution Discharge Elimination System (NPDES) permit schedule and requirements.

Policy SF 1.4

Where an approved stormwater system has been altered, resulting in negative impacts to neighboring properties, Brevard County shall require property owners to return these systems to their original design or to an approved design which is a betterment, as appropriate. Any such improvements shall be consistent with the adopted Stormwater Management Criteria within the Land Development Regulations: Chapter 62, Article X, Division 6.

Policy SF 1.5

Brevard County shall address modification of existing development which does not meet stormwater management standards within the Stormwater Management Criteria, and should use available financial mechanisms for the modification of such development.

Criteria:

- A. ~~Stormwater~~ During modification of existing development, stormwater management facilities within existing developments should be ~~retrofit~~ retrofitted to provide for treatment of runoff (including sediment removal where appropriate) prior to release to receiving waters. The Level of Service Standards for these facilities shall ~~be~~ include the reduction of the pollutant loading as necessary to enhance or maintain the beneficial uses of the receiving water and to meet receiving water standards per Florida Administrative Code. All facilities should be maintained at design capacity.
- B. ~~Properties~~ During modification of existing development, properties with bulkheads or seawalls ~~should be modified~~ shall be enhanced so that runoff is detained prior to release to the receiving body. This may be achieved by planting native or other appropriate vegetation along the shoreline to retain silt, sediment, and nutrients so that the quality and rate of runoff is equivalent to the pre-development state.
- C. ~~Properties~~ During modification of existing development, properties with altered vegetated shorelines ~~should modify the shorelines~~ shall be enhanced to retain silt, sediment, and nutrients by planting native ~~vegetation~~.

SURFACE WATER MANAGEMENT

or other appropriate vegetation. A detention structure, swale, and/or berm may be used to allow sediments to settle and nutrient uptake to occur only if non-native vegetation is predominant. Runoff quality and rates should be equivalent to the pre-development state.

Policy SF 1.6

Brevard County's Stormwater ~~Utilities~~ Utility Program will continue to include a program for periodic, scheduled inspections of stormwater management facilities.

Policy SF 1.7

Brevard County should continue the public information program on the value of stormwater management. The County should continue to coordinate this program with ~~Natural Resource Conservation Service (NRCS)~~ FDEP, SJRWMD, the Indian River Lagoon National Estuary Program, and other appropriate organizations and agencies.

Policy SF 1.8

Brevard County shall ~~determine the feasibility of~~ consider innovative methods of stormwater treatment. ~~Innovative methods of stormwater treatment should be construed as any technique~~ other than standard retention and detention basin, ~~and which~~ shall include such alternatives as stormwater reuse and nature-based ~~area wide~~ stormwater management ~~facilities~~ systems.

Policy SF 1.9

Brevard County shall pursue funding from federal, state, and regional sources to investigate and utilize innovative methods of stormwater treatment.

Policy SF 1.10

Funding sources for development and implementation of the ~~Stormwater Management Plans~~ stormwater area studies will continue to include the stormwater utility which is also identified within the Capital Improvements Element.

Policy SF 1.11

Brevard County shall continue to implement the stormwater utility as a reliable long-term funding mechanism to correct existing deficiencies and to provide for future stormwater management needs. Fee structure may be related to type of development, quantity of runoff generated, impervious surface, or other "user related" standard.

Policy SF 1.12

~~Land use decisions relating to water resources and natural drainage features should be consistent with comprehensive water basin management plans. Area wide water quality management plans should be considered during the continued development of the BMAP. All new development shall meet the established stormwater requirements. If during the time that the Stormwater Ordinance is being implemented~~ reviewed and updated, it becomes apparent that additional regulations are required in order to protect

SURFACE WATER MANAGEMENT

water quality in surface water bodies in Brevard County, the County will initiate protective regulations through the adoption or revision of land development regulations.

Policy SF 1.13

~~During continued development of the Stormwater Ordinance, the~~ The County shall ~~initiate the adoption of~~ periodically review and update as necessary its retention and detention standards for stormwater throughout Brevard County.

Policy SF 1.14

Brevard County should support a program to retrofit large drainage canals with water control structures or rapid infiltration basins to hold canal stages high during the dry season. This would reduce irrigation demands, conserve ground water resources, and reduce degradation of water quality of the Indian River Lagoon and the St. Johns River.

Policy SF 1.15

Nonstructural methods of stormwater management that reduce the generation and accumulation of potential stormwater runoff contaminants should be utilized to the maximum extent possible. Nonstructural methods of stormwater management include pesticide and herbicide control, proper fertilizer management, erosion control, proper waste disposal, etc. In addition, the use of wetlands and floodplains should be utilized whenever feasible in such a manner as to maintain the natural function and biodiversity of the system.

Policy SF 1.16

No new structures (such as dams, weirs, locks, levees, or other artificial mechanisms) designed to control the stage and/or flow of waters of the State shall be constructed, except where no practical alternative exists and where such structures are necessary to protect the public safety; ; safeguard existing flood control structure, habitable structures, and other public investments; ; improve water quality; or restore the function of the natural water dependent ecosystem. The use of temporary structural modifications to control the stage or flow of a water body as a part of any government sanctioned program of flood control, water quality restoration, habitat restoration, or exotic plant control should be designed and operated so as to minimize harm to non-target organisms or natural ecosystems.

Policy SF 1.17

The channelization, dredging, or impoundment of natural waters of the State shall be prohibited, except where no practical alternative exists for those operations necessary to correct existing threats to public health or safety, allow maintenance of existing navigational waterways, improve water quality, or provide reasonable access to water dependent shore-based facilities. All practical steps shall be taken to minimize adverse impacts to biological attributes of the water resources and water-dependent natural systems.

SURFACE WATER MANAGEMENT

Meeting Future Needs

Objective SF 2

Require stormwater management facilities to meet future development requirements, consistent with the County's Stormwater Ordinance.

Policy SF 2.1

Brevard County's ~~Stormwater Management Plans~~ stormwater area studies shall coordinate the timing and location of stormwater management facilities to projected future needs and the Future Land Use plan. Intensity and levels of stormwater services shall be tied to the development of an area, and consistent with level of service standards.

Policy SF 2.2

The Stormwater ~~Utilities~~ Utility Program shall continue to leverage alternative methods of funding for the provision of projected future stormwater management needs. These may include, but are not limited to, impact fees, capacity reservation fees, or hookup fees to pay for new public facilities or improvements to existing public facilities required for new development.

Policy SF 2.3

Brevard County requires that new stormwater management facilities or techniques shall not negatively impact adjacent properties.

Policy SF 2.4

Brevard County should develop a schedule for maintenance of all existing County maintained stormwater management facilities.

Policy SF 2.5

The provision of stormwater management facilities by the County shall be coordinated and consistent with the provision of other facilities, as directed by this Comprehensive Plan, including the Future Land Use, Conservation, Coastal Management, Transportation, and Capital Improvements Elements.

Policy SF 2.6

The development and use of stormwater management facilities by Brevard County shall be undertaken to maximize the overall public benefit, while minimizing construction, operation, and maintenance costs.

Concurrency Management

Objective SF 3

Require new development to adequately manage stormwater generated by the development.

SURFACE WATER MANAGEMENT

Policy SF 3.1

The Brevard County Land Development Regulations shall require all new development being site planned or subdivided to provide for stormwater management, which meets the following Level of Service Standards, at a minimum:

Criteria:

- A. Retention and detention requirements shall at a minimum meet SJRWMD Criteria.
- B. Retention of the first inch of runoff.
- C. Post-development rate of discharge shall not exceed pre-development rate of discharge for a 25 year - 24 hour storm event.
- D. Stormwater discharge facilities shall be designed so as to not lower receiving water quality or degrade the receiving water body below the minimum conditions necessary to assure the suitability of water for the designated use of its classification as established in Chapter 62-302 FAC.

Policy SF 3.2

Brevard County shall maintain Land Development Regulations consistent with the following minimum criteria:

Criteria:

- A. Land Development Regulations shall be consistent with Brevard County Subdivision and Site Plan Regulations and subsequent amendments or any subsequent stormwater land development regulation, whichever is more stringent.
- B. Land Development Regulations shall require any other design standards as may be required, including the flexibility for the use of the 2-pond retention/detention system or other innovative method of stormwater management approved by the Natural Resources Management Department.
- C. Land Development Regulations shall require performance bonds, annual operating fee or other fee structure for the maintenance of private systems which are accepted by the County for maintenance but not for ownership.
- D. If it becomes apparent that additional regulations are required in order to protect water quality in surface water bodies, Brevard County will initiate protective regulations through the adoption or revision of Land Development Regulations.
- E. A plan amendment will be required to change or alter the level of service standards adopted for drainage facilities.

SURFACE WATER MANAGEMENT

Policy SF 3.3

Brevard County shall require stormwater management systems to employ the most efficient and cost-effective control techniques available, including Best Management Practices to control siltation and prevent erosion.

Policy SF 3.4

Brevard County shall continue record keeping on stormwater management practices and monitoring of selected facilities. This information will provide a database for state, regional, and local programs.

Policy SF 3.5

Brevard County shall provide stormwater treatment facilities for all roadways, which it constructs or improves for the purpose of increasing traffic flow. These facilities shall be designed, constructed, operated, and maintained consistent with County and state standards.

Policy SF 3.6

~~Brevard County should investigate the delegation of stormwater permitting from the SJRWMD or the FDEP, as appropriate.~~ If Brevard County accepts delegation of stormwater permitting from the SJRWMD or the FDEP, this program shall be properly funded and adequately staffed.

Policy SF 3.7

The Natural Resources Management Department shall ~~review~~ consider and comment ~~as necessary~~ on the impact of new development on stormwater conveyance systems. If the ~~conveyance system is~~ stormwater impacts from proposed development are determined to ~~be deficient~~ cause or contribute to adverse local or downstream impacts, the developer shall be required to retain additional runoff on site, or make improvements to the conveyance system equal to the impact of the new development.

Natural Drainage Functions

Objective SF 4

Maintain the function of natural drainage features within Brevard County by reducing loss of flood storage capacity, protecting the functional value of wetlands, and by reducing the interbasin diversion of waters from the St. Johns River basin into the Indian River Lagoon. Quality of waters which are diverted into the Lagoon system shall be improved.

Policy SF 4.1

Surface water interbasin diversions for new development shall be prohibited. The reduction or elimination of existing interbasin diversions to re-establish the historic St. Johns River drainage basin shall be encouraged.

SURFACE WATER MANAGEMENT

Policy SF 4.2

Brevard County shall review and provide comments on all state and federal proposals for controlling or retrofitting the existing interbasin canals for consistency with this Comprehensive Plan. The County shall request compliance and consistency with this Comprehensive Plan.

Policy SF 4.3

Brevard County should support the development of a program by the SJRWMD to coordinate surface water management data. ~~Information should be collected, reviewed, and placed on a computer model to~~ and determine cumulative effects of new development on discharge rates and volumes.

Policy SF 4.4

Brevard County should continue to coordinate stormwater management plans within the County with municipalities and State and Federal land holders.

Policy SF 4.5

~~Development within areas prone to flooding due to localized soil conditions or hydrology~~ shall not negatively impact adjacent properties or receiving surface water body quality.

Policy SF 4.6

Brevard County shall ~~fulfill the intent of the Conservation and Coastal Management elements of this Comprehensive Plan for~~ provide for the protection of the County's natural drainage features in coordination with the Conservation and Coastal Management Elements of this Comprehensive Plan.

Policy 4.7

~~Public facilities should not be located within the 100-year floodplain or wetland areas unless the following apply:~~

~~Criteria:~~

- ~~A.—The facilities are water-dependent, such as boat ramps, docks, mosquito-control facilities excluding their chemical storage areas, or other uses described as water-dependent in the glossary of this Comprehensive Plan ; or,~~
- ~~B.—The facilities are water-related, or surface water management facilities or other uses described as water-related in the glossary of this Comprehensive Plan ; or,~~
- ~~C.—The facilities are not adversely affected by periodic flooding or standing water, such as highway bridges and some recreational facilities; or,~~
- ~~D.—The building structures are flood proofed and located above the 100-year flood elevation or removed from the floodplain by appropriately constructed dikes or levees; or,~~

SURFACE WATER MANAGEMENT

- ~~E. The facilities are found to be in the public interest and there is no feasible alternative.~~

Policy 4.8-

Brevard County shall continue its implementation of a mosquito impoundment management plan which should address the following criteria, at a minimum:

Criteria:

- ~~A. Acquisition of impoundments for maintenance and operation.~~
- ~~B. Appropriate water management system shall be utilized.~~
- ~~C. Impoundments shall be restored or reconnected with the Indian River Lagoon when a public benefit can be demonstrated.~~
- ~~D. Proposed alteration of an impoundment should be reviewed by Mosquito Control. Brevard County should compensate property owners for mosquito impoundments when this use precludes all use by the owner or when no alteration would be acceptable to Mosquito Control.~~
- ~~E. Non-permitted alteration of an impoundment shall be enforced by Brevard County.~~
- ~~F. All mosquito impoundments should be evaluated and those found to be breached or non-functional should be repaired by the appropriate Mosquito Control District.~~
- ~~G. Those fully functioning impoundments determined to be needed by the Mosquito Control District, should be placed under a rotational impoundment management plan as approved by the Florida Coordinating Council on Mosquito Control.~~
- ~~H. Any other "source reduction" mosquito control activities that also reduce the natural habitat required by freshwater or marine organisms should be prohibited.~~
- ~~I. Mosquito control impoundments shall be managed in a manner that avoids adverse impacts to the water quality of receiving water bodies.~~
- ~~J. The primary use of mosquito control impoundments shall be to protect human health through the control of mosquito populations. Secondary uses may include stormwater management, habitat improvement, wildlife management, and other uses as appropriate. Brevard County shall encourage multiple uses of mosquito control impoundments.~~

SURFACE WATER MANAGEMENT

- K. ~~Brevard County should develop a program to acquire right-of-way or easements for drainage systems and mosquito control systems which the County maintains, if not already acquired.~~

Policy 4.9 SF 4.7

~~Brevard County shall continue a water and sediment quality monitoring program within the Indian River Lagoon system, and shall to coordinate such a program water quality and sediment monitoring programs within the Indian River Lagoon system with other federal, state, and local agencies. Specific methods of coordination include making data available to other agencies, and coordinating possible management strategies. A water and sediment monitoring program will be evaluated at least every 5 years to determine deficiencies or other necessary changes.~~

Policy 4.10 SF 4.8

Brevard County will continue to identify and map point and non-point sources of pollution within the Indian River Lagoon and St. Johns River watersheds to reduce pollutant loading sources. This program shall be coordinated with other federal, state, and local agencies.

Policy 4.11 SF 4.9

Where illegal or accidental discharges of materials, or violations of water quality standards are observed, such violations will be reported to the appropriate federal, state, and local regulatory agencies for further action and enforcement.

Policy 4.12 SF 4.10

Brevard County shall continue to participate in the development and implementation, as appropriate, of the BMAP, as developed in coordination with the FDEP and SJRWMD.

CHAPTER PART III

RECREATION AND OPEN SPACE ELEMENT

TABLE OF CONTENTS

Park and Open Space System	1
Visual Appeal.....	3
Public and Private Access to Waterways.....	4
Maintenance of Parks and Open Space System.....	4
Environmentally Endangered Lands	5
Level of Service.....	6
Public and Private Partnerships	6

GOALS, OBJECTIVES, AND POLICIES

GOAL ROS 1

Provide a comprehensive park and open space system which offers opportunities for a variety of passive and active recreation, promotes visual appeal, and provides relief from expanses of development.

Park and Open Space System

Objective ROS 1.1

Provide a system of parks and open space to meet the recreational needs of the public.

Policy ROS 1.1.1

The Brevard County Parks and Recreation Department develops, operates, and maintains the County's parks and recreational areas as well as other facilities ~~managed from~~ owned by the State of Florida, Brevard County School Board Public Schools, and other lands ~~managed or other entities~~. This involves the general management of the facilities and program evaluation to identify existing deficiencies and recreational needs for future development. ~~The Department's responsibilities extend to the construction, operation and maintenance of all county recreational facilities.~~

Policy ROS 1.1.2

~~A~~ The County shall strive to maintain a system of parks and recreational facilities meeting the needs of the population ~~shall be maintained to provide for the~~ as defined by acceptable levels of service (LOS) standards.

Policy 1.3

~~Brevard County establishes an acceptable level of service (A.L.O.S.) of total developed acreage of County owned or managed parks, except for the city owned and County operated parks of Titusville, Rockledge, Cocoa and Brevard County School sites, at 3.0 acres per 1,000 people living in the unincorporated areas of the County.~~

Policy 1.4

~~Brevard County establishes three Parks Operations Areas:~~

- ~~• North Area Parks Operations;~~
- ~~• Central Area Parks Operations; and~~
- ~~• South Area Parks Operations.~~

RECREATION AND OPEN SPACE ELEMENT

Policy 1.5 ROS 1.1.3

~~Provide~~ The County shall provide adequate maintenance to ensure that existing facilities remain open to the public.

Policy 1.6 ROS 1.1.4

~~Develop~~ The County shall develop and enhance existing parks and open space sites to provide additional facilities based on the needs of the public and as funding ~~become~~ becomes available.

Policy 1.7 ROS 1.1.5

~~Acquire~~ The County shall acquire additional parks and open space based on the needs of the public and as funding becomes available.

Policy 1.8 ROS 1.1.6

Brevard County shall continue to identify appropriate linear open spaces for potential greenway network programming, potential acquisition, planning, and development as funding becomes available. A greenways network shall be coordinated to promote, develop, and maintain linear connections between existing and proposed parks and open spaces. The greenways network shall provide for pedestrian, bicycle, non-motorized, and other passive uses.

Policy 1.9

Brevard County's Land Development Regulations shall continue to implement the following provisions:

- ~~Regulations which preserve scenic vistas and establish vegetative coverage requirements for developing and redeveloping properties; and~~
- ~~Regulations concerning the provision of oceanfront and riverfront breezeways.~~

Policy 1.10

~~Oceanfront breezeways shall be provided to permit unrestricted movement of onshore breezes and preserve visual access to the ocean. All oceanfront property, except single-family residential, shall have a minimum of 30 percent of the width clear as breezeway/visual corridor pursuant to current Land Development Regulations.~~

Policy 1.11

~~Riverfront breezeways shall provide for a minimum 30 percent breezeway, as measured along the waterfront and visual corridor of each property's river frontage, except single-family residential, pursuant to current Land Development Regulations.~~

RECREATION AND OPEN SPACE ELEMENT

Policy ROS 1.1.7

Brevard County shall protect its established and planned greenway network trail facilities by prohibiting ingress and egress crossings to those properties that have alternative access options.

Policy ~~1.12~~ ROS 1.1.8

Brevard County shall maintain, and update as may be necessary, an inventory of County-owned or managed ~~by agreement parks that are open to the public by Parks Operations Area~~. This inventory will be used to assess whether the ~~adopted acceptable~~ Levels of Service are being achieved and maintained. The inventory of parks will be reviewed for amendment to the Future Land Use Map, as needed.

Visual Appeal

Objective ROS 1.2

Provide for natural visual appeal and relief from visual expanses of development throughout the County.

Policy ROS 1.2.1

Brevard County shall maintain regulations to preserve scenic vistas and establish vegetative coverage requirements for developing and redeveloping properties.

Policy ROS 1.2.2

The County shall require oceanfront breezeways to permit unrestricted movement of breezes and to preserve visual access to the ocean. All developed oceanfront property except single-family residential shall have a minimum of 30 percent of the lot width as breezeway/visual corridor.

Policy ROS 1.2.3

The County shall require riverfront breezeways to permit unrestricted movement of breezes and to preserve visual access to the river. All developed riverfront property except single-family residential shall have a minimum of 30 percent of the lot width as breezeway/visual corridor.

Goal

~~Provide a comprehensive program of active and passive recreation that meets the needs of the public.~~

RECREATION AND OPEN SPACE ELEMENT

Public and Private Access to Waterways

Objective 2 ROS 1.3

To ensure that Brevard's waterways are a publicly-accessible local system of waterways linked to a larger regional system that contributes to the greatest possible recreational and commercial access to the navigable waters of the State of Florida in a manner that does not jeopardize their environmental values.

Policy 2.1 ROS 1.3.1

The County shall ~~identify, maintain an inventory and characterize of~~ its system of waterways in terms of use, capacity, and relationship to recreational and commercial working waterfronts.

Policy 2.2 ROS 1.3.2

The County shall use this data when identifying future public access opportunities, for integrating waterways with recreational and commercial working waterfronts and when coordinating with other jurisdictions on the potential regional aspects.

Maintenance of Parks and Open Space System

Objective 3 ROS 1.4

A system of parks and recreation facilities meeting the needs of the population shall be maintained to provide for organized recreational programs and passive enjoyment of park resources.

Policy 3.1 ROS 1.4.1

~~Recreational programs shall be offered~~ The County shall offer recreational programs at existing facilities as funding becomes available based on facility capacities, staff resources, and the leisure pursuit interests of the public.

Policy 3.2 ROS 1.4.2

The County will strive to locate future parks at, nearby or adjoining existing school sites through coordination with ~~the Brevard County School Board~~ Public Schools, other government agencies and not-for-profit organizations, where feasible.

Policy 3.3 ROS 1.4.3

The County will strive to coordinate joint-use agreements with Brevard ~~County~~ schools Public Schools.

RECREATION AND OPEN SPACE ELEMENT

Policy 3.4 ROS 1.4.4

~~Adequate levels of staff shall be maintained~~ The County shall maintain adequate levels of staff to ensure that recreational programs are cost effective and properly administered.

Policy 3.5 ROS 1.4.5

~~Persons with disabilities shall be provided access~~ The County shall provide adequate accessibility to county owned or operated recreational facilities in accordance with the Americans with Disabilities Act.

Policy 3.6 ROS 1.4.6

~~Enhance~~ The County shall enhance the existing public access sites to beaches, shores, parks, and conservation lands by providing additional facilities as determined by need, the character of the land, and as funding becomes available.

Policy 3.7 ROS 1.4.7

Brevard County shall encourage cultural and related programs.

Environmentally Endangered Lands

Objective ROS 1.5

Continue to provide for the protection of environmentally endangered lands and maintain appropriate public access, recreational use, and environmental education opportunities.

Policy ROS 1.5.1

Brevard County shall continue the Environmentally Endangered Lands Program (EEL), as authorized by the voter-approved public referenda in 1990 and 2004. In coordination with the goals, objectives, and policies of the Conservation Element, this program shall continue to provide appropriate passive recreation and environmental education opportunities for the County's citizens and visitors.

GOAL ROS 2

Attain public and private support for the acquisition, development, operation, and maintenance of recreational facilities and open space areas and for the development and operation of recreational programs.

RECREATION AND OPEN SPACE ELEMENT

Level of Service

Objective 4 ROS 2.1

Provide adequate funding to achieve the ~~appropriate~~ acceptable levels of service in a cost-effective manner.

Policy ~~4.1~~ ROS 2.1.1

~~Various means shall be utilized by Brevard County to fund~~ The County shall prioritize available funding for the acquisition, and development, operation, and maintenance of parks and recreational areas and to provide recreational programs.

Policy ~~4.2~~ ROS 2.1.2

~~Establish~~ The County may establish user fees and/or enterprise funds to offset costs at park sites where facilities and programs are ~~intensive and require continued care and operational guidance;~~ provided.

Policy ~~4.3~~ ROS 2.1.3

~~Monitor~~ The County shall monitor joint-use and contractual agreements to ensure cost effectiveness and that County needs are served.

Policy ~~4.4~~ ROS 2.1.4

The County may seek grant funding to acquire, develop, operate, and maintain parks and to provide recreational programs.

Public and Private Partnerships

Objective 5 ROS 2.2

Coordinate public and private resources to meet recreational demands.

Policy ~~5.1~~ ROS 2.2.1

~~Development of residential areas shall provide~~ The County shall require the provision of active recreation and open space areas through the use of Planned Unit Development, open-space subdivisions, and other techniques, to augment public recreational facilities and to provide direct, convenient facilities to meet the recreational needs of the residents.

Policy ~~5.2~~ ROS 2.2.2

Brevard County may acquire lands, funds, or both, to ~~gain~~ provide for additional ~~neighborhood or community parks and open space as~~ necessary to support new residential development.

RECREATION AND OPEN SPACE ELEMENT

~~APPENDIX~~

~~LIST OF TABLES~~

~~Table Title~~

~~1. Park Inventory by Park Operations Area~~

TABLE 1

Brevard County Parks and Recreation Department

2017 Acceptable Level of Service Acreage
July, 2017

<i>North Area</i>	
<i>Bernice G. Jackson Park</i>	<i>21.62</i>
<i>Blue Hole Park</i>	<i>.45</i>
<i>Chain of Lakes</i>	<i>270.19</i>
<i>City Point Community Church</i>	<i>.40</i>
<i>Cuyler Park</i>	<i>13.31</i>
<i>Fay Lake Wilderness Park</i>	<i>192.70</i>
<i>Fay Park</i>	<i>11.10</i>
<i>Fox Lake Park</i>	<i>31.57</i>
<i>Friendship Park</i>	<i>.96</i>
<i>Gibson Complex and Fields</i>	<i>22.71</i>
<i>Harry T. & Harriette V. Moore Memorial Park</i>	<i>11.93</i>
<i>Hatbill Park</i>	<i>15.00</i>
<i>Holder Park</i>	<i>40.95</i>
<i>Kennedy Point Park</i>	<i>5.38</i>
<i>Manatee Hammock</i>	<i>26.45</i>
<i>Mims Launch Ramp</i>	<i>.75</i>
<i>Nicol Park</i>	<i>5.27</i>

RECREATION AND OPEN SPACE ELEMENT

North Brevard Senior Center	16.68
Parrish Park—Scottsmoor	16.95
Parrish Park—Titusville	36.60
Port St John Boat Ramp	1.03
Port St John Community Center	5.48
Rotary Riverfront Park	5.79
Sandrift Community Center	2.41
Scottsmoor Landing	3.04
Scottsmoor Meeting Hall	.46
Sherwood Park	4.00
Singleton Tennis Courts	4.42
Six Mile Creek	4.15
Space Coast Communities Sports Complex	207.18
Stuart Park	3.00
Tom Statham Park	5.15
W. W. James Park	40.17
William J. Manzo Memorial Prk	2.37

~~Total ALOS Park Acreage—North Area~~ ~~1,029.62~~

Central Area	
Cherie Down Park	6.99

RECREATION AND OPEN SPACE ELEMENT

LPA Adoption June 16, 2025

Cocoa West Recreation Area	18.85
Dolphin Park	.72
F. Burton Smith Regional Park	1,103.95
Harbor Point Park	.09
Intracoastal Waterway Park	8.50
James G. Bourbeau Memorial Park	194.54
Kelly Park East	15.37
Kelly Park West	40.93
Kings Park	240.00
Kiwanis Island Park	23.93
Lee Wenner Park	11.55
Leroy Wright Recreation Area	55.56
Lori Wilson Park	34.50
Manatee Cove Park	29.52
Margaret & Danny Strickland Park	.25
McLarty Park	19.85
Mitchell Ellington Park	114.15
Osteen Park	3.60
Pineda Park	4.52
Pineview Park	3.77
Riverwalk—A Family Park	6.37
Robert P. Murkshe Memorial Park	2.50
Rotary Park Merritt Island	37.90

RECREATION AND OPEN SPACE ELEMENT

LPA Adoption June 16, 2025

Silver Pines Park	3.77
Ulumay Wildlife Sanctuary	436.53
Veterans Memorial Park	68.66
Watts Park	2.07
Woody Simpson Park	8.91
Beach Access Sites	3.64
Total ALOS Park Acreage—Central Area	2,501.49

South Area	
Bonsteel Park	2.34
Brevard Zoo Linear Park	37.03
Canova Beach Park	9.10
Christenson's Landing	3.92
Coconut Point Park	36.90
Eau Gallie Causeway Boat Ramp	1.40
Erna Nixon Park	53.93
First Street Boat Ramp	.64
Fisherman's Landing	7.48
Flutie Athletic Complex	36.49
Howard E. Futch Memorial Park	12.39
Irene H. Canova Park	3.95

RECREATION AND OPEN SPACE ELEMENT

LPA Adoption June 16, 2025

John Jorgensen's Landing	1.01
Juan Ponce de León Landing Park	13.66
Judith Resnick Memorial Park	10.06
Kiwanis Park at Geiger Point	7.00
Lake Shepard Boat Ramp	.12
Lake Washington Park	26.83
Long Point Park	84.50
Max K. Rodes Park	134.38
Micco Park	9.27
Pineda Causeway	.97
POW/MIA Park	4.90
Police Foundation Park	6.34
Rotary Park at Suntree	10.36
Sarno Lakes	41.25
Seagull Park	1.60
South Beach Community Park	65.65
South Mainland Community Center—Micco	10.38
South Patrick Community Park	8.12
Spessard Holland North Beach Park	9.25
Spessard Holland South Beach Park	5.25
S.P.R.A. Park	.83
Viera Regional Park	124.62
Wickham Park	476.27

RECREATION AND OPEN SPACE ELEMENT

LPA Adoption June 16, 2025

<i>Beach Access Sites</i>	<i>5.57</i>
---------------------------	-------------

Total ALOS Park Acreage—South Area —1,270.87

Total ALOS Park Acreage

Unincorporated Brevard County —4,801.98

RECREATION AND OPEN SPACE ELEMENT

LPA Adoption June 16, 2025

CHAPTER PART IV

HISTORIC PRESERVATION ELEMENT

TABLE OF CONTENTS

Historical Resource Inventory.....	1
Preservation of Historical Resources.....	5
Public Awareness.....	10
Public and Private Partnerships.....	11
Historical Homes	11

GOALS, OBJECTIVES, AND POLICIES

GOAL HP

Identify, protect, preserve, recognize, and mitigate impacts upon the resources which are significant in terms of historic, archaeological, architectural, and cultural values, and serve as reminders of Brevard County's heritage.

Historical Resource Inventory

Objective HP 1

Brevard County will continue to develop and maintain an inventory of the resources which are significant in local, state and national history.

Policy HP 1.1

A survey of historic resources will continue to be supported and conducted by Brevard County.

Criteria:

- A. As a first priority, areas should be surveyed that are experiencing or are anticipated to experience pressures for development.
- B. Both reconnaissance or intensive survey efforts shall be conducted by professionals with expertise in historic resource survey work.
- C. The public should be encouraged to participate in these survey efforts, by submitting known locations of historic resources to increase public support for preservation and to reduce survey costs.
- D. Information on those resources identified as historically significant shall be submitted to the Florida Division of Historical Resources for inclusion in the Florida Master Site File. Sites or properties deemed significant or potentially significant should be proposed for listing in the National Register of Historic Places.
- E. Information obtained from these surveys shall be utilized in the development of appropriate historic preservation measures for Brevard County.

Policy HP 1.2

Historic sites and landmarks should be identified and evaluated for significance in local, state, and national history utilizing the minimum criteria below:

Criteria:

- A. Character, interest, or value as part of the development, heritage or cultural characteristics of an area;

HISTORIC PRESERVATION ELEMENT

- B. Location or site of a significant historic event;
- C. Identification with a person or persons of historical fame, or who have significantly contributed to the culture and development of an area;
- D. Exemplification of the cultural, economic, social, or historic heritage of an area;
- E. Portrayal or exemplification of the environment of a group of people in an era of history characterized by a distinctive architectural style;
- F. Embodiment of distinguishing characteristics of an architectural type or specimen;
- G. Identification as the work of an architect or master builder whose individual work has influenced the development of an area;
- H. Embodiment of elements of architectural design, detail, materials, or craftsmanship that represent a significant architectural innovation or style;
- I. Relationship to other distinctive structures, properties, or areas that are eligible for preservation according to a plan based on a historical, cultural, or architectural motif;
- J. Unique location or singular physical characteristic representing an established and familiar visual feature of an area;
- K. Religious properties deriving primary significance from architectural or artistic distinction, or historical importance;
- L. A building or structure removed from its original location, but which is significant primarily for architectural value, or which is the surviving structure most importantly associated with a historic person or event;
- M. A birthplace marker or grave of a historical figure of outstanding importance if there is no appropriate site or building directly associated with his or her life;
- N. A cemetery which derives its primary significance from graves of persons of historic importance, from age, from distinctive design features, or from association with historic events;

HISTORIC PRESERVATION ELEMENT

- O. A reconstructed building when accurately executed in a suitable environment and/or presented in a dignified manner as part of a restoration master plan, and no other building or structure with the same association has survived;
- P. A property primarily commemorative in intent if design, age, tradition, or symbolic value has invested it with its own exceptional importance;
- Q. A property achieving significance within the past fifty years if it is of exceptional importance; and
- R. A property, structure, or group of structures that represent the qualities and characteristics of a particularly fine or unique example of a utilitarian purpose, and having a high level of architectural integrity or significance. Examples include but are not limited to farmhouses, barns, citrus packing houses, gasoline stations, and other commercial structures.

Policy HP 1.3

Archaeological resources shall be identified and evaluated for significance utilizing the minimum criteria below:

Criteria:

- A. An important historical event, person, or group of people was associated with the site;
- B. The quality of the site or the data recoverable from the site is of sufficient significance that it would provide unique information on prehistoric or historical events;
- C. The site was the focus of discrete types of activities such as habitation, religious practice, burial, fortification, etc.;
- D. The site was the location of historic or prehistoric activities during a particular period of time; and
- E. The site maintains a sufficient degree of environmental integrity to reflect some aspect of the relationship of the site's original occupants to the environment.

Policy HP 1.4

Maintain a Local Register of Historic Places to recognize those historic resources that may be ineligible for state or national listing but are significant in Brevard County's history.

Criteria:

HISTORIC PRESERVATION ELEMENT

- A. The criteria for determining historic and archaeological significance, as listed under Policies 1.2 and 1.3 of this element should be used to guide the selection of properties for the Local Register.
- B. The County Historical Commission should coordinate this effort with the County Historic Preservation Officer, municipalities, local historical societies, local arts councils, and museums.
- C. Official listing on the Local Register shall be at the will of the property owner; however, serious efforts shall be taken to encourage property owners to include their properties on the Local Register. Property owners shall retain the right to remove their property from the Local Register, providing no public financial or other incentives have been received for the preservation of the historic resource on that property.

Policy HP 1.5

Develop a computerized inventory of the buildings, structures, districts, sites, objects, and places in the County which are designated as being historically significant.

Criteria:

- A. Resources listed on the National Register of Historic Places, the Florida Master Site File, and the Local Register of Historic Places shall be included in the inventory.
- B. Locally significant historic resources should be included to recognize those not eligible for national or state recognition in and of themselves.
- C. Historic resources should be classified according to their period, functions, and characteristics, to aid in proper and adequate information filing, storage, and retrieval.

Policy HP 1.6

Maintain a campaign to encourage property owners to provide information for the Florida Master Site File, and to prepare nomination forms for historic resources that may be eligible for listing in the National Register of Historic Places or the Local Register of Historic Places.

Criteria:

- A. Technical assistance in the completion of the nomination forms should be provided by the Florida Bureau of Historic Preservation, the County Historical Preservation Officer, and the County Historical Commission.
- B. The municipalities, private businesses and industries, local historical societies, local arts councils, schools, and museums should be encouraged to participate in this campaign which will strengthen community pride,

HISTORIC PRESERVATION ELEMENT

increase tourism opportunities, and enhance the preservation of the historic resources.

Policy HP 1.7

The identification and evaluation of all historic resources shall be coordinated with the Florida Division of Historical Resources to ensure that these efforts are conducted in an appropriate and efficient manner.

Policy HP 1.8

Brevard County shall coordinate the collection, preservation, and maintenance of historical records, in accordance with federal and state standards, as may be applicable.

Preservation of Historical Resources

Objective HP 2

Brevard County should adopt and implement measures for the protection and preservation of the historic resources in the County.

Policy HP 2.1

The County should facilitate the adoption of a historic preservation ordinance to provide appropriate protection for significant historic resources.

Criteria:

- A. The ordinance should provide protection for the resources listed on the National Register of Historic Places, the Florida Master Site File, the Local Register of Historic Places, and those to be discovered in the future.
- B. The ordinance should outline standards for the identification and evaluation of historic resources.
- C. The ordinance should establish a review board to be responsible for evaluating development proposals for their impact on historic resources. Representatives should be appointed to this board based upon their knowledge in dealing with both historical structures and archaeological sites. A County Historic Preservation Officer should be designated to serve as staff to this board.
- D. The ordinance should establish procedures for the review of all development and redevelopment proposals, including those for infrastructure, for the impact upon designated historic resources. Alterations to these resources should also be reviewed prior to approval. The Standards for Rehabilitation of the Secretary of the U.S. Department of the Interior should be used in the review of alterations to historic buildings.

HISTORIC PRESERVATION ELEMENT

Policy HP 2.2

Upon adoption of the historic preservation ordinance, Brevard County shall pursue certification of the ordinance from the U.S. Department of the Interior.

Policy HP 2.3

All public and private development and redevelopment proposals, including those for infrastructure, should be reviewed for the impact upon designated historic resources.

Criteria:

- A. The resources designated as being historically significant are those on the National Register of Historic Places, the Florida Master Site File, the Local Register of Historic Places, and those to be discovered in the future.
- B. If a determination is made that there will be a potentially negative impact to a historic resource, the County shall notify the Florida Division of Historical Resources and the County Historic Preservation Officer.
- C. Every effort shall be taken to preserve the resource. Where preservation is not a feasible alternative, the resource shall be relocated, information regarding the resource shall be recorded, or elements of the resource shall be salvaged for further study.

Policy HP 2.4

Public and private development and redevelopment activities, including those for infrastructure, shall cease where artifacts of historical or archaeological significance are discovered to allow for an evaluation of historical significance.

Criteria:

- A. Immediately upon discovery, notification shall be given to the Florida Division of Historical Resources and the County Historic Preservation Officer.
- B. Ground disturbing activities shall be suspended within 20 feet of the discovery for up to 30 days from the day of notification to allow for an initial evaluation of significance. If the resource is found to be potentially significant, activities shall be further suspended for up to 30 days to allow for further evaluation. Ground disturbing activities shall be undertaken with caution in the surrounding area. Efforts shall be taken to evaluate the site in a timely and reasonable manner. The property owner should be allowed to hire a professional archaeologist to evaluate the site.
- C. Where the discovery is determined to be historically significant, every effort should be taken to preserve the resource. Where preservation is not a feasible alternative the resource should be relocated, information regarding the resource should be recorded, or elements of the discovery should be

HISTORIC PRESERVATION ELEMENT

salvaged for further study. Funding for these efforts should be supported by the public sector, where financially feasible, and through voluntary support from the private sector. The County should encourage private participation in these efforts through incentives.

Policy HP 2.5

Develop a transfer of development rights program that would encourage the protection of historic resources from the potential impacts of development and redevelopment.

Policy HP 2.6

Brevard County shall utilize the Standards for Rehabilitation of the Secretary of the U.S. Department of the Interior, as amended, for all rehabilitation projects subsidized by public funds and should facilitate proposals that encourage their use in private rehabilitation efforts through investment tax credits or other incentives.

Criteria:

- A. Every reasonable effort shall be made to provide a compatible use for a property which requires minimal alteration of the building, structure, or site and its environment, or to use a property for its originally intended purpose.
- B. The distinguishing original qualities or character of a building, structure, or site and its environment shall not be destroyed. The removal or alteration of any historic material or distinctive architectural features should be avoided when possible.
- C. All buildings, structures, and sites shall be recognized as products of their own time. Alterations that have no historical basis and which seek to create an earlier appearance shall be discouraged.
- D. Changes which may have taken place in the course of time are evidence of the history and development of a building, structure, or site and its environment. These changes may have acquired significance in their own right, and this significance shall be recognized and respected.
- E. Distinctive stylistic features or examples of skilled craftsmanship which characterize a building, structure, or site shall be treated with sensitivity.
- F. Deteriorated architectural features shall be repaired rather than replaced, whenever possible. In the event replacement is necessary, the new material should match the material being replaced in composition, design, color, texture, and other visual qualities. Repair or replacement of missing architectural features should be based on accurate duplications of features, substantiated by historic, physical, or pictorial evidence rather than on

HISTORIC PRESERVATION ELEMENT

conjectural designs or the availability of different architectural elements from other buildings or structures.

- G. The surface cleaning of structures shall be undertaken with the gentlest means possible. Sandblasting and other cleaning methods that will damage the historic building materials shall not be undertaken.
- H. Every reasonable effort shall be made to protect and preserve archaeological resources affected by or adjacent to any project.
- I. Contemporary design for alterations and additions to existing properties shall not be discouraged when such alterations and additions do not destroy significant historical, architectural, or cultural material, and such design is compatible with the size, scale, color, material, and character of the property, neighborhood, or environment.
- J. Whenever possible, new additions or alterations to structures shall be done in a manner that if such additions or alterations were to be removed in the future, the essential form and integrity of the structure would be unimpaired.

Policy HP 2.7

Support modifications to the State enabling legislation to encourage the rehabilitation of historic buildings by the private sector.

Policy HP 2.8

Efforts should be taken to protect the designated historic resources from vandalism and destruction.

Criteria:

- A. Exact locations of known archaeological resources shall not be publicized to protect these resources from harm.
- B. Publicly-owned or maintained resources should be protected with appropriate security devices and private property owners should be encouraged to do the same.

Policy HP 2.9

The responsibilities of the County Historical Commission should be expanded to more fully involve the Commission in the implementation of the directives of this element.

Criteria:

- A. The Board of County Commissioners should appoint three members to the Historical Commission for each district. Members should be appointed based upon their knowledge in dealing with historic and archaeological resources. Expertise in the fields of anthropology, archaeology,

HISTORIC PRESERVATION ELEMENT

architecture, civil engineering, history, law, and planning should be considered.

- B. The Historical Commission should be provided adequate office space and access to County staff as necessary. All actions of the Historical Commission shall be coordinated through the County Historic Preservation Officer.
- C. The Historical Commission shall be responsible for the preparation of an annual report of their activities for presentation to the Board.

Policy HP 2.10

Encourage the private sector to utilize easements or deed restrictions, or to donate property to assist in the protection of historic resources.

Policy HP 2.11

Brevard County shall support efforts to encourage the municipalities within the County to adopt historic preservation ordinances or other preservation measures.

Policy HP 2.12

Brevard County should pursue Certified Local Government status from the State and the U.S. Department of the Interior in recognition of the County's commitment to historic preservation.

Policy HP 2.13

Brevard County shall work with and support the efforts of the Federal, State, and local agencies and organizations involved in historic preservation.

Criteria:

- A. Federal agencies and organizations include the U.S. Department of the Interior, National Park Service, National Aeronautics and Space Administration, National Trust for Historic Preservation, and the Society of Professional Archaeologists.
- B. State agencies and organizations include the Division of Historical Resources of the Florida Department of State, Florida Trust for Historic Preservation, Florida Archaeological Council, Florida Historical Society, Florida Anthropological Society, Florida Folklore Society, and the Florida Academy of Sciences.
- C. Local agencies and organizations include the County Historical Commission, Grant Historical Society, South Brevard Historical Society, Indian River Anthropological Society, Brevard Museum, and the Brevard Arts Council.

HISTORIC PRESERVATION ELEMENT

Public Awareness

Objective HP 3

Brevard County shall increase the public's knowledge and appreciation of the County's historic resources and preservation activities.

Policy HP 3.1

Facilitate the preparation and distribution of information or materials that increase the public's knowledge and appreciation of the County's heritage.

Criteria:

- A. Information should be provided on the County's history.
- B. A variety of resources should be considered including pamphlets, brochures, newspaper articles, photo exhibits, video tapes, cassette tapes, and radio and television broadcasts.
- C. Information should be made available to the public in a variety of locations including the Brevard County Service Complexes, County libraries, Tourist Development Office, schools, colleges and universities, recreational facilities, senior centers, museums, Brevard Arts Council, Brevard Economic Development Council Office, chambers of commerce, and city halls.

Policy HP 3.2

Maintain and support a local historic landmark program to recognize the significant historic resources in Brevard County.

Criteria:

- A. Landmarks should recognize the resources listed on the National Register of Historic Places, Florida Master Site File, and Local Register of Historic Resources. However, exact locations of known archaeological resources should not be identified where proper security cannot be provided.
- B. Informational materials should be prepared and made available to the public to promote the local historic landmark program. The materials should identify contact persons if further information is desired.
- C. The landmark program should be coordinated with the municipalities, local historical societies, local arts councils, museums, private businesses and industries, and interested individuals.

Policy HP 3.3

Brevard County should provide information regarding the County's historic preservation programs to interested groups and organizations in an effort to increase public awareness of the County's heritage and commitment to preservation.

HISTORIC PRESERVATION ELEMENT

Policy HP 3.4

A collection of historic preservation publications should be developed, maintained and made available to the public.

Criteria:

- A. The collection should be centrally located and administered by the County Historic Preservation Officer.
- B. Copies of selected publications should also be provided to the County libraries.

Public and Private Partnerships**Objective HP 4**

Brevard County should increase the level of funding for historic preservation through mechanisms that involve both the public and private sectors.

Policy HP 4.1

Brevard County shall pursue the Federal and State Historic Preservation Grants-in-Aid funding to support the efforts to identify, evaluate, protect, and preserve its historic resources and support public education programs.

Policy HP 4.2

As a part of the "Historic Brevard!" campaign, seek contributions from private businesses, industries, foundations, and civic organizations to support the historic preservation efforts throughout the County.

Policy HP 4.3

Utilize volunteers, where feasible, in all aspects of the historic preservation program to involve interested individuals with knowledge of local historic resources.

Policy HP 4.4

Allocate portions of the Tourist Development Tax funding to support the County's historic preservation efforts, in recognition of the positive impact of historic preservation upon tourism.

Historical Homes**Objective HP 5**

Brevard County shall increase the knowledge and appreciation of the historically significant housing in Brevard County through measures which identify, preserve, protect, and educate the community about the heritage of such housing.

HISTORIC PRESERVATION ELEMENT

Policy HP 5.1

Brevard County should continue to implement the policies of the Historic Preservation element of the Comprehensive Plan regarding the identification, evaluation, protection, and preservation of the housing which is historically significant, including those listed within the following databases when established:

Criteria:

- A. National Register of Historic Places;
- B. Florida Master Site File; or
- C. Local Register of Historic Places

Policy HP 5.2

Brevard County should provide technical assistance to owners of historically significant housing or other individuals that are interested in preservation activities.

Criteria:

- A. Assistance to be provided should include, but not be limited to, that for the preparation of National Register and Florida Master Site File nomination forms, preparation of grant applications, and the identification of historic resources.
- B. Assistance should also be provided in the interpretation and application of the Historic Preservation element of this Comprehensive Plan and any regulations prepared pursuant to that element.

Policy HP 5.3

Pursue available Federal, State, and local funding sources to support efforts to preserve or protect historically significant housing.

Criteria:

- A. At a minimum, applications should be made for the Historic Preservation Grants-in-Aid program administered by the Division of Archives, History and Records Management of the Florida Department of State.
- B. Appropriate activities eligible for grant funding are classified as Acquisition and Development or Survey and Planning activities (Chapter 1A-34, F.A.C.). Emphasis should be placed on surveys and evaluations of historic resources, research efforts to study the effectiveness of preservation programs and techniques, and on community relations and education programs.

HISTORIC PRESERVATION ELEMENT

CHAPTER PART V

HOUSING ELEMENT

TABLE OF CONTENTS

Affordable Housing	2
Housing Programs Awareness	8
Equal Housing Opportunities	9
Adequate Residential Choices	9
Residential Environments	11
Residential Types	14
Public and Private Partnerships	14
Historic Housing Preservation	15

GOALS, OBJECTIVES, AND POLICIES

GOAL HOU 1

To produce and preserve affordable homeownership and multifamily housing. To benefit very low, low, and moderate income residents of Brevard County.

Affordable Housing

Objective HOU 1.1

Brevard County should act within its authority to substantially increase the supply of affordable housing through implementation of programs that meet the needs of eligible households . Eligible households are determined by HUD, as adjusted for family size.

Policy HOU 1.1.1

Brevard County has established the following as the definitions of for affordable and workforce housing:

Criteria:

- A. ~~Brevard County defines Affordable Housing as a single or multi-family owner occupied or rental housing unit that has a gross household income at or below 120% of the Area Median Income (AMI), as adjusted for family size; Affordable Housing means that monthly rents or monthly mortgage payments including taxes, insurance, and utilities do not exceed 30 percent (20 percent for Affordable Workforce Housing) of that amount which represents the percentage of the median adjusted gross annual income for the households as “extremely low-income persons”, “low-income persons”, “moderate-income persons”, or “very-low-income persons” as further described in section 420.004 F.S. Housing costs include: contract rent and utilities; and payment of principal, interest, taxes, and insurance for owner-occupied units.~~
- B. ~~Brevard County defines Workforce Housing as a single or multi-family owner occupied or rental housing unit that has a gross household income at or below 140% of the Area Median Income (AMI), as adjusted for family size. Workforce housing means a single-family owner occupied, or multi-family owner occupied, or rental unit, that has a mortgage or rental payment, including utilities, not exceeding 20 percent of the annual gross income of households at or below 140 percent of the area median income (AMI), as adjusted for family size. Affordable Workforce Housing means housing that is affordable to a person who earns less than 120 percent of the area median income, or less than 140 percent of the area median income if located in a county in which the median purchase price for a single-family existing home exceeds the statewide median purchase prices as determined in the Florida~~

HOUSING ELEMENT

[Sales Report, Single-Family Existing Homes, released each January by the Florida Association of Realtors and the University of Florida Real Estate Research Center. {Ref section 380.0651\(1\)\(h\), F.S.}](#)

- C. ~~Housing costs include: contract rent and utilities; and payment of principal, interest, taxes and insurance for owner occupied units.~~ [Extremely-Low-Income Persons, as defined in section 420.0004, F.S., means one or more natural persons or a family whose total annual household income does not exceed 30 percent of the median annual adjusted gross income for households within the state. The Florida Housing Finance Corporation may adjust this amount annually by rule to provide that in lower income counties, extremely low income may exceed 30 percent of area median income and that in higher income counties, extremely low income may be less than 30 percent of area median income.](#)
- D. ~~Low-Income Persons, as defined in section 420.0004, F.S., means one or more natural persons or a family, the total annual adjusted gross household income of which does not exceed 80 percent of the median annual adjusted gross income for households within the state, or 80 percent of the median annual adjusted gross income for households within the metropolitan statistical area (MSA) or, if not within an MSA, within Brevard County, whichever is greater.~~
- E. ~~Moderate-Income Persons, as defined in section 420.0004, F.S., means one or more natural persons or a family, the total annual adjusted gross household income of which is less than 120 percent of the median annual adjusted gross income for households within the state, or 120 percent of the median annual adjusted gross income for households within the metropolitan statistical area (MSA) or, if not within an MSA, within Brevard County, whichever is greater.~~
- F. ~~Very-Low-Income Persons, as defined in section 420.0004, F.S., means one or more natural persons or a family, not including students, the total annual adjusted gross household income of which does not exceed 50 percent of the median annual adjusted gross income for households within the state, or 50 percent of the median annual adjusted gross income for households within the metropolitan statistical area (MSA) or, if not within an MSA, within Brevard County, whichever is greater.~~

Policy HOU 1.1.2

Newly constructed dwelling units shall comply with the requirements of the 5th-Edition 2014 Florida Building Code as published by the Southern Building Code Congress International, as amended from time to time.

HOUSING ELEMENT

Policy HOU 1.1.3

Brevard County should increase the supply of affordable housing within the County by utilizing the following strategies for eligible households based upon available funding:

Criteria:

- A. Utilize federal, state, and local sources of funding, ~~when available~~, to enable ~~low income families~~ eligible households to purchase their first homes through down-payment assistance, interest buy-downs, and/or other financing.
- B. Provide housing counseling assistance to prospective first time homebuyers.
- C. Provide counseling to home owners who are in danger of mortgage default or who may require special assistance in obtaining other aid, ~~as funding allows~~.
- D. Ensure that homes purchased through Brevard County Purchase Assistance Program are in compliance with applicable building codes or standards.
- E. Encourage mortgage lenders to invest in housing for low and very low income families.
- F. Encourage mortgage lenders to investigate and utilize existing programs, such as Fannie Mae, for low income homebuyers.
- G. Forge public - private partnerships to facilitate a community based first time homebuyers' program.
- H. Increase developer awareness of federal and state sources of loans and grants for rental property rehabilitation and construction.
- I. Provide technical assistance to owners, developers, and potential developers of affordable housing.
- J. Recruit, identify, and develop partnerships with non-profits to develop capacity for successful rehabilitation/construction, and management of affordable units.
- K. Review the County's permitting process on a continual basis and conduct pre-application meetings with affordable housing developers.
- L. Continue to utilize a joint review of development plans at scheduled meetings to expedite the permitting process.

- M. Establish and maintain the Affordable Housing ~~Council~~ Advisory Committee, pursuant to Florida Statute 420.9076, as part of the process by which each new proposed regulation will be reviewed for its impact upon housing.

Policy 1.4

~~————Brevard County shall define 'significant economic impact(s)' which result from regulation, and require each new proposed regulation to be reviewed and evaluated accordingly. Brevard County shall include the Housing and Human Services Department, Affordable Housing Council, Planning and Development and other Departments as needed in the process by which each new proposed regulation will be reviewed for impact of cost upon housing. The Affordable Housing Council will weigh that cost impact against the quality of life aspects of the regulations' intent and purpose.~~

Policy HOU 1.1.54

The Housing and Human Services Department should focus on the development and rehabilitation of housing which is affordable to low income households.

Policy HOU 1.1.65

Brevard County shall ~~continue to~~ identify and establish, as appropriate, ~~a local funding source~~ sources to assist in the provision of ~~very low income housing, including affordable housing for eligible households and~~ housing for households with special housing needs. This funding source shall be a stable, consistent and broad-based financial resource.

Criteria:

- A. ~~The following funding~~ Funding sources, when available, ~~should~~ include, but are not ~~be~~ limited to:
1. Public Housing Authorities
 2. Community Development Block Grant Program
 3. Community Reinvestment Act
 4. State Housing Initiatives Partnership (SHIP) Program
 5. Rural Development
 6. HOME Investment Partnership Program
 7. Florida Housing Finance Corporation
 8. Brevard County Housing Finance Authority
 9. Non-profit Organization
 10. Tax Increment Financing
 11. Interest on Real Estate Escrow Accounts
 12. General Obligation Bonds
 13. Housing Finance Authority Reserves
 14. Private Investments
 15. Tax Credit Program
 16. Local Option Sales Tax
 17. Property Tax Relief

HOUSING ELEMENT

Policy HOU 1.1.76

Identify public or private vacant lands or structures that would be suitable for the location of housing affordable to very low income households or to meet the needs of the homeless and identify the funding sources for an acquisition and development program.

Criteria:

- A. Suitable locations should be conveniently located to the essential public facilities and services, employment centers, shopping, mass transit, schools, health services, and other community services.
- B. Such locations should be residential in character, with a variety of locations being available throughout the County so as not to cluster this development in limited locations.

Policy HOU 1.1.87

Housing and Human Services Department will ~~support and provide input to~~ collaborate with entities that provide services to the homeless in order to determine the need for temporary shelters and transitional housing so as to target ~~available~~ available funding, when available, to these areas.

Policy HOU 1.1.98

As a part of Development of Regional Impact reviews, Chapter 380, F.S., Brevard County should review these proposals with respect to the impact upon the need for affordable housing for very low and low income households within the County and East Central Florida Region.

Policy HOU 1.1.109

Brevard County encourages Developments of Regional Impact (DRI's) to incorporate affordable and workforce housing within the boundaries of the project. Developers will be encouraged to meet with County staff to discuss opportunities for including affordable and workforce housing in their project through a Community Benefits Agreement for the provision of such housing.

Policy HOU 1.1.1110

Brevard County shall continue to encourage the use of the Affordable and Workforce Housing Incentives sections of the County Land Development Regulations.

Policy HOU 1.1.1211

The Board of County Commissioners and respective County departments and agencies recognize that affordable/workforce housing is a vital component of the local economy and will participate in solution oriented efforts to facilitate, preserve, and increase affordable and workforce housing inventory.

Policy HOU 1.1.~~13~~12

The County, when funding is available, will continue to offer down payment assistance to ~~very low, low and moderate income homebuyers~~ income-eligible households.

Policy HOU 1.1.~~14~~13

The County shall use the existing Workforce and Supportive Housing Trust Fund, and proceeds from Board of County Commissioners authorized dedicated funding sources, to generate revenues for the provision of affordable/workforce housing by the private and non-profit sectors.

Policy HOU 1.1.~~15~~14

The County shall continue to provide local regulatory incentives through the State Housing Initiatives Partnership (SHIP) Local Housing Assistance Plan and other programs and opportunities for affordable housing, and eliminate disincentives that negatively affect housing costs and supply in the private and non-profit sectors, consistent with state statutes. These incentives shall be annually reviewed by the Affordable Housing ~~Council~~ Advisory Committee, and forwarded with any recommendations to the Board of County Commissioners.

Policy HOU 1.1.~~16~~15

The County shall review its Building Code, Land Development and Zoning Regulations to identify, modify, or eliminate those regulations and/or procedures that unnecessarily increase the cost of housing.

Policy HOU 1.1.~~17~~16

The County shall analyze the effect impact fees and concurrency will have on affordable housing and evaluate, if appropriate, methods that could be used to reduce identified adverse impacts.

Policy HOU 1.1.~~18~~17

The County shall further evaluate, and if appropriate adopt, local regulatory incentives in the Zoning and Land Development Regulations, including, but not limited to, transfer of development rights, density bonuses, and other similar incentives.

Policy HOU 1.1.~~19~~18

The County shall maintain, develop, and review procedures to expedite review of affordable housing developments and housing for essential employees and special needs groups within its Land Development Regulations.

Housing Programs Awareness

Objective HOU 1.2

Brevard County shall increase the public's awareness of housing programs and activities, especially those which target very low income households through effective marketing of available programs.

Policy HOU 1.2.1

The Housing and Human Services Department should maintain a list of the various housing programs and opportunities that are available from the public and private sectors and ensure that this information is readily available to the public.

Policy HOU 1.2.2

A Housing Resource webpage and brochure will be available to provide information; on the housing assistance programs.

Policy HOU 1.2.3

The Housing and Human Services Department should maintain information on trends and needs in the housing market to assist the participants in the housing delivery system in the provision of housing which meets the physical, economic, and social needs of the residents.

Criteria:

- A. At a minimum, information should be maintained and distributed on general housing and population characteristics, housing units by type, residential building permits by type and general location, housing vacancy rates, and land use acreage.
- B. This information should be updated in coordination with the 5 Year Consolidation Plan where possible.

Policy HOU 1.2.4

The County, when funding is available, shall provide and maintain a comprehensive and effective education program, using existing programs and resources, to prepare low-income families for homeownership and long term affordability. This program should include the following components: homebuyer education, homebuyer counseling, and mortgage default prevention counseling.

Policy HOU 1.2.5

The County shall continue to meet quarterly and coordinate County housing assistance programs with other municipal, regional, State, and Federal programs that are designed to provide housing opportunities for very low, low, and moderate income groups.

Policy HOU 1.2.6

Brevard County will encourage, whenever possible, the use of Section 3 certified and Minority Business Enterprise/Women Business Enterprise (MBE/WBE) contractors pursuant to Section 3 of the Housing and Urban Development Act of 1968 and 24CFR Part 85.36 (e) (1), respectively.

Policy HOU 1.2.7

Brevard County will affirmatively further fair housing, pursuant to Section 808(e)(5) of the Fair Housing Act (42 U.S.C. 3608(e)(5)).

Equal Housing Opportunities**Objective HOU 1.3**

Brevard County shall seek to achieve a housing market with mechanisms to ensure that the market is fair and balanced, and provides equal housing opportunity for all residents of the County.

Policy HOU 1.3.1

All housing, community development, and redevelopment activities of Brevard County shall be administered in accordance with Title VIII of the Civil Rights Act of 1968, the Florida Fair Housing Act, ~~Chapter~~ Sections 760.20 – 760.37, F.S., and a local fair housing ordinance if adopted.

Adequate Residential Choices**Objective HOU 1.4**

Brevard County shall continue to provide plan for adequate lands for residential land uses in a wide variety of housing types, housing price levels, and broad geographic choices to meet the needs of all existing and anticipated residents in the County.

Policy HOU 1.4.1

Land development regulations and Comprehensive Plan policies shall continue to designate adequate lands for residential development which allows for a variety of housing types, while providing residents with choices in residential locations. The following criteria shall apply:

Criteria:

- A. Land development regulations shall continue to designate lands for single-family, multi-family, manufactured, and mobile home residential development in a range of densities consistent with the service sectors, Future Land Use Map, and this Comprehensive Plan.

- B. Land development regulations shall continue to designate lands for residential development where the public facilities and services are available at the adopted levels of service in this Comprehensive Plan. Where public facilities are not available, residential development should only be permitted at densities which allow for self-sufficiency for water and sewer service.
- C. Land development regulations should continue to provide for a variety of minimum lot sizes, minimum floor areas, setbacks, and residential land use mixes that allow for choice in housing types, designs, and price levels.
- D. Land development regulations shall continue to provide for appropriate land use relationships to be considered in the review of development proposals to ensure land use compatibility between residential and surrounding uses.

Policy HOU 1.4.2

The Land Development Regulations should ~~allow for~~ enable affordable supportive and workforce housing ~~which is affordable to very low, low, and moderate income households,~~ to be located conveniently to major employment centers, mass transit corridors, shopping, schools, health centers, and other community facilities and services.

Policy HOU 1.4.3

The County shall update, as needed, the location evaluation matrix and needs analysis methods in the land development regulations to aid in determining favorable locations for ~~affordable/workforce~~ affordable supportive and workforce housing development and determining eligibility for funding and incentives. Current mapping resources and programs may be adopted into the Comprehensive Plan and land development regulations to help evaluate and guide in the location and development of ~~affordable/workforce~~ affordable supportive and workforce housing.

Policy 4.4

~~The County will study accessory units as a method for use by private families and individuals in the provision of affordable/workforce housing opportunities and solutions on their own properties, in areas with established infrastructure. The County will consider land development regulations and other ordinances as needed that would regulate their use as permitted by state statute.~~

Policy HOU 1.4.4

In response to a recommendation by the Affordable Housing Advisory Committee, the County will study the use of accessory dwelling units in single-family residential areas for the provision of affordable housing; and no later than 2026, the County may consider revising its land development regulations to streamline the permitting of these affordable housing options.

HOUSING ELEMENT

Policy HOU 1.4.5

The County will study and determine the opportunities for the co-location and joint use of county owned lands and facilities to provide affordable/workforce housing and discuss these opportunities with other government agencies in the County.

Policy HOU 1.4.6

As an incentive and resource the County, before eliminating residential density on County owned lands, will consider allowing a transfer of a portion of the residential development rights to an eligible receiver site, or the housing trust fund unit mitigation bank.

Policy HOU 1.4.7

The County shall, as needed, utilize the Affordable Housing/Workforce Team, per County Ordinance 62-6302(1), to monitor building and demolition permit applications, and monitor the number of housing units attributable to new construction, conversions, mobile home replacements, and removals. The Affordable Housing/Workforce Team shall include staff from the following offices and departments and include, but is not limited to: Land Development, Planning and Zoning, Natural Resources Management, Housing and Human Services, Traffic Engineering, ~~an~~ and Space Coast Transportation Planning Organization (SCTPO).

Residential Environments**Objective HOU 1.5**

~~Brevard County shall reduce the degree of~~ continue to administer housing and land use regulations to promote improved housing stock and eliminate substandard housing conditions, improve residential environments, and ensure for relocation housing or assistance to ensure that adequate housing and suitable residential neighborhoods are available for all residents of the County.

Policy HOU 1.5.1

A local minimum housing code shall be adopted, enforced, and amended as necessary; to ensure the construction and maintenance of sound, safe, and sanitary housing for the public health, safety, and welfare.

Criteria:

- A. ~~The Standard Minimum Housing Code~~ Florida Building Code shall be adopted as the local minimum housing code. Amendments may be made to this Code to meet unique circumstances in its administration in Brevard County.
- B. ~~The following codes~~ National Electric Code should also be adopted and enforced, with regard to housing construction and maintenance, and maintained through adoption of subsequent revisions~~±~~.

HOUSING ELEMENT

- ~~1.—National Electric Code~~
- ~~2.—Standard Building Code~~
- ~~3.—Standard Plumbing Code~~
- ~~4.—Standard Swimming Pool Code~~
- ~~5.—Standard Mechanical Code~~
- ~~6.—Standard Gas Code~~
- ~~7.—Standard Aluminum Code~~

Policy HOU 1.5.2

Portions of available funding in compliance with applicable regulations should be allocated to rehabilitation, reconstruction, and/or demolition of residential structures as well as to the provision, renovation, and/or reconstruction of public facilities and services which target income eligible households and neighborhoods.

Criteria:

- A. These funds shall be dedicated to improve the housing conditions and residential environments of income eligible households and neighborhoods.
- B. Public education measures shall be strengthened through affirmative outreach efforts to low income households to ensure that the persons or neighborhoods eligible for such assistance are aware of its availability and procedures for obtaining such assistance. Public workshops should be held in areas where these needs are demonstrated.

Policy HOU 1.5.3

Redevelopment plans supported by Brevard County should provide for a variety of housing types and price levels, while ensuring that such provisions do not reduce the supply of housing which is affordable to very low, low, and moderate income households.

Criteria:

- A. Redevelopment plans which will result in the displacement of households shall make advance written determination of the extent of displacement and shall provide a relocation plan with strategies for mitigation. Provisions for notice and hearing should be included.
- B. The provisions of section 421.55, F.S., and the Uniform Relocation Assistance and Real Property Acquisition Act of 1970, as amended, shall be used to guide mitigation.

Policy HOU 1.5.4

Residents who are displaced as a result of redevelopment, demolition, or other public projects shall be provided prompt equitable compensation to affected property owners or assistance in locating comparable relocation housing for displaced tenants.

Criteria:

- A. Relocation housing should be comparable to the existing dwelling as much as possible, with an emphasis on the number of rooms, size of living space, location to commercial and public facilities and place of employment, and shall be within the financial means of the displaced household. Relocation housing shall be a sound, safe, and sanitary dwelling meeting all locally adopted minimum housing codes.
- B. Relocation housing or equitable compensation shall be provided prior to the time displacement occurs.
- C. The provisions of section 421.55, F.S., and the Uniform Relocation Assistance and Real Property Acquisition Act of 1970, as amended, shall direct the fulfillment of this policy.

Policy HOU 1.5.5

In order to assist in the preservation of affordable housing unit inventory, the County may require that solution oriented relocation efforts are made by property owners, and when needed and as permitted by law, pursue mitigation solutions for the loss of affordable housing units.

Policy HOU 1.5.6

The County encourages the use and application of the Affordable and Workforce Housing Incentives Section of the County Land Development Regulations to aid in mitigation solutions related to housing displacement.

Policy HOU 1.5.7

The County, ~~as needed, will study manufactured housing, mobile home parks and subdivisions that provide affordable/workforce~~ will continue to identify ways to increase the affordable supportive and workforce housing inventory, and will consider creating solutions to help upgrade these uses while maintaining affordability. The County recognizes and will abide by the preemptions in section 723.004, F.S., that limit local government's regulation of mobile homes. The Affordable/Workforce Housing Team, the Affordable Housing ~~Council~~ Advisory Committee, and/or Legal staff will evaluate existing policies and regulations, ~~as needed~~, and develop recommendations ~~and options~~ for consideration by the Board of County Commissioners.

Policy HOU 1.5.8

Every five (5) years, The Housing and Human Services Department shall survey and report affordable housing needs through a 5 Year Consolidated Plan.

Residential Types

Objective HOU 1.6

Brevard County shall integrate care facilities, group homes, child and adolescent care facilities, and retirement homes into residential areas of the County, and provide the opportunity for these facilities to be located in a variety of urban and rural locations.

Policy HOU 1.6.1

The Group Homes Ordinance of the Land Development Regulations shall continue to allow for the location of group home facilities in all residential and other areas of the County as a permitted or conditional use, to ensure that the facility residents have access to normal residential settings.

Policy HOU 1.6.2

The Group Homes Ordinance of the Land Development Regulations shall be reviewed continually to ensure its effectiveness in integrating care facilities, group homes, child and adolescent care facilities, and retirement homes into a variety of urban and rural residential locations.

Policy HOU 1.6.3

The County Code shall continue to require compliance with Chapter 553, Florida Statutes, which requires special exterior and interior design in the construction of dwelling units to make them accessible for persons with physical or developmental disabilities and senior citizens.

Policy HOU 1.6.4

The County shall continue to support transitional housing programs and developments which will enable homeless people to live as independently as possible. The Board of County Commissioners may utilize at their discretion the reasonable accommodation standards and procedures and temporary use agreements sections of the County Code to evaluate and permit transitional and emergency housing facilities.

Public and Private Partnerships

Objective HOU 1.7

Brevard County shall increase the coordination between the public and private sector entities involved in the provision of housing, community development, and redevelopment activities.

Policy HOU 1.7.1

Brevard County Housing and Human Services Department shall coordinate with applicable private agencies and assist them in obtaining housing information, preparing

recommendations, and implementing programs and activities that would target the housing needs for the very low income households.

Policy HOU 1.7.2

The Planning and Development Department should be responsible for ensuring the review of housing, community development, and redevelopment proposals or activities for consistency with this Comprehensive Plan.

Policy HOU 1.7.3

Brevard County should initiate efforts to standardize all building and housing codes utilized by Brevard County and the municipalities within the County for efficiency in the development process.

Policy HOU 1.7.4

Review of amendments to the Housing Element of the Comprehensive Plan will be conducted by the Affordable Housing/Workforce Housing Team ~~and representatives of the Affordable Housing Council.~~

GOAL HOU 2

To identify, preserve, and protect historically significant housing.

Historic Housing Preservation

Objective HOU 2.1

Brevard County shall encourage preservation of historically significant housing.

Policy HOU 2.1.1

Brevard County shall, in coordination with the Florida Division of Historical Resources, continue to identify and encourage the preservation of historically significant housing in accordance with the Historic Preservation Element of the Brevard County Comprehensive Plan.

BREVARD COUNTY COMPREHENSIVE PLAN

CHAPTER PART VI

POTABLE WATER ELEMENT

TABLE OF CONTENTS

	Page
Goals, Objectives, and Policies	2
Appendix A: WSFWP	8
Appendix B: List of Maps	45

POTABLE WATER ELEMENT

GOALS, OBJECTIVES, AND POLICIES

GOAL PW 1

Brevard County shall pursue a potable water supply which does not deplete the freshwater resource and is safe, environmentally sound, and efficient.

Identify and Correct Existing Deficiencies

Objective PW 1

Brevard County shall identify and correct existing water facility deficiencies within its water system.

Policy PW 1.1

Development shall continue to meet the County's design and construction requirements as specified in current criteria, policies, and ordinances as approved by the Board of County Commissioners.

Policy PW 1.2

The evaluation of utility service area expansions shall be coordinated with the Future Land Use Element and Housing Element and the Planning and Development Department and Housing and Human Services Department to meet current and future demands.

Policy PW 1.3

In order to receive water service from County facilities, new development must be located within the County's existing water service area.

Policy PW 1.4

Brevard County shall evaluate all fees and rates to assure adequate funds are available to fund all current and future projects included in the Schedule of Potable Water and Sanitary Sewer Improvements in the Capital Improvements Element.

Policy PW 1.5

Brevard County shall provide adequate water treatment plant capacity to maintain the adopted level of service standard contained in the Capital Improvements Element.

Utilize Potable Water Efficiently

Objective 1 PW 2

Brevard County shall strive to utilize potable water more efficiently ~~on a per capita basis.~~

Policy 1.1 PW 2.1

Brevard County shall maintain efforts to increase public awareness and acceptance of water conservation techniques including wastewater reclamation.

Policy 1.2 PW 2.2

The County shall include ~~the following~~ provisions within Land Development Regulations ~~as they pertain to subdivision and site plan reviews in an effort to reduce per capita consumption.~~

- A. ~~New irrigation systems shall be designed to use non-potable water or reclaimed water as the source when a reclaimed water supply source is available in accordance with Potable Water Element Policy 1.4~~
- B. ~~New industrial or commercial development that does not require water meeting potable water quality standards shall be designed to use non-potable water or reclaimed water when a non-potable water or reclaimed water supply source is available in accordance with Potable Water Element Policy 1.4~~
- C. ~~New irrigation systems shall utilize micro-irrigation techniques to the greatest extent practical.~~
- D. ~~Landscaping for new development shall utilize waterwise landscaping principles including limits on the use of landscaping that requires irrigation.~~
- E. ~~Brevard County shall maintain at a minimum, but not limited to, the following practices and provisions:~~
 - a. ~~Showerhead exchange program;~~
 - b. ~~Toilet rebate program;~~
 - c. ~~Water main replacement program;~~
 - d. ~~Require low flow plumbing fixtures;~~
 - e. ~~Require dual piping for reclaimed water in reclamation areas.~~
 - f. ~~Provision of leak detection/water conservation kits;~~
 - g. ~~Provision of water conservation and restriction messages on utility bills.~~

Policy 1.3

~~The County shall strengthen and enforce the provisions found in the Brevard County Water Source Heat Pump Ordinance in an effort to protect water resources.~~

POTABLE WATER ELEMENT

Policy 1.4

The County shall identify additional reclamation zones and implement the provisions found in the Brevard County Wastewater Reuse Ordinance.

Policy 1.5 PW 2.3

~~Brevard County shall continue to collaborate with SJRWMD and consider land development regulations aimed at conserving water and reducing demand of potable water.~~ Maximize reuse of treated wastewater and water conservation techniques while maintaining an adequate reuse level of service to recover and diminish the demand for potable water.

Policy 1.6

~~Brevard County's Utility Services Department shall maintain a rate schedule of connection and service fees at an adequate level to provide necessary annual operation and maintenance funds, capital improvements, and renewal and replacement funds, for all County operated potable water systems.~~

Policy 1.7 PW 2.4

Brevard County shall conserve water by continually seeking ways to improve efficiency and resiliency in the design, maintenance, and operation of its public water facilities.

Policy 1.8

~~Brevard County shall cooperate with SJRWMD during declared water shortage emergencies by conserving water resources and assisting SJRWMD with enforcement of water shortage emergency declarations, orders, and plans (Rule 40C-21, F.A.C., SJRWMD water shortage plan).~~

Policy 1.9

~~Brevard County shall continue to implement its Water Conservation Plan submitted to SJRWMD as part of the consumptive use permitting process.~~

Water Quality Standards**Objective 2-PW 3**

All Brevard County Utilities Department public water supply systems serving Brevard County residents shall be maintained at accepted water quality standards to protect the health of the users of potable water.

Policy 2.1 PW 3.1

Brevard County shall ~~meet or exceed the~~ ensure water quality standards found in Chapter 62-550, F.A.C. ~~to provide a safe and efficient water supply for its consumers.~~

POTABLE WATER ELEMENT

Policy 2.2

Brevard County shall cooperate with the Florida Department of Environmental Protection (FDEP) to ensure that the appropriate purveyor of potable water shall notify the users of the public water supply systems when violations of water quality standards occur by following, at a minimum, the procedure found in Chapter 17-22, F.A.C.

Policy 2.3

Brevard County, municipalities, the School Board, and all primary and support agencies designated within the Brevard County Comprehensive Emergency Management Plan (CEMP), being governed by the authority of Public Law 93-288, Chapter 62-22, F.A.C., Chapter 252, F.S. and the St. Johns River Water Management District Water Shortage Plan (40C-21, F.A.C.), shall ensure the provision of potable water supplies to users of potable water within Brevard County during or after natural or man-made catastrophes.

Policy 2.4

Anyone proposing a new public water supply well shall comply with the policies contained in the Conservation Element.

Accessibility to Potable Water

Objective 3 PW 4

Ensure that the present and future population has access to potable water that is consistent with the service sectors defined in the Future Land Use Element of this Comprehensive Plan.

Policy 3.1

The following acceptable level of service standards (LOS) are hereby adopted, and shall be used as the basis for determining the availability of facility capacity and the demand generated by a development within the respective service areas. Potable water service areas are those areas depicted in Map 1:

POTABLE WATER	
SERVICE AREA	LEVEL OF SERVICE STANDARD
BCUSD	200 gal/ERC/day
Barefoot Bay Water & Sewer District	150 gal/ERC/day
City of Cocoa	340 gal/ERC/day or 122 gal/capita/day
City of Melbourne	100 gal/capita/day
City of Palm Bay	225 gal/ERC/day
City of Titusville	96.4 gal/capita/day
City of West Melbourne	210 gal/ERC/day

POTABLE WATER ELEMENT

Policy PW 4.1

Brevard County shall provide adequate water treatment plant capacity to maintain the adopted level of service standard in the Capital Improvements Element of the County's Comprehensive Plan. ~~The level of service standard for planning purposes is 220 gallons per day per equivalent residential connection (ERC) in all areas of the County potable water service area except for Barefoot Bay Water and Sewer District, which will be 150 gallons per day per ERC.~~

Policy 3.2 PW 4.2

Brevard County's ~~Water and Wastewater Division~~ Utility Services Department shall develop and implement a procedure to monitor the potable water system's level of service (LOS) status, and to determine the impact of a requested development order on available potable water capacity. ~~Consistency with the established LOS determines approval of the development order as it pertains to the Potable Water Element as it pertains to the Potable Water Element. The gallons per day criteria for residential and non-residential consumption as established by the individual water suppliers shall be used as the criteria to measure the available capacity of the applicable water treatment plant.~~

Policy 3.3

~~Recognizing that acceptable level of service standards may not be achieved in practice and to avoid the possibility of curtailment of potable water service, the Brevard County water service agency shall initiate action (including introduction into the Capital Improvement Element), utilizing a lead time based on a calculated number of years before the design capacity has been reached using the following formulas to ensure additional capacity is on-line within five years:~~

~~design capacity - actual capacity = ————— # of years to design capacity
growth rate~~

~~# years to design capacity - 5 years = ————— # of years before necessary inclusion
within the CIE~~

~~growth rate = ————— percentage capacity increase per year.~~

Policy 3.4 PW 4.3

Potable water facilities and services intended to serve future development needs that are not located in the 0-20 year future potable water service area ~~(see Map 1)~~ shall not be permitted or provided unless the potable water service area is amended ~~in the Potable Water Element of the Comprehensive Plan~~ or a non-governmental entity is the provider of the potable water facilities, so long as the private potable water service is consistent with the Brevard County Comprehensive Plan, and the Water Supply Facilities Work Plan of the County, the St. Johns River Water Management District, the City of Cocoa, the City of Melbourne, the City of Palm Bay, the City of Titusville, and the City of West Melbourne.

POTABLE WATER ELEMENT

~~Nothing in this element will prevent a private property owner from utilizing on-site water sources, such as a well, for individual and personal potable water use.~~

Necessary Facilities Provided to Meet Projections

Objective 4 PW 5

Provide the facilities necessary to meet the projected needs of the County-operated public water supply system for ~~the next twenty~~ a minimum of ten years.

Policy ~~4.1~~

~~Brevard County shall continue to implement a wellfield expansion program in order to provide an adequate and dependable water supply source to meet the current and future needs of the County-operated water system.~~

Policy ~~4.2~~ PW 5.1

Brevard County shall continue cooperative efforts with other governmental entities, both within the County and outside of the County, including regional, state and federal agencies, for the planning, implementation, and management of water resources and supplies. The County's Utility Services Department shall coordinate needs for potable water expansion with the Future Land Use Element and Housing Element.

Policy ~~4.3~~

~~For potable water uses, Brevard County should utilize the highest quality water source, whenever economically and environmentally feasible.~~

Policy ~~4.4~~

~~Brevard County shall continue to participate in the development of updates to the St. Johns River Water Management District Central Springs / East Coast Regional Water Supply Plan and any other water supply development-related initiatives facilitated by the District that would affect the County.~~

Policy ~~4.5~~ PW 5.2

The County will monitor and participate, as necessary, in its water service providers' water supply planning process to ensure that these entities account for and meet the County's current and future water needs for the respective unincorporated areas.

Policy ~~4.6~~ PW 5.3

The County shall maintain a Water Supply Facilities Work Plan (~~Work Plan~~) (WSFWP) that is coordinated with SJRWMD's Central Springs/ East Coast Regional Water Supply Plan (CSEC RWSP) Regional Water Supply Plan (RWSP). The Work Plan WSFWP and related comprehensive plan policies will be updated, as necessary, within 18 months of an update of the ~~CSEC RWSP~~ that affects the County.

Policy ~~4.7~~ PW 5.4

POTABLE WATER ELEMENT

The County's Water Supply Facilities Work Plan (2023-2035) is incorporated into the comprehensive plan as Appendix A of the Potable Water Element.

Policy ~~4.8~~ PW 5.5

The Water Supply Facilities Work Plan shall identify the traditional and alternative water supply projects and programs, along with the water conservation and reuse practices, necessary to meet existing and future water demands.

Policy ~~4.9~~ PW 5.6

The Water Supply Facilities Work Plan shall identify those projects (if any) contained in the ~~CSE~~ RWSP and selected by the County for implementation (if any).

Maximize Use of Existing Potable Water

Objective 5 PW 6

Brevard County shall maximize the use of existing potable water supplies to discourage urban sprawl and encourage efficient, sustainable development and re- development.

Policy ~~5.1~~ PW 6.1

The development and use of County-owned potable water facilities and systems shall be for the overall public benefit by providing potable water for public consumption, maximizing the efficient and effective provision of potable water and minimizing construction, operation, and maintenance costs.

Policy PW 6.2

The County shall prohibit private potable water treatment systems.

POTABLE WATER ELEMENT APPENDIX A: BREVARD COUNTY WATER SUPPLY FACILITIES WORK PLAN

February 2024

Prepared for:



Prepared by:

BONNIE LANDRY
& ASSOCIATES Professional Planning Services

Kimley»Horn
Expect More. Experience Better.

Updated February 20, 2024



EXECUTIVE SUMMARY

The purpose of the Water Supply Facilities Work Plan (WSFWP) is to establish future water demands and potential water sources and facilities to meet those demands for the 2035 planning horizon. Brevard County's WSFWP has been prepared in accordance with Section 163.3177 and Section 373.709, F.S.

Unincorporated Brevard County is served by several potable water suppliers, including the Brevard County Utility Services Department (BCUSD), the utilities of the Cities of Cocoa, Melbourne, Palm Bay, Titusville, and West Melbourne, and a number of neighborhood-scale plants. BCUSD and Municipal utilities draw and treat groundwater as well as surface water from Lake Washington and Taylor Creek Reservoir.

Brevard County's unincorporated population is projected to rise 17% to 261,809 by 2035. Most of this population growth is projected to be served by municipal water utilities and Domestic Self-Supply (DSS).

Brevard County	2020	2035	Delta	% Increase
Unincorporated Population	223,591	261,809	38,218	17.1%
BCUSD Population	17,769	20,806	3,037	17.1%
BCUSD Water Demand	1.30 MGD	1.74 MGD	0.44 MGD	34.2%

Recent historical production data from BCUSD's three Water Treatment Plants (WTP) – Mims, Barefoot Bay, and San Sebastian - shows that current potable water consumption falls well within adopted Level of Service (LOS) standards, design capacities, and Consumptive Use Permit (CUP) allocations. Further, there is adequate CUP allocation and capacity to serve projected BCUSD customer demand through 2035.

		2020	2025	2030	2035
Mims WTP	Population	7,958	8,548	8,989	9,318
	Permitted Surplus (MGD)	0.26	0.16	0.08	0.03
	Design Surplus (MGD)	1.46	1.36	1.28	1.23
Barefoot Bay WTP	Population	9,665	10,382	10,917	11,317
	Permitted Surplus (MGD)	0.34	0.25	0.18	0.13
	Design Surplus (MGD)	0.40	0.31	0.24	0.19
San Sebastian WTP	Population	146	157	165	171
	Permitted Surplus (MGD)	0.033	0.032	0.031	0.030
	Design Surplus (MGD)	0.027	0.025	0.024	0.024

The St. Johns River Water Management District's (SJRWMD) most recent 2020 Regional Water Supply Plan (RWSP) finds that traditional groundwater supply is insufficient to meet projected increasing demands region-wide. This plan highlights conservation and reuse policies to mitigate local demand.

As required by statute, this plan lists and amends as necessary Comprehensive Plan policies which coordinate the WSFWP with all applicable Elements and the SJRWMD RWSP, and also includes adopted and proposed potable and reuse water Capital Improvement Plan (CIP) projects.

TABLE OF CONTENTS

Executive Summary	2
Purpose.....	5
Introduction.....	5
Planning Period.....	5
Statutory Requirements	6
Florida Regulations for Water Supply and Facility Planning.....	6
Data & Analysis.....	7
Sources and Methods	7
Water supply Facilities Work Plan Schedules	7
Table 1 – Water Supply Facilities Work Plan Dates	7
Water Infrastructure	7
Population	8
Demand and LOS	8
Table 2 - RWSP Public Supply Population, Demand, and rate 2020-2035	8
Table 3A – Proposed BCUSD Potable Water Level of Service Standards.....	8
Table 3B – Municipal Potable Water Level of Service (LOS)	9
Table 4 – Potable Water Agreements between Brevard County and Municipal Utilities	9
Water Use Permit Information	10
Table 5 – Public Water Providers to Unincorporated Brevard County.....	10
Inventory of Existing Water Supply & Facilities	11
BCUSD Water Treatment Plants	11
Mims Water Treatment Plant (WTP) (FACID: 3050834, CUP Permit #: 233).....	11
Barefoot Bay Water Treatment Plant (WTP) (FACID: 3050057, CUP Permit #: 236).....	11
San Sebastian Water Treatment Plant (WTP) (FACID: 3054170, CUP Permit #: 1742).....	11
Municipally Owned Water Treatment Plants (WTP):	12
City of Titusville (CUP Permit #: 10647).....	12
City of Palm Bay (CUP Permit #: 202)	12
City of Melbourne (CUP Permit #: 50301)	12
City of WEST Melbourne (CUP Permit #:173509).....	12
City of Cocoa (CUP Permit #: 50245)	12
Other Large and Small Public Supply Utilities Serving Unincorporated County	13
Table 6 – Other Potable Water Suppliers to Brevard County.....	13
Unincorporated Brevard County Population Analysis	14
Table 7 – 2020 RWSP Public Supply Population Projections 2020-2035	14
Table 8 - 2023 BEBR Population Projections 2020-2035	14
BCUSD WTP Potable Water Per Capita Demand	15
Table 9A - Average Demand Per Day from MOR Data (2018-2023)	15

Table 9B - Maximum Demand Per Day from MOR Data (2018-2023)	15
BCUSD WTP Level of Service (LOS)	16
Table 10 - Current Demand Level of Service Comparison	16
BCUSD Potable Water Projections.....	16
Mims WTP Future Water Demand	17
Figure 1 - Mims WTP Future Daily Water Demand.....	17
Table 11 - Mims WTP Future Potable Water Demand (2020-2035)	17
Barefoot Bay WTP Future Water Demand.....	18
Figure 2 - Barefoot Bay WTP Future Daily Water Demand.....	18
Table 12 - Barefoot Bay WTP Future Potable Water Demand (2020-2035)	18
San Sebastian WTP Future Water Demand	19
Figure 3 - San Sebastian WTP Future Daily Water Demand	19
Table 13 - San Sebastian WTP Future Potable Water Demand (2020-2035).....	19
Potable Water Service Area Boundaries and Domestic Self-Supply.....	20
Table 14 – Brevard County Domestic Self-Supply Population and Demand 2020-2035	20
Conservation Measures	20
Table 15 - BCUSD Wastewater Flow and Reuse Information	21
SJRWMD 2020 RWSP Project Options	21
Capital Improvements	21
Table 16 - 5-Year Capital Improvement Plan Through FY 2027 – Potable and Reuse Water Projects	22
Relevant Regional Water Supply Issues.....	23
Conservation, Reuse, and Source Protection Measures.....	23
Water Conservation	24
Reuse	24
Source Protection	24
Conclusion and Recommendations	25
Existing Water Service Area Boundary Maps.....	26
Existing Reclaimed Service Area Boundary Maps.....	30
Proposed Service Area Expansion Maps.....	34

PURPOSE

The purpose of this document is to assess and plan for adequate water supply for the County's future unincorporated population. This Water Supply Facilities Work Plan (WSFWP) has been prepared in accordance with Chapter 163, Part II, Florida Statutes (F.S.) and 373.709, F.S. The F.S. requires local governments to maintain a WSFWP to assess the water supply sources and facilities necessary to meet existing and projected water use demands for a minimum planning period of 10 years in coordination with the Regional Water Supply Plan (RWSP) of their Water Management District(s). This WSFWP addresses projected supply and demand for the years 2020-2035.

INTRODUCTION

An important role of the St. Johns River Water Management District is to ensure there are adequate and sustainable water supplies to meet future needs while protecting the environment. In addressing water supply, the District divided its water supply planning into three plan areas: Central Florida Water Initiative (CFWI); Central Springs/East Coast (CSEC) Planning Area and North Florida Regional Water Supply Partnership. Brevard County is in the CSEC Regional Water Supply Plan (RWSP) area which includes all or part of six counties — Volusia, Lake, Marion, Brevard (excluding the City of Cocoa, which is included in the CFWI), Indian River and Okeechobee counties. This plan is coordinated with the CSEC 2020 RWSP and the CFWI 2020 RWSP to assess all of Brevard County including the City of Cocoa. There are six public providers of potable water for Brevard County's unincorporated areas: the Cities of Cocoa, Melbourne, Palm Bay, Titusville and West Melbourne, and Brevard County.



PLANNING PERIOD

The Planning Horizon for the Brevard Water Supply Facilities Work Plan (WSFWP) is 2020-2035. Florida Statutes require local governments plan to a 10-year horizon at minimum.

RWSPs are based on available data at the time of plan development. The base year for both the CSEC and CFWI RWSPs is 2015, which was the most current year with population and water use data available at the time the projections were developed. RWSP demand projections were based on actual use data over the 2011-2015 period to incorporate per-capita trends. For BCUSD's own Water Treatment Plants (WTP), demand projections were based on more current actual use data (2018-2023).

Pursuant to Chapter 163, F.S., local governments are required to update their WSFWP and Comprehensive Plan every 5 years, within 18 months of an update to their related Water Management District RWSP. For governments comprised of more than one RWSP area, updates must be made within 18 months of the most recent RWSP update. Brevard County is included in two RWSP areas: the CSEC, covering all of Brevard except for the City of Cocoa, and the CFWI, covering the City of Cocoa.

STATUTORY REQUIREMENTS

FLORIDA REGULATIONS FOR WATER SUPPLY AND FACILITY PLANNING

Brevard County is required by Florida Statutes to adopt a Water Supply Facilities Work Plan that complies with the following regulations for water supply and facility planning and related Comprehensive Elements:

- I. {163.3177(4)(a), F.S.}: Coordinate with the St. Johns River Water Management District Coordinate aspects of the comprehensive plan with the associated regional water supply plan and adjacent utilities.
- II. {163.3177(6)(a), F.S.}: Ensure the Future Land Use Plan is based upon availability of adequate water supplies and public facilities and services. Data and analyses demonstrating adequate water supplies and public facilities available to meet project growth demands. **(Future Land Use)**
- III. {163.3180(2), F.S.}: Consult with the water supplier, ensure adequate water supplies and potable water facilities are available to serve new development no later than the issuance by the local government of a certificate of occupancy or its functional equivalent. **(Future Land Use)**
- IV. {163.3177(6)(c), F.S.}: Work plan will cover at least a 10-year planning period to meet existing and projected demand. The work plan must address those facilities that provide service within the local government jurisdiction and include any facilities needed to develop alternative water supplies. The work plan must also identify conservation and reuse measures to meet future needs identified in the RWSP. **(Potable Water)**
- V. {163.3177(3)(a)4, F.S.}: Identify water supply capital projects over next 5 years for which the county is responsible (both publicly and privately funded) needed to achieve and maintain adopted levels of service. The projects would include funded and unfunded projects. If unfunded include the level of priority for funding. **(Capital Improvements)**
- VI. {163.3177(6)(d)3, F.S.} & {163.3167(9), F.S.}: Assess current and projected water needs and sources for at least a 10-year planning period considering existing levels of water conservation, use and protection, and applicable policies of the water management district. Address water supply sources for existing and projected water use demand. **(Conservation)**
- VII. {163.3177(6)(h)1}: Ensure internal consistency between the Comprehensive Plan and the Water Supply Plan. **(Intergovernmental Coordination)**

DATA & ANALYSIS

SOURCES AND METHODS

Population projection trends are derived from the most recent 2023 University of Florida Bureau of Economic Business Research (BEBR) reports. The Unincorporated County population is based on 2022 UF BEBR data. County-wide water demand projections are sourced from the SJRWMD CSEC 2020 RWSP and CFWI 2020 RWSP. Brevard County Utilities Services Department (BCUSD) WTP population and water demands are based on 5-year analyses of Monthly Operation Reports (MORs).

WATER SUPPLY FACILITIES WORK PLAN SCHEDULES

Municipal water utilities are planned for and managed in accordance with their respective WSWFPs. The dates of the most current Work Plan (at the time this plan was drafted) are summarized in **Table 1** below.

TABLE 1 – WATER SUPPLY FACILITIES WORK PLAN DATES

Municipal Utility	Last WSWFP
City of Cocoa	2009
City of Melbourne	2021
City of Palm Bay	N/A
City of Titusville	2023
City of West Melbourne	N/A

Due to recent changes in state law requiring regular 5-year updates to all WSWFPs, Brevard County anticipates that the less recent municipal Work Plans will be updated within the next Fiscal Year.

WATER INFRASTRUCTURE

Potable water is provided to unincorporated Brevard County by several large and small suppliers, including three (3) BCUSD Water Treatment Plants (WTP), five (5) municipal utilities, and eight (8) other suppliers comprised of mostly smaller, neighborhood-specific plants. The majority of potable water is supplied by BCUSD and Municipal utilities. Maps of the existing BCUSD and Municipal potable water utility service areas, as well as the proposed BCUSD potable water area expansion, are included in this report.

The BCUSD potable water distribution facilities include more than 121 miles of pipe ranging from smaller than 4 inches to 24 inches in diameter. Throughout the potable water service areas identified, the existing water mains are composed mostly of PVC pipe. There are also small areas of BCUSD water mains constructed of ductile iron, asbestos, or high-density polyethylene (HDPE).

Descriptions of the potable water infrastructure maintained by the municipal suppliers to unincorporated Brevard County are included in their respective Work Plans.

POPULATION

By 2035, the population of unincorporated Brevard County is projected to rise by 38,218 (+17.1%) to a total of 261,809. This population analysis can be found later in **Tables 7 and 8** of this document. This plan addresses these trends in the population projections and anticipated demands, identifying conservation initiatives to accommodate additional users while conserving water supply.

DEMAND AND LOS

The SJRWMD RWSPs analyze prior actual use data against BEBR population projections to estimate demand into the future. The most recent RWSPs estimate demand through 2040 based on use data from 2011-2015. These figures represent projections for total Public Supply demand and use rates in Gallons/Capita/Day in Brevard County, served by BCUSD, Municipal, and other large public supply utilities.

TABLE 2 - RWSP PUBLIC SUPPLY POPULATION, DEMAND, AND RATE 2020-2035

Planning Area	2020	2025	2030	2035
CSEC – Brevard PS Population	419,811	441,484	455,304	472,027
CSEC – Brevard PS Demand (MGD)	37.51	39.00	39.95	41.07
CSEC – Brevard Rate (GPCD)	89	88	88	87
CFWI – Cocoa PS Population*	190,375	199,285	206,178	211,309
CFWI – Cocoa PS Demand (MGD)*	25.13	29.91	30.82	31.49
CFWI – Cocoa Rate (GPCD)*	132	150	149	149

Sources: CSEC and CFWI 2020 RWSP; *Cocoa's utility included as it serves some unincorporated County

Level of Service (LOS) standards are adopted by Brevard County to ensure sufficient water supply for existing and future development. LOS standards are used in land use decisions to estimate increased demand from development; and they are an important measure for estimating the necessity of utility expansion. Brevard County proposes to amend its LOS standards in the Potable Water Element and Capital Improvements Element to align with current rate resolutions, shown below in **Table 3A**. Service areas are proposed to be reorganized into two groups, one comprising the Barefoot Bay Water and Sewer District service area, which also includes the San Sebastian WTP, and the other comprising all other BCUSD potable water facilities.

TABLE 3A – PROPOSED BCUSD POTABLE WATER LEVEL OF SERVICE STANDARDS

Service Area	LOS
BCUSD (Countywide)	200 GPD / ERC
Barefoot Bay Water and Sewer District	150 GPD / ERC

Source: BCUSD Rate Resolutions

To calculate per-capita rates for the following updated demand projection analysis, proposed LOS are divided by the current BEBR Average Household Size for Brevard (2.33), resulting in a per-capita LOS of 86 GPCD for BCUSD and 64 GPCD for Barefoot Bay.

Municipal Utility per capita LOS are included per their respective Comp Plans, shown in **Table 3B**.

TABLE 3B – MUNICIPAL POTABLE WATER LEVEL OF SERVICE (LOS)

Service Area	LOS (Avg Daily Demand)	LOS (Max Daily Demand)
City of Cocoa	340 GPD / ERC 122 GPCD	510 GPD / ERC
City of Titusville	96.4 GPCD	-
City of Melbourne	100 GPCD	-
City of Palm Bay	225 GPD / ERC	-
City of West Melbourne	210 GPD / ERC	575 GPD / ERC

Source: Comprehensive Plans of City of Cocoa, City of Titusville, City of Melbourne, City of Palm Bay, and City of West Melbourne

Because Brevard County cannot manage municipal utility LOS, it relies upon intergovernmental coordination to ensure sufficient facilities for unincorporated Brevard County within municipal utility service areas. Brevard County maintains agreements with municipalities for potable and wastewater services and maintains Comprehensive Plan policies outlining concurrency analysis for development decisions in municipal service areas. As specified in Intergovernmental Coordination and Capital Improvements Elements, Brevard County requires (1) written acknowledgement of sufficiency within a municipal water service area prior to permits and (2) requires availability of water service at levels within the adopted LOS prior to issuance of certificate of occupancy.

TABLE 4 – POTABLE WATER AGREEMENTS BETWEEN BREVARD COUNTY AND MUNICIPAL UTILITIES

Agreement With	Type	Established	Expiration	Recommendation
City of Cocoa	Merritt Island Agreement	1982	-	Maintain
City of Melbourne	Franchise Agreement	2000	2030	Maintain
City of Melbourne	Joint Settlement Agreement	2001	-	Maintain
City of Palm Bay	Joint Settlement Agreement	2001	-	Maintain
City of Titusville	Interconnect ILA	1997	-	Maintain
City of West Melbourne	Joint Settlement Agreement	2001	-	Maintain

WATER USE PERMIT INFORMATION

The SJRWMD issues Consumptive Use Permits (CUPs) authorizing withdrawal of ground and surface waters for public supply within Brevard County.

Table 5 below is a summary of the primary BCUSD and Municipal potable water utilities serving unincorporated Brevard County and their source allocations.

TABLE 5 – PUBLIC WATER PROVIDERS TO UNINCORPORATED BREVARD COUNTY

Provider	CUP Allocation (MGY)	Source	Permit #	Permit Expiration
Barefoot Bay WTP*	291.72	Groundwater from surficial aquifer, with backup from Upper Floridan Aquifers (UFA)	236	2029
Mims WTP*	383.3	Groundwater from surficial aquifer	233	2038
San Sebastian WTP*	29.15	Groundwater from surficial aquifer	1742	2031
City of Titusville	2,193.65	Groundwater from surficial aquifer	10647, 99052	2031
City of Palm Bay	6,267.05	Groundwater from surficial aquifer and Floridan Aquifers	202	2029
City of Melbourne	8,592.23	Surface water from Lake Washington and groundwater from the brackish Upper Floridan aquifer (UFA)	50301	2049
City of West Melbourne	1,372.40	Groundwater from the Upper Floridan Aquifers (UFA).	173509	2041
City of Cocoa	14,537.95	Surface water from the Taylor Creek Reservoir, Groundwater from the intermediate aquifer system and UFA	50245	2052

Source: OCULUS, FL Department of Environmental Protection (DEP) 2023 Current consumptive use permits

* = BCUSD Facilities

INVENTORY OF EXISTING WATER SUPPLY & FACILITIES

BCUSD WATER TREATMENT PLANTS

MIMS WATER TREATMENT PLANT (WTP) (FACID: 3050834, CUP PERMIT #: 233)

The Mims WTP is a 1.05 million gallon per day (MGD) annual average daily flow (AADF) permitted potable water treatment facility. The facility treats raw water from surficial aquifer wells located in the Mims area through aeration, lime softening, secondary clarification, tertiary filtration, and high-level disinfection to generate potable water meeting all FDEP and Potable Water criteria requirements. It has a SJRWMD CUP authorization limit of 383.3 MGY, with source water obtained from the surficial aquifer. This WTP is permitted by SJRWMD through 2038 to serve a population of 9,700.

BAREFOOT BAY WATER TREATMENT PLANT (WTP) (FACID: 3050057, CUP PERMIT #: 236)

The Barefoot Bay WTP is a 0.8 MGD AADF permitted potable water treatment facility. The facility treats raw water from surficial aquifer wells located in Barefoot Bay through softening, filtration, and primary disinfection to generate potable water meeting all FDEP and Potable Water criteria requirements. It has a SJRWMD CUP authorization limit of 291.72 MGY, with source water obtained from the surficial aquifer and Upper Floridian aquifer as a backup. This WTP is permitted by SJRWMD through 2029 to serve a population of 10,600.

SAN SEBASTIAN WATER TREATMENT PLANT (WTP) (FACID: 3054170, CUP PERMIT #: 1742)

The San Sebastian WTP is a 0.08 MGD AADF permitted potable water treatment facility. The facility treats raw water from surficial aquifer wells located at the facility through aeration and disinfection to generate potable water meeting all FDEP and Potable Water criteria requirements. It has a SJRWMD CUP authorization limit of 29.15 MGY, with source water obtained from the surficial aquifer. This WTP is permitted by SJRWMD through 2031 to serve a population of 330.

MUNICIPALLY OWNED WATER TREATMENT PLANTS (WTP):

CITY OF TITUSVILLE (CUP PERMIT #: 10647)

The City of Titusville owns 61 wells. It has a SJRWMD CUP authorization of 6.01 MGD (2,193.65 MGY) of groundwater from the surficial aquifer system and the Floridan aquifer. The city is permitted by SJRWMD through 2031 to serve a population of 63,369.

CITY OF PALM BAY (CUP PERMIT #: 202)

The City of Palm Bay owns 59 wells. It has a SJRWMD CUP authorization of 4.9 MGD of groundwater from the surficial aquifer system and 12.27 MGD of groundwater from the Floridan aquifer (6267.05 MGY total). The city is permitted by SJRWMD through 2029 to serve a population of 144,867.

CITY OF MELBOURNE (CUP PERMIT #: 50301)

The City of Melbourne owns 12 wells. It has a SJRWMD CUP authorization of 23.54 MGD (8,592.1 MGY) of surface water from Lake Washington and groundwater from the brackish Upper Floridan aquifer (UFA). The city is permitted by SJRWMD through 2049 to serve a population of 233,937.

CITY OF WEST MELBOURNE (CUP PERMIT #:173509)

The City of West Melbourne owns 5 wells. It has a SJRWMD CUP authorization of 3.76 MGD (1372.4 MGY) of groundwater from the Upper Floridan Aquifer (UFA). The city is permitted by SJRWMD through 2041 to serve a population of 41,570.

CITY OF COCOA (CUP PERMIT #: 50245)

The City of Cocoa owns 63 wells. It has a SJRWMD CUP authorization of 8.83 MGD of surface water from the Taylor Creek Reservoir, 3 MGD of groundwater from the intermediate aquifer system and 28 MGD of groundwater from the Upper Floridan Aquifer (UFA) (14,537.95 MGY total). The city is permitted by SJRWMD through 2052 to serve a population of 256,385.

OTHER LARGE AND SMALL PUBLIC SUPPLY UTILITIES SERVING UNINCORPORATED COUNTY

Portions of unincorporated Brevard County are served by other CUP-permitted suppliers listed in Table 6, the majority of which are neighborhood-scale providers.

Some larger utilities are located primarily outside Brevard County, but have service territory extensions within the unincorporated County. Farmton Services LLC is not yet active, but it will serve a portion of northwest Brevard County within the "Farmton Local Plan". Similarly, Deseret Ranches extends into western Brevard County from Orange and Osceola Counties, though the majority of its public-supply use allocation is for seasonal camp residents primarily outside of Brevard County.

SJRWMD defines "Large" suppliers as those producing at least 0.1 MGD and "Small" suppliers as those producing less than 0.1 MGD potable water. CUP allocations below reflect quantities for public supply type use only; some CUPs have additional allocations for non-potable uses such as irrigation.

TABLE 6 – OTHER POTABLE WATER SUPPLIERS TO BREVARD COUNTY

Utility	Size	CUP PS Allocation (MGY)	Source	Permit #	Permit Expiration
Farmton Services LLC*	Large	5.0 MGD	Groundwater from the Floridan aquifer	127579	2034
CSWR-Florida Utility Operating Company, LLC (aka Aquarina Utilities)	Large	156.7	Groundwater from the Upper Floridan aquifer	1719	2039
South Brevard County Utilities (aka South Brevard Water CO-OP)	Large	46.355	Groundwater from the Upper Floridan aquifer	1606	2041
South Shores Utility Assoc	Small	29.2	Groundwater from the Floridan aquifer	1749	2032
East Central Florida Services Inc (aka Deseret Ranches)	Small	16.41	Groundwater from the surficial and Floridan aquifers	3426	2032
Pelican Bay Communities LLC	Small	10.95	Groundwater from the surficial aquifer	1738	2042
River Grove mobile Home Village 1 & 2	Small	10.22	Groundwater from the surficial aquifer	1804	2024
Sebastian Inlet State Park	Small	6.95	Groundwater from the Upper Floridan aquifer	1807	2041
Summit Cove Condo Assoc	Small	3.25	Groundwater from the surficial aquifer	1808	2043

Source: Current SJRWMD CUPs; * Farmton Services LLC is not yet active and has varying annual allocations of varying sources for varying uses. 5.0 MGD is the maximum public supply type use allocation.

UNINCORPORATED BREVARD COUNTY POPULATION ANALYSIS

As required by all Comprehensive Plan amendments, the WSFWP must be based upon data relevant to Brevard County. Per Section 163.3177, F.S., comprehensive plans shall be based upon permanent and seasonal population estimates. However, RWSPs are based on the University of Florida's Bureau of Economic and Business Research (BEBR) "medium" projections as required by 373.709(2)(a)1a, F.S., and as such they do not include seasonal or other types of temporary residents.

The CSEC and CFWI RWSPs identify the "Public Supply Population" as a discrete portion of the overall population, since not all developments receive public water services. **Table 7** provides the estimated Public Supply Population in the RWSPs across the 2020 – 2035 planning horizon including customers for all BCUSD, Municipal, and other large and small public water suppliers. These projections were based on BEBR publications from 2016-2017, which were the most up-to-date reports available at that time. Note that CFWI - City of Cocoa includes a Public Supply Population larger than the municipal population, due to its utility's service to non-Cocoa areas, including portions of unincorporated Brevard County.

TABLE 7 – 2020 RWSP PUBLIC SUPPLY POPULATION PROJECTIONS 2020-2035

Public Supply Population	2020	2025	2030	2035
CSEC (Brevard)	421,797	443,557	457,385	474,114
CFWI (City of Cocoa)	190,375	199,285	206,178	211,309
Total Brevard - All RWSP	612,172	642,842	663,563	685,423
% Growth 5-Year		+ 5.0%	+ 3.2%	+ 3.3%
% Growth over 2020		+ 5.0%	+ 8.4%	+ 12.0%

Source: CSEC 2020 RWSP Appendix B; CFWI 2020 RSWP Appendices

To account for known increases in population growth trends over time since the publication of the RWSP, more recent BEBR projections are used in this WSFWP. **Table 8** provides the "Medium" BEBR growth trend projections released in April 2023 for Brevard County through 2035 and associated projections for unincorporated County population. These increased growth rates are used in the BCUSD demand projections later in this WSFWP to estimate future demand more accurately.

TABLE 8 - 2023 BEBR POPULATION PROJECTIONS 2020-2035

Brevard County	2020	2025	2030	2035
Total Population	606,612	651,600	685,200	710,300
% Growth 5-Year		+ 7.4%	+ 5.2%	+ 3.7%
% Growth over 2020		+ 7.4%	+ 13.0%	+ 17.1%
Unincorporated Population	223,591	240,173	252,558	261,809

Sources: BEBR: Projections of Florida Population by County, 2025–2050, Medium, (April 2023)

BCUSD WTP POTABLE WATER PER CAPITA DEMAND

Monthly Operation Reports (MOR) covering January 2018 – April 2023 from each Water Treatment Plant (WTP) were used to establish the rates of water demand across the populations served in each service area. These figures were based on the actual water produced by each WTP by month and include the populations served by each.

MORs were analyzed for both Average and Maximum monthly production to project both typical and maximum demands over the planning horizon.

Tables 9A and 9B analyze MOR data for each BCUSD WTP to establish Average and Maximum demand per capita per day.

TABLE 9A - AVERAGE DEMAND PER DAY FROM MOR DATA (2018-2023)

WTP	Average Month Demand (GPM)	Average Total WTP GPD	Average Per Capita GPD	Population Served	AADF Permitted (GPD)
Mims	23,723,071	780,261	99	7,947	1,050,000
San Sebastian	1,417,650	46,612	320	146	80,000
Barefoot Bay	13,998,466	461,569	48	9,636	800,000
TOTAL	39,139,187	1,288,442	73	17,729	1,930,000

TABLE 9B - MAXIMUM DEMAND PER DAY FROM MOR DATA (2018-2023)

WTP	Maximum Month Demand (GPM)	Max Total WTP GPD	Max Per Capita GPD	Population Served	Design Capacity (GPD)
Mims	28,907,000	932,484	118	7,947	2,400,000
San Sebastian	2,270,000	73,226	502	146	100,000
Barefoot Bay	18,244,000	588,516	62	9,636	1,000,000
TOTAL	49,421,000	1,594,226	91	17,729	2,700,000

**Tables 9A & 9B were calculated using maximum demand per day from January 2018-April 2023 MOR data for each BCUSD WTP.*

The per capita use rates were calculated by determining both the average and maximum volume of potable water produced by the BCUSD WTPs from January 2018 to April 2023 and dividing it by the population served. Using this method, the Mims WTP averaged 99 GPD per capita (GPCD) with a max day of 118 GPCD; the Barefoot Bay WTP averaged 48 GPCD with a max day of 62 GPCD; and the San Sebastian WTP averaged 320 GPCD with a max day of 502 GPCD. Overall, the total demand across the three BCUSD WTPs averaged 73 GPCD with a max day of 91 GPCD.

BCUSD WTP LEVEL OF SERVICE (LOS)

Brevard County has adopted Level of Service (LOS) standards to ensure sufficient water quantity for current and future development. Per the County's Comp Plan, LOS considers maximum daily demand. There are separate LOS standards for Mims and South Brevard. Mims' LOS varies across Residential and Non-Residential uses, ranging from 400 gallons per Residential Unit per day for residential uses to 250 gallons per Equivalent Unit per day for non-residential uses. Because the scope of this Work Plan contemplates per capita consumption, Brevard's per-capita LOS can be calculated using BEBR Average Household Size for Brevard (2.33), resulting in a per-capita LOS of 172 GPCD. South Brevard LOS is a standard 125 GPCD. This Work Plan defines the South Brevard region as comprising the Barefoot Bay and San Sebastian WTPs combined.

TABLE 10 - CURRENT DEMAND LEVEL OF SERVICE COMPARISON

BCUSD Service Area	Average GPCD	Max GPCD	Current Level of Service GPCD	Meets LOS?
Mims	99	118	172	Yes
South Brevard	52	68	125	Yes

**This table was calculated using maximum demand per day over 5 years of MOR data from each BCUSD WTP. LOS from Brevard County Comp Plan, adjusted with BEBR average Household Size of 2.33*

As shown, current maximum daily demand falls well below adopted LOS for both regions. It is recommended that the Comprehensive Plan be amended to revise LOS standards to reflect current ERC rate resolutions for BCUSD and Barefoot Bay Water and Sewer District.

BCUSD POTABLE WATER PROJECTIONS

BEBR population figures and projections were used to establish overall growth rates in 5-year increments through 2035. These rates as shown previously in **Table 7** are applied to each current BCUSD WTP service area population.

The projected demand is calculated by multiplying the current GPCD average and max use rates from **Tables 9A & 9B** for the existing population as of 2020 and multiplying all incremental population by adopted LOS for each service area as shown in **Table 3A**. Because LOS standards are used for concurrency planning, it is appropriate to plan for new users at those standards while assuming existing users are likely to consume at historical rates.

MIMS WTP FUTURE WATER DEMAND

FIGURE 1 - MIMS WTP FUTURE DAILY WATER DEMAND




TABLE 11 - MIMS WTP FUTURE POTABLE WATER DEMAND (2020-2035)

Year	Total Population Estimated	Average Gal. Per Capita (GPCD)	Average Day Demand (MGD)	Maximum Gal. Per Capita (GPCD)	Maximum Day Demand (MGD)	Permitted Surplus on Average Day (MGD)	Design Surplus on Max. Day (MGD)
2020	7,958	99	0.79	118	0.94	0.26	1.46
2025	8,548	104	0.89	122	1.04	0.16	1.36
2030	8,989	107	0.97	124	1.12	0.08	1.28
2035	9,318	110	1.02	126	1.17	0.03	1.23

As shown in **Table 11**, Mims WTP is projected to have an average daily demand of 1.02 MGD and a maximum daily demand of 1.17 MGD across 9,318 customers by 2035. With 1.05 MGD CUP allocation through 2038 and 2.4 MGD design capacity, It is estimated to be able to accommodate estimated demand through 2035.

BAREFOOT BAY WTP FUTURE WATER DEMAND

FIGURE 2 - BAREFOOT BAY WTP FUTURE DAILY WATER DEMAND




TABLE 12 - BAREFOOT BAY WTP FUTURE POTABLE WATER DEMAND (2020-2035)

Year	Total Population Estimated	Average Gal. Per Capita (GPCD)	Average Day Demand (MGD)	Maximum Gal. Per Capita (GPCD)	Maximum Day Demand (MGD)	Permitted Surplus on Average Day (MGD)	Design Surplus on Max. Day (MGD)
2020	9,665	48	0.46	62	0.60	0.34	0.40
2025	10,382	53	0.55	66	0.69	0.25	0.31
2030	10,917	57	0.62	69	0.76	0.18	0.24
2035	11,317	59	0.67	71	0.81	0.13	0.19

As shown in **Table 12**, the Barefoot Bay WTP is projected to have an average daily demand of 0.67 MGD and a maximum daily demand of 0.81 MGD by 2035, serving 11,317 customers. As it is currently permitted for 0.8 MGD through 2029 with a design capacity of 1.0 MGD, Barefoot Bay is projected to be able to satisfy demand through the expiration of its CUP and beyond, assuming maintained allocation.

SAN SEBASTIAN WTP FUTURE WATER DEMAND

FIGURE 3 - SAN SEBASTIAN WTP FUTURE DAILY WATER DEMAND




TABLE 13 - SAN SEBASTIAN WTP FUTURE POTABLE WATER DEMAND (2020-2035)

Year	Total Population Estimated	Average Gal. Per Capita (GPD)	Average Day Demand (MGD)	Maximum Gal. Per Capita (GPD)	Maximum Day Demand (MGD)	Permitted Surplus on Average Day (MGD)	Design Surplus on Max. Day (MGD)
2020	146	320	0.047	502	0.073	0.033	0.027
2025	157	307	0.048	476	0.075	0.032	0.025
2030	165	298	0.049	459	0.076	0.031	0.024
2035	171	292	0.050	447	0.076	0.030	0.024

As shown in **Table 13**, the San Sebastian WTP is projected to have an average daily demand of 0.050 MGD and a maximum daily demand of 0.076 MGD by 2035, serving a projected 171 residents. As it is permitted for 0.08 MGD through 2031 with a design capacity of 0.10 MGD, it can accommodate projected future demands through the expiration of its CUP and beyond, assuming maintained allocation.

San Sebastian currently exceeds South Brevard LOS. Despite the relatively small size of the San Sebastian WTP service territory, its per capita consumption is significantly higher than other BCUSD areas and in the region. This may be due to irrigation of large single-family lots, or other non-potable or non-residential uses. Water conservation measures are recommended.

POTABLE WATER SERVICE AREA BOUNDARIES AND DOMESTIC SELF-SUPPLY

This WSFWP addresses demands for potable water within the established planning horizon of 2020-2035. Demand is driven by general population growth trends and changes to utility service area boundaries. For the purposes of this Work Plan, BCUSD demand projections assume static service area boundaries. As Brevard County does not govern municipal utilities, it is possible that unincorporated areas near current municipal utility service areas may be provided service within this planning horizon. However, any service expansion is properly accounted for during the plan review process by capacity verification prior to issuance of permit and certificate of occupancy.

Portions of Brevard County do not receive potable water service by public or small utilities and are instead served by Domestic Self-Supply (DSS). These include both unincorporated and incorporated municipal areas. Per the SJRWMD Central Springs/East Coast (CSEC) 2020 RWSP, there was a DSS population of more than 41,242 in 2020 with an estimated water use of 2.80 MGD. There were no DSS attributable to Brevard County in the SJRWMD Central Florida Water Initiative (CFWI) 2020 RWSP. The projected DSS growth rate is similar to the RWSP public supply population growth rate, but it is anticipated to be reduced due to new state regulation of septic systems and extension of utilities.

TABLE 14 – BREVARD COUNTY DOMESTIC SELF-SUPPLY POPULATION AND DEMAND 2020-2035

CSEC 2020 RWSP – Brevard County	2020	2025	2030	2035
DSS Population	41,242	43,305	44,946	46,130
DSS Pop 5-Year Growth Rate	-	+ 5.0%	+ 3.8%	+ 2.6%
DSS Water Use (MGD)	2.80	2.94	3.06	3.14
DSS Use Rate (GPCD)	67.9	67.9	68.1	68.1

Source: SJRWMD CSEC 2020 RWSP Appendix B – Population and Water Demand Projections

The Indian River Lagoon Protection Program (IRLPP), established in 2023, will impact BCUSD and unincorporated County DSS. The IRLPP sets deadlines for sewer hookup or septic system upgrade within IRL Basin Management Action Plan areas, which include much of the unincorporated area surrounding existing BCUSD service territories. As such, BCUSD will begin master planning in FY 2024 to respond to this regulation. Significant service area expansions are anticipated, which will include coordination with SJRWMD for new and revised permitting.

CONSERVATION MEASURES

Although not necessary to meet projected potable water demand through 2035, Brevard County has established and continues to develop a variety of conservation programs including outreach and educational programs, irrigation restrictions, leak detection audits, and water reuse.

BCUSD's reuse water systems help to significantly offset unnecessary use of potable water for non-potable uses such as landscape irrigation. The following table displays the reuse capacity permitted for BCUSD's

wastewater treatment facilities and 10-year average daily reuse. Note that reuse demand varies by season; average daily reuse figures do not fully communicate seasonal demand highs. In dry season, demand exceeds available reuse supply.

TABLE 15 - BCUSD WASTEWATER FLOW AND REUSE INFORMATION

Wastewater Treatment Facility	Permitted Reuse (MGD)	Average Daily Flow (MGD)	Average Daily Reuse (MGD)	Reuse %
Barefoot Bay	1.041	0.700	0.538	77%
Mims (North Brevard) aka John D. Wright	2.000	0.330	0.271	82%
Port St. John	0.606	0.470	0.368	78%
South Beaches	3.000	6.400	1.446	48%*
South Central	10.700	4.003	4.003	81%
Sykes Creek	4.500	1.466	1.466	43%

Source: OCULUS, FL Department of Environmental Protection (DEP) 2023

*South Beaches reuse % based on permitted rather than total flow.

SJRWMD 2020 RWSP PROJECT OPTIONS

One important aspect of the SJRWMD RWSP updates is to organize water resource development project options, water supply development project options, and water conservation project options for the various public and large private water users in the planning regions. The Water Supply Facilities Work Plan process requires local governments include all projects identified in the RWSP that correspond to the government listed as an implementing entity.

According to the most recent CSEC 2020 RWSP, Brevard County is listed as an implementing entity for one water resource development project option: the "Brevard County Abandoned Artesian Well Plugging Program (FY 2020 – FY 2022)". This project, in partnership with the SJRWMD, provides for abandonment of artesian wells throughout Brevard County resulting in an additional water resource capacity of 4.5 MGD. This project was completed as of FY 2022.

CAPITAL IMPROVEMENTS

The County established funding plans for potable and reuse water infrastructure in the annual Capital Improvement Plan (CIP) for Fiscal Year 2022-2023 to Fiscal year 2026-2027. It is a requirement that the WSWFP include all potable water, reuse, and water conservation CIP projects. **Table 16** includes applicable BCUSD capital improvement projects included in the County's CIP and proposed projects to meet future water demand.

TABLE 16 - 5-YEAR CAPITAL IMPROVEMENT PLAN THROUGH FY 2027 – POTABLE AND REUSE WATER PROJECTS

Timeline	Project Cost	Program Name	Project Name	Project Description	Funded Program	District
Oct 2019-Sept 2027	\$11,229,439	County Water and Wastewater	Mims: Watermain Asbestos Cement Pipe	This project will replace the asbestos cement and thin-walled PVC pipe in the Mims water distribution system and includes changing over the water service connections to the new pipes.	6980111	1
Oct 2019-Sept 2024	\$3,200,500	County Water and Wastewater	Mims: Plant Additional Wells	This project consists of installing new water wells to the Mims water system. Current wells have been underperforming in their water withdrawal resulting in the installation of new wells to meet customer water demand.	6983105	1
Oct 2019-Sept 2024	\$1,600,000	County Water and Wastewater	South Central: Additional Plant Reject Pond	Install additional reject pond and pumping system north of the two existing storage ponds needed to optimize reclaimed water production at SCWWTF and provide additional capacity.	6540423	4
Oct 2019-Sept 2024	\$992,741	County Water and Wastewater	Sykes: Reclaimed Water Improvements	This is phase 1 of 3 providing necessary improvements to the reclaimed water production facility to meet future demands of a growing population in the north Merritt Island region.	6300236	2
Aug 2023-	\$50,000,000	Barefoot Bay Water and Wastewater	*PROPOSED: New Water Treatment Plant in South Brevard	This proposed project will build a new water treatment facility in South Brevard to serve customers in the Barefoot Bay and San Sebastian service areas.	N/A	3
Aug 2023-	\$65,000,000	Barefoot Bay Water and Wastewater	*PROPOSED: Barefoot Bay: South Brevard Advanced WWTP (SF 1410) (HF 1586)	This proposed project will build an advanced wastewater treatment facility to serve customers in the Barefoot Bay service area so they may switch from septic tanks to a centralized system as required by subparagraph 403.067(7)(a)9. a. of the Florida Statutes. The County has received \$1,500,000 in state allocations for this project.	N/A	3
Aug 2023-	\$45,000,000	County Water and Wastewater	*PROPOSED: Mims Water: North WTP Expansion and Potable Water Wells (SF 1629) (HF 1040)	This proposed project consists of expanding the Mims Water Treatment Plant (WTP) and installing new potable water wells in order to increase plant capacity and be able to accommodate future demand after the desired expansion of the WTP's service area. The County has received \$1,500,000 in state allocations for this project.	N/A	1

*Proposed projects related to eventual expansion of BCUSD WTPs and service areas, not obtained from Brevard County Annual CIP

RELEVANT REGIONAL WATER SUPPLY ISSUES

The SJRWMD 2020 Central Springs/East Coast (CSEC) Regional Water Supply Plan (RWSP) does foresee water quality issues impacting traditional supply region-wide, primarily due to aquifer saltwater intrusion. District UFA monitoring wells in addition to public utility well water quality monitoring reports show increasing salinity concentrations, especially along the Indian River Lagoon, likely due to lateral intrusion as well as to vertical intrusion. Lateral intrusion is mostly due to coastal geography and sea-level rise, whereas vertical intrusion is due to excessive withdrawal. The District estimates that many of these wells already do or will exceed Secondary Drinking Water Standard chloride limits by 2040, its RWSP planning horizon. While this is unlikely to result in impacts to most municipal utilities due to existing Reverse Osmosis (RO) water treatment infrastructure, increasing withdrawals may compromise water quality for neighboring DSS systems and BCUSD WTP surficial wells.

Data from Surficial Aquifer System (SAS) public supply wells show that while saltwater intrusion is increasingly compromising this resource overall, adoption and adherence to wellfield protection plans are demonstrated to reduce and even reverse chloride concentration trends, as has been demonstrated around the Titusville wellfield protection area.

Brevard County is encouraged to consider investigation of alternative water supply projects including Reverse Osmosis treatment, and to continue to adopt and expand water conservation policies, wellfield protection plans, land conservation for groundwater recharge, Low-Impact Design (LID) and Green Stormwater Infrastructure (GSI) incentives or requirements, and reuse projects in line with the SJRWMD recommendations.

CONSERVATION, REUSE, AND SOURCE PROTECTION MEASURES

Although additional measures are not necessary to meet projected potable water demand through 2035 as demonstrated previously, Brevard County has established and continues to develop a variety of water conservation, reuse, and source protection practices and programs, some of which are enabled by Comprehensive Plan policies.

WATER CONSERVATION

Water conservation is important to ensure water supply is used in a sustainable way. The County's water conservation practices include the following:

- Implementation of the BCUSD Water Conservation Plans submitted to SJRWMD as part of the Consumptive Use Permit process.
- Increasing public awareness and acceptance of water conservation techniques
- Requiring that certain irrigation systems utilize micro-irrigation techniques.
- Requiring new development to utilize waterwise landscaping principles.
- Implementation of various water conservation-related programs including the following:
 - Showerhead exchange program
 - Toilet rebate program
 - Water main replacement program
 - Requiring low flow plumbing fixtures
 - Provision of leak detection/water conservation kits
 - Provision of water conservation and restriction messages on utility bills
- Development of a water conservation program in the Code of Ordinances including plumbing feature requirements and water shortage emergency regulations
- Implementing a conservation rate structure in the Mims/North Brevard service area
- Promoting information on water conservation strategies via the BCUSD website

REUSE

Utilization of non-potable (reuse) water is important to reduce potable water demand. The County's reuse practices include the following:

- Maximizing reuse water to reduce the demand of potable water.
- Implementation of the wastewater reuse ordinance
- Requiring certain irrigation systems to be designed to use reuse water.
- Requiring dual piping for reclaimed water

SOURCE PROTECTION

Water source protection is important to ensure the sustainability of the County's water supplies. The County water source protection practices include the following:

- Implementing an aquifer protection ordinance
- Coordination with the City of Titusville on aquifer protection
- Conducting public education on importance of protecting the surficial and Floridan aquifers
- Regulating septic tanks, underground storage tanks, hazardous materials and other substances in certain aquifer recharge areas

CONCLUSION AND RECOMMENDATIONS

Unincorporated Brevard County's population is expected to increase by more than 17% cumulatively by 2035. This population will be served primarily by public supply utilities including BCUSD and municipal utilities. The BCUSD potable water customer population is expected to increase to an estimated 20,806 customers, and overall water demand will increase 34% to 1.74 MGD on average, by 2035.

	2020	2035	Delta	% Increase
BCUSD Population	17,769	20,806	3,037	17.1%
BCUSD Water Demand	1.30 MGD	1.74 MGD	0.44 MGD	34.2%


Current CUP allocations and infrastructure are projected to be sufficient to accommodate future water demands through 2035 for all three BCUSD WTPs. Portions of unincorporated Brevard County served by municipal potable water utilities are planned for in those respective WSFWPs. Concurrency for all unincorporated County development, whether served by BCUSD or other utilities, is managed during the development review process as verification of facility capacity is required prior to permit and CO issuance.

		2020	2025	2030	2035
Mims WTP	Population	7,958	8,548	8,989	9,318
	Potable Water Demand (MGD)	0.79	0.89	.097	1.02
	CUP Allocation (MGD)	1.05	1.05	1.05	1.05
	Design Capacity (MGD)	2.40	2.40	2.40	2.40
Barefoot Bay WTP	Population	9,665	10,382	10,917	11,317
	Potable Water Demand (MGD)	0.46	0.55	0.62	0.67
	CUP Allocation (MGD)	0.80	0.80	0.80	0.80
	Design Capacity (MGD)	1.00	1.00	1.00	1.00
San Sebastian WTP	Population	146	157	165	171
	Potable Water Demand (MGD)	0.047	0.048	0.049	0.050
	CUP Allocation (MGD)	0.080	0.080	0.080	0.080
	Design Capacity (MGD)	0.100	0.100	0.100	0.100

Current BCUSD potable water use falls within adopted LOS standards overall, however, despite its relatively low population, San Sebastian WTP customers exceed South Brevard LOS, where additional investigation and conservation measures are recommended. It is also recommended that Brevard County's LOS standards be revised downward to reflect actual use trends, as well as amended to include non-residential per-ERC rates for the South Brevard region to plan for other land uses.


The Brevard County Comprehensive Plan includes policies which enable coordination and implementation of this WSFWP and the SJRWMD RWSP. Additional Comprehensive Plan amendments have been proposed with this WSFWP to ensure consistency.

The 2023 Indian River Lagoon Protection Program requires expedited utility extension to unincorporated County areas. BCUSD will begin master planning to address these and other new regulations in FY 2024.



EXISTING WATER SERVICE AREA BOUNDARY MAPS

K:\TAL_Uilities\01_Production\140600 - Brevard County\003 - Brevard Water Supply Plan\Design\GIS\ArcPro_Projects\Brevard_County_ArcPro



Source: ESRI, FDOT, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Kimley»Horn

© 2022 Kimley-Horn and Associates, Inc.
2619 Centennial Boulevard, Suite 200
Tallahassee, FL 32308
Phone (850) 553-3500
www.kimley-horn.com

Existing Water Service Area Boundary (North)


**Brevard County
Utility Service Area Map**

1 inch = 4.7 miles

PROJECT NUMBER: 140600003.1.300

FEBRUARY 2024

K:\TAL_Uilities\01_Production\140600 - Brevard County\003 - Brevard Water Supply Plan\Design\GIS\ArcPro_Projects\Brevard_County_ArcPro\



Source: ESRI, FDOT, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Kimley»Horn

© 2022 Kimley-Horn and Associates, Inc.
2619 Centennial Boulevard, Suite 200
Tallahassee, FL 32308
Phone (850) 553-3500
www.kimley-horn.com

Existing Water Service Area Boundary (Central)


**Brevard County
Utility Service Area Map**

1 inch = 4.7 miles

PROJECT NUMBER: 140600003.1.300

FEBRUARY 2024

K:\TAL_Uilities\01_Production\140600 - Brevard County\003 - Brevard Water Supply Plan\Design\GIS\ArcPro_Projects\Brevard_County_ArcPro



Source: ESRI, FDOT, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Kimley»Horn

© 2022 Kimley-Horn and Associates, Inc.
2619 Centennial Boulevard, Suite 200
Tallahassee, FL 32308
Phone (850) 553-3500
www.kimley-horn.com

Existing Water Service Area Boundary (South)

**Brevard County
Utility Service Area Map**

1 inch = 4.7 miles


PROJECT NUMBER: 140600003.1.300

FEBRUARY 2024



EXISTING RECLAIMED SERVICE AREA BOUNDARY MAPS

K:\TAL_Uilities\01_Production\1406000 - Brevard County\003 - Brevard Water Supply Plan\Design\GIS\ArcPro_Projects\Brevard_County_ArcPro\



Source: ESRI, FDOT, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Kimley»Horn

© 2022 Kimley-Horn and Associates, Inc.
2619 Centennial Boulevard, Suite 200
Tallahassee, FL 32308
Phone (850) 553-3500
www.kimley-horn.com

Existing Reclaimed Service Area Boundary (North)


**Brevard County
Utility Service Area Map**

1 inch = 4.7 miles

PROJECT NUMBER: 140600003.1.300

FEBRUARY 2024

K:\TAL_Utilities\01_Production\140600 - Brevard County\003 - Brevard Water Supply Plan\Design\GIS\ArcPro_Projects\Brevard_County_ArcPro



Source: ESRI, FDOT, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Kimley»Horn

© 2022 Kimley-Horn and Associates, Inc.
2619 Centennial Boulevard, Suite 200
Tallahassee, FL 32308
Phone (850) 553-3500
www.kimley-horn.com

Existing Reclaimed Service Area Boundary (Central)


**Brevard County
Utility Service Area Map**

1 inch = 4.7 miles

PROJECT NUMBER: 140600003.1.300

FEBRUARY 2024

K:\TAL_Uilities\01_Production\1406000 - Brevard County\003 - Brevard Water Supply Plan\Design\GIS\ArcPro_Projects\Brevard_County_ArcPro



Source: ESRI, FDOT, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Kimley»Horn

© 2022 Kimley-Horn and Associates, Inc.
2619 Centennial Boulevard, Suite 200
Tallahassee, FL 32308
Phone (850) 553-3500
www.kimley-horn.com

Existing Reclaimed Service Area Boundary (South)

**Brevard County
Utility Service Area Map**

1 inch = 4.7 miles


PROJECT NUMBER: 140600003.1.300

FEBRUARY 2024



PROPOSED WATER SERVICE AREA BOUNDARY MAPS

K:\TAL_Utillities\01_Production\1406000 - Brevard County\003 - Brevard Water Supply Plan\Design\GIS\ArcPro_Projects\Brevard_County_ArcPro



Source: ESRI, FDOT, Maxar, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA, USGS, AeroGRID, IGN, and the GIS User Community

Kimley»Horn

© 2022 Kimley-Horn and Associates, Inc.
2619 Centennial Boulevard, Suite 200
Tallahassee, FL 32308
Phone (850) 553-3500
www.kimley-horn.com

Future Water Service Area Boundary (Central)

**Brevard County
Utility Service Area Map**

1 inch = 4.2 miles


PROJECT NUMBER: 140600003.1.300

FEBRUARY 2024

APPENDIX B


LIST OF MAPS

Map	Title
1	Potable Water Treatment Plants <u>North Brevard Service Area</u>
2	Existing Potable Water Customers and Future <u>South Brevard</u> Service Areas



Potable Water Element
Potable Water Treatment Plants


POTABLE WATER ELEMENT



POTABLE WATER ELEMENT


LPA Adoption June 16, 2025

VI - 47



Potable Water Element
Existing Potable Water Customers and Future Service Areas

POTABLE WATER ELEMENT



Potable Water Map

Page Index
 South Brevard Service Area

0 2,500 5,000 10,000
 Feet



Brevard County Information Technology Department
 Data Source: BOCC Utility Services Department

POTABLE WATER ELEMENT

LPA Adoption June 16, 2025

VI - 49

CHAPTER PART VII

SANITARY SEWER ELEMENT

TABLE OF CONTENTS

Operations and Maintenance	1
Planning and Evaluation	2
Service Provision and Expansion.....	3
Maintaining a Public Benefit	8
Reclaimed Water System	9
Public Education.....	10
Appendix.....	11

GOALS, OBJECTIVES, AND POLICIES

GOAL SS

Brevard County shall operate and maintain ~~an environmentally sound, and efficient wastewater~~ a sanitary sewer system, that includes collection, treatment, and disposal system that protects the public health, in all matters that are required by the Florida Department of Environmental Protection.

Operations and Maintenance

Objective SS 1

Brevard County shall operate and maintain its sanitary sewer system in a manner that protects the health of the public and the resource values of the natural environment as a top priority.

Policy SS 1.1

Brevard County's wastewater treatment and disposal systems shall, ~~at a minimum,~~ be operated consistent with all local, state, and federal standards.

Policy SS 1.2

Brevard County shall maintain its practice of no new direct discharges of wastewater into surface water bodies.

Policy SS 1.3

Untreated wastewater shall not be discharged into drainage ditches, surface waters or aquifers.

Policy SS 1.4

~~Florida Department of Health in Brevard County shall~~ may permit the use of on-site sewage treatment and disposal systems to satisfy wastewater requirements only in areas where a sewer system is not available, ~~and then only when the system is consistent with the regulations found in Section 381, F.S. and Chapter 64E, F.A.C. and if permitted by the Florida Department of Health.~~

Policy 1.5

~~Guidance on the maintenance and operation of on-site sewage disposal systems shall be developed and monitored by Brevard County.~~

~~Criteria:~~

- ~~A. Brevard County shall continue public education programs on the proper use, inspection requirements, maintenance and abandonment of septic tanks.~~

SANITARY SEWER ELEMENT

Planning and Evaluation

Objective SS 2

Brevard County shall identify and correct existing sewer facility deficiencies within its sewer system.

Policy SS 2.1

Capital improvements planning should include comparative evaluation of the costs and benefits of upgrading, expanding or modifying existing public facilities versus the costs of constructing new facilities.

Policy SS 2.2

~~In cases where infrastructure is inadequate to meet the needs of new development, the developer shall be allowed to construct infrastructure improvements to provide the necessary capacity. Development shall continue to meet the County's design and construction requirements as specified in current criteria, policy, and ordinance as approved by the Board of County Commissioners.~~

Policy SS 2.3

~~The utilization of County-owned sewer facilities should be maximized through innovative redesigns and improvements required where County-owned sewer facilities are available.~~

Policy SS 2.4

Brevard County shall continue to evaluate its ~~own~~ sanitary sewer service areas in order to ~~respond when needs are identified~~ assure that the level of service standard adopted in the Capital Improvements Element is achieved, ~~which is 220 gallons per day per equivalent residential connection (ERC) countywide and 150 gallons per day per ERC for Barefoot Bay.~~

Policy SS 2.5

~~The evaluation of service area expansions shall be done in coordination with the Future Land Use Element and Housing Element and the Planning and Development Department and Housing and Human Services Department in order to meet current and future demands.~~

Policy 2.5 SS 2.6

~~In order to reduce the number of package plants, Brevard County shall discourage new package treatment plants, except as provided in Policy 3.17, and encourage sewer connection prohibit private wastewater systems.~~

Policy 2.6 SS 2.7

Brevard County shall continue to implement the Schedule of Potable Water and Sanitary Sewer Improvements in the Capital Improvement Program Element to correct existing deficiencies in the County-owned sewer facilities.

Policy 2.7

~~The provision of public facilities and services shall be based on the most cost-effective method of production and delivery.~~

Policy 2.8

~~As a priority, Brevard County shall continue to implement its program to reduce or eliminate infiltration and inflow into the collection system.~~

Service Provision and Expansion**Objective SS 3**

Brevard County shall ensure the provision of sewer service consistent with projected needs.

Policy SS 3.1

Promote the management of wastewater as a dual function that can protect public health and generate recovered water as a resource.

Policy SS 3.2

~~Promote~~ Prioritize the use of ~~best available technology in the collection, treatment, disposal and reuse of~~ advanced wastewater treatment wherever economically feasible.

Policy SS 3.3

Encourage cooperation and coordination between the County, municipalities and other entities to manage present and future sanitary sewer service needs.

Policy SS 3.4

Maximize reuse of treated wastewater and water conservation techniques while maintaining an adequate reuse level of service to recover and diminish the demand for potable water.

Policy SS 3.5

Brevard County shall ensure the provision of sanitary systems coordinated with other public facilities and services through the Schedule of Potable Water and ~~Sanitary~~ Sanitary Sewer Improvements in the Capital Improvement Program Element.

Policy SS 3.6

In order to ~~be provided~~ receive sewer service ~~by from~~ County-operated facilities, new development must be located within ~~the existing or future sewer service areas~~ utility service boundary as adopted in the Comprehensive Plan.

Policy SS 3.7

~~The "user pays" concept, which encourages the users of public facilities to be financially responsible for bearing any added, marginal costs of additional public facilities created by new development, should be one of the primary revenue bases for financing expansion, operation and maintenance of all County-owned wastewater facilities and services. Brevard County shall evaluate all fees and rates to assure adequate funds are available to fund all current and future projects included in the Schedule of Potable Water and Sanitary Sewer Improvements in the Capital Improvements Element.~~

Policy SS 3.8

Brevard County shall provide adequate wastewater treatment plant capacity to maintain ~~the proportion of the permit plant capacity divided by the number of equivalent units as more than 200 gallons per day per equivalent unit, except in the South Central Service Area service area, where the equivalent unit per day will be 165 gallons per day~~ level of service standard adopted in the Capital Improvements Element. ~~Level of service standard for planning purposes is 220 gallons per day per equivalent residential connection (ERC) countywide and 150 gallons per day per ETC for Barefoot Bay.~~

Policy 3.9

~~Treatment and disposal system capacity should be available prior to expansion of the active collection system.~~

Policy 3.10 SS 3.9

Brevard County shall evaluate whether adequate sanitary sewer facility capacity is available or will be available when needed to serve development.

Policy 3.11 SS 3.10

Brevard County shall insure that County-issued development orders do not cause ~~municipal~~ wastewater treatment systems to exceed ~~their own~~ established level of service standards.

Policy 3.12 SS 3.11

Brevard County shall designate future sewer service areas in ~~1-5 year and 6-15 year increments~~ based upon the location, health/environmental needs, and the needs of future growth. These future sewer service areas shall represent areas for which the County is committed only to make treatment plant capacity available within the designated period of time.

Policy ~~3.13~~ SS 3.12

~~Coordinate the extension of sanitary sewer service areas with the Future Land Use Element and Housing Element of this Comprehensive Plan and the Comprehensive Plans of all affected local governments and the Planning and Development Department and Housing and Human Services Department. Priority will be given to areas that have a Future Land Use Map designation of four units per acre or higher.~~

Policy SS 3.13

Brevard County shall maintain land development regulations which encourage development to locate in areas within a designated sewer service area with adequate capacity and in the appropriate service sector for the future land use.

Policy SS 3.14

~~Brevard County shall continue to review and comment on wastewater infrastructure plans for developments connecting to the County owned sewer system for consistency with the County's Comprehensive Plan. Brevard County shall prioritize the elimination of septic systems consistent with the intent of the Save Our Indian River Lagoon program and as may be required by Florida Statutes.~~

Policy SS 3.15

~~All new development requiring a centralized sewer system within future sewer service areas shall connect to the public wastewater treatment plant if there is sufficient available capacity, or the building permit will be denied. Within the County's jurisdiction, for any development of more than fifty (50) residential lots, whether built or unbuilt, with more than one (1) onsite sewage treatment and disposal system (OSTDS) per one (1) acre, the County shall consider the feasibility of providing sanitary sewer services within a 10-year planning horizon and must identify the name and location of the wastewater treatment facility that could receive sanitary sewer flows after connection; the capacity of the facility and any associated transmission facilities; the projected wastewater flow at that facility for the next twenty (20) years, including expected future new construction and connections of OSTDS to sanitary sewer; and a timeline for the construction of the sanitary sewer system. The County shall update its feasibility analysis as needed to account for future applicable developments. By September 30, 2025, the County shall include in the Five-Year Schedule of Capital Improvement, with an annual update as necessary, a list of projects for providing sanitary sewer to the development(s), as applicable. This analysis shall be conducted pursuant to Section 163.3177(c)3 of the Florida Statutes, incorporated by reference in this element.~~

Policy 3.16

~~All new development requiring a centralized sewer system outside of the 6-20 year future sewer service area shall choose one of the following options:~~

~~Criteria:~~

- ~~A. Amend the Future Sewer Service area map and connect to the public sewage system if capacity is available; or~~

SANITARY SEWER ELEMENT

- ~~B. — Install a private treatment plant excepting that no new private treatment plants shall discharge to surface waters and all new private waste water treatment plants will meet the requirements outlined in Policy 3.17 of this element.~~

Policy 3.17

Private treatment plants shall be permitted subject to all of the following criteria:

Criteria:

- ~~A. — Private treatment plants shall be permitted under any of the following circumstances:~~
- ~~1. — When environmental conditions exist which preclude on-site sewage disposal, connection to the central sewer system is not feasible and the establishment of a private treatment plant is the only alternative for wastewater treatment;~~
 - ~~2. — To serve commercial land uses located at interstate interchanges to accommodate regional traffic;~~
 - ~~3. — To serve commercial land uses adjacent to existing residential uses in the urban fringe, urbanizing or urban density areas. Such commercial uses shall reduce an existing deficiency in commercial area, defined as less than 160 square feet of commercial area for each residence within a two-mile radius;~~
 - ~~4. — To serve developments with a mixture of uses located as an extension of existing residential uses and of an overall project density no greater than that permitted in the density area;~~
 - ~~5. — To serve residential development using a transfer of density to protect an environmentally sensitive area. Such development shall be located as an extension of existing residential uses, and shall be of an overall project density no greater than that permitted in the density area.~~
- ~~B. — Under no circumstances shall the development of a private treatment plant be used to increase the density of an area beyond the density permitted by the Future Land Use element or any other portion of the Comprehensive Plan.~~
- ~~C. — Private treatment plants shall meet the technical standards of the Florida Department of Environmental Protection.~~
- ~~D. — Developers of new private treatment plants in areas where potable water is used as the irrigation source are strongly encouraged to utilize reclaim water to assist in meeting the irrigation needs for the development or should configure a ground water disposal system to recharge the surficial aquifer.~~

- E. ~~An agreement may be established for all new private treatment plants and such agreement will, at a minimum, address the following:~~
1. ~~Execution of a closure agreement with a permanent service provider, such as a municipality or the County. The closure agreement shall identify the amount of and payment schedule for connection or impact fees, as may be applicable.~~
 2. ~~Terms of closure for the private treatment plant facility, including the ownership of the private treatment plant and land.~~
 3. ~~Escrow account for the purpose of funding the prepayment of connection charges for connecting units served by private treatment plants to the permanent service provider shall be made by the developer into the escrow account at the time of certificate of occupancy.~~
 4. ~~Other facility requirements and costs such as force mains, pump stations, a reuse needs analysis, and other related infrastructure needs.~~
 5. ~~Timing and conditions for connection to the permanent service provider.~~
 6. ~~Notification of ultimate owners within the project that the private treatment plant is temporary and will eventually be connected to a permanent system, subject to applicable fees, regulations and benefits.~~

Policy 3.18

~~Interim and/or “package-type” waste water treatment facilities shall be required, at the option of the County, to connect to the public centralized system when access to the system is made available.~~

Policy 3.19

~~When a private sanitary sewer facility is phased out and connected to the County sewer system, the cost of the connection to the system including impact fees shall be incurred solely by the owner.~~

Policy 3.20

~~All private sanitary sewer facilities may be permitted to expand their service beyond the project boundaries for which they are approved, only if they are consistent with the Future Land Use Map Series and all other applicable comprehensive plan elements and land development regulations.~~

Criteria:

- A. ~~The expansion of sewer service areas, or facilities should be based on excess capacity availability and approved by the Board of County Commissioners.~~

- ~~B. Any expansions shall require approval by the Board of County Commissioners after two public hearings.~~
- ~~C. Expansions of the private treatment plant service area shall not be permitted to cross natural water bodies; such as the Indian River Lagoon and its tributaries, St. Johns River and its lakes, Mullet Creek and Sykes Creek.~~
- ~~D. An application for expansion of the service area shall include the following, at a minimum:
 - ~~1. A financial statement certifying the current financial condition of the party responsible for the management and operation of the private treatment plant.~~
 - ~~2. Certification by the Florida Department of Environmental Protection (DEP) that the treatment plant meets current DEP operating requirements; and sufficient capacity exists to provide for existing and proposed development.~~~~

Maintaining a Public Benefit

Objective 4

~~Brevard County shall maximize the use of existing facilities to discourage urban sprawl.~~

Policy 4.1

~~Ensure that the Brevard County public sewer system is economically self-sustaining and that new growth pays its fair, full share of the total sewer infrastructural improvement costs.~~

Policy 4.2

~~The development and use of public facilities and systems shall be undertaken to maximize the overall public benefit while minimizing construction, operation and maintenance costs.~~

Policy 4.3

~~Brevard County shall maintain land development regulations which encourage development to locate in areas within a designated sewer service area with adequate capacity and in the appropriate service sector for the land use proposal.~~

Reclaimed Water System

Objective 5 SS 4

Develop and implement a system for the efficient reuse of treated wastewater to reduce demands on fresh water resources, conserve existing resources, and to reduce effluent disposal by deep well injection.

Policy ~~5.1~~ SS 4.1

Maximize the reuse of treated wastewater to reduce demand for fresh water and prioritize funding of reuse water lines in an effort to eliminate wasteful discharge of recyclable water.

Policy ~~5.2~~ SS 4.2

Brevard County shall continue to expand its wastewater reuse program, ~~where~~ feasible.

Policy ~~5.3~~

~~Brevard County shall strive to reuse or otherwise reclaim 75 percent of the wastewater generated by public sewer systems operated by the County.~~

Policy ~~5.4~~ SS 4.3

All projects to be served by treatment plants should design and construct a reclaimed water system as part of the wastewater disposal system, where a supply of reuse is available.

Policy ~~5.5~~ SS 4.4

Brevard County should maximize economic benefits derived from the utilization of treated effluent and sludge without compromising public health or the environment.

Policy ~~5.6~~ SS 4.5

All new development in designated reuse areas shall provide reclaimed water lines to the specifications established by Brevard County.

Policy ~~5.7~~

~~In existing development within designated reclaimed water areas, Brevard County will budget for the installment of reclaimed water lines whenever the existing sewer lines are exposed for major replacement, or new sewer service is provided, where practical and economically feasible.~~

Policy ~~5.8~~ SS 4.6

Brevard County shall support and encourage the use of reclaimed water for industrial purposes through cooperative efforts with municipalities and other reuse water generators.

Public Education

Objective SS 5

Brevard County shall prioritize public outreach and education regarding on-site sewage treatment and disposal systems.


Policy SS 5.1

Brevard County shall continue to provide public education programs on the proper use, inspection requirements, maintenance, and abandonment of on-site sewage treatment and disposal systems.

APPENDIX

LIST OF MAPS

<u>Map</u>	<u>Title</u>
1	Existing Sewer Customers and Future Sewer Service Areas <u>Proposed Wastewater Service Areas</u>
2	Waste Water Treatment Plants
3	General Soil Association for Septic Tank Suitability




SANITARY SEWER ELEMENT

LPA Adoption June 16, 2025



Brevard County - Comprehensive Plan


EAR Amendments 2009



**Sanitary Sewer Element
Waste Water Treatment Plants**

SANITARY SEWER ELEMENT

LPA Adoption June 16, 2025



SANITARY SEWER ELEMENT

LPA Adoption June 16, 2025

CHAPTER PART VIII

SOLID WASTE AND HAZARDOUS MATERIALS ELEMENT

TABLE OF CONTENTS

Environmentally Sound Operations	1
Efficiency	1
Resource Recovery	2
Proper Waste Disposal Activities.....	2
Concurrency Management	3
Hazardous Waste	3
Enforcement.....	4
Emergency Response.....	5
Hazardous Waste Collection	5

GOALS, OBJECTIVES, AND POLICIES

GOAL SWH 1

Brevard ~~county~~ County shall ~~ensure an~~ protect public health by providing an efficient and environmentally sound and efficient solid waste management system for Brevard County's customers which utilizes resource recovery, recycling, and source reduction.

Environmentally Sound Operations

Objective SWH 1.1

The County shall ensure that the ~~solid waste management system~~ Solid Waste Management System is operated in an environmentally sound manner and is, at a minimum, consistent with federal and state requirements.

Policy SWH 1.1.1

Ensure that Brevard County's Solid Waste Management Facilities ~~minimize impacts to groundwater, surface water, and air pollution from leachate, stormwater, and landfill gas management systems~~ minimize ground and surface water and air pollution by solid waste facilities.

Efficiency

Objective SWH 1.2

Maintain or improve the existing efficiency of the ~~solid waste management system~~ Solid Waste Management System.

Policy SWH 1.2.1

All collection components of the system shall be conducted in a manner which is consistent with Chapter 94 of the Brevard County Code of Ordinances, as amended. Collection of solid waste shall also adhere to all sections of the current Solid Waste and Recycle Collection Contract.

Policy SWH 1.2.2

The ~~private franchised collectors~~ Contracted Collector(s) and County disposal operations shall be monitored annually to ensure that reasonable fees for the collection and disposal of solid waste are maintained.

Policy SWH 1.2.3

Brevard County shall ensure that the solid waste collection system has capacity to accommodate twice per week solid waste collection service to improved residential properties, including garbage, recycling, yard waste, and bulk/special waste collection.

SOLID WASTE AND HAZARDOUS MATERIALS ELEMENT

Policy SWH 1.2.4

Brevard County shall provide for the disposal of all solid waste generated by Brevard County's population.

Resource Recovery**Objective SWH 1.3**

The volume of solid waste disposed of in landfills shall be reduced through resource recovery programs, where environmentally sound and economically feasible.

Policy SWH 1.3.1

Brevard County shall monitor and assess resource recovery technology; and implement those programs that are determined to be most effective and efficient.

Criteria:

- A. Implement curbside collection program for the reuse and recycling of materials including, but not limited to glass, paper, plastic, aluminum, metal, and green waste.
- B. Maintain and enforce procedures for the removal and recycling of abandoned solid waste objects and materials as described in Chapter 705 and section 403.413, F.S., and Chapter 94, Brevard County Code of Ordinances.
- C. Resource recovery feasibility assessments shall, at a minimum, include consideration of recycling, waste-to-energy, ~~and renewable natural gas production,~~ composting, and other viable alternative technologies.

Policy SWH 1.3.2

Brevard County shall educate and encourage consumers to reduce solid waste generation, participate in recycling programs, and avoid products which do not lend themselves to recycling through distribution of information via various media; and presentations given by County staff and private organizations to local groups and ~~learning~~ educational institutions.

Proper Waste Disposal Activities**Objective SWH 1.4**

Implement programs and legislation that monitor and ensure proper waste disposal activities.

Policy SWH 1.4.1

Prohibit improper disposal of solid and hazardous waste by strict enforcement of the Brevard County Code and ensuring the County Code conforms to U.S. EPA; and Florida Department of Environmental Protection solid waste regulations.

Policy SWH 1.4.2

Brevard County shall develop programs, policies, and other measures to substantially reduce littering and unauthorized dumping.

Concurrency Management**Objective SWH 1.5**

Provide the solid waste management facilities and services necessary to meet the projected disposal needs of residents and businesses of the County for the next twenty years by developing and implementing a Solid Waste Capital Improvements Program.

Policy SWH 1.5.1

Brevard County shall develop a financial plan to maintain a Solid Waste Capital Improvements Program and provide adequate funds for ~~renewal~~ repair and replacement of the solid waste system equipment and facilities and expansion of disposal capacity on an annual basis to replace equipment and facilities as needed.

Policy SWH 1.5.2

Brevard County shall develop and implement Closure Plans (as required by Chapter 62-701, F.A.C.) for the Sarno Road Class III landfill, and the Central Disposal Facility Class I landfills, and the US192 Solid Waste Management Facility landfills.

GOAL SWH 2

Brevard County shall ensure a safe, environmentally sound, and efficient county-wide hazardous materials management system.

Hazardous Waste**Objective 6 SWH 2.1**

Brevard County shall increase public awareness of the nature, harmful effects, source reduction, and proper disposal and recycling methods associated with hazardous wastes through public information programs. ~~Information on source reduction and recycling of hazardous wastes shall also be made available.~~

Policy 6.1 SWH 2.1.1

County shall continue to disseminate information to the public and provide public information educational programs to residents and schools regarding its household hazardous waste collection program, and the County shall also continue to advise the commercial sector on the proper handling and disposal of hazardous wastes.

Policy 6.2 SWH 2.1.2

Brevard County shall research, compile, and disseminate hazardous waste information to homeowners and businesses to help facilitate source reduction and recycling of hazardous wastes, including, but not limited to batteries, fluorescent lamps, mercury devices, paints, pesticides, oil, etc.

Enforcement**Objective 7 SWH 2.2**

Brevard County shall establish and maintain programs and enforcement mechanisms to ensure that ~~all users of hazardous materials and generators of hazardous waste properly transport, store, and dispose of hazardous waste~~ is transported, stored, and disposed of properly.

Policy 7.1 SWH 2.2.1

Brevard County shall continue to operate the ~~household hazardous waste collection centers~~ Household Hazardous Waste Collection Centers to manage hazardous wastes from residents and facilitate the proper management of hazardous waste from small businesses and other ~~low-volume generators~~ Very Small Quantity Generators through the EnviroBusiness hazardous waste disposal program.

Policy 7.2 SWH 2.2.2

Brevard County shall, where appropriate, incorporate into the Brevard County Code by reference all state statutes relating to environmental pollution or hazardous materials.

Policy 7.3 SWH 2.2.3

All hazardous waste incineration or treatment facilities and specialized units shall be required to acquire any and all county, state, and federal permits.

Policy 7.4 SWH 2.2.4

Brevard County shall train and equip all involved enforcement and compliance personnel to ensure adequate enforcement of federal, state, and local hazardous materials regulations and codes.

Policy 7.5 SWH 2.2.5

Brevard County's Natural Resources ~~Office~~ Management Department shall maintain a hazardous waste Small Quantity Generator assessment, notification, and verification program in accordance with Chapter 403, F.S., and Chapter 62-731, F.A.C.

Emergency Response**Objective 8 SWH 2.3**

Brevard County shall provide adequate emergency response and cleanup capabilities for the uncontrolled or accidental releases of hazardous materials.

Policy 8.1 SWH 2.3.1

The Brevard County Fire Rescue Special Operations Team shall be maintained and provided with adequate training and equipment, ~~(including a field communication network)~~, on a permanent basis.

Policy 8.2 SWH 2.3.2

Operating costs shall be recovered from parties responsible for the cause of hazardous material incidents.

Policy 8.3 SWH 2.3.3

~~Brevard County shall maintain and expand a hazardous materials computer database (accessible to other County Departments) which identifies the characteristics, locations, types and quantities of hazardous materials for emergency response purposes.~~

Brevard County shall continue to coordinate with the Local Emergency Planning Committee (LEPC) Regional Coordinator through the East Central Florida Regional Planning Council to review information on the characteristics, locations, types, and quantities of hazardous materials for emergency response purposes.

Hazardous Waste Collection**Objective 9 SWH 2.4**

Brevard County shall implement a program to assess the present and future facility needs for the collection and consolidation of household hazardous wastes.

Policy 9.1 SWH 2.4.1

Brevard County shall maintain ~~household hazardous waste collection centers~~ Hazardous Waste Collection Centers at the County's solid waste facilities and provide recycling services for wastes collected, where feasible.

APPENDIX

LIST OF MAPS

Map	Name
1	Solid Waste Management Facilities

Solid Waste Management Facilities



Landfill Facility

- 3 Kennedy Space Center Landfill
- 4 Cape Canaveral Air Force Landfill
- 5 Central Brevard Disposal Facility
- 6 Sarno Road Landfill & Transfer Station
- 7 Melbourne Landfill / Private
- 8 US-192 Facility (future)



Transfer Facility


- 1 Mockingbird Way Mulching Facility
- 2 Titusville Transfer Station
- 9 Yard Waste / Transfer Facility (future)

 Rivers, Lakes & Ponds

 Incorporated Areas

 Unincorporated Area

Note: Facility locations are approximate.



Solid Waste Element



SOLID WASTE AND HAZARDOUS MATERIALS ELEMENT

LPA Adoption June 16, 2025

CHAPTER PART IX

TRANSPORTATION ELEMENT

TABLE OF CONTENTS

Performance, Monitoring, and Evaluation	1
Coordinated Improvements	4
Roadway Network	5
Safety.....	6
Prioritization of Transportation Improvements	6
Concurrency Management	10
Multi-modal Transportation	14
Airport, Sea Port, Spaceport, and Rail Facilities.....	16
Land Use and Transportation Coordination.....	18
Public Participation.....	19
Intergovernmental Coordination	19
Scenic Highways.....	22
Complete Streets.....	25
Roadway Network	27
Complete Streets.....	27

GOALS, OBJECTIVES, AND POLICIES

GOAL TRA 1

~~Brevard County seeks to ensure a~~ A safe, convenient, and energy efficient transportation system in Brevard County that supports the community defined by this comprehensive plan and enhances the mobility of people and goods while reducing reliance upon the automobile and minimizing impacts to neighborhoods, cultural resources and natural habitats.

Performance, Monitoring, and Evaluation

Objective TRA 1.1

Brevard County will continue to explore the availability and/or development of performance indicators for the transportation network and incorporate such indicators into the county's improvement programming decisions as appropriate.

Objective 1 Policy TRA 1.1.1

~~Brevard County will Routinely~~ routinely monitor and evaluate the performance of county and state roadways and other modes (bicycle, pedestrian, transit, port, airport, and rail facilities) as appropriate the transportation network.

Policy TRA 1.1.2

Brevard County shall ~~participate~~ collaborate with the Space Coast Transportation Planning Organization (TPO), the Florida Department of Transportation (FDOT), and other local governments to ~~establish a performance monitoring system for~~ monitor the performance of arterial and collector roadways. Brevard County will review performance data provided annually by the Space Coast TPO to identify existing and projected intermodal deficiencies and needs. The data will include but not be limited to:

Criteria:

- A. ~~Brevard County should, at a minimum, utilize the traffic count data provided annually by the Space Coast TPO. The Space Coast TPO annually conducts and publishes traffic counts on arterial and collector roadways, in cooperation with the local governments and the FDOT. Vehicle Miles Traveled~~
- B. ~~Brevard County shall coordinate with the Space Coast TPO, the FDOT, and the municipalities to develop, enhance and maintain a centralized transportation data reporting system. Identify congested roadways (operating at >.85 Maximum Acceptable Volume)~~
- C. ~~Brevard County shall monitor and assist in developing the "State of the System Report" published annually by the Space Coast TPO. The report monitors trends, conditions and performance in the following areas:~~

TRANSPORTATION ELEMENT

1. ~~System Trends and Conditions~~
 - a. ~~Vehicle Miles of Travel (annual and daily vehicle miles traveled by total system, sub-area and per capita)~~
 - b. ~~Roadways Operating at Congested Conditions (number of lane miles and VMT operating >0.85 Maximum Acceptable Volume)~~
 - c. ~~Duration of congestion (number of lane miles with congestion >0.85 Maximum Acceptable Volume for one or more hours per day.~~
 - d. ~~Use of Transit (annual number of transit trips and vehicle revenue miles)~~
2. ~~Roadway Segment Condition~~
 - a. ~~Severity of existing congestion~~
 - b. ~~Severity of congestion by 2040, or the horizon year of the latest adopted Space Coast TPO Long Range Transportation Plan, with no improvements~~
 - c. ~~Number of vehicles affected~~
 - d. ~~Intermodal connectivity and economic significance~~
 - e. ~~Crash history~~
 - f. ~~Hurricane evacuation route designation~~
 - g. ~~Prior funding commitments~~

Transit usage

- D. The State of the System Report shall be provided to the local governments and the FDOT for the purpose of analyzing levels of congestion, determining appropriate mitigation measures, and shall be considered when prioritizing and programming local, state and federal transportation improvement funds: Crash history

- E. Hurricane evacuation routes

Policy 1.2

Brevard County should develop a roadway classification system appropriate for Brevard County roads that is based on actual roadway and travel characteristics:

Criteria:

- A. ~~Brevard County should base this classification system on the Federal Functional Classification System and should refine this system to address local needs.~~
- B. ~~Brevard County, in cooperation with the Space Coast TPO and the municipalities, should periodically review the Federal Functional Classification System to insure the classification addresses local conditions.~~
- C. ~~Traffic circulation maps shall be based on the Federal Functional~~

TRANSPORTATION ELEMENT

Classification System:

Policy 1.3

Brevard County shall maintain level of service (LOS) standards for all county arterial and collector roadways:

Criteria:

- A. The level of service standards are as follows:
 - 1. Brevard County arterial and collector roadways within the urban area boundary: Level of Service E.
 - 2. Brevard County arterial and collector roadways within the rural area, except as noted above: Level of Service D.
 - 3. State arterial roadways (excluding Florida Intrastate Highway System) within the urban area boundary: As adopted by FDOT
 - 4. State arterial roadways (excluding Florida Intrastate Highway System), outside the urban area boundary (rural area): As adopted by FDOT
- B. The level of service standards for the Florida Intrastate Highway System (Interstate 95 and SR 528) shall be established by FDOT. In general, the standards are LOS E within the urban area boundary and LOS D outside the urban area boundary.

Policy 1.4

Brevard County shall maintain a two-tiered level of service analysis procedure where the FDOT generalized level of service tables are used for a first-tier analysis and a more detailed analysis is performed on those roadways experiencing significant congestion:

Criteria:

- A. The level of service analyses should be coordinated with affected local governments.
- B. The level of service analysis should be incorporated into the Space Coast TPO's congestion management system, where applicable.
- C. The level of service analysis should be incorporated into Brevard County's concurrency management system, where applicable.

Policy 1.5

Brevard County shall monitor high accident locations and coordinate with other agencies as appropriate to address safety deficiencies. High-accident locations may be identified through the Community Traffic Safety Team, an intergovernmental and interagency group formed to address safety issues.

Policy 1.6

Brevard County shall participate with the Space Coast TPO in the operation of the

TRANSPORTATION ELEMENT

Congestion Management System (CMS):

Criteria:

- A. ~~_____ The CMS shall contain the numerical indicators against which the achievement of area's mobility goals can be measured.~~
- B. ~~_____ Space Coast Area Transit should participate in the CMS process, since the CMS addresses both highway and non-highway modes.~~

Policy 1.7

~~Brevard County should explore the availability and/or development of performance indicators for other modes and incorporate such indicators into the county's improvement programming decisions as appropriate.~~

Coordinated Improvements

Objective TRA 1.2

Brevard County will coordinate with the Space Coast TPO and FDOT to utilize the best available data and transportation management strategies to improve the mobility and performance of the transportation network.

Policy TRA 1.2.1

Brevard County will collaborate with the Space Coast TPO and Space Coast Area Transit to identify and evaluate congestion management strategies to improve the mobility of all modes of transportation.

Policy TRA 1.2.2

Brevard County shall encourage the use of transportation demand management strategies as a means to reduce peak hour travel demand and the number of vehicle miles traveled in the region.

Policy TRA 1.2.3

Brevard County shall encourage the use of transportation systems management strategies to preserve the capacity of existing transportation systems.

Criteria:

- A. Brevard County shall review arterial and collector corridors that are nearing deficiency for opportunities to increase capacity through transportation management strategies.
- B. Where feasible, transportation system management strategies shall be incorporated into major roadway improvement projects to maximize future capacity.
- C. Brevard County shall follow accepted industry-standard traffic and transportation design standards to guide the implementation of

transportation systems management strategies. Such standards may apply to the provision of driveway access, bicycle facilities, traffic signals, transit facilities, and intersection design.

Policy TRA 1.2.4

The following state roads are classified as limited access roadways: SR 528, I-95, and SR 404 (Pineda Causeway). Portions of the Pineda Extension and St. Johns Heritage Parkway controlled by Brevard County shall be classified as a limited access roadway and are subject to the following conditions:

- A. Access to this roadway should be limited to maximize its function as a hurricane evacuation route and as a primary traffic route.
- B. The classification of this route as a limited access roadway shall not prohibit pedestrian or bicycle usage in the right of way (ROW) or on the roadway.
- C. The above criteria shall not apply to those limited access facilities controlled by the Florida Department of Transportation.

Policy TRA 1.2.5

Brevard County will consider establishing performance standards for alternative modes of transportation.

Roadway Network

Objective TRA 1.3

Brevard County shall undertake measures designed to assist in the free flow of traffic along major roads and strive to maintain and improve the [level of service \(LOS\)](#) on those roadways if at any time they operate at a lower LOS than the adopted standard.

Policy TRA 1.3.1

The County shall continue to coordinate with the Space Coast TPO and FDOT on transportation systems management and operations initiatives.

Policy TRA 1.3.2

The Space Coast TPO shall maintain a record of traffic counts for major roadways in the County's network and update those records on an annual basis.

Safety

Objective TRA 1.4

Brevard County seeks a transportation system that is safe for all users.

Policy TRA 1.4.1

Brevard County shall support FDOT in their efforts to identify major transportation improvements that would ensure timely and safe evacuation prior to an impending natural disaster.

Policy TRA 1.4.2

Brevard County shall monitor high accident locations and coordinate with other agencies as appropriate to address safety deficiencies. High-accident locations may be identified through the Community Traffic Safety Team, an intergovernmental and interagency group formed to address safety issues.

Policy TRA 1.4.3

Brevard County shall maintain and enforce land development regulations that improve the safety of motorists, pedestrians, and bicyclists in accordance with the following criteria:

Criteria:

- A. Minimize points of conflict along local roadways from driveway connections and other access points.
- B. Identify, evaluate, and mitigate, as appropriate, potential traffic safety hazards within the traffic impact area of a proposed major project.

GOAL TRA 2

Brevard County is committed to prioritizing and pursuing improvements to transportation facilities while exploring innovative funding solutions to address critical infrastructure needs.

Prioritization of Transportation Improvements

Objective TRA 2.1

Major transportation improvements shall be identified based on need, incorporate accepted design standards and be consistent with the Comprehensive Plan.

Policy TRA 2.1.1

~~Using the performance monitoring documents identified under Objective 1,~~ Brevard County shall develop short-range (1-5 years) and long-range (6-15 years) transportation improvement programs for the expenditure of county transportation funds.

Criteria:

- A. Short-range and long-range transportation improvement programs shall be financially structured as follows:
 - 1. The short range transportation improvement program shall be financially feasible by having available revenues from committed

TRANSPORTATION ELEMENT

- funding sources for the first three years. Years 4-5 shall have or will have available revenue from committed or planned funding sources.
2. The long range transportation improvement program shall be structured to achieve or maintain the adopted Levels of Service by utilizing the best available information on projected population growth and demands on the transportation system.
 3. The short range transportation improvement program shall be evaluated and modified as necessary on an annual basis as part of the annual update of the Capital Improvements Element.
- B. Transportation improvement programs should be multi-modal, including consideration of modes other than automobile.
 - C. Transportation improvement programs should be flexible and responsive to community needs.
 - D. Transportation projects should strive to incorporate a balance between mobility and quality of life.
 - E. Brevard County's short range transportation improvement program should be identified in the Brevard County Capital Improvements Plan (CIP).
 - F. Brevard County's long range transportation improvement program should be coordinated with the TPO Long Range Plan and the Florida Transportation Plan.
 - G. Brevard County ~~shall~~ should investigate and pursue additional funding sources for the long-range transportation improvement program.

Policy 2.2 TRA 2.1.2

~~Using the performance monitoring documents identified under Objective 1, Brevard County shall assist the Space Coast TPO in developing short-range (1-5 years) and long-range transportation (6-20 years) improvement programs for the expenditure of state and federal transportation funds within Brevard County.~~

Policy 2.3

~~Brevard County design standards shall incorporate generally accepted traffic, multi-modal and transportation engineering standards as appropriate.~~

Criteria:

- A. ~~Land development regulations and county design policies shall be reviewed periodically to ensure consistency with generally accepted traffic, multimodal and transportation engineering standards.~~
- B. ~~Benefit/cost ratio, aesthetics, neighborhood preservation, demand, user-~~

TRANSPORTATION ELEMENT

~~types and available funding, may also be considered in establishing or waiving design standards, without compromising public safety.~~

~~C. Brevard County may consider design initiatives proposed by the private sector that do not compromise public safety.~~

~~D. Locally initiated regulations and policies may also be developed to allow innovative designs that do not compromise public safety.~~

Policy 2.4

~~Major transportation system improvement proposals and associated ancillary facilities shall be thoroughly evaluated for consistency with the Comprehensive Plan, applicable Florida Statutes and federal regulations to minimize adverse environmental impacts and maximize economic and social benefits. A “major improvement” could involve roadway, rail, airport, port and/or other mode.~~

Criteria:

- ~~A. Adequate project data, including an analysis of benefits, impacts, and proposed mitigation measures should be provided. As appropriate, the following items should be considered:~~
- ~~1. Current and future public need;~~
 - ~~2. Project impacts to natural resources, including floodplains, aquifer recharge areas, soils, wetlands, surface water, groundwater, drainage, natural communities and wildlife, spheres of influence, air quality, and species listed as endangered, threatened or species of special concern as designated by federal, state or local agencies;~~
 - ~~3. Project impacts to significant historical and archaeological resources such as those listed on the National Register of Historic Places or Florida Master Site File;~~
 - ~~4. Noise and visual implications, including the provision of adequate landscaping;~~
 - ~~5. Management of hazardous materials including emergency planning, emergency response, spill control and spill prevention;~~
 - ~~6. Hurricane evacuation strategies and capacities;~~
 - ~~7. Project impacts to the local economy, including wages and job generation;~~
 - ~~8. Project impacts to the intraregional mobility function of the Florida Intrastate Highway System;~~
 - ~~9. Land use compatibility with existing and future development including established neighborhoods;~~
 - ~~10. Proliferation of urban sprawl as defined in Florida Statutes;~~
 - ~~11. Long term maintenance responsibilities;~~
 - ~~12. Capacity of other infrastructure, such as water and sewer, to accommodate the project and/or ancillary elements associated with the project.~~

- B. ~~The Board of County Commissioners shall determine consistency of a major transportation system improvement with the Comprehensive Plan upon review and consideration of all technical data and analysis; recommendations of the staff, Local Planning Agency and input from the public.~~

Policy 2.5

~~Brevard County recognizes that visually attractive roadways are an asset to the community and shall consider landscaping opportunities within future county major roadway improvement projects and funding for the design, installation and maintenance.~~

Criteria:

- A. ~~Roadway landscaping design should consider the following at a minimum:~~
- ~~1. To ensure vehicular safety, professionally accepted roadway design standards consistently applied should guide the selection of plant materials, street furniture and other landscape elements.~~
 - ~~2. Methods to reduce long term maintenance requirements, such as xeriscaping or self-sustaining vegetation, should be considered.~~
 - ~~3. Native vegetation should be considered.~~
 - ~~4. Landscaping should not compromise pedestrian and bicycle safety by creating visual barriers at intersections, for example.~~
 - ~~5. Irrigation requirements, costs and availability, including reuse water, should be evaluated.~~
- B. ~~Brevard County should consider innovative public and private sector cooperative landscaping maintenance programs such as “adopt-a-median”.~~
- C. ~~Brevard County should coordinate with other local governments or agencies to address the visual appearance and landscaping of gateway roads leading into the county and/or to major tourist destinations.~~

Policy 2.6

~~Brevard County shall monitor the needs of the coastal population and identify major transportation improvements to maintain performance levels, as set forth in the Coastal Management Element, for ensuring timely evacuation prior to an impending natural disaster.~~

Policy 2.7 TRA 2.1.3

The improvements identified in the Capital Improvements Element [of the County's Comprehensive Plan](#) and the TPO's Long Range Transportation Plan and Transportation Improvement Program represent projects that may become part of Brevard County's future transportation network.

Policy 2.8 TRA 2.1.4

In addition to the projects contained in the documents identified in Policy 2.7 TRA 2.1.3, Brevard County should consider supporting roadway improvement projects that:

- A. Provide additional capacity necessary to accommodate planned growth;
- B. Establish corridors parallel to existing congested roadways;
- C. Improve roadway continuity;
- D. Provide operational and safety benefits to various transportation modes using the corridor;
- E. Enhance evacuation and public safety capability;
- F. Upgrade inadequate stormwater management systems; or
- G. Reconstruct existing roads to address maintenance, bicycle, and pedestrian; safety, transit, appearance, or access management concerns.
- H. Are consistent with the State Comprehensive Plan and limit urban sprawl.

Policy 2.9

~~The land development regulations shall implement the Transportation Corridor Management Area Ordinance for the St. Johns Heritage Parkway. This code section shall be reviewed periodically for consistency with all Preliminary Design and Engineering Studies and all Final Design and Engineering plans prepared for this corridor on behalf of Brevard County.~~

Policy 2.10 TRA 2.1.5

Brevard County continue to maintain a comprehensive access management policies for roadways within Brevard County within the land development regulations.

GOAL TRA 3

Brevard County seeks to resolve transportation deficiencies.

Concurrency Management**Objective TRA 3.1**

Brevard County shall implement methods to prevent future transportation system deficiencies.

Policy TRA 3.1.1

Brevard County's adopted Concurrency Management System shall continue to monitor the roadway system in order to identify when proposed development may degrade a roadway (excluding the Florida Intrastate Highway System) below an acceptable level of service.

Policy TRA 3.1.2

Brevard County shall maintain level of service (LOS) standards for all County arterial and collector roadways.

Policy TRA 3.1.3

Brevard County shall maintain a two-tiered level of service analysis procedure where the FDOT generalized level of service tables are used for a first-tier analysis and a more detailed analysis is performed on those roadways experiencing significant congestion.

Criteria:

- A. The level of service analyses should be coordinated with affected local governments.
- B. The level of service analysis should be incorporated into the Space Coast TPO's congestion management system, where applicable.
- C. The level of service analysis should be incorporated into Brevard County's concurrency management system, where applicable.

Policy TRA 3.1.4

New development and redevelopment must demonstrate that the adopted roadway level of service can be maintained in the buildout year of the development. Brevard County will require that applications include a traffic study, prepared by a registered Professional Engineer, identifying existing and future traffic volumes at buildout of the development, as well as recommendations for roadway improvements, if any.

Policy TRA 3.1.5

If a proposed project in Brevard County cannot meet the concurrency requirement for transportation, Brevard County's Land Development Regulations shall include provisions for the use of "proportionate fair-share mitigation for transportation facilities" consistent with F.S. 163.3180, as may be amended from time to time.

Policy TRA 3.1.6

Proportionate fair-share mitigation shall be applied as a credit against such impact fees to the extent that all or an apportion of the fair share mitigation is used to address the same capital infrastructure improvements contemplated by the County's impact fee ordinance.

Policy TRA 3.1.7

Brevard County may enter into a development agreement, as provided by F.S. 163.3221, with the developer to provide construction of the facilities necessary to support said development if they are not available, consistent with concurrency requirements of F.S. 163.3180. The agreement must provide that after an applicant makes its contribution or constructs its proportionate share, the project shall be considered to have mitigated its transportation impacts and allowed to proceed (if the applicant has satisfied all other local government development requirements for the project).

Policy TRA 3.1.8

Brevard County recognizes that the impact of one (1) single family residence on any lot already recorded as platted or which can otherwise be demonstrated to the satisfaction of the County to have been in existence on December 1, 2006 shall always be considered "de minimis" and no application for an approval for development in this manner of any one such lot shall be subject to any transportation concurrency analysis under any circumstance.

Policy ~~3.2~~ TRA 3.1.9

Land use changes may be considered as a means to reduce transportation demand, when providing transportation improvements is too costly or has significant community impact.

Policy ~~3.3~~ TRA 3.1.10

Brevard County recognizes that land uses outside the jurisdiction of Brevard County have significant impacts on Brevard County roadways.

Policy TRA 3.1.11

In order to discourage urban sprawl, encourage infill development, and reduce greenhouse gases and congestion, the County shall evaluate several strategies for alternatives to transportation concurrency including, but not limited to a Transportation Concurrency Management Area (TCMA), Multi-modal Transportation District (MTD), Transportation Concurrency Exception Area (TCEA), and Long Term Transportation Concurrency Management System (LTCMS) along roadways that are unable to meet level of service standards.

Policy ~~3.4~~ TRA 3.1.12

Brevard County should continue to implement measures that facilitate the preservation of right-of-way for transportation facilities including but not limited to roadway, transit, and pedestrian facilities.

Policy ~~3.5~~

~~Brevard County shall encourage the use of transportation demand management strategies as a means to reduce peak hour travel demand and the number of vehicle miles traveled in the region.~~

TRANSPORTATION ELEMENT

Criteria:

- A. — ~~Developments of Regional Impact (DRI) review shall specifically include consideration of transportation demand management strategies.~~
- B. — ~~Brevard County shall contact major employers, operators of major traffic generators and major educational facilities to encourage staggered work hours, ridesharing and other strategies in those areas where major arterials are near deficiency.~~
- C. — ~~Space Coast Area Transit should continue to provide carpool matching services, park and ride facilities and vanpool support in addition to more traditional transit services.~~
- D. — ~~Brevard County should develop draft incentive measures for the private sector to promote alternatives to the single-occupant vehicle as the primary means of transportation.~~

Policy 3.6

~~Brevard County shall encourage the use of transportation systems management strategies to preserve the capacity of existing transportation systems.~~

Criteria:

- A. — ~~Brevard County shall review arterial and collector corridors that are nearing deficiency for opportunities to increase capacity through transportation management strategies.~~
- B. — ~~Where feasible, transportation system management strategies shall be incorporated into major roadway improvement projects to maximize future capacity.~~
- C. — ~~Brevard County shall follow accepted industry-standard traffic and transportation design standards to guide the implementation of transportation systems management strategies. Such standards may apply to the provision of driveway access, bicycle facilities, traffic signals, transit facilities, and intersection design.~~

Policy 3.7

~~Brevard County shall maintain and enforce land development regulations that improve the safety of motorists, pedestrians and bicyclists in accordance with the following criteria:~~

Criteria:

- A. — ~~Minimize points of conflict along local roadways from driveway connections and other access points.~~
- B. — ~~Identify, evaluate and mitigate, as appropriate, potential traffic safety~~

TRANSPORTATION ELEMENT

hazards within the traffic impact area of a proposed major project.

Policy 3.8

~~The following state roads are classified as limited access roadways: SR 407, SR 528, I-95, and SR 404 (Pineda Causeway). Portions of the Pineda Extension and St. Johns Heritage Parkway controlled by Brevard County shall be classified as a limited access roadway and are subject to the following conditions:~~

- ~~A. Access to this roadway should be limited to maximize its function as a hurricane evacuation route and as a primary traffic route.~~
- ~~B. The classification of this route as a limited access roadway shall not prohibit pedestrian or bicycle usage in the right of way (ROW) or on the roadway.~~
- ~~C. The above criteria shall not apply to those limited access facilities controlled by the Florida Department of Transportation.~~

GOAL TRA 4

Brevard County seeks transportation options for all.

Multi-modal Transportation

Objective TRA 4.1

Brevard County ~~shall~~ should encourage multi-modal transportation alternatives that accommodate existing and proposed major trip generators and attractors.

Policy TRA 4.1.1

Brevard County shall emphasize safety and convenience in the location, design, and construction of bicycle and pedestrian facilities.

Criteria:

- A. The Space Coast TPO shall guide and promote a countywide perspective in planning and implementation of facilities to accommodate bicycle and pedestrian needs.
- ~~B. Brevard County should continue to designate a portion of local option gas taxes, transportation impact fees and other revenues for bicycle and pedestrian projects.~~
- ~~C. B. Bicycle~~ Providing safe bicycle and pedestrian facilities shall be included as a should be the standard component in the planning and development of transportation facilities. Bicycle Inclusion of safe bicycle and pedestrian facilities shall be established considered in conjunction with the construction, reconstruction, or other significant change of any major county

TRANSPORTATION ELEMENT

roadway, provided their establishment would not be contrary to public safety or their cost would not be excessively disproportionate to the need or future use.

- ~~D. C.~~ Brevard County shall continue to maintain land development regulations that accommodate bicycling and walking and consider bicycle and pedestrian facilities in the development review process.

Policy ~~4.2~~ TRA 4.1.2

Transit should routinely be considered as an alternative to roadway widening and as a supplement to roadway improvement projects.

Criteria:

- A. Brevard County should promote and encourage the use of public transit and should continue efforts to improve the public transportation system, based upon the adopted Transit Development Plan, public input, and availability of resources.
- B. Land development regulations should be maintained to ensure that development allows and encourages accessibility to public transit and incorporates improvements in compliance with ADA standards.

Policy ~~4.3~~ TRA 4.1.3

Brevard County shall work cooperatively with the municipalities to establish parking strategies and to identify potential park-and-ride sites and encourage their development through joint projects with the Florida Department of Transportation.

Policy ~~4.4~~ TRA 4.1.4

Brevard County shall continue to promote and encourage expansion of the vanpool program to the extent resources are available and based on demand for the service.

Policy ~~4.5~~ TRA 4.1.5

Brevard County shall continue efforts to provide services to the “transportation disadvantaged” to the extent resources are available.

Criteria:

- A. The scope and methods by which transportation disadvantaged services will be provided will be outlined in the adopted Transportation Disadvantaged Service Plan and Transportation Development Plan.
- ~~B. Brevard County should participate in the area’s welfare-to-work plan that addresses welfare-related transportation issues, recognizing the important role transit can play in assisting in the transition from welfare to employment.~~

Policy TRA 4.1.6

Brevard County will evaluate and implement, as appropriate, strategies to improve intermodal access to seaport, spaceport, airports, and rail facilities when such needs or deficiencies are identified.

Policy TRA 4.1.7

Brevard County land development regulations should encourage land use patterns and site planning that can be economically and conveniently served by transit, bicycle, and pedestrian modes.

GOAL TRA 5

Brevard County supports port, air, and rail as efficient ways to move people and goods.

Airport, Sea Port, Spaceport, and Rail Facilities**Objective TRA 5.1**

Brevard County shall encourage the use and expansion, as needed, of Brevard County port, airport, and rail facilities for the safe, efficient, and timely movement of goods and passengers.

Policy TRA 5.1.1

Brevard County should continue to participate in the review of the development plans or airports within Brevard County and support those development plans which are consistent with the Brevard County Comprehensive Plan and compatible with surrounding land uses as designated by the Future Land Use Element.

Criteria:

- A. Brevard County shall support environmentally and economically sound development of Valkaria Airport, which should be developed to serve general aviation traffic as its primary purpose, as may be determined by the Board of County Commissioners, based upon public input and findings of fact.
- B. Brevard County shall support environmentally and economically sound development of Space Center Executive, Merritt Island, and Dunn Airports, as may be determined by the Board of County Commissioners and the TICO Airport Authority, based upon public input and findings of fact.

Policy 5.2 TRA 5.1.2

Brevard County should support the development and maintenance of a comprehensive rail system to meet current and future needs and further economic growth of the County, to the extent that the development is compatible with the Brevard County Comprehensive Plan.

Policy 5-3 TRA 5.1.3

Brevard County shall encourage aerospace industry related development in the Gateway Center/Spaceport Florida area and other areas in proximity to the Kennedy Space Center and other areas in Brevard County.

Policy 5-4 TRA 5.1.4

Brevard County should continue to participate in the review of the development plans for Port Canaveral and encourage utilization of the Port's lands for water-dependent uses and uses which support or augment port-related activities, provided that they are consistent with the Brevard County Comprehensive Plan; specifically the Future Land Use Element, the Coastal Management Element, and the Conservation Element.

Policy 5-5 TRA 5.1.5

The location of new water-dependent businesses in the vicinity of Port Canaveral shall be in compliance with the Brevard County Comprehensive Plan.

Criteria:

- A. Brevard County shall not permit heavy industrial development along the Barge Canal.
- B. Development orders for projects adjacent to the Barge Canal shall provide for the mitigation of off-site negative impacts on natural and historic resources and land uses.

Policy 5-6 TRA 5.1.6

Brevard County shall coordinate with Port Canaveral, as described in the Brevard County Peacetime Emergency Plan, for evacuation from natural disasters.

Policy 5-7

~~Brevard County will evaluate and implement, as appropriate, strategies to improve intermodal access to seaport, spaceport, airports and rail facilities when such needs or deficiencies are identified.~~

Policy TRA 5.1.7

Brevard County shall continue to implement land use development standards which protect the port, airport, spaceport, rail, and related facilities from the encroachment of incompatible land uses.

Policy TRA 5.1.8

Brevard County shall coordinate the siting of new, or expansion of existing, ports, airports, or related facilities with the future land use, coastal management, and conservation elements.

GOAL TRA 6

Brevard County seeks to ensure land use patterns are compatible with the transportation network.

Land Use and Transportation Coordination

Objective TRA 6.1

Brevard County recognizes the inter-relationship of land use patterns and transportation needs and shall implement methods to address land use/transportation interactions.

Policy TRA 6.1.1

Brevard County ~~shall~~ should continue, in cooperation with the cities, the practice of information sharing using Geographic Information Systems technology and other electronic data sharing methods.

Policy ~~6.2~~ TRA 6.1.2

Brevard County ~~shall continue to~~ may analyze the feasibility of using marginal cost pricing as a method to determine the costs and benefits of development patterns.

Policy ~~6.3~~ TRA 6.1.3

Brevard County shall continue to conduct small area planning studies that analyze land use and transportation relationships in a specific area.

Policy ~~6.4~~ TRA 6.1.4

Brevard County shall utilize the most up to date version of the Central Florida Regional Planning Model to determine future transportation improvement needs. It is recognized that more detailed models may be required.

Policy TRA 6.1.5

The County shall continue to coordinate with the Space Coast TPO and FDOT on all connections and access points of driveways and roads to county and state roadways, respectively.

Policy ~~6.5~~

~~Brevard County shall continue to implement land use development standards which protect the port, airport, spaceport, rail, and related facilities from the encroachment of incompatible land uses.~~

Policy ~~6.6~~

~~Brevard County land development regulations should encourage land use patterns and site planning that can be economically and conveniently served by transit, bicycle, and pedestrian modes.~~

Policy ~~6.7~~

~~Brevard County shall coordinate the siting of new, or expansion of existing, ports,~~

TRANSPORTATION ELEMENT

~~airports, or related facilities with the future land use, coastal management, and conservation elements.~~

GOAL TRA 7

Brevard County seeks to ensure early and continuous public involvement in the transportation planning process.

Public Participation

Objective TRA 7.1

Brevard County shall encourage public involvement in the transportation planning process.

Policy 7.1

~~Brevard County shall continue to use citizen advisory committees for particular projects, drawing the committee members from users, residents, businesses and property owners in the affected area.~~

Policy 7.2 TRA 7.1.1

Brevard County shall continue to encourage public involvement in specific projects through the use of surveys, speaking engagements, and user-friendly public meetings and workshops to augment the input from advisory committees.

Policy 7.3 TRA 7.1.2

Brevard County shall incorporate, where feasible, input from all credible public sources, to guide transportation decision-making.

Policy 7.4 TRA 7.1.3

Brevard County shall continue to participate in the public involvement efforts of SCAT, FDOT, Space Coast TPO, and other related agencies as necessary.

GOAL TRA 8

Brevard County seeks collaboration with regional partners and other local governments in planning the transportation network.

Intergovernmental Coordination

Objective TRA 8.1

Brevard County shall pursue intergovernmental coordination to address transportation system improvements.

Policy TRA 8.1.1

Brevard County should coordinate with the Space Coast TPO, FDOT, the East Central Florida Regional Planning Council (ECFRPC), and local governments to ensure an integrated and comprehensive transportation planning process.

Criteria:

- A. Brevard County shall, when timely and appropriate, review local government Transportation Elements, the Regional Policy Plan, modal agency plans, and the TPO long range plan. An objective of the review will be to assess potential impacts on county facilities and policies posed by the programs and projects contained in the plans.
- B. Brevard County shall prepare the Transit Development Plan, the primary strategic plan for Space Coast Area Transit, every three years as required by FDOT. The Transit Development Plan shall be developed with proactive public and interagency involvement and shall identify specific, achievable short and long-range improvement projects and policy actions that can enhance transit services and ridership in Brevard County.
- C. Brevard County shall continue to participate in the Space Coast TPO planning process which is the primary forum for cooperative decision-making on regional transportation policy and planning. Through the Space Coast TPO and in cooperation and coordination with other local governments and FDOT, the County shall:
 - 1. Review and evaluate access to intermodal facilities located in the County. Agencies such as the Canaveral Port Authority, Orlando Melbourne International Airport, and the Spaceport Florida Authority are largely independent of the Board of County Commissioners. The TPO is the designated forum for review of impacts on regionally significant transportation facilities generated by these agencies and for the identification of improvements needed to enhance access.
 - 2. Continue to participate in the updates of the Space Coast TPO long range transportation plan. The update process follows guidance issued by FDOT and the Federal Highway Administration.
 - 3. Continue to participate in the Space Coast TPO Technical Advisory Committee; Bicycle, Pedestrian and Trails Advisory Committee; and Growth Management Subcommittee, all of which include representatives from all local governments and transportation agencies. These committees discuss transportation planning, programming, and prioritization issues common to local governments and transportation agencies.
 - 4. Participate with other local governments and affected agencies in the update of the Space Coast TPO Bicycle, Pedestrian, and Trails Mobility Plan.
 - 5. Participate in the transportation monitoring and prioritization process

administered by the TPO. Through the TPO's annual regional monitoring program (~~see Policy 1.1~~), roadway improvement needs shall be identified. Projects requiring state and federal funds shall be submitted to the Space Coast TPO for prioritization prior to transmittal to FDOT. The roadway improvement needs information shall also be evaluated when identifying projects to implement with local Brevard County Funds.

- D. Brevard County shall enter into agreements as necessary with other governmental entities to define the mechanisms, strategies, and mutual commitment to a coordinated transportation planning, review, and/or impact assessment process.

Policy 8.2 TRA 8.1.2

Brevard County shall promote interagency coordination of transportation activities that will ensure the orderly development of highway, water, rail, and air transportation facilities.

Criteria:

- A. Brevard County shall provide opportunities for the Canaveral Port Authority to review and comment on natural resource management plans that may impact the Port.
- B. Brevard County should enter into agreements as necessary with other modal agencies to define the mechanisms, strategies, and mutual commitment to a coordinated transportation planning, review, and/or impact assessment process.
- C. Brevard County shall coordinate its operation of and improvements to the transportation system with the plans and programs of the Space Coast TPO, Canaveral Port Authority, the TICO Airport Authority, and the Florida East Coast Railroad.
- D. Brevard County shall coordinate its operation of and improvements to the transportation system with the FDOT's "Florida Transportation Plan" and Adopted Work Program.

GOAL TRA 9

Brevard County seeks to ensure that transportation facilities are designed in harmony with the surrounding environment and community character.

Scenic Highways

Objective TRA 9.1

Brevard County shall take actions necessary to establish and maintain a roadway network that enhances the social and natural environment while minimizing any potential negative impacts.

Policy TRA 9.1.1

Brevard County recognizes that visually attractive roadways are an asset to the community and should consider landscaping opportunities within future county major roadway improvement projects and funding for the design, installation, and maintenance.

Criteria:

- A. Roadway landscaping design should consider the following at a minimum:
 - 1. To ensure vehicular safety, professionally accepted roadway design standards consistently applied should guide the selection of plant materials, street furniture, and other landscape elements.
 - 2. Methods to reduce long term maintenance requirements, such as xeriscaping or self-sustaining vegetation, should be considered.
 - 3. Native vegetation should be considered.
 - 4. Landscaping should not compromise pedestrian and bicycle safety by creating visual barriers at intersections, for example.
 - 5. Irrigation requirements, costs, and availability, including reuse water, should be evaluated.
- B. Brevard County should consider innovative public and private sector cooperative landscaping maintenance programs such as “adopt-a-median”.
- C. Brevard County should coordinate with other local governments or agencies to address the visual appearance and landscaping of gateway roads leading into the county and/or to major tourist destinations.

Policy TRA 9.1.2

Brevard County design standards shall incorporate generally accepted traffic, multi-modal, and transportation engineering standards as appropriate.

Criteria:

- A. Land development regulations and county design policies shall be reviewed periodically to ensure consistency with generally accepted traffic, multimodal, and transportation engineering standards.
- B. Benefit/cost ratio, aesthetics, neighborhood preservation, demand, user-types, and available funding may also be considered in establishing or waiving design standards, without compromising public safety.
- C. Brevard County may consider design initiatives proposed by the private

sector that do not compromise public safety.

- D. Locally initiated regulations and policies may also be developed to allow innovative designs that do not compromise public safety.

Policy TRA 9.1.3

Major transportation system improvement proposals and associated ancillary facilities shall be thoroughly evaluated for consistency with the Comprehensive Plan, applicable Florida Statutes, and federal regulations to minimize adverse environmental impacts and maximize economic and social benefits. A “major improvement” could involve roadway, rail, airport, port, and/or other mode.

Criteria:

- A. Adequate project data, including an analysis of benefits, impacts, and proposed mitigation measures should be provided. As appropriate, the following items should be considered:
1. Current and future public need;
 2. Project impacts to natural resources, including floodplains, aquifer recharge areas, soils, wetlands, surface water, groundwater, drainage, natural communities and wildlife, spheres of influence, air quality, and species listed as endangered, threatened, or species of special concern as designated by federal, state, or local agencies;
 3. Project impacts to significant historical and archaeological resources such as those listed on the National Register of Historic Places or Florida Master Site File;
 4. Noise and visual implications, including the provision of adequate landscaping;
 5. Management of hazardous materials including emergency planning, emergency response, spill control, and spill prevention;
 6. Hurricane evacuation strategies and capacities;
 7. Project impacts to the local economy, including wages and job generation;
 8. Project impacts to the intraregional mobility function of the Florida Intrastate Highway System;
 9. Land use compatibility with existing and future development including established neighborhoods;
 10. Proliferation of urban sprawl as defined in Florida Statutes;
 11. Long term maintenance responsibilities;
 12. Capacity of other infrastructure, such as water and sewer, to accommodate the project and/or ancillary elements associated with the project.
- B. The Board of County Commissioners shall determine consistency of a major transportation system improvement with the Comprehensive Plan upon review and consideration of all technical data and analysis.

TRANSPORTATION ELEMENT

recommendations of the staff, Local Planning Agency, and input from the public.

Policy TRA 9.1.4

The following are designated as scenic roadways in order to preserve the adjacent natural features:

1. U.S. 1, from the intersection of SR 46 to Volusia County Line;
2. SR 46, from a point 1.75 miles west of I-95 to Volusia County Line;
3. SR 50, from a point 1.25 miles west of I-95 interchange to the Orange County Line;
4. SR 405, from its intersection with SR 50 eastward to the boundary of the Kennedy Space Center;
5. U.S. 1, from the south corporate limits of the City of Titusville to Golden Knights Boulevard;
6. SR 407, entire length;
7. SR 528, entire length;
8. SR 524, entire length;
9. SR 520, from intersection of SR 524 to the Orange County Line;
10. SR 3, from SR 528 to the boundary of the Kennedy Space Center;
11. Tropical Trail, entire length;
12. SR 515, from northern terminus to north corporate limits of the City of Cocoa, and from the south corporate limits of the City of Rockledge, to the southern terminus of SR 515;
13. SR 404, entire length;
14. Wickham Road, from SR 404 intersection to I-95;
15. SR A1A, from southern corporate limits of City of Melbourne Beach to the Indian River County Line;
16. U.S. 1, from southern corporate limits of the Town of Malabar to the Indian River County Line;
17. Babcock Street, from southern corporate limits of the City of Palm Bay to the Indian River County Line;
18. U.S. 192, from a point of the 1.75 miles west of I-95 to the Osceola County Line;
19. U.S. 1, east side, from the south corporate limits of the City of Rockledge to the northern corporate limits of the City of Melbourne;
20. SR A1A, unincorporated areas, between south boundary of Patrick Air Force Base and north boundary of the Town of Indialantic.

Policy 9.2 TRA 9.1.5

Brevard County shall encourage the protection and preservation of scenic features through implementation of the following:

Criteria:

- A. Property owners along designated roadways shall be encouraged to preserve trees and vegetation during development of these properties.

TRANSPORTATION ELEMENT

- B. Billboards and other physical barriers, such as fences, exceeding four feet in height, excluding primary and accessory structures, that interfere with or prevent visual access to the scenic qualities of the roadways designated as scenic resources, shall be prohibited. Non-conforming existing billboards and the referenced opaque physical barriers shall be amortized.
- C. Vegetation and trees growing adjacent to scenic roadways within the rights-of-way for those roads shall be protected by the land development regulations regarding land clearing activities except in those cases involving health and safety concerns or those which would deny visual access beyond the immediate area.
- D. Public or private linear projects and utility corridors developed or maintained by governmental or investor-owned regulated utilities that do not require an active development order are exempt if determined to be in the public interest as defined in the Brevard County Comprehensive Plan Glossary per Sec 62-4334 of the Brevard County Code of Ordinances.

Policy 9.3 TRA 9.1.6

The following description defines the limits of the Indian River Lagoon Scenic Highway route: the limits of the corridor begin at Ais Lookout Point, just north of the intersection of Robert Conlan Boulevard and US 1 in Palm Bay, proceed south on US 1 to the Wabasso Causeway (CR510), east across the causeway to SR A1A, north on A1A to Port Canaveral, then west on SR 528 (the Bennett Causeway) to SR 3, north to the NASA Causeway, west to US 1, north to Brewer Causeway/Beach Road, northeast to the Canaveral National Seashore, then south on the mainland to Ais Lookout Point to complete the circuit. The SR 520, SR 404, SR 518, and US 192 causeways are also included in the corridor as intermediate connectors. The Vision of the Indian River Lagoon Scenic Highway and the Preliminary Goals and Objectives of the Indian River Lagoon Scenic Highway, as stated in the Indian River Lagoon Scenic Highway Corridor Management Entity Agreement, shall be encouraged within the Indian River Lagoon Scenic Highway Corridor.

Complete Streets

Objective TRA 9.2

Brevard County should undertake measures to establish Complete Streets policies to enable safe access for the community. The Complete Streets program ensures that the feasibility of providing safe access for all users is considered during design of roadways.

Policy TRA 9.2.1

The County should review the existing Land Development Code for amendments to

TRANSPORTATION ELEMENT

provide for the implementation of feasible Complete Streets principles.

Policy TRA 9.2.2

The County should evaluate the existing review process to determine appropriate staff input during the design review process to implement feasible Complete Streets.

Policy TRA 9.2.3

The County shall offer Complete Streets training opportunities, including third party trainers, to planners and engineers involved in the design review process.

Policy TRA 9.2.4

The County shall encourage streets, bridges, and transit stops within the communities to be planned, designed, operated, and maintained, so that pedestrians, bicyclists, transit users, and motorists of all ages and functional abilities can travel safely where feasible.

Policy TRA 9.2.5

The planning for the Complete Streets Program shall consider the needs of all users, including the following elements:

Criteria:

- A. Sidewalk space for pedestrians
- B. Bike lanes or bike routes
- C. Appropriately sized travel lanes for motorized vehicles
- D. Transit vehicles, facilities, and routes
- E. On-street parking where applicable
- F. Median use for traffic flow, safety, and pedestrian refuge
- G. Adequate buffer areas for pedestrian safety, utility placement, drainage, and possible landscaping
- H. Landscaping or hardscaping adding pedestrian protection
- I. Existing and future land use context of a roadway or corridor

Policy TRA 9.2.6

The Space Coast TPO shall consider assisting Complete Streets corridors for jurisdictions responsible for the roadway that have adopted a Complete Streets Policy and other criteria that may be determined by the Space Coast TPO.

Policy TRA 9.2.7

The Space Coast TPO may require a Corridor Feasibility Study be completed to be considered for funding assistance through the Complete Streets Program.

Roadway Network

Objective 10

~~Brevard County shall undertake measures designed to assist in the free flow of traffic along major roads and strive to maintain and improve the LOS on those roadways if at any time they operate at a lower LOS than the adopted standard.~~

Policy 10.1

~~The County shall continue to coordinate with the Space Coast Transportation Planning Organization and FDOT on a transportation systems management and operations initiatives.~~

Policy 10.2

~~The County shall continue to coordinate with the Space Coast Transportation Planning Organization and FDOT on all connections and access points of driveways and roads to county and state roadways, respectively.~~

Policy 10.3

~~The County shall maintain a record of traffic counts for major roadways in the County's network, and update those records on an annual basis.~~

Policy 10.4

~~In order to discourage urban sprawl, encourage infill development, reduce greenhouse gases and congestion, the County shall evaluate several strategies for alternatives to transportation concurrency including, but not limited to a Transportation Concurrency Management Area (TCMA), Multi-modal Transportation District (MTD), Transportation Concurrency Exception Area (TCEA) and Long Term Transportation Concurrency Management System (LTCMS) along roadways that are unable to meet level of service standards.~~

Complete Streets

Objective 11

~~Brevard County shall undertake measures to establish Complete Streets policies to enable safe access for the community. The Complete Streets program ensures that the feasibility of providing safe access for all users is considered during design of roadways.~~

Policy 11.1

The County shall review the existing Land Development Code for amendments to provide for the implementation of feasible Complete Streets principles.

Policy 11.2

The County shall evaluate the existing review process to determine appropriate staff input during the design review process to implement feasible Complete Streets. —

Policy 11.3

The County shall offer Complete Streets training opportunities, including third party trainers, to planners and engineers involved in the design review process.

Policy 11.4

The County shall encourage streets, bridges, and transit stops within the communities to be planned, designed, operated, and maintained, so that pedestrians, bicyclists, transit users and motorists of all ages and functional abilities can travel safely where feasible.

Policy 11.5

The planning for the Complete Streets Program shall consider the needs of all users, including the following elements:

—— **Criteria:**

- A. —— Sidewalk space for pedestrians
- B. —— Bike lanes or bike routes
- C. —— Appropriately sized travel lanes for motorized vehicles
- D. —— Transit vehicles, facilities and routes
- E. —— On-street parking where applicable
- F. —— Median use for traffic flow, safety, and pedestrian refuge
- G. —— Adequate buffer areas for pedestrian safety, utility placement, drainage, and possible landscaping
- H. —— Landscaping or hardscaping adding pedestrian protection
- I. —— Existing and future land use context of a roadway or corridor

Policy 11.6

The Space Coast TPO shall consider assisting Complete Streets corridors for jurisdictions responsible for the roadway that have adopted a Complete Streets Policy and

~~other criteria that may be determined by the Space Coast TPO.~~

Policy 11.7


~~The Space Coast TPO may require a Corridor Feasibility Study be completed to be considered for funding assistance through the Complete Streets Program.~~

APPENDIX

LIST OF MAPS

<u>Map</u>	<u>Name</u>
-------------------	--------------------

<u>1</u>	<u>2023 Average Annual Daily Traffic and Functional Classifications</u>
<u>2</u>	<u>Transit System</u>
<u>3</u>	<u>Existing Bicycle Facilities: North</u>
<u>4</u>	<u>Existing Bicycle Facilities: Central</u>
<u>5</u>	<u>Existing Bicycle Facilities: South</u>
<u>6</u>	<u>Existing Pedestrian Facilities: North</u>
<u>7</u>	<u>Existing Pedestrian Facilities: Central</u>
<u>8</u>	<u>Existing Pedestrian Facilities: South</u>
<u>9</u>	<u>2024 Strategic Intermodal System Projects</u>
<u>10</u>	<u>2024 Regionally Significant Projects</u>
<u>11</u>	<u>2024 Transportation Systems Management & Operations Projects</u>
<u>12</u>	<u>2024 Bicycle & Pedestrian Projects</u>
<u>13</u>	<u>2024 Shared Use Network Trails Projects</u>
<u>14</u>	<u>2024 Planning/Studies</u>
<u>15</u>	<u>2024 Fully Funded Projects</u>



Brevard County SYSTEM MAP

Effective March 30, 2024

Route 1 – Titusville/Viera

Route 2 – Titusville

Route 3 – Merritt Island

Route 4 – 520 Connector

Route 5 – Titusville/Mims

Route 6 – Cocoa/Rockledge

Route 7 – Rockledge/Viera

Route 8 – West Cocoa

Route 9 – Cape Canaveral/Cocoa Beach

Route 10 – Central Titusville

Route 11 – Port St. John

Route 20 – Heritage-West Melbourne

Route 21 – Downtown Melbourne

Route 22 – South Palm Bay

Route 23 – West Palm Bay

Route 24 – Melbourne

Route 25 – Melbourne/Palm Bay

Route 26 – South Beach

Route 27 – East Palm Bay

Route 28 – North Melbourne

Route 29 – Melbourne/Viera

Route 30 – South Beach Connector

Route 33 – Eau Gallie Arts District

321Transit.com

**New Website & App
Featuring Contactless
Mobile Ticketing**

321Transit



**SPACE
COAST
AREA TRANSIT**

RideLine 321.633.1878

[f](#) [i](#) [t](#) [@321Transit](#)



MIMS

TITUSVILLE

PORT
ST. JOHN

COCOA

ROCKLEDGE

VIERA

PALM
SHORES

MELBOURNE

MELBOURNE VILLAGE

WEST MELBOURNE

PALM BAY

MALABAR

MICCO

KENNEDY
SPACE
CENTER

MERRITT
ISLAND

PORT CANAVERAL

CAPE CANAVERAL

COCOA BEACH

ATLANTIC
OCEAN

PATRICK
AIR FORCE BASE

SATELLITE BEACH

INDIAN
HARBOR BEACH

INDIALANTIC
MELBOURNE BEACH





Figure 37

Existing Bicycle Facilities: North

- Existing Bicycle Facilities
- Master Plan Roadway Network
- Incorporated Cities/Towns



Existing Bicycle Facilities: Central



Figure 39

Existing Bicycle Facilities: South




Figure 40

Existing Pedestrian Facilities: North

- Existing Pedestrian Facilities
- Master Plan Roadway Network
- Incorporated Cities/Towns




Figure 41

Existing Pedestrian Facilities: Central





Figure 42

Existing Pedestrian Facilities: South




0 2 4 Miles



2024 Strategic Intermodal System (SIS) Projects

Project Ranking FY 26-30


- 1 Ellis Road (426905-4)
- 2 Cape Canaveral Spaceport Intelligent Transportation System (ITS) (447994-1)
- 3 SR 528 (E of SR 3 to SR 401 (Port)) (407402-4)
- 4 SR 528 (E of Industry Rd to SR 3) (407402-3)
- 5 SR 401 Bridge (444787-1)
- 6 I-95 Interchange at Malabar Road



APRIL 2024

FUNDED PROJECT PHASES

- Unfunded
- Planning
- Project Development & Env.
- Design
- Right of Way
- Construction



2024 Regionally Significant Projects



Project Ranking FY 26-30


- 1 Malabar Rd (437210-1)
- 2a SR A1A (430202-5)
- 2b SR A1A (452688-1)
- 3 Babcock St (437204-1)
- 4 SR A1A (430202-8)
- 5 SR 501 (Clearlake Rd) (433605-1)
- 6 SR 524 (437983-1)
- 7 SR 3 (Courtenay Pkwy) (435631-2)
- 8 SR 514 (Malabar Rd) (430136-1)
- 9 US 1 @ Viera Blvd and @ Barnes Blvd (433604-1)
- 10 SR 507 (Babcock St) (237650-6)
- 11 SR 518 (Eau Gallie Blvd) @ Wickham Rd (443734-1)
- 12 SR 405 (South St)
- 13 SR A1A NB (441445-1)
- 14 SR 518 (Eau Gallie Blvd) @ SR 5054 (Sarno Rd)
- 15 SR 519 (Fiske Blvd) @ Roy Wall Blvd (446600-1)
- 16 Cocoa Multimodal Station (453045-2)
- 17 Wickham Rd @ Post Rd
- 18 Hollywood Blvd (437203-1)
- 19 Minton Road

APRIL 2024

FUNDED PROJECT PHASES

- Unfunded
- Planning
- Project Development & Env.
- Design
- Right of Way
- Construction






- 1 Traffic Management Center (441584-1)
- 2 SR A1A
- 3 Malabar Rd (443731-1)
- 4 Emerson Drive (443733-1)
- 5 San Filippo Drive (443732-1)
- 6 US 1
- 7 SR 50
- 8 Intelligent Transportation System (ITS)
Operational Support (Not Mapped)
(428930-1)

APRIL 2024

FUNDED PROJECT PHASES

- Unfunded
- Planning
- Project Development & Env.
- Design
- Right of Way
- Construction



2024 Bicycle & Pedestrian Projects



Project Ranking FY 26-30

- 1 SR A1A (Volunteer Way to Roosevelt Ave) (447150-2)
- 2 Jackson Ave Complete Street (446675-1)
- 3 SR A1A (Grosse Pointe Ave to Flug Ave) (447151-1)
- 4 SR 518 (Eau Gallie Cswy Trail) (443670-1)
- 5 SR A1A (Shearwater Pkwy to Pineda Cswy - SR 404) (447150-1)
- 6 SR A1A (S Orlando) (7th St S. to 6th St S.) (441443-1)
- 7 US 1 (Gran Ave to Port Malabar Blvd)
- 8 US 1 (Kirkland Rd to RJ Conlan Blvd)
- 9 Aurora Street (S. of SR 520 to N. of Jackson St)
- 10 US 1 (Viera Blvd to Barnes Blvd) (433604-1)

APRIL 2024

FUNDED PROJECT PHASES

- Unfunded
- Planning
- Project Development & Env.
- Design
- Right of Way
- Construction





2024 Shared Use Network (SUN) Trails Projects


Project Ranking FY 26-30

- 1** Space Coast Trail (437093-2)
- 2** US 1 - East Coast Greenway (447608-1)
- 3** Space Coast Trail (437093-1)
- 4** N Merritt Island Pioneer Trl (Trail Study Area Mapped) (439893-1)

APRIL 2024

FUNDED PROJECT PHASES

- Unfunded
- Planning
- Project Development & Env.
- Design
- Right of Way
- Construction




Project Ranking FY 26-30

- 1** Long Range Transportation Plan (Not Mapped)
- 2** SR A1A Complete Street
- 3** SR 520 Cocoa Beach Causeway
- 4** SR 519 (Fiske Blvd)
- 5** Transportation Planning Support (Not Mapped)
- 6** Dixon Blvd. Complete Street Analysis
- 7** Indian River Linear Trl (US 1) (443622-1)
- 8** Minton Rd.
- 9** Norfolk Pkwy Extension
- 10** S. Brevard Trails Master Plan (Not Mapped)
- 11** Cross City Trail (Not Mapped) (443619-1)

APRIL 2024


FUNDED PROJECT PHASES

- Unfunded
- Planning
- Project Development & Env.
- Design
- Right of Way
- Construction



2024 Fully Funded Projects

Project Ranking FY 26-30




APRIL 2024

FUNDED PROJECT PHASES

- Unfunded
- Planning
- Project Development & Env.
- Design
- Right of Way
- Construction

- A** Strategic Intermodal System (SIS): Space Commerce Way (INFRA)
- B** Strategic Intermodal System (SIS): 405 NASA Cswy/Indian River Bridge (INFRA)
- C** US 1 (Lake Washington to Post) (FY 22)
- D** Melbourne SW Canal Trails (FY 23) (443620-1)
- E** Parrish Park Trailhead (FY 23) (441778-1)
- F** SR 520 (US 1 to Hubert Humphrey Bridge) (FY 23) (435628-1)
- G** SR 501 (SR 520 to Michigan Ave) (FY 23)
- H** Traffic Management Center (FY 24) (441584-1)
- I** US 192 & Hollywood/Evans (FY 24) (433655-1)
- J** NASA Blvd Sidewalk (Eddie Allen to Evans) (FY 24) (445872-1)
- K** US 1 (Canoe Creek Bridge to WH Jackson St) (FY 24)
- L** NASA Blvd Intelligent Transportation System (ITS) Infrastructure (Wickham to US 1) (FY 24) (445858-1)
- M** SR A1A Sidewalk (SR 518 to Volunteer Way) (FY 25) (437939-1)
- N** Michigan Ave Trail (FY 26)
- O** Space Coast Trail (FY 25) (437093-2)
- P** Jackson Avenue Complete Street (446675-1)
- Q** SR A1A (430202-5)



CHAPTER PART X

COASTAL MANAGEMENT ELEMENT

TABLE OF CONTENTS

Estuarine Pollution.....	1
Water Quality/Seagrasses	2
Fisheries	3
Beaches and Dunes	4
Water-Dependent Land Uses.....	9
Coastal High Hazard Areas	24
Coastal Residential Densities	26
Hurricane Evacuation.....	26
Hurricane Shelters	29
Post-Disaster Redevelopment	31
Coastal Access.....	34
Port Canaveral.....	36
Recreational and Commercial Working Waterfronts	36
Coastal Development and Redevelopment.....	39
APPENDIX	43

GOAL, OBJECTIVES, AND POLICIES

GOAL CM

Establish growth management strategies that will allow growth to continue within the coastal zone which does not damage or destroy the function of coastal resources, protects human life, and limits public expenditures in areas subject to destruction by natural disasters.

Estuarine Pollution

Objective CM 1

Improve areas within the Indian River Lagoon basin with fair or poor water quality as measured by the State of Florida Department of Environmental Protection using the trophic state index, and maintain areas with good water quality.

Policy CM 1.1

The Brevard County Natural Resources Management Department shall coordinate with the Florida Department of Environmental Protection (FDEP) to develop and implement Basin Management Action Plans to comply with National Pollutant Discharge Elimination System Permits and meet the Total Maximum Daily Loads established for local surface waters.

Policy 1.2

~~Brevard County shall maintain within the land development code regulations that implement standards consistent with National Pollutant Discharge Elimination System Permits and Total Maximum Daily Loads.~~

Policy 1.3 CM 1.2

Brevard County shall continue to cooperate with other agencies and municipalities that perform fisheries studies and submerged aquatic vegetation mapping and use this data to assist in establishing priority areas for surface water improvement efforts. ~~In addition, Brevard County shall coordinate the manatee protection plan with municipalities and appropriate agencies.~~

Policy 1.4 CM 1.3

The Brevard County Natural Resources Management ~~Office~~ Department shall review and comment, as necessary, on dredge-and-fill applications and/or Environmental Resource Permits from the Florida Department of Environmental Protection, St. Johns River Water Management District (SJRWMD), the U.S. Army Corps of Engineers, or other appropriate agencies.

Policy 1.5 CM 1.4

Brevard County shall continue to consider recommendations of ~~the Marine Resources Council~~ FDEP, St. Johns River Water Management District (SJRWMD), the Indian River National Estuary Program (IRLNEP), and other appropriate groups in the development of estuarine studies.

Policy 1.6 CM 1.5

Brevard County shall coordinate surface water management and protection efforts with ~~the Indian River National Estuary Program (IRNEP)~~ IRLNEP, FDEP, SJRWMD and other appropriate agencies.

Policy 1.7

~~Brevard County supports coordinated regional fisheries management plans developed by the Atlantic States Marine Fisheries Commission.~~

Water Quality/Seagrasses**Objective CM 2**

Improve existing water quality to enhance seagrass and other submerged aquatic vegetation quantity, health, diversity, and distribution within the Indian River Lagoon.

Policy CM 2.1

Brevard County shall support the St. Johns River Water Management District's (SJRWMD) mapping of submerged aquatic vegetation within the Indian River Lagoon system. Evaluation results shall be made available to municipalities and other agencies or programs. Areas that show decline should be targeted for increased watershed management, including non-point source pollution, ~~and restoration control~~. Management strategies shall be coordinated with the municipalities and other agencies.

Policy CM 2.2

Brevard County shall continue to participate in the ~~Indian River Lagoon Advisory Committee~~ IRLNEP and its associated advisory groups.

Policy CM 2.3

Brevard County shall continue to protect Submerged Aquatic Vegetation (SAV) from the impacts of local land development by implementing the Surface Water Protection Ordinance. At a minimum, the following criteria shall be addressed:

Criteria:

- A. Maintain upland vegetation within required setbacks to reduce runoff.
- B. Require proper use of turbidity screens during construction activities.

- C. Control discharge rates to promote on-site settlement of sediment loads and meet minimum retention requirements for runoff from storm events.
- D. Coordinate with FDEP Aquatic Preserve staff when development is within or adjacent to an aquatic preserve.

Policy CM 2.4

Brevard County ~~shall address modification of~~ should require stormwater retrofits during redevelopment of existing development which does not meet current stormwater management standards.

Policy CM 2.5

Brevard County supports the goals of the National Estuary Program's Comprehensive Conservation and Management Plan (CCMP) for recovery of the Lagoon. This support is reflected in the strategies identified in the County's ~~Action Plan Implementation Status Report~~ annual submittal to the EPA Work Plan, as amended, for the CCMP.

Policy CM 2.6

Where possible, local stormwater, as well as state and federal surface water programs should reduce or eliminate freshwater inputs to the Indian River Lagoon ~~via interbasin diversions~~.

Fisheries

Objective CM 3

Maintain fisheries in and adjacent to Brevard County through habitat production, maintenance and restoration.

Policy CM 3.1

Brevard County shall encourage habitat evaluation and fisheries studies. These studies should be coordinated with federal and state programs and funded through a combination of the proceeds from a saltwater fishing license and state and federal grants.

Policy CM 3.2

Mosquito impoundments should be reconnected to the Indian River Lagoon where benefits can be demonstrated to increase habitat value of the impoundments and benefits to the Lagoon.

Policy CM 3.3

Brevard County supports coordinated regional fisheries management plans developed by the Atlantic States Marine Fisheries Commission.




Figure 1

Note: Figure 1 is intended for illustrative purposes only. Actual delineations shall be determined by survey.

Beaches and Dunes

Objective CM 4

Brevard County shall implement and improve as necessary a comprehensive beach and dune management program which protects, enhances and restores a naturally functioning beach system as funding is available.

Policy CM 4.1

The Land Development Regulations shall maintain regulations governing the location, construction and maintenance of development adjacent to the Atlantic shoreline. Development seaward of the Florida Department of Environmental Protection (FDEP) 1981 Coastal Construction Control Line (CCCL), which coincides with the Brevard County Coastal Construction Line (CCL), Brevard County Coastal Setback Line (CSL) shall be governed by the following conditions, at a minimum:

Criteria:

- A. The 1981 FDEP ~~CCCL~~ Florida Department of Environmental Protection (FDEP) Coastal Construction Control Line (CCCL) coincides with the Brevard County ~~CCL~~ Coastal Construction Line (CCL), as adopted by Brevard County in Ordinance 85-17. The Brevard County ~~Coastal Setback Line (CSL)~~ CSL is

COASTAL MANAGEMENT ELEMENT

described as a line which is twenty five (25) feet west of the 1981 FDEP CCCL by perpendicular measurement. ~~Figure 1 schematically depicts the spatial relationship of these reference lines. Actual delineations shall be determined by survey.~~

- B. Oceanfront development shall be required to maintain at least 50% of the native dune vegetation on site. ~~Native~~ In addition, native dune vegetation seaward of the FDEP ~~1981 Coastal Construction Control Line (CCCL)~~ CCCL shall not be removed unless necessary for approved emergency vehicle access or coastal protection needs.
- C. In order to maintain the freshwater lens of the surficial aquifer and reduce saltwater intrusion, post-development groundwater recharge volume and rate shall equal pre-development recharge volume and rate.
- D. No new shoreline hardening structures shall be permitted in unincorporated Brevard County south of ~~Patrick Air Force Base (PAFB)~~ Patrick Space Force Base (PSFB) property or within the Archie Carr National Wildlife Refuge, with ~~exception of emergency provisions as provided for in Florida Statutes Chapter section 163.3187(1)(a) "Amendment of Adopted Comprehensive Plan"~~
- E. North of the ~~PAFB~~ PSFB, no new shoreline hardening structures should be permitted.
- F. ~~Pursuant to Criteria C and D of this policy,~~ if a shoreline hardening structure is deemed necessary, the following criteria shall apply:
 - 1. Vertical wood or concrete structures and rock revetments shall only be approved when less structural alternatives, such as beach renourishment, dune restoration and sandbag systems have been determined not to be feasible.
 - 2. All shoreline protection measures shall be designed to minimize adverse impacts to the naturally functioning beach and dune system and adjacent properties.
 - 3. The County may require dune restoration and revegetation as a component of the shoreline hardening approval both landward and seaward of the proposed structure.
 - 4. All shoreline protection shall be designed and constructed so as to not impede public access to or along the shore.
 - 5. Setbacks or other non-structural methods of shoreline protection shall be given the highest priority. Reducing setbacks from A1A will be considered where it is necessary to maintain and maximize setback requirements from the ocean.

COASTAL MANAGEMENT ELEMENT

6. Reconstruction of shoreline hardening structures which are more than fifty (50) percent destroyed should be considered new construction and should be regulated as such, except for the maintenance of existing public navigational projects, such as Port Canaveral and Sebastian Inlet.
- ~~G. — Setbacks or other non-structural methods of shoreline protection shall be given the highest priority. Reducing setbacks from A1A will be considered where it is necessary to maintain and maximize setback requirements from the ocean.~~
- ~~H. — Reconstruction of existing hard erosion control structures which are more than fifty (50) percent destroyed should be considered new construction and should be regulated as such, except for the maintenance of existing public navigational projects, such as Port Canaveral and Sebastian Inlet.~~
- ~~F.G.~~ Underground storage tanks or the storage of hazardous materials are not permitted.
- ~~F.H.~~ Septic tanks or septic tank drainfields shall not be permitted seaward of the Brevard County ~~Coastal Setback Line (CSL)~~ CSL. Septic tanks shall be located landward of the most seaward portion of the habitable structure.
- ~~K. — All activities seaward of the 1986 FDEP Coastal Construction Control Line (CCCL) shall be subject to FDEP permitting requirements.~~

Policy CM 4.2

Brevard County shall enforce development restrictions associated with the Brevard ~~Coastal Setback Line (CSL)~~, County CSL and the Brevard County ~~Coastal Construction Line (CCL)~~ and re-evaluate the effectiveness of these lines from time to time as coastline changes dictate. The County shall provide FDEP with their findings and request a review of the FDEP ~~Coastal Construction Control Line CCCL~~, if deemed appropriate.

Policy CM 4.3

Brevard County shall continue to adopt and enforce standards for maintenance or re-establishment of dune areas. These standards shall include, at a minimum, the following provisions:

Criteria:

- A. Native dune vegetation shall be maintained on site unless removal or alteration is permitted by both Brevard County and the Florida Department of Environmental Protection, ~~or~~ and other appropriate regulatory agency.
- B. Public and private beach access shall be allowed only at designated cross-over structures or historical access sites.

COASTAL MANAGEMENT ELEMENT

- C. Erosion control strategies will be utilized at unimproved public access sites until these can be improved or alternate access provided.
- D. Dune cross-overs, boardwalks, walkways and other permissible structures seaward of the Brevard County ~~Coastal Setback Line~~ CSL shall be elevated above dune vegetation and shall be designed to allow adequate light penetration.
- E. Shore-parallel boardwalks shall be prohibited seaward of the ~~Coastal Setback Line~~ Brevard County CSL, except as required for ~~handicap~~ Americans with Disabilities Act (ADA) compliant access.
- F. Publicly owned dunes, especially those identified for beach access sites, which have been denuded or damaged by vehicular or pedestrian traffic shall be prioritized for dune renourishment and revegetation. Improvements or erosion controls shall be implemented at the time of renourishment to prevent further site degradation.
- G. Private property owners should be encouraged to re-establish dune vegetation which has been destroyed by non-designated access activities or storm damage.
- H. Structures and impacts that are necessary for public safety or meet the best public interest shall be permitted if approved by the Board of County Commissioners.

Policy CM 4.4

Brevard County's beach and dune restoration program shall include an analysis of environmental, financial and social criteria.

Criteria:

- A. The first priority for beach renourishment shall be given to the protection of life and property.
- B. Priority shall also be given to environmental considerations.
- C. Public areas which are heavily utilized for recreation, including surfing, fishing or swimming, shall be considered for beach or dune renourishment or restoration, as applicable. Long-term management of these areas shall be included with all site improvements.
- D. A feasibility or benefit/costs analysis should be performed for any renourishment project. Such analyses shall include, as appropriate, present and future benefits for property protection, recreation and tourism over the life of the project.

COASTAL MANAGEMENT ELEMENT

Policy CM 4.5

The County shall continue to utilize the information and materials available from the State regarding dune maintenance and revegetation and supplement these materials, as necessary.

Policy CM 4.6

Brevard County shall maintain an ongoing program to initiate and monitor data collection projects related to beach dynamics, sand transport and coastal processes. This program should include data generated by the Florida Department of Environmental Protection, the U.S. Army Corps of Engineers, the Florida Sea Grant ~~College program~~, universities and other appropriate agencies.

Policy CM 4.7

Brevard County shall develop an inter-local agreement with adjacent municipalities and the State of Florida for funding of beach maintenance and restoration programs.

Policy CM 4.8

Brevard County shall prohibit motorized vehicles on the dune and beach system except for governmental vehicles, ~~(police and sheriff), fire trucks, ambulances~~ public safety vehicles, or vehicles necessary to repair utilities, or vehicles utilized during approved renourishment programs or approved scientific investigations. Pedestrian traffic within the vegetated dune areas shall be limited to emergency operations, scientific research, maintenance, cleaning or improvements as authorized by the Natural Resources Management Department and consistent with FDEP regulations.

Policy CM 4.9

Brevard County shall continue to collect and make available to the public information related to sea level changes.

Policy CM 4.10

Outer Continental Shelf (OCS) activities such as oil and gas exploration or mining adjacent to Brevard County are discouraged for several reasons. The County's beaches are the most heavily nested beaches by sea turtles in the western Atlantic. Impacts to water quality, beach quality and fisheries could negatively impact the threatened and endangered species that nest here. Brevard County should review and comment on all ~~Outer Continental Shelf (OCS)~~ OCS and off shore drilling leases proposed for waters adjacent to the county. This policy does not discourage OCS sand and gravel mining conducted as part of Brevard County's shore protection and restoration strategy.

Water-Dependent Land Uses

Objective CM 5

By 2010, Brevard County shall ~~develop and adopt~~ maintain guidelines which direct the location and management of water-dependent, water-related and water-enhanced facilities, giving highest priority to water-dependent uses along the Indian River Lagoon System in order to provide for the increased demand for these facilities.

Policy CM 5.1

Brevard County shall continue to implement performance standards for marinas and marine-related facilities within the coastal zone which include at a minimum: setbacks, height limitations, parcel size, architectural guidelines, seagrass protection, and the protection of water quality including the maintenance and containment of stormwater runoff and wash-down water for dry storage areas. Marina performance standards shall meet the criteria within the MPP, as amended, and include the following minimum criteria:

Criteria:

- A. Existing marina facilities should be allowed to continue their operation provided these facilities meet the County's adopted operational standards.
- B. While the expansion of existing facilities is preferred over construction of new facilities, the development of new marinas must remain a viable alternative as many existing marinas will not be capable of meeting adopted operational and environmental standards.
- C. Policies and incentives should encourage new and expanded marina facilities to utilize dry storage to the fullest extent possible.
- D. New marina facilities shall retain all work area runoff in a separate retention area. In addition, the first inch of stormwater runoff from a 10-year 24-hour storm shall be retained on site.
- E. Prior to operation of any new marina fueling facility, a fuel management/spill contingency plan will be developed and provided to the Natural Resources Management Department for review. The plan shall describe methods to be used in dispensing fuel and all the procedures, methods, and materials to be used in the event of a fuel spill and shall meet Brevard County Fire Prevention Codes and Rules of the State Fire ~~Marshall's~~ Marshal's office.
- F. New marina facilities shall demonstrate they will not result in any adverse effect on any archaeological or historic resource, as defined in Brevard County's Comprehensive Plan Glossary. In the event a previously undiscovered historical or archaeological site is discovered during construction of a marina project, construction will stop until knowledgeable

experts can be brought in to evaluate the discovered resource and make provisions for its removal or preservation.

- G. Brevard County should encourage the construction of marine sanitation device (MSD) pump-out facilities.
- H. Prior to amending marina performance standards, Brevard County shall review proposed amendments in coordination with the Florida Fish and Wildlife Conservation Commission (FWC) for compliance with the MPP.

Policy 5.2

~~Brevard County should continue to develop and implement regulations governing live-aboards within the coastal zone. The regulations shall include the following criteria at a minimum:~~

Criteria:

- ~~A. Floating structures shall be considered within live-aboard regulations. Floating structures shall be defined as: A vessel with no means of operative propulsion which is inhabited for thirty (30) consecutive days or more.~~
- ~~B. Motorized live-aboard vessels shall be defined as vessels which are occupied for more than seven (7) consecutive days within Brevard County. These shall not include floating structures (as defined in Criterion A).~~
- ~~C. The County shall investigate designating certain areas of the Indian River Lagoon for mooring of motorized live-aboard vessels which are not docked within marinas. Live-aboard vessels moored outside of marinas shall be required to utilize pump-out facilities or a municipal sewer facility if they are moored for over three (3) days.~~
- ~~D. The County shall coordinate with the Marine Patrol to eliminate live-aboards permanently anchored outside of a marina or area specially designated for live-aboards.~~
- ~~E. Floating structures shall be required to moor within marinas or to privately owned riparian property and shall be connected to pump-out facilities or a municipal sewer facility.~~
- ~~F. Live-aboards shall be considered as part of the community and will be considered as residential units when assessing impacts of such development on community facilities and services.~~

Policy 5.3 CM 5.2

Retrofitting or modification of existing marina facilities within the coastal zone shall be required to meet the criteria within the MPP, as amended, and the following minimum criteria:

Criteria:

- A. Stormwater retention/detention requirements as established by county and state stormwater management criteria. in the Stormwater Management Criteria Ordinance as adopted on August 23, 1993.
- B. Substantially expanded marina facilities shall retain all work area runoff. For those projects with combined detention areas of five (5) acres or greater, the work area runoff shall be retained in a separate retention area. In addition, the first inch of stormwater runoff from a 10-year, 24 hour storm event shall be retained on site or shall meet the water quality standards as required by the state, whichever is more restrictive. For projects with a combined detention area of less than five (5) acres, stormwater and work area runoff may be retained in a single retention/detention area.
- C. When ten (10) slips or ten (10) percent or more of the total number of slips, whichever is greater, are added, pumpout pump-out facilities shall be required, as recommended by the Marine Sanitation Study (1990), sufficient to accommodate the pump-out requirements concurrent with the total number of slips.
- D. Prior to operation of any new marina fueling facility or expansion due to an existing facility, a fuel management/spill contingency plan will be developed and provided to the Natural Resources Management Department for review. The plan shall describe methods to be used in dispensing fuel and all the procedures, methods, and materials to be used in the event of a fuel spill.
- E. Brevard County shall review all proposed modification of existing marina facilities in coordination with FWC for compliance with the MPP.

Policy 5.4 CM 5.3

Brevard County shall continue to implement standards for marina and boat ramp siting within the coastal zone which shall address the following criteria at a minimum:

Criteria:

- A. All proposed marina siting projects in unincorporated areas of Brevard County shall come before the Board of County Commissioners for their review. Marina development may be considered within any appropriate zoning classification, if it is consistent with the performance standards developed by the County. Uplands at the marina site shall be greater than or equal to one acre. Residential marinas shall be allowed as a permitted use, subject to the boat facility siting criteria ~~established in section B below~~

COASTAL MANAGEMENT ELEMENT

within the MPP, as amended, and in the policies under Objectives CON 3 and CON 9 of the Conservation Element, in all of the current conditional use zoning classifications for residential/recreational marinas, except Recreational Vehicle Park (RVP) and Government Managed Lands (GML).

- B. At the beginning of the zoning or development order application process, all marina and boat ramp development proposals must submit a conceptual plan to be reviewed by the Natural Resources Management Department and FWC for compliance with the following boat facility siting criteria within the MPP, as amended.:-

PRELIMINARY ASSESSMENT CRITERIA

The following listed criteria are recommended as the preliminary test of suitability for boat facility siting:-

1.—Water Depth

- a. ~~Water depth at the proposed mooring area of the site shall be at least four (4) feet mean low water.~~
- b. ~~Water depth at the site must be adequate for the proposed vessel use such that there be a minimum of one foot clearance between the deepest draft of the vessel (including the engine) and the bottom at mean low water.~~
- c. ~~Proposed boat facilities in areas that contain seagrass shall not be approved unless water depth at the site's turning basin, access channel, and other such areas will accommodate the proposed vessel use to insure that a minimum of one (1) foot clearance is provided between the deepest draft of the vessel (including the engine) and the top of the resources at mean low water.~~

2.—Seagrass

- a. ~~Marinas shall not be located in areas containing 10% or more seagrass.~~
- b. ~~Designated boat docking areas shall not be located over seagrasses.~~
- c. ~~Covered boat slips, covered walkways, or covered terminal platforms shall not be permitted in areas containing seagrass.~~
- d. ~~Boat docks using open mesh grating and pilings made from recycled materials (plastic/wood composites for example) are preferred to pressure treated wood. Any materials or permitted construction techniques proven to allow a minimum of 75% light transmittance may be exempt from design criteria e and f below in this subsection.~~
- e. ~~For Residential Marinas, main access docks and connecting or crosswalks shall not exceed six (6) feet in width.~~
- f. ~~Access piers should be located and designed to minimize their shadowing impact on seagrass.~~
- g. ~~Reasonable alteration to these criteria may be authorized to accommodate persons with disabilities.~~

COASTAL MANAGEMENT ELEMENT

- 3.—Manatee Related Best Management Practices
- a.—Dock designs shall not entrap manatees or otherwise prevent them from accessing forage areas.
 - b.—Docks with exposed reinforcement structures on floating docks shall be prohibited due to their potential to entrap or entangle manatees in the structure itself or in the marine debris that commonly occurs in these areas.
- 4.—Water Quality
- a.—New seawalls or bulkheads should be prohibited along the Indian River Lagoon except as provided in Brevard County Code Section 62-3666 or when the project would improve the water quality by acting as a swale and reducing the amount of pollutants which would enter the Indian River Lagoon, where the placement of a seawall does not disturb existing native vegetation, prohibit the reestablishment of native vegetation, or where the reestablishment of native vegetation is not viable.
 - b.—All facilities shall adhere to the provisions for surface water protection per the guidelines set forth in Brevard County Code Section 62-3666. The provisions for a shoreline protection buffer established in the Code and Conservation Element (CE) policies include the following:
 - Class I waters - 200 foot buffer — Conservation Element Policy 3.2 A
 - Class II waters - 50 foot buffer — Conservation Element Policy 3.3 A
 - Class III waters - 25 foot buffer — Conservation Element Policy 3.4 A
 - On lots with unarmored shorelines the waterward extent of the buffer is the mean high water line. On bulkheaded lots, the waterward extension of the buffer is established by the bulkhead line. A maximum width of 25 feet or 20% (whichever is greater) may be cleared for access.
- 5.—Powerboat-To-Shoreline Ratios
- a.—Boat Facility Siting Zone A: In Boat Facility Siting Zone A, powerboat siting ratios shall be limited to one powerboat slip per 100 feet of contiguous linear shoreline that is owned or legally controlled by the applicant, as applied to all new and expanding boating facilities. Boat facilities in Zone A may qualify for a variance under Section e, Variance Criteria. Also, the establishment of new boating research, design, development or manufacturing facilities whose operations include on-water testing of motorized watercraft, are prohibited from locating in uplands within Boat Facility Siting Zone A.
 - b.—Boat Facility Siting Zone B (Barge Canal): In Boat Facility Siting Zone B along the Barge Canal (as defined), powerboat siting ratios shall be limited to a 1:100 powerboat-to-shoreline ratio (tied to a parcel's deed). Any boat facility, which desires to exceed the 1:100 powerboat-to-shoreline ratio, must acquire additional development rights from other properties, which have linear shoreline parallel to the Barge Canal and adjoin the Port Canaveral control easement. Any development rights

COASTAL MANAGEMENT ELEMENT

transferred must be recorded on both the selling and receiving parcels deeds.

- c. ~~Boat Facility Siting Zone C (Port Canaveral Harbor): In Boat Facility Siting Zone C, there shall be no powerboat-to-shoreline restrictions within the Canaveral Harbor provided current slow speed regulations remain in effect.~~
- d. ~~Boat Facility Siting Zone D: The map features described in Table 1 below are to be applied in Boat Facility Siting Zone D. Manatee habitat feature points per Table 1 shall be determined using the map series and data update schedule identified in Appendix C of this Element and using current site surveys for seagrass. In Boat Facility Siting Zone D, Manatee habitat feature points from Table 1 shall be summed and the sum shall be used in Table 2 below to determine the applicable powerboat-to-shoreline ratio per 100 feet of contiguous owned or controlled linear shoreline.~~

Limiting Habitat Features	Criteria for Evaluation (each increases the number of habitat features by 1, unless otherwise specified)
Manatee Abundance	1st level: 10 or more manatees observed/overflight within 5 mile radius (1 point) 2nd level: 25 or more manatees observed/overflight within 5 mile radius (2 points)
Manatee Mortality	1st level: # of watercraft mortalities within a 5-mile radius/total number of watercraft mortalities in Brevard (≥ 0.05 is significant) (1 point) 2nd level: # of watercraft-related deaths within a 5 mile radius in the last 5 years/total number of watercraft mortalities in Brevard in the last 5 years (> 0.10 is significant) (2 points)
Seagrass	5% or more present on the project site is significant
Class II, OFW, or Aquatic Preserves	Site is located in one of these designated areas
Offsetting Features	Criteria for Evaluation (each decreases the number of habitat features by 1)
Speed Zones	Site is located within a year-round "Slow Speed" or "Idle Speed" Zone
Within 3 miles of Sebastian inlet	Site is located within 3 mile radius of Sebastian Inlet

Table 1

# Manatee Habitat Features	Existing Facility	New Facility
0	5:100	4:100
1	5:100	4:100
2	3:100	2:100
3	2:100	1:100
4	1:100	1:100
5	1:100	1:100
6	1:100	1:100

Table 2

- e. **Variance Criteria:** It is recommended that a variance may be given to the powerboat-to-shoreline ratio for those existing marina and boat launching facilities subject to the 1 powerboat slip to 100 feet of owned contiguous shoreline restriction (1:100), provided the facility meets all the variance criteria listed below and can demonstrate that it will not have an adverse impact on manatees. If an existing facility meets all of the variance criteria, it may be permitted to increase the powerboat-to-shoreline ratio by 1:100 if the waters in and adjacent to the channels leading to the facility are designated "slow speed" or "idle speed" year-round as authorized by the Florida Manatee Sanctuary Act Chapter 68G-22.003, F.A.C. or other federal regulations or local ordinances, or if the facility is within 3 miles of the Sebastian Inlet. The facility may be allowed to increase the powerboat-to-shoreline ratio by 2:100 if both are applicable. In no case shall the maximum total buildout of 3 powerboat slips per 100 feet of owned contiguous shoreline (3:100) be exceeded. However, adherence to these criteria does not automatically ensure the applicant's ability to exceed the allowable powerboat restrictions as defined above. The plan restrictions will remain in effect, if at the time of review, additional information about manatees or the proposed facility indicates threats not addressed by these criteria. Consideration can be given for additional site-specific factors or operating practices (e.g. seasonal operation, etc.) that may be proposed by either the applicant or the County that may result in improved conditions for manatees or manatee protection. Nothing in this section shall exempt any marina from obtaining the usual required permits and/or authority from all applicable reviewing agencies with proper jurisdictional authority.

Criteria:

- 1) The facility is not located within a 1st- or 2nd-level manatee aggregation area (using the Manatee Abundance Habitat Feature as defined in 5 d

of this Policy and in the Table above), or other area where sensitive manatee activities occur.

- ~~2) The facility must provide net benefit to manatees and/or their habitat. For example, facilities may include a manatee “refuge” space as part of the design, a conservation easement, restoration of adjacent wetlands such as mangrove or seagrass restoration to increase the net coverage of the nearby area, reduced nutrient input to receiving waters, requiring prop guards on any high traffic vessels such as water taxis or dive boats or rental boats, etc. The marina construction and subsequent uses will neither destroy nor negatively impact mangrove and benthic (seagrass, hard bottom, etc.) communities and the water quality.~~
 - ~~3) The facility must have sufficient water depth, as stated in B. 1. a. of this Policy, in the marina basin and in any access channel, and does not require any new dredging or filling that would degrade shallow water habitat (this may exclude maintenance dredging, or pile installation). Entrance/exit channels near marinas shall be adequately marked if marina repairs or expansion are proposed.~~
 - ~~4) The site shall contain appropriate signage (including vessel speed and manatee information signs), and provide educational material advising boaters of essential manatee habitats in the vicinity.~~
 - ~~5) Multi-family residential docking facilities will require that all vessels moored at the site be registered to individuals residing at the site.~~
 - ~~6) The marina has adequate water circulation, tidal flushing, and meets State of Florida and local water quality standards.~~
 - ~~7) Before expanding and exceeding the allowable powerboat slips defined above, an existing facility must demonstrate not less than 85% occupancy over the previous 2 years of operation. New facilities should be able to demonstrate the need for additional boat slips in the vicinity based on occupancy of existing marina slips within the boater sphere of influence. The boater’s sphere of influence shall be a five (5) mile radius.~~
6. ~~Boat Ramps~~
- In order to minimize adverse impacts to manatees, boat ramps are best located in areas with few natural resources, with relatively low manatee abundance and relatively low watercraft-induced manatee mortalities, and with deep water access and marked navigation channels. Boat ramp siting or expansion in Brevard County shall be evaluated using the following criteria:

- a. ~~All sites considered by Brevard County for new or expanded boat ramp facilities shall be evaluated for site suitability prior to acquisition and development.~~
- b. ~~All proposed new boat ramps or the expansion of existing boat ramps in the unincorporated areas of Brevard County shall be brought before the Board of County Commissioners for their review.~~
- c. ~~The siting of new or the expansion of existing boat ramp facilities shall be limited to areas that meet the Preliminary Assessment Criteria for water depth stated in section B. 1. a. of this Policy.~~
- d. ~~The siting of new or the expansion of existing boat ramp facilities shall be prohibited in areas that meet or exceed the 2nd level of manatee abundance or the 2nd level of manatee mortality as shown in Table 1 above.~~
- e. ~~The siting of new or expansion of existing boat ramp facilities shall be prohibited in areas with greater than 5% seagrass coverage including all ramps, docks, access walkways, finger piers, mooring areas, turning basins, and ingress and egress pathways.~~
- f. ~~The siting of new or the expansion of existing boat ramp facilities shall be required to meet the criteria included in Policy 3.3 E of the Conservation Element and Section B. of this Policy with the exception of Seagrass (5.4 B. 2.), Manatee Related Best Management Practices (5.4 B. 3.), and Water Quality (5.4 B. 4.).~~
- g. ~~All sites considered for the siting of new or the expansion of existing boat ramp facilities shall be evaluated for the number of habitat features present using the Boat Ramp Feature Assessment table below and using the manatee mortality and abundance criteria as defined under Manatee Habitat Features in the glossary.~~
- h. ~~Boat Facility Siting Zone A is not considered preferable for additional boat ramp siting due to the high number of habitat features present. In Boat Facility Siting Zone A, a site that has less than 2 habitat features based on the criteria in the Boat Facility Feature Assessment may be considered for a new or expanded boat ramp with up to a maximum of 15 parking spaces.~~
- i. ~~In Boat Facility Siting Zone B (Barge Canal), the establishment of a new public or private boat ramp for public use shall be the same requirements as for the development of a new or expanded marina as described in Boat Facility Siting Zone B (5.4 B. 5.). For the purposes of boat ramps, one boat-trailer parking space shall be considered the equivalent of one powerboat slip. New or expanded boat ramps on the Barge Canal which are associated with a marina and which are to be used solely by the tenants of that marina for the launching of boats stored at that marina shall not be limited in the number of parking spaces.~~

COASTAL MANAGEMENT ELEMENT

j.—In Boat Facility Siting Zone C (Port Canaveral Harbor), the siting of new or expansion of existing boat ramps shall be unrestricted.

LIMITING HABITAT FEATURES	Criteria for Evaluation (each increases number of habitat features by 1, unless otherwise specified)
Manatee Abundance	1st level: 10 or more manatees observed/overflight within 5 mile radius (1 point) 2nd level: 25 or more manatees observed/overflight within 5 mile radius (2 points)
Manatee Mortality	1st level: # of watercraft mortalities within a 5 mile radius/total number of watercraft mortalities in Brevard (≥ 0.05 is significant) (1 point) 2nd level: # of watercraft-related deaths within a 5 mile radius in the last 5 years/total number of watercraft mortalities in Brevard in the last 5 years (> 0.10 is significant) (2 points)
Class II, OFW, or Aquatic Preserves	Site is located in one of these designated areas
Offsetting Features	Criteria for Evaluation (each decreases the number of habitat features by 1)
Speed Zones	Site is located within a year-round “Slow Speed” or “Idle Speed” Zone
Within 3 miles of an inlet	Site is located within 3 mile radius of Sebastian Inlet

Table 3
Boat Ramp Feature Assessment

k.—In Boat Facility Siting Zone D, a site with no more than 2 habitat features shall be considered suitable for siting of a new boat ramp or the expansion of an existing boat ramp. Sites with 0 or 1 habitat feature shall be eligible for a boat ramp with up to a maximum of 40 boat trailer parking spaces. Sites with 2 habitat features shall be eligible for a boat ramp with up to a maximum of 15 boat trailer parking spaces.

t.—Boat Ramp Variance Criteria: The ability to secure additional parking slots at public ramps could be reconsidered by the FWC if additional law enforcement, additional preservation, or impact reduction along the lagoon is demonstrated.

m. The following specific sites are identified individually to address existing boat ramp deficiencies in Brevard County and are exempted from the boat ramp siting criteria above:

- 1) It is recommended that Brevard County’s relocation of the Pineda Landing facility include 36 parking spaces.
- 2) It is recommended that Brevard County provide 50 additional parking spaces by expanding existing public ramp facilities or by developing a

COASTAL MANAGEMENT ELEMENT

~~new location in the south mainland area. The expansion of an existing facility or the siting of a new facility, as provided for above shall minimize impacts to manatees and natural resources and should be evaluated by the Boat Ramp Manatee Habitat Feature Assessment as defined above. It is recommended that the evaluation result in a score of no greater than two habitat features. The County will screen sites to select the most appropriate and coordinate with FWC staff on the site selection.~~

- ~~G. Commercial/industrial and commercial/recreational marina development within commercial, heavy and light industrial and planned industrial park land use designations shall require a Conditional Use Permit. Residential/recreational marinas shall be a permitted use in these land use designations.~~
- ~~D. Residential/recreational marinas may be considered within residential land use designations with a Conditional Use Permit and a Binding Development Plan.~~
- ~~E. No fueling or repair facilities are permitted within residential zoning classifications.~~
- ~~F. When locating new marinas or expanding existing marinas, biologically productive habitats shall be preserved to the fullest extent possible. Mitigation is the last resort for habitat destruction, and shall be of a two-to-one or greater ratio of in-kind replacement.~~
- ~~G. Marina facilities shall be located where maximum physical advantage for flushing and circulation exists, where the least dredging and maintenance are required, and where marine and estuarine resources will not be significantly affected.~~
- ~~H. Marina basins shall be sited where there is an existing basin and access channel with an average water depth of three (3) feet below mean low water, except at the shoreline.~~
- ~~I. Marinas and docking facilities should be approved which require minimal or no dredging or filling to provide access by canal, channel or road. Preference shall be given to marina sites with existing channels. In the event that dredging is required, the mooring areas and the navigation access channels shall not be dredged to depths greater than eight (8) feet. Any required dredging operations shall utilize appropriate construction techniques and materials to comply with state water quality standards, such as turbidity screens, hydraulic dredges, properly sized and isolated spoil deposition area~~

COASTAL MANAGEMENT ELEMENT

~~to control spoil dewatering. All dredging activities must be done with effective turbidity controls. Where turbidity screens or similar devices are used, they should be secured and regularly monitored to avoid manatee entrapment.~~

- ~~J. —Marinas shall be located in areas with good flushing and circulation. New marina or substantially expanded facilities shall be designed to take advantage of existing water circulation and shall not adversely affect existing circulation patterns. Improvement of circulation shall be a consideration when expanding or upgrading existing facilities. However, any buffer zone established by the Florida Department of Environmental Protection Shellfish Environmental Assessment Section (FDEP-SEAS) shall be maintained.~~
- ~~K. —The proposed site shall be compatible with existing land use designations. Marinas shall demonstrate that they have sufficient upland areas to accommodate all needed support facilities. These standards include, but should not be limited to, adequate parking, work areas and retention areas for stormwater and work area runoff, and shoreline protection buffers.~~
- ~~L. —Marina facilities shall not degrade water quality below existing Florida Department of Environmental Protection water classification standards.~~
- ~~M. —Marinas shall not be located in approved or conditionally approved shellfish harvesting waters or Class II waters, or other environmental areas designated by the County so as to substantially and materially have a negative impact on these waters.~~
- ~~N. —Commercial/recreational and commercial/industrial marinas shall not be located in Aquatic Preserves, or Outstanding Florida Waters, or other environmental areas designated by the County so as to substantially and materially have a negative impact on these waters.~~
- ~~O. —Construction of multi-slip docking facilities and boat ramps shall be directed to locations where there is quick access to deep, open water at least eight (8) feet in depth (dredgeable), where the multi-slip docking facilities take the place of several single-slip docks and allow public access to the water, and where the associated increase in boat traffic will be outside of known manatee aggregation areas, and where seagrass beds or other wetlands supporting manatee habitat will not be disturbed.~~
- ~~P. —All marina facilities shall comply with manatee protection measures established in Conservation Element Policy 9.9:~~

COASTAL MANAGEMENT ELEMENT

Policy 5.5 CM 5.4

Brevard County shall require hurricane plans to be submitted to the Florida Division of Emergency Management in conjunction with marina site plans for review.

Policy 5.6 CM 5.5

Marinas within the coastal zone shall be inspected ~~annually~~ periodically by Brevard County and results of these inspections shall be coordinated with other agencies. Inspections shall be coordinated with existing programs and duplication with existing inspection programs shall be avoided. It is recommended that inspection of commercial marinas occur as part of the business ~~license~~ tax receipt renewal procedure. Items to be inspected and reviewed may include the following.

Criteria:

- A. ~~Pumpout~~ Pump-out facilities and marine sanitation devices, if required.
Live-aboards and floating structures at marinas shall be inspected to ensure that marine sanitation devices are present and operational.
- B. Compliance with power/sailboat mix, if required.
- C. Spill prevention, control, containment and cleanup plans.
- D. Waste collection and disposal methods.
- E. Fire fighting equipment, if required.
- F. Monitoring of marina basin water quality for bacteriological levels to ~~insure~~ ensure compliance with state and federal standards. ~~Live-aboards at marinas shall be inspected to ensure that marine sanitation devices (MSDs) are present and operational.~~ If a water monitoring program is required, water-dependent uses shall be assessed an annual fee adequate to fund a water quality monitoring program.

Policy CM 5.6

Brevard County should continue to develop and implement regulations governing live-aboards within the coastal zone. The regulations shall include the following criteria at a minimum:

Criteria:

- A. Floating structures shall be considered within live-aboard regulations.
- B. The County shall investigate designating certain areas of the Indian River Lagoon for mooring of live-aboard vessels that are not docked within marinas. Live-aboard vessels moored outside of marinas shall be required

COASTAL MANAGEMENT ELEMENT

to utilize pump-out facilities or a municipal sewer facility if they are moored for over three (3) days.

- C. The County shall coordinate with the Marine Patrol and Coast Guard to eliminate live-aboards permanently anchored outside of a marina or area specially designated for live-aboards.
- D. Floating structures shall be required to moor within marinas or to privately owned riparian property and shall be connected to pump-out facilities or a municipal sewer facility.
- E. Live-aboards and floating structures shall be considered as part of the community and will be considered as residential units when assessing impacts of such development on community facilities and services.
- F. The County shall investigate the management of live-aboards through the designation of certain areas of the Indian River Lagoon as Anchoring Limitation Areas.

Policy CM 5.7

Brevard County shall investigate the utilization of tourist taxes or boating improvement funds to develop public boat launching facilities and related amenities.

Policy CM 5.8

Brevard County should consider the acquisition of property for boat ramps in their recreational purchasing program.

Policy CM 5.9

All new boat ramps should have parking areas constructed utilizing permeable pavement where appropriate and have the proper stormwater management system in place.

Policy CM 5.10

Brevard County shall review shoreline development within the coastal zone in order to maximize opportunities for water-dependent land uses. The following criteria, at a minimum, shall be utilized.

Criteria:

- A. Water-related and water-enhanced uses shall be built on uplands.
- B. Development which is feasible only through creation of land by dredging and filling of areas below the mean high water line shall not be approved. Exceptions may be considered where overriding public benefit to the natural resource can be demonstrated.

- C. Water-dependent commercial and industrial uses may be considered for siting adjacent to the Indian River Lagoon.
- ~~D. Water-related commercial and industrial uses may be considered for siting only adjacent to Class III waters of the Indian River Lagoon.~~

Policy CM 5.11

The Brevard County Land Development Regulations shall include a provision for water-enhanced commercial development uses within the coastal zone. Such uses shall be permitted as Conditional Uses within the BU-1 zoning category.

Policy CM 5.12

Brevard County ~~should develop and implement a~~ supports the development and implementation of water and sediment quality monitoring ~~program~~ programs for water-dependent users, man-made canals, and other selected areas with significant upland runoff within the coastal zone.

Criteria:

- ~~A. Brevard County shall establish a classification program for the various water dependent uses.~~
- ~~B. Brevard County shall establish a water quality monitoring program for each of the designated classes of water dependent uses.~~
- ~~C. Water-dependent uses shall be assessed an annual fee adequate to fund the required water quality monitoring program.~~
- ~~D. The County shall require the activity to cease if adopted water quality standards are not maintained.~~
- ~~E. Continued operation resulting in degradation of the water quality below accepted standards shall result in a fine, as established by Brevard County.~~
- ~~F. Waiver provisions should be included for operations below an established threshold.~~
- ~~G. This program shall be in coordination with the Florida Department of Environmental Protection and other appropriate agencies.~~

Policy 5.13

Brevard County shall support environmentally and economically sound development of Port Canaveral and related facilities, which is consistent with this Comprehensive Plan (Policy 5.4 of the Transportation Element).

Policy ~~5.14~~ CM 5.13

Brevard County should continue to monitor boating activity and boat facility demand.

Policy ~~5.15~~ CM 5.14

During rezoning and other development order approval reviews, Brevard County should give immediate shoreline use priorities (in descending order of priority) to:

Criteria:

- A. Water-dependent uses such as fish, shellfish and wildlife production, recreation, water dependent industry and utilities, marinas, and navigation;
- B. Water-related uses such as certain utilities, ~~commerce~~ commercial, and industrial uses;
- C. Water-enhanced uses such as some recreation uses;
- D. Non-water dependent or related activities such as residential; and
- E. Of lowest priority are those uses which are non-water-dependent, non-water enhanced, and which result in an irretrievable commitment of coastal resources.

Policy ~~5.16~~

~~Brevard County should encourage the construction of marine sanitation device (MSD) pumpout facilities.~~

Policy ~~5.17~~ CM 5.15

Brevard County shall utilize available management plans in developing standards for marina siting and other water-dependent uses. These management plans include, but are not limited to, Aquatic Preserve Management Plans, the Surface Water Improvement Management (SWIM) Plan and the ~~RLCCMP~~ CCMP.

Coastal High Hazard Areas

Objective CM 6

Limit future public expenditures for infrastructure and service facilities which subsidize growth within the coastal high hazard areas of Brevard County. Expenditures for public land acquisition or enhancement of natural resources shall be encouraged.

Policy CM 6.1

Brevard County shall designate coastal high hazard areas to be those areas below the elevation of the Category 1 storm surge elevation as established by a Sea, Lake and

Overland Surges from Hurricanes (SLOSH) computerized storm surge model, as defined in Chapter 163, Florida Statute.

Policy ~~CM~~ 6.2

Brevard County shall not support or finance new local transportation corridors which lie within the coastal high hazard area or areas zoned as Environmental Area, except where there are no other cost-feasible alternatives. Corresponding improvements may only be considered when the facilitation of such improvements is needed to support the densities programmed on the Future Land Use Map (FLUM) series of the Comprehensive Plan or for the protection of the transportation facilities from flooding and storm surge.

Policy ~~CM~~ 6.3

Brevard County should not locate sewer and water transmission lines within the coastal high hazard area, except where there is no practical and cost-feasible alternative due to engineering, safety and cost considerations, lack of alternative existing rights-of-way, or for septic to sewer conversion projects selected specifically to improve ground and surface water quality. Such transmission lines shall be designed to withstand flooding and storm surge.

Policy ~~CM~~ 6.4

If County utility lines are relocated for any purpose, they should be located outside of the coastal high hazard area, except where there is no cost-feasible alternative.

Policy ~~CM~~ 6.5

Public facilities, except for recreational facilities, shall not be located by Brevard County within the coastal high hazard area, except where there are no other cost-feasible alternatives. Corresponding improvements may only be considered when the facilitation of such improvements is needed to support the densities programmed on the ~~Future Land Use Map (FLUM)~~ FLUM series of the Comprehensive Plan, to improve surface or groundwater quality, or to provide for resiliency from flooding and storm surge.

~~Policy 6.6~~

~~Brevard County shall continue to implement the Transfer of Development Rights program which has been established to transfer density from transfer districts within the coastal high hazard area to receiving districts outside of the coastal high hazard area.~~

~~Policy 6.7~~ CM 6.6

Brevard County shall review federal and state development proposals which are to be located within the coastal high hazard areas and shall support those projects which are consistent with this Plan.

~~Policy 6.8~~ CM 6.7

The existence of sewer, water, roadways, or other public infrastructure shall not be considered adequate rationale for an increase in zoning density or intensity within the coastal high hazard area.

Policy ~~6.9~~ CM 6.8

Once public acquisition of recreation and/or conservation lands occurs within coastal high hazard areas, the ~~Future Land Use Map~~ FLUM shall be amended to designate the same as Recreation or Conservation lands. Such redesignation shall not serve as a basis for increasing established residential density designations in said coastal high hazard area.

Coastal Residential Densities

Objective CM 7

Limit densities within the coastal high hazard area and direct development outside of this area.

Policy CM 7.1

Brevard County shall not increase residential density designations for properties located on the barrier island between the southern boundary of Melbourne Beach and the Sebastian Inlet.

~~Policy 7.2~~

~~Brevard County shall continue its program of land acquisition and management for recreation and preservation, contingent upon availability of funding.~~

~~Policy 7.3~~

~~Brevard County shall maintain the Brevard County Comprehensive Emergency Management Plan (BrevCEMP). This plan shall be consistent with this Comprehensive Plan, and shall be coordinated with the municipalities, the appropriate state and federal agencies, and be approved by the appropriate state agency(s).~~

~~Policy 7.4~~

~~Public facilities, such as hospitals, wastewater treatment plants or fire stations, shall not be located on causeways.~~

Hurricane Evacuation

Objective CM 8

Reduce excessive evacuation times where they currently exist; and maintain all other evacuation times within the acceptable standard. ~~Acceptable evacuation standards will be reviewed and updated as necessary but shall not exceed the times indicated in the current Brevard County Comprehensive Emergency Management Plan.~~ Evacuation clearance times are determined by the most current Florida Regional Evacuation Study maintained by

COASTAL MANAGEMENT ELEMENT

the East Central Florida Regional Planning Council. Evacuation times are adopted in the Brevard County Comprehensive Emergency Management Plan (Brevard CEMP), Evacuation Concept of Operations.

Policy CM 8.1

Brevard County shall maintain acceptable hurricane evacuation times based upon the following:

Criteria:

- A. ~~The most current behavioral response scenario. The information contained in the Florida Regional Evacuation Study.~~
- B. ~~The requirement to evacuate prior to sustained~~ The goal to complete all evacuations prior to the onset of tropical storm force (40 39 mph) winds, as outlined in the Evacuation Concept of Operations.

Policy CM 8.2

~~Brevard County shall coordinate with the municipalities and appropriate state agencies to develop Evacuation Zone Management Plans to reduce evacuation times above the current optimum behavioral response time. The following shall be considered, at a minimum:~~ all appropriate agencies and manage the planning for, and implementation of, evacuations as outlined in the Evacuation Concept of Operations.

Criteria:

- A. ~~Roadway and other infrastructure improvements and funding mechanisms.~~
- B. ~~Programs designed to improve the behavioral response to hurricane evacuation orders.~~
- C. ~~Land use strategies.~~

Policy 8.3

~~Brevard County Emergency Management shall continue to coordinate with NASA to allow evacuation of North Merritt Island through Kennedy Space Center, if necessary.~~

Policy 8.4 CM 8.3

~~Brevard County shall identify roadway and operational improvements to the hurricane evacuation network based upon the number of people who cannot be evacuated within an optimum evacuation time limit~~ capabilities, limitations, and vulnerabilities.

Criteria:

- A. ~~Priority shall be given to improvements of roadway networks serving the zone hurricane evacuation routes with the highest greatest number of people remaining after the current optimum evacuation time.~~
- B. ~~The remaining improvements shall be given priority in descending order according to the number of people remaining after the optimum evacuation time. Priority will be given to enhancing roadway networks that service~~

COASTAL MANAGEMENT ELEMENT

evacuation zones, with an emphasis on improvements that facilitate the movement of the largest volume of people.

- C. Brevard County, in cooperation with the Florida Department of Transportation, shall identify key hurricane evacuation routes that are vulnerable to flooding, erosion and critical points of congestion during the established evacuation time.
- D. Brevard County shall present recommended roadway, operational and maintenance improvements to the appropriate implementing and funding agencies.

Policy 8.5 ~~CM 8.4~~

In those areas where citizens cannot be evacuated within the ~~evacuation standards in the Brevard County Emergency Management Plan adopted January 1, 2008; adopted evacuation clearance times outlined in the Florida Regional Evacuation Study.~~ development orders may be deferred until such time as adequate evacuation capacity has been programmed.

Policy 8.6 ~~CM 8.5~~

Brevard County shall consider hurricane evacuation times, as well as other factors, in determining the timing and priority of roadway improvements which are programmed by the Board of County Commissioners.

Policy 8.7

~~Brevard County shall cooperate with the Red Cross and other agencies to develop an on-going public education program to notify the public as to the necessity to evacuate as quickly as possible in order to reduce or eliminate evacuation times in excess of the optimum behavioral response time.~~

Policy ~~CM 8.6~~

Brevard County shall continue to conduct a robust public messaging campaign focused on ensuring residents know their risk, have a disaster supply kit, make a plan, stay informed, and get involved in their community preparedness, with an emphasis on how to evacuate quickly and safely.

Policy 8.8

~~Brevard County's Comprehensive Emergency Management Plan (BrevCEMP) shall be consistent with the state comprehensive emergency management plan.~~

Policy ~~CM 8.7~~

Brevard County shall make every effort to ensure the Brevard Comprehensive Plan and the Brevard CEMP are consistent and coordinated with all appropriate agencies and comply with all statutory requirements.

COASTAL MANAGEMENT ELEMENT

Policy 8.9 CM 8.8

Based upon hurricane vulnerability concerns and excessive evacuation times, new mobile home development or recreational vehicle parks shall not be permitted on the barrier island, to the extent permitted by law. Expansions to an existing mobile home development may be permitted if such development results in a decrease in land use intensity and an overall reduction in programmed residential densities and is consistent with the character of the surrounding area.

Policy 8.10 CM 8.9

Brevard County shall require a hurricane management plan which reduces excessive hurricane evacuation time for existing recreational vehicle park development within the south beaches.

Policy 8.11 CM 8.10

Brevard County shall encourage the State of Florida to identify a dedicated funding source for the improvement of primary hurricane evacuation routes, such as US 192, SR 528, SR 520 and Interstate 95. The funding source should be in addition to state and federal funds already received by Brevard County for urban area roadway improvements.

Hurricane Shelters**Objective CM 9**

Provide for adequate, safe hurricane shelter space to meet the needs of the at risk and special needs population ("shelter space" shall be considered to include both private and public shelters); those at risk from the impacts of hurricanes as identified in the Florida Statewide Emergency Shelter Plan.

Policy 9.1

Brevard County shall continue to cooperate with the Red Cross and State Emergency Management to provide an emergency shelter manager training course and encourage interested citizens of Brevard County to become shelter managers.

Policy CM 9.1

Brevard County shall continue to utilize the Brevard Emergency Support Team (BEST) program to train and staff shelters as outlined in the Shelter Concept of Operations.

Policy 9.2

Brevard County Office of Emergency Management shall continue to cooperate with the Red Cross to develop a public education program on hurricane preparedness, including the locations of hurricane evacuation shelters and the need for emergency shelter managers.

Policy CM 9.2

Brevard County shall continue to conduct a robust public messaging campaign focused on ensuring residents know their risk, have a disaster supply kit, make a plan, stay informed, and get involved in their community preparedness, with an emphasis on local sheltering options and what to expect when seeking public shelter.

Policy 9.3

~~Brevard County shall cooperate with the Red Cross in designating appropriate public and private structures as hurricane shelters.~~

Policy CM 9.3

Brevard County shall work with the State of Florida to designate appropriate public structures as emergency shelters as outlined in the most current Florida Statewide Emergency Shelter Plan.

Policy 9.4

~~Brevard County shall utilize the Housing and Human Services Department to provide appropriate facilities and adequate staffing for the special needs shelters.~~

Policy 9.5 CM 9.4

~~Brevard County shall support the School Board~~ Brevard Public Schools in their efforts to utilize enhanced hurricane emergency shelter protection standards for all reconstruction and new development ~~in accordance with FS 235.26 as outlined in the most current Florida Statewide Emergency Shelter Plan.~~

Policy 9.6

~~Public buildings within Brevard County should be reviewed to determine if qualified to be utilized as hurricane sheltering. Beginning in the year 2000, all newly constructed public buildings shall meet the criteria established for enhanced shelter protection in the State Requirements for Educational Facilities (SREF).~~

Policy 9.7

~~Brevard County shall study the feasibility of increasing residential construction standards to reduce hurricane shelter deficits and ensure the delivery of safe housing for citizens of Brevard County.~~

Policy 9.8 CM 9.5

~~Brevard County shall develop a hazard~~ maintain a local mitigation strategy in its land development regulations which prohibits the development of new recreational, mobile or manufactured housing and the expansion of existing recreational, mobile or manufactured housing unless the developer/owner has provided emergency sheltering sufficient to house a minimum of 50% of the residents of that development.

Policy 9.9 CM 9.6**COASTAL MANAGEMENT ELEMENT**

Brevard County will encourage all existing recreational, mobile or manufactured housing communities to have ~~emergency shelters and a hurricane management plan that will result in faster~~ to increase evacuation times for their residents.

Post-Disaster Redevelopment

Objective CM 10

Expedite post-disaster recovery and reduce or eliminate the future risk to human life, and public and private property from natural hazards via recovery and re-development strategies adopted in the ~~BrevCEMP~~ Brevard CEMP.

Policy CM 10.1

Brevard County shall review all non-emergency and long-term redevelopment proposals utilizing the following:

Criteria:

- A. If utility lines, including but not limited to sewer, water, gas, electric and cable TV, must be relocated after a storm event, they should be permanently located landward (west) of the ~~1986 FDEP Coastal Construction Control Line~~ Brevard County CSL and underground, except for feed lines servicing individual parcels. Repair of these lines on a temporary basis to protect health and safety shall be permitted in their existing locations.
- B. Underground storage tanks which are located seaward of the Brevard County ~~Coastal Setback Line (CSL)~~ CSL shall be relocated landward (west) of the ~~1986 FDEP Coastal Construction Control Line~~ Brevard County CSL.
- C. Water-dependent commercial uses seaward of the ~~1981 FDEP Coastal Construction Control Line~~ CCCL which are damaged by more than 50% of their assessed value or fair market value as determined by an MAI appraisal supplied by the property owner may be reconstructed seaward (east) of the ~~1981 FDEP CCCL~~ consistent with the coastal zone construction requirements.
- D. Water-related commercial uses seaward (east) of the ~~1981 FDEP Coastal Construction Control Line~~ CCCL which are damaged by more than 50% of their assessed value or fair market value as determined by an MAI appraisal supplied by the property owner should be relocated landward (west) of the

~~1981~~ FDEP CCCL unless the project has no feasible alternative and is found to be in the public interest.

- E. Water-enhanced commercial uses seaward (east) of the ~~1981 FDEP Coastal Construction Control Line~~ CCCL which are damaged by more than 50% of their assessed value or fair market value as determined by an MAI appraisal supplied by the property owner should be relocated landward (west) of the ~~1981~~ FDEP CCCL.
- F. If non-habitable minor structures which are damaged by more than fifty (50) percent of their assessed value or fair market value as determined by an MAI appraisal supplied by the property owner are reconstructed, they shall be relocated and constructed in compliance with coastal zone construction requirements.
- G. Brevard County should develop a program for the possible relocation of residential housing, if required after a natural disaster.

Policy 10.2

~~The replacement of infrastructure shall be constructed in conjunction with existing development or as part of an integral network of infrastructure.~~

Policy 10.3 CM 10.2

Brevard County should continue to analyze those public structures within the high risk vulnerability zone or coastal zone which are most likely to be damaged or destroyed during a hurricane. The analysis shall ~~be coordinated by the Planning and Development Department and~~ shall consider the following, at a minimum:

Criteria:

- A. The cost effectiveness of relocation versus repair shall be analyzed.
- B. Alternatives shall be considered in the light of mitigative impacts, growth management consistency, impacts to the public, timeliness, legal issues, environmental impacts and cost.
- C. The following alternatives, at a minimum, shall be analyzed:
 - 1. Repair of the structure to the pre-disaster conditions.
 - 2. Repair of the structure to the pre-disaster conditions with physical protective structures, as may be legally permissible, ~~such as seawalls or revetments~~ when consistent with policy 5 of this element and the Conservation Element.
 - 3. Vertical relocation of the structure, e.g. elevating roadways with bridges.
 - 4. Relocation further inland.

COASTAL MANAGEMENT ELEMENT

- D. Reconstruction or relocation of SR A1A and other roadway segments within the coastal high hazard area shall be included within this study.
- E. Analysis of County service center and other facilities shall be in conjunction with the County's Space/Needs Assessment.
- ~~F. Those structures within the high risk vulnerability zone to be included are the Central Brevard Service Complex, District II Commission Office, District II Road and Bridge, County Sign Shop, public libraries and County fire stations.~~
- ~~G.~~ F. The study shall be consistent with the East Central Florida Regional Planning Council studies. The hurricane scenarios and loss estimates shall be consistent with the Hurricane Loss Study Local Mitigation Strategy and shall be coordinated with other appropriate agencies.
- ~~H.~~ G. The impact of sea level rise and ~~the projected 30-year erosion line~~ erosion data shall also be analyzed.

Policy ~~10.4~~ CM 10.3

In the event of a disaster, all infrastructure and other County owned improvements, which were not included within the above outlined study, shall be analyzed to determine the cost effectiveness of relocation versus repair.

Policy ~~10.5~~ CM 10.4

The Brevard County shall provide copies of building permits which have been issued for storm damage repair to the ~~County Hazard Mitigation Team~~ Local Mitigation Strategy Steering Committee for their evaluation for identification of areas susceptible to repeated damage by hurricane erosion and flooding.

Policy ~~10.6~~ CM 10.5

Brevard County shall ~~continue to~~ conduct disaster ~~related~~ focused exercises with community partners at regular intervals, as determined by the Brevard Emergency Management Office, Department ~~or in conjunction with the East Central Florida Regional Planning Council, Local Emergency Planning Committee and other state or federal agencies.~~

Policy ~~10.7~~ CM 10.6

As identified in the ~~BrevCEMP~~ Brevard CEMP, Emergency Support Function ~~18 (ESF 18)~~ 19 (ESF 19) shall be the primary lead to conduct a post-disaster evaluation to assess property damages ~~necessary for disaster relief and post-disaster redevelopment funds.~~ The ESF 18 should have available a listing of property values coordinated with land use maps to facilitate such property assessment procedures. ~~County staff, such as the Planning and Development Department, will be utilized as manpower.~~ as outlined in the ESF 19 Annex.

COASTAL MANAGEMENT ELEMENT

Policy 10.8

~~The BrevCEMP shall be coordinated with other local, regional and state entities. As additional interagency hazard mitigation reports are received, they shall be reviewed and incorporated into the BrevCEMP.~~

Policy CM 10.7

Brevard County shall work to reduce the long-term risk of hazards to life, property, and the environment, focusing on coordination with partner agencies, municipalities, and the community, as outlined in the Local Mitigation Strategy and the Brevard CEMP.

Policy 10.9

~~Brevard County should require that when utility lines, including, but not limited to sewer, water, gas, electric and TV cable, are relocated for any purpose, they shall be placed underground.~~

Coastal Access**Objective CM 11**

Provide adequate public access to the beach, estuarine and river shorelines consistent with public needs and the shoreline's natural resource requirements.

Policy CM 11.1

Brevard County shall acquire new beach access sites, improve existing sites or provide alternative access to non-designated beach access points. The following minimum criteria shall apply:

Criteria:

- A. Acquisition and site improvements of those areas of the beach identified as most deficient for beach access shall be given the highest priority. Efforts shall be undertaken to provide public access to all of Brevard County's beaches consistent with the FDEP's criteria for state cost-share funding for beach management.
- B. Site improvements, parking facilities and drainage shall be secondary to improvements to the naturally functioning dune system.
- C. Access shall be consistent with the standards included in the Recreation and Open Space Element of this Plan.
- D. Priority shall be given to those sites which are heavily utilized for beach recreation.
- E. Brevard County shall make efforts to balance the demand for beach access with the protection of the beach and dune habitat and species.

COASTAL MANAGEMENT ELEMENT

Policy 11.2

~~Brevard County shall complete the Beach and Riverfront Acquisition Program, contingent upon availability of funding, with priority being given to the acquisition of land to fulfill the Identified Needs, as adopted by the Brevard County Board of County Commissioners.~~

Policy CM 11.2

Brevard County shall continue its program of land acquisition and management for recreation and preservation, contingent upon availability of funding.

Policy CM 11.3

Brevard County shall prioritize future improvements to those oceanfront properties, contingent upon availability of funding, which have been purchased and are identified for additional beach access development.

Policy CM 11.4

Brevard County shall continue to coordinate with all beachfront municipalities and appropriate agencies on the continued development and implementation of the Brevard County Beach Management Program. ~~The Beach Erosion Advisory Committee, established by Chapter 70-603, Laws of Florida, should continue to function as a mechanism to communicate with the beachfront municipalities and on beach-related issues and as the primary technical advisory committee to the Board of County Commissioners on the beach program.~~

Policy CM 11.5

Brevard County shall continue to pursue funds for dune revegetation to be used when constructing dune crossovers as replacements for unimproved dune access.

Policy CM 11.6

Brevard County shall coordinate with the Florida Department of Transportation in providing waterfront access on causeways and bridges.

Policy CM 11.7

Brevard County shall require private property owners to allow public use of beaches which are renourished with public funds. Access can be accomplished through publicly owned access points or improved dune crossovers located on easements.

Policy CM 11.8

Brevard County shall review beachfront development to ensure that it does not interfere with public access in those instances where the public has established ocean access-ways through private lands by prescription, prescriptive easement or other legal means. The developer may improve, consolidate, or relocate such public access provided it is consistent with this Plan.

Policy CM 11.9

Brevard County shall investigate the feasibility of acquiring narrow strips of land along the Indian River Lagoon, where such areas could provide visual access or provide parking for passive recreation within the Lagoon.

Port Canaveral

Objective CM 12

~~Brevard County will continue to identify provisions of the Port Master Plan which it considers inconsistent with the Coastal Management Element of the County Comprehensive Plan and will continue to offer to coordinate with Port Canaveral in resolving any inconsistencies and review its Port Master Plan for consistency with the County's policies. Brevard County shall continue to request copies of proposed plan amendments submitted for transmittal to the Department of Economic Opportunity and shall continue to review and comment on such amendments to the Port Master Plan consistent with the County's procedure for reviewing plans of other jurisdictions and Chapter 163.3177(6)(g)~~

Policy CM 12.1

~~Brevard county shall continue to request copies of proposed Port Master Plan amendments submitted for transmittal to state agencies and shall continue to review and comment on such amendments consistent with the County's procedure for reviewing plans of other jurisdictions and sections 163.3177(6)(g) and 163.3178, F.S.~~

Policy ~~12.1~~ CM 12.2

Brevard County shall continue to cooperate with the Port Canaveral Authority and the Florida Inland Navigation District in the identification of suitable spoil disposal sites within unincorporated Brevard County.

Recreational and Commercial Working Waterfronts

~~In 2005 and 2006, the Legislature recognized that there is an important state interest in facilitating boating and other recreational access to the state's navigable waters. This access is vital to recreational users and the marine industry in the state, to maintaining or enhancing the \$57 billion economic impact of tourism and the \$14 billion economic impact of boating in the state annually, and to ensuring continued access to all residents and visitors to the navigable waters of the state. The Legislature recognizes that there is an important state interest in maintaining viable water-dependent support facilities, such as~~

COASTAL MANAGEMENT ELEMENT

public lodging establishments, boat hauling and repairing and commercial fishing facilities; and in maintaining the availability of public access to the navigable waters of the state. The Legislature further recognizes that the waterways of the state are important for engaging in commerce and the transportation of goods and people upon such waterways and that such commerce and transportation is not feasible unless there is access to and from the navigable waters of the state through recreational and commercial working waterfronts.

The purpose of the Brevard County Working Waterfront Objective is to implement the relevant and mandated provisions of Chapter 2005-157, and Chapter 2006-220 of the Laws of Florida. The Legislature requires that local governments, through their comprehensive plans, address development activities that diminish access to the state's navigable waters. The recreation and open space element of all local comprehensive plans now must include waterways. (F.S. § 163.3177(6)(e)) In addition, all coastal counties and municipalities in Florida now have a legislatively-mandated duty to include, in the coastal management element of their Comprehensive Plan, strategies that will be used to preserve recreational and working waterfronts. (F. S. § 163.3178(2)(g)) Further, coastal counties must amend the future land use element of their comprehensive plan to create "regulatory incentives and criteria" that encourage the preservation of recreational and commercial working waterfronts. More specifically, the purpose is to protect and promote Brevard County as a recreational and commercial working waterfront community; protect and improve public access to the shorelines and waters of Brevard County; preserve and protect the cultural heritage and physical character of the area as a working waterfront community; and enhance the aesthetic character of the area by directing development in a manner that maintains the working waterfront identity of the County.

Objective CM 13

To establish a comprehensive program to promote and protect public access to the marine and coastal waters of the County, and to ensure the economic viability of recreational and commercial working waterfronts.

Policy CM 13.1

The County shall ~~identify, inventory and characterize~~ continue to maintain an inventory of all existing publicly-accessible recreational and commercial working waterfronts in Brevard County on a parcel-by-parcel basis, including but not limited to parking facilities for beach and shoreline access, coastal roads, facilities providing scenic overlooks, public lodging establishments, docks, wharfs, lifts, wet and dry marinas, boat ramps, boat hauling and repair facilities, commercial fishing facilities, boat construction facilities, and other support structures over the water ~~and shall continue to maintain this inventory.~~

Policy CM 13.2

The County shall ~~identify, inventory and characterize~~ continue to maintain an inventory of all private facilities that would otherwise qualify as recreational or commercial

COASTAL MANAGEMENT ELEMENT

working waterfronts because they provide access to the marine and coastal waters of the County and shall continue to maintain this inventory.

Policy CM 13.3

The County should ~~identify, inventory and characterize~~ continue to maintain an inventory of all parcels suitable for future development as publicly-accessible recreational and commercial working waterfronts in Brevard County. Suitable for future development includes vacant parcels and developed parcels not currently being used for water dependent activities which, because of their proximity, biophysical nature or other factors, could become recreational and commercial working waterfronts through a change in land use.

Policy CM 13.4

The County should ~~identify, inventory and characterize~~ continue to maintain an inventory of existing right-of-ways ~~rights-of-way~~, easements and other public property interests adjacent to or capable of providing public access or enhancing public access to the shorelines and waters of Brevard County.

Policy CM 13.5

The County should continue to monitor boating activity and boat facility demand and assess the future demand for public water access to the shorelines and waters of Brevard and ~~shall establish activity-based levels of service standards for public water access.~~

Policy CM 13.6

The Brevard Marine Advisory Council shall continue to review and make recommendations to the Board concerning recreational and commercial working waterfronts in Brevard County.

Policy CM 13.7

The County shall continue to develop strategies to ensure continued public access to navigable waters through the identification and implementation of regulatory incentives and criteria.

Policy CM 13.8

The County shall prioritize recreational and commercial working waterfronts in existing or new land acquisition programs to purchase suitable parcels or the non-water dependent development rights to suitable parcels as determined by the ~~inventory inventories~~ created under the ~~Coastal Management Element of the comprehensive plan~~ this objective. ~~Current funding strategies can include tourist taxes, or boating improvement funds to develop public launching facilities and related amenities.~~

Criteria:

- ~~A. Funding may come from fees, bonds, community redevelopment district financing, or other sources as approved by Board, and may be supplemented through revenue sharing with appropriate state and federal programs.~~
- ~~B. The County's share of revenue collected from boating registration fees shall be spent on boating infrastructure projects pursuant to Chapter 328.72(15), F.S.~~

Policy CM 13.9

The County shall not vacate, diminish, or otherwise permanently impair publicly-owned pathways, sidewalks, roads, parking areas, docks or boat launching facilities, and other access points that are currently used, or susceptible to use, by the public to access the shorelines unless specific findings are made demonstrating that the action is necessary and suitable mitigation measures are or will be in place and only after a public hearing and decision by a super majority of the Board of Commissioners. ~~(currently in Board Policy)~~

Policy CM 13.10

The County shall continue to inventory the waters of Brevard County to determine appropriate sites for one or more managed anchorages and/or mooring fields that shall be available to the boating public on a first come, first served basis. If one or more suitable sites are found, the County may establish a publicly accessible-managed anchorage and mooring field(s), taking into account environmental protection requirements and the concerns of shore side residents.

Policy CM 13.11

The County should develop incentives for encouraging private waterfront property owners to make their properties available for public use for purposes that are consistent with the uses permitted in recreational and commercial working waterfronts.

Coastal Development and Redevelopment

Objective CM 14

Create procedures to allow consideration of the changing dynamics of flooding, sea level rise, and storm surge in growth management decisions within the unincorporated areas of Brevard County over short, mid, and long-term planning horizons.

Policy CM 14.1

The County should utilize a range of sea level rise projections as recommended in the adopted East Central Florida Regional Resilience Action Plan (RRAP), as amended, for planning purposes based upon vulnerability, risk, project service life of a facility or growth management.

Policy CM 14.2

The County should consider designating Adaptation Action Areas (AAAs), as allowed by Florida Statute, as a mechanism to prioritize resilient planning, infrastructure investments, and strategies to address current and future flood impacts in areas identified as vulnerable to coastal flooding, storm surge, and sea level rise.

Policy CM 14.3

Using best available data, the County should consider identifying areas vulnerable to current and future flooding impacts which may benefit from nature-based design standards and/or Low Impact Development projects that reduce run-off; mitigate flood impacts; provide for the on-site absorption, capture, and reuse of stormwater; and preserve and restore natural drainage characteristics.

Policy CM 14.4

The County should consider the results of the Brevard County Vulnerability Analysis when planning for development, redevelopment, and improvements to critical facilities and infrastructure.

Policy 14.5

~~The County should consider initiatives within the Brevard County Emergency Operations Local Mitigation Strategy (LMS) and ECFRPC RRAP that focus on solutions for flood impacts; and develop methodologies for prioritizing public project expenditures based on a cost-benefit analysis, feasibility, and short- versus long-term benefits.~~

Policy CM 14.5

The County should work to reduce hazard exposure for coastal communities by coordinating with municipalities and ECFRPC to identify, scope, and recommend hazard mitigation projects as outlined in the Local Mitigation Strategy.

Policy CM 14.6

The County ~~must develop mechanisms to~~ should continue to evaluate and recommend new design and development standards for public and private infrastructure projects that consider future climate conditions, and amend Land Development Regulations to reduce obstacles that hinder nature-based design standards and/or Low Impact Development ~~unless it can be clearly demonstrated that:~~

- ~~a. Strict application will be contrary to the public interest;~~
- ~~b. The public values being protected are insignificant and strict application will result in an excessive hardship to the project;~~
- ~~c. Strict application will place an excessive hardship on the project, and an alternative action is available which is equal to or superior than the original requirements in reaching the policy's objective, or~~
- ~~d. The activity is not financially feasible for the local government.~~

Policy CM 14.7

The County should identify development and redevelopment performance standards designed to minimize or withstand permanent and/or temporary inundation from flooding, sea level rise, and storm surge. These standards may include increased freeboard elevations, the consideration of future tailwater elevations for stormwater infrastructure, and/or multi-use temporary flood storage areas.

Policy CM 14.8

The County should continually identify strategies and engineering solutions that minimize the loss of flood storage capacity in all floodplains and areas vulnerable to natural hazards such as flooding, storm surge, and sea level rise, and consider incorporating them into the Land Development Regulations.

Policy CM 14.9

~~Based on the 2021 Resilient Brevard Community Survey, completed by the ECFRPC, the~~ The County ~~must~~ should continue to encourage nature-based design standards and/or Low Impact Development design for development and redevelopment within areas vulnerable to current and future flooding impacts. ~~unless it can be clearly demonstrated that:~~

- ~~a. —Strict application will be contrary to the public interest;~~
- ~~b. —The public values being protected are insignificant and strict application will result in an excessive hardship to the project;~~
- ~~c. —Strict application will place an excessive hardship on the project, and an alternative action is available which is equal to or superior than the original requirements in reaching the policy's objective, or~~
- ~~d. —The activity is not financially feasible for the local government.~~

Such adaptation strategies may include:

- a. Multi-use stormwater parks,
- b. Bioswales as stormwater management techniques,
- c. Green streets,
- d. Reduced impervious areas,
- e. Florida-friendly landscaping/xeriscaping, ~~and or~~
- f. Ecological asset preservation (e.g., tree canopy, natural areas, mangroves, wetlands, dunes, aquifer recharge areas).

Policy CM 14.10

The County should educate the community about flood mitigation principles, strategies, and engineering solutions that can be implemented to protect property and reduce insurance losses.

Policy CM 14.11**COASTAL MANAGEMENT ELEMENT**

The County should pursue private and public funding sources for the implementation of flood resiliency strategies – including, but not limited to, avoidance, protection, accommodation, strategic relocation - within areas identified as vulnerable to current and future flooding impacts. As funding opportunities arise, the County should consider removing real property structures from coastal FEMA flood zones through acquisition of repetitive loss properties, for use as green space or stormwater management.

Policy CM 14.12

The County should continue to implement policies within the Comprehensive Plan, including but not limited to the Conservation Element, to ensure avoidance and minimization of impacts to natural coastal ecosystems, including wetlands, floodplains, aquifer recharge areas, and dunes.

Policy CM 14.13

The County should continue to analyze best available data to maintain or update relevant and current coastal hazard vulnerability projections and update maps, as applicable. The County should continue to identify and understand the risks, vulnerabilities, and opportunities for strategies within short, mid, and long-term planning horizons as established in the RRAP Formal Recommendation, as amended.


Policy CM 14.14

Public facilities, such as hospitals, wastewater treatment plants or fire stations, shall not be located on causeways.

APPENDIX ~~A~~

LIST OF MAPS

Map	Title
1	Marine Facilities <u>Coastal High Hazard Area</u>
2	Evacuation Routes
3a, 3b, 3c	Coastal High Hazard Areas



COASTAL MANAGEMENT ELEMENT

Map 1 Legend
(Webpage Note: Reverse Side of Map – Enlarged for Display Online)

MAP REF #	STREET	CITY	WATERBODY
-1	2000 Jones Av.	Mims	Indian River
-2	801 Marina Road	Titusville	Indian River
3	451 Marina Road	Titusville	Indian River
4	419 N. Washington Ave.	Titusville	Indian River
-5	41 N. Broad Street	Titusville	Indian River
-6	S. Washington Ave. North of SR-50	Titusville	Indian River
7	4749 S. Washington Ave.	Titusville	Indian River
8	River Moorings Drive	N. Merritt Island	Indian River
9	1300 E. Hall Rd.	Merritt Island	Banana River
10	505 Glen Cheek Dr.	Port Canaveral	Port Canaveral
11	520 Glen Cheek Drive	Port Canaveral	Port Canaveral
12	628 Glen Cheek Drive	Port Canaveral	Port Canaveral
13	960 Mullet Road	Port Canaveral	Port Canaveral
14	350 SeaRay Dr.	Merritt Island	Barge Canal
15	2700 Harbortown Drive	Merritt Island	Barge Canal
16	800 Scallop Dr.	Port Canaveral	Port Canaveral
17	910 Mullet Road	Port Canaveral	Port Canaveral
18	290 Marine Harbor Drive	Merritt Island	Barge Canal
19	2750 Tingley Drive	Merritt Island	Barge Canal
20	6701 N. Atlantic Ave.	Cape Canaveral	Banana River
21	6815 N. Atlantic Ave.	Cape Canaveral	Banana River
22	Winar Drive	Merritt Island	Sykes Creek
23	20 Myrtice Ave.	Merritt Island	Indian River
24	14 Myrtice Ave.	Merritt Island	Indian River
25	P.O. Box 1886	Cocoa	Indian River
26	12 Marina Isles Blvd.	Indian Harbor Beach	Banana River
27	96 Willard St. Unit 101	Cocoa	Indian River
28	410 E. Cocoa Beach Cswy.	Cocoa Beach	Banana River
29	1872 E. 520 Cswy.	Merritt Island	Banana River
30	1872 E. 520 Cswy.	Merritt Island	Banana River
31	96 Willard St. Unit 101	Cocoa	Indian River
32	480 Cocoa Beach Cswy.	Cocoa Beach	Banana River
33	100-104 Riverside Dr.	Rockledge	Indian River
34	582 S. Banana River Dr	Merritt Island	Banana River
35	1025 Riveredge Drive	Rockledge	Indian River


36	200 S. Banana River Drive	Merritt Island	Banana River
37	1360 S. Banana River Dr.	Merritt Island	Banana River
38	1825 Minuteman Cswy.	Cocoa Beach	Banana River
39	1611 Minuteman Cswy.	Cocoa Beach	Banana River
40	1525 Minuteman Cswy.	Cocoa Beach	Banana River
41	2705 S. Tropical Trail	Merritt Island	Indian River
42	760 S. Brevard Ave.	Cocoa Beach	Banana River
43	2290 S. Hwy A1A	Cocoa Beach	Banana River
44	3360 S. Atlantic Ave.	Cocoa Beach	Banana River
45	5695 U.S. Highway 1	Viera	Indian River
46	199 Utopia Circle	Merritt Island	Indian River
47	1629 Atlas Ave.	PAFB	Banana River
48	Tequesta Harbor	Merritt Island	Indian River
49	6155 N. U.S. Hwy 1	Melbourne	Indian River
50	6175 N. Harbor City Blvd.	Melbourne	Indian River
51	5435 N. U.S. Highway 1	Melbourne	Indian River
52	4399 N. Harbor City Blvd.	Melbourne	Indian River
53	876 Marina Road	PAFB	Banana River
54	40 Palmer Road	Indian Harbor Beach	Banana River
55	1399 Banana River Drive	Indian Harbor Beach	Banana River
56	100 Datura Drive	Indian Harbor Beach	Banana River
57	96 E. Eau Gallie Cswy.	Melbourne	Indian River
58	587 Young Street	Melbourne	Eau Gallie River
59	1135 U.S. Highway 1	Melbourne	Eau Gallie River
60	911 N. Harbor City Blvd.	Melbourne	Eau Gallie River
61	729 N. Harbor City Blvd.	Melbourne	Indian River
62	705 S. Harbor City Blvd.	Melbourne	Indian River
63	2210 S. Front Street.	Melbourne	Crane Creek
64	1202 E. River Drive	Melbourne	Crane Creek
65	1208 E. River Drive	Melbourne	Crane Creek
66	1308 E. River Drive	Melbourne	Crane Creek
67	Riverside Drive	Melbourne Beach	Indian River
68	160 Versailles Drive	South Beaches	Indian River
69	Landings Road off A1A	South Beaches	Indian River
70	Solway Drive off A1A	South Beaches	Indian River
71	Ocean Way off A1A	South Beaches	Indian River
72	4220 Dixie Hwy NE	Palm Bay	Turkey Creek
73	4350 Dixie Hwy NE	Palm Bay	Indian River
74	5001 Dixie Hwy NE	Palm Bay	Indian River

COASTAL MANAGEMENT ELEMENT


LPA Adoption June 16, 2025

75	3800 U.S. Highway 1	Valkaria	Indian River
76	750 Mullet Creek Rd.	South Beaches	Indian River
77	240 Hammock Shore Dr.	South Beaches	Mullet Creek
78	4660 U.S. Highway 1	Grant	Indian River
79	5185 U.S. Highway 1	Grant	Indian River
80	6075 U.S. Highway 1	Grant	Indian River
81	8525 U.S. Highway 1	Micco	Indian River
82	9502 S. A1A	South Beaches	Indian River
83	8685 N. U.S. Highway 1	Micco	Indian River
84	4015 Main Street	Micco	Sebastian River
85	6485 S. U.S. Highway 1	Rockledge	Indian River
86	6533 S. U.S. Highway 1	Melbourne	Indian River
87	4263 N. U.S. Highway 1	Melbourne	Indian River
88	2459 Pineapple Ave.	Melbourne	Indian River
89	1477 Pineapple Ave.	Melbourne	Indian River

COASTAL MANAGEMENT ELEMENT




Coastal High Hazard Area Map



Brevard County Information Technology Department
Data Source: East Central Florida Regional Planning Council (ECFRPC) Source Date: 09/2021

COASTAL MANAGEMENT ELEMENT


LPA Adoption June 16, 2025



COASTAL MANAGEMENT ELEMENT

LPA Adoption June 16, 2025

Brevard Coastal High Hazard Area Map



Category 1

 Coastal High Hazard Area

Source: East Central Florida Regional Planning Council
Regional Evacuation Study Program - Storm Tide Atlas



Map generated by best available data on 4/29/2022. Map subject to change, please contact Brevard County for map confirmation.

Disclaimer: This map displays general County information and was created from best data available. It is not suitable for site-specific uses. The Brevard County Board of Commissioners expressly disclaims all responsibility for errors or omissions thereof.

North Brevard CHHA Region Display




COASTAL MANAGEMENT ELEMENT

LPA Adoption June 16, 2025

X - 50

Brevard Coastal High Hazard Area Map



Category 1

 Coastal High Hazard Area


Source: East Central Florida Regional Planning Council
Regional Evacuation Study Program - Storm Tide Atlas



Map generated by best available data on 4/29/2022. Map subject to change, please contact Brevard County for map confirmation.

Disclaimer: This map displays general County Information and was created from best data available. It is not suitable for site-specific uses. The Brevard County Board of Commissioners expressly disclaims all responsibility for errors or omissions thereof.

Central Brevard CHHA Region Display




COASTAL MANAGEMENT ELEMENT

LPA Adoption June 16, 2025

X - 51

Brevard Coastal High Hazard Area Map



Category 1

 Coastal High Hazard Area

Source: East Central Florida Regional Planning Council
Regional Evacuation Study Program - Storm Tide Atlas



Map generated by best available data on 4/29/2022. Map subject to change, please contact Brevard County for map confirmation.

Disclaimer: This map displays general County Information and was created from best data available. It is not suitable for site-specific uses. The Brevard County Board of Commissioners expressly disclaims all responsibility for errors or omissions thereof.

South Brevard CHHA Region Display



COASTAL MANAGEMENT ELEMENT

LPA Adoption June 16, 2025

APPENDIX

LIST OF FIGURES

Figure	Title	Page
1	Diagram Reflecting the Spatial Relationship between the FDEP 1981 Coastal Construction Control Line (CCCL) and the Brevard County Coastal Setback Line (CSL)	6

MANATEE HABITAT FEATURE MAP SERIES AND UPDATE SCHEDULE

MAPS:

1.—**Submerged Aquatic Vegetation (SAV)**—1994 coverage supplied with the draft MPP:

Source:

———St. Johns River Water Management District
———(904) 329-4500

Update Schedule: As available

2.—**Manatee Abundance (Aerial Surveys)**—September 1997-September 1999 map supplied with the draft MPP:

Source:

———Florida Fish and Wildlife Conservation Commission
———Bureau of Protected Species Management
———(904) 922-4330

Update Schedule: As available

3.—**Manatee Mortality**—Watercraft-related or Total Manatee Mortality (all causes) from 1974-2001 supplied with the draft MPP:

Source:

———Florida Fish and Wildlife Conservation Commission
———Bureau of Protected Species Management
———(904) 922-4330

Update Schedule: As available

4.—**Manatee Protection Boat Speed Zones**—October 2000 as provided with the draft MPP, or more recent data:

———Source:

———Florida Fish and Wildlife Conservation Commission
———Bureau of Protected Species Management
———(904) 922-4330

———Update Schedule: As needed

5.—**Manatee Freshwater Sources Map**—March 1994 as provided with the MPP:

Source:

———Brevard County
———Natural Resources Management Department

~~———— (321) 633-2016~~
~~Update Schedule: As available~~

~~6. **Class II Waterbody, Outstanding Florida Waterway (OFW), or Aquatic Preserve**~~
~~2001 as provided in the MPP.~~

~~Source:~~

~~———— Florida Department of Environmental Protection~~
~~———— Division of Surface Water Quality~~
~~———— (850) 245-8427~~

~~Update Schedule: As available~~

CHAPTER PART XI
FUTURE LAND USE ELEMENT

TABLE OF CONTENTS

PREFACE	1
ADMINISTRATIVE POLICIES	2
GOAL, OBJECTIVES, AND POLICIES.....	6
Residential Land Uses	6
Commercial Land Uses	16
Industrial Land Uses.....	31
Agricultural Land Uses.....	40
Conservation Land Uses	42
Public Facilities Land Uses	44
Recreation Land Uses.....	45
Developments of Regional Impact (DRIs)	46
New Town Overlay West Viera Area	50
Transfer of Development Rights (TDRs)	64
Redevelopment & Regentrification	66
Service Delivery, Concurrency, and Growth	72
Land Development Regulations.....	77
Establishment of Zoning Classifications to Meet Residential Needs.....	78
Consistency with Comprehensive Plan, Zoning, and Land Development Regulations.....	79
Military Base Land Use Compatibility	82
The Farmton Local Plan	83
Sustainability/Energy Efficiency	110
Working Waterfronts	111
Public Airport Land Use Compatibility	112
Implement Directives from Small Area Studies.....	113
Residential Density Rightsizing Study Areas	115
APPENDIX	117

PREFACE

Planning Horizons

Section 163.3177, F.S., requires that each comprehensive plan include at least two planning horizons: one for at least 10 years and one for at least 20 years. The two planning horizons established for the Brevard County Comprehensive Plan are fiscal year 2035 for the short-term planning period and fiscal year 2045 for the long-term planning period.

Future Land Use Map Designations

The following Future Land Use designations shall be adopted as part of the Future Land Use Map:

Residential

Residential 30 Directive (up to 30 dwelling units per acre)
Residential 15 (up to 15 dwelling units per acre)
Residential 12 Directive (up to 12 dwelling units per acre)
Residential 10 (up to 10 dwelling units per acre)
Residential 8 Directive (up to 8 dwelling units per acre)
Residential 6 (up to 6 dwelling units per acre)
Residential 6 Directive (up to 6 dwelling units per acre)
Residential 5 Directive (up to 5 dwelling units per acre)
Residential 4 (up to 4 dwelling units per acre)
Residential 4 Directive (up to 4 dwelling units per acre)
Residential 3 Directive (up to 3 dwelling units per acre)
Residential 2 (up to 2 dwelling units per acre)
Residential 2 Directive (up to 2 dwelling units per acre)
Residential 1 (up to 1 dwelling unit per acre)
Residential 1:2.5 (up to 1 dwelling unit per 2.5 acres)

Commercial

Neighborhood Commercial (NC)
Community Commercial (CC)

Industrial

Heavy/Light Industrial
Planned Industrial

Agricultural

Conservation

Public Conservation
Private Conservation

Public Facilities

Recreation

Developments of Regional Impact

FUTURE LAND USE ELEMENT

ADMINISTRATIVE POLICIES

Administrative Policy 1

The Brevard County zoning official, planners, and the Director of the Planning and Development Department, however designated, are recognized as expert witnesses for the purposes of Comprehensive Plan amendments as well as zoning, conditional use, special exception, and variance applications.

Administrative Policy 2

Upon Board request, members of the Brevard County planning and zoning staff shall be required to present written analysis and a recommendation, which shall constitute an expert opinion, on all applications for zoning, conditional uses, comprehensive plan amendments, vested rights, or other applications for development approval that come before the Board of County Commissioners for quasi-judicial review and action. The Board may table an item if additional time is required to obtain the analysis requested or to hire an expert witness if the Board deems such action appropriate. Staff input may include the following:

Criteria:

- A. Staff shall analyze an application for consistency or compliance with comprehensive plan policies, zoning approval criteria and other applicable written standards.
- B. Staff ~~shall~~ may conduct site visits of property which are the subject of analysis and recommendation. As part of the site visit, the staff ~~shall take a videotape or photographs~~ may record images or video where helpful to the analysis and conduct an inventory of surrounding existing uses. ~~Aerial photographs shall also be used where they would aid in an understanding of the issues of the case.~~
- C. In cases where staff analysis is required, both the applicant and the staff shall present proposed findings of fact for consideration by the Board.
- D. For development applications where a specific use has not been proposed, the worst case adverse impacts of potential uses available under the applicable land use classification shall be evaluated by the staff.

Administrative Policy 3

Compatibility with existing or proposed land uses shall be a factor in determining where a rezoning or any application involving a specific proposed use is being considered. Compatibility shall be evaluated by considering the following factors, at a minimum:

Criteria:

- A. Whether the proposed use(s) would have hours of operation, lighting, odor, noise levels, traffic, or site activity that would significantly diminish the

FUTURE LAND USE ELEMENT

enjoyment of, safety or quality of life in existing neighborhoods within the area which could ~~foresee-ably~~ foreseeably be affected by the proposed use;

- B. Whether the proposed use(s) would cause a material reduction (five per cent or more) in the value of existing abutting lands or approved development.
- C. Whether the proposed use(s) is/are consistent with an emerging or existing pattern of surrounding development as determined through an analysis of:
 - 1. historical land use patterns;
 - 2. actual development over the immediately preceding three years; and
 - 3. development approved within the past three years but not yet constructed.
- D. Whether the proposed use(s) would result in a material violation of relevant policies in any elements of the Comprehensive Plan.
- E. In determining whether an established residential neighborhood exists, the following factors must be present:
 - 1. The area must have clearly established boundaries, such as roads, open spaces, rivers, lakes, lagoons, or similar features.
 - 2. Sporadic or occasional neighborhood commercial uses shall not preclude the existence of an existing residential neighborhood, particularly if the commercial use is non-conforming or pre-dates the surrounding residential use.

Administrative Policy 4

~~Character of a neighborhood or area shall be a factor for consideration whenever a rezoning or any application involving a specific proposed use is reviewed. The character of the area must not be materially or adversely affected by the proposed rezoning or land use application. In evaluating the character of an area, the following factors shall be considered:~~

Criteria:

- A. ~~The proposed use must not materially and adversely impact an established residential neighborhood by introducing types or intensity of traffic (including but not limited to volume, time of day of traffic activity, type of vehicles, etc.); parking, trip generation, commercial activity or industrial activity that is not already present within the identified boundaries of the neighborhood.~~
- B. ~~In determining whether an established residential neighborhood exists, the following factors must be present:~~
 - 1. ~~The area must have clearly established boundaries, such as roads, open spaces, rivers, lakes, lagoons, or similar features.~~
 - 2. ~~Sporadic or occasional neighborhood commercial uses shall not preclude the existence of an existing residential neighborhood, particularly if the commercial use is non-conforming or pre-dates the surrounding residential use.~~

FUTURE LAND USE ELEMENT

3. ~~An area shall be presumed not to be primarily residential but shall be deemed transitional where multiple commercial, industrial or other non-residential uses have been applied for and approved during the previous five (5) years.~~

Brevard County shall allow a diverse mix of residential uses in the Commercial and Industrial land use categories as shown on the Future Land Use Map if the development provides affordable housing according to the provisions of section 125.0155(7), F.S., as may be amended from time to time. The provisions of this law do not apply to properties defined as recreational and commercial working waterfront in any area zoned as industrial.

Administrative Policy 5

In addition to the factors specified in Administrative Policies 2; ~~and 3, and 4~~, in reviewing a rezoning, conditional use permit or other application for development approval, the impact of the proposed use or uses on transportation facilities either serving the site or impacted by the use(s) shall be considered. In evaluating whether substantial and adverse transportation impacts are likely to result if an application is approved, the staff shall consider the following:

Criteria:

- A. Whether adopted levels of service standards will be ~~compromised~~ exceeded;
- B. Whether the physical quality of the existing road system that will serve the proposed use(s) is sufficient to support the use(s) without significant deterioration;
- C. Whether the surrounding existing road system is of sufficient width and construction quality to serve the proposed use(s) without the need for substantial public improvements;
- D. Whether the surrounding existing road system is of such width and construction quality that the proposed use(s) would realistically pose a potential for material danger to public safety in the surrounding area;
- E. Whether the proposed use(s) would be likely to result in such a material and adverse change in traffic capacity of a road or roads in the surrounding area such that either design capacities would be significantly exceeded or a de facto change in functional classification would result;
- F. Whether the proposed use(s) would cause such material and adverse changes in the types of traffic that would be generated on the surrounding road system, that physical deterioration of the surrounding road system would be likely;
- G. Whether projected traffic impacts of the proposed use(s) would materially and adversely impact the safety ~~or welfare~~ of residents in existing residential neighborhoods.

FUTURE LAND USE ELEMENT

Administrative Policy 6

The use(s) proposed under the rezoning, conditional use or other application for development approval must be consistent with (a) all written land development policies set forth in these administrative policies; and (b) the future land use element, coastal management element, conservation element, potable water element, sanitary sewer element, solid waste management element, capital improvements element, recreation and open space element, surface water element and transportation elements of the comprehensive plan.

Administrative Policy 7

Proposed use(s) shall not cause or substantially aggravate any (a) substantial drainage problem on surrounding properties; or (b) significant, adverse and unmitigatable impact on significant natural wetlands, water bodies or habitat for listed species.

Administrative Policy 8

These policies, the staff analysis based upon these policies and the applicant's written analysis, if any, shall be incorporated into the record of every quasi-judicial review application for development approval presented to the Board including rezoning, conditional use permits and vested rights determinations.

Administrative Policy 9

Brevard County shall not amend its Comprehensive Plan, Future Land Use Map, zoning districts, or land development regulations in a matter that would conflict with a resiliency facility's classification as a permitted and allowable use and that would cause a resiliency facility to be a nonconforming use, structure, or development, per section 163.3210, F.S.

GOAL, OBJECTIVES, AND POLICIES

GOAL FLU

To manage growth in Brevard County in a manner that enhances natural and man-made systems and meets the public's social and economic needs.

Residential Land Uses

Objective FLU 1

Brevard County shall facilitate the development of residential neighborhoods that offer the highest quality of life to the citizenry through the implementation of policies that accomplish the following:

Criteria:

- A. Ensure the compatibility of new development with its surroundings;
- B. Ensure the delivery of services that meet or exceed established levels of service;
- B. Discourage the occurrence of inefficiencies inherent in urban sprawl as defined by Florida Statutes;
- C. Strive to decrease identified hurricane evacuation deficiencies;
- D. Produce neighborhoods that complement adjacent land uses;
- E. Permit mixed use developments which, through the application of appropriate performance standards, ~~juxtaposes juxtapose~~ juxtapose neighborhood services and employment centers with residential uses in order to promote efficient use of land; ~~and~~
- G. Encourage open space within residential developments and promote interconnectivity with surrounding land uses through innovative land regulations and bonus incentives;
- H. Protect environmental and ecological resources in accordance with the goals of the Conservation Element and Coastal Management Element; and
- I. Comply with the goals of Basin Management Action Plans (BMAP) that include the County.
- J. Binding Development Plans are not to be used to determine consistency with the zoning classifications outside of Section 62-1255 of the zoning regulations.

FUTURE LAND USE ELEMENT

Residential Land Use Designations

Policy FLU 1.1

The residential land use designations adopted as part of the Future Land Use Map represent maximum density thresholds. Approved densities may be lower than the maximum allowed by a residential land use designation as a result of one or more of the following:

Criteria:

- A. Environmental constraints, including BMAP requirements, identified in applicable objectives and policies of the Conservation Element and Coastal Management Element which impose more stringent density guidelines;
- B. Land use compatibility pursuant to Administrative Policy 3;
- C. Unavailability or inadequacy of public facilities and services, including educational facilities, to accommodate adopted density allowances, as set forth in Policy FLU 1.2 and the policies found in the 'Service Delivery, Concurrency and Growth' section of this Element as well as related objectives and policies in the Capital Improvements Element. Binding Development Plans shall not be used to exempt or otherwise waive compliance with infrastructure requirements contained in Policy FLU 1.2;
- D. Character of the general area, pursuant to Administrative Policy 4 3;
- E. Hurricane evacuation capabilities; and
- F. Policies established in specialized plans, including binding development plans, as may be adopted by the Board of County Commissioners. Binding development plans shall not be used to establish consistency between Future Land Use Map designations and zoning classifications.
- G. The Future Land Use Map designations of RES 2 Directive, RES 3 Directive, RES 4 Directive, RES 5 Directive, RES 6 Directive, RES 8 Directive, and RES 12 Directive are limited to the stated density and are not entitled to density bonuses for development of a Planned Unit Development.

Public Facilities and Services Requirements

Policy FLU 1.2

Minimum public facilities and services requirements should increase as residential density allowances become higher. The following criteria shall serve as guidelines for approving new residential land use designations:

Criteria:

- A. Adequate roadways, solid waste disposal, drainage, potable water, sanitary sewer, and recreation public school facilities to serve the needs of associated

FUTURE LAND USE ELEMENT

development shall be available concurrent with development in all residential land use designations.

- B. Fire and police protection, ~~and emergency medical services, and recreation facilities~~ to serve the needs of associated development ~~shall~~ should be available concurrent with development in all residential land use designations ~~in accordance with policies set forth in the 'Service Delivery, Concurrency and Growth' section of this Future Land Use Element.~~
- C. In the Residential 30 Directive, Residential 15, Residential 12 Directive, Residential 10, Residential 8 Directive, Residential 6, Residential 6 Directive, ~~and Residential 5 Directive~~, Residential 4, ~~and Residential 4 Directive~~ future land use designations, centralized potable water and wastewater treatment shall be available concurrent with the impact of the development.
- D. Where public ~~water sewer~~ service is available, residential development proposals ~~with densities greater than four units per acre within BMAP areas~~ shall be required to connect to a ~~centralized~~ the sewer system.
- E. Where public water service is not available, residential development proposals with densities greater than two units per acre shall be required to connect to a centralized sewer system. Within BMAP areas where public sewer service is not available, the installation of enhanced nutrient-reducing onsite sewage treatment and disposal systems or other wastewater treatment systems that achieve at least 65 percent nitrogen reduction is required.
- F. The County shall not extend public utilities and services outside of established service areas to accommodate new development in Residential 3 Directive, Residential 2, Residential 2 Directive, or Residential 1 future land use designations unless within BMAP areas, or in ~~and~~ Residential 1:2.5 land use designations, unless an overriding public benefit can be demonstrated. This criterion is not intended to preclude acceptance of dedicated facilities and services by the County through MSBU's, MSTU's, and other means through which the recipients pay for the service or facility.

Residential 30 Directive (maximum of 30 dwelling units per acre)

Policy FLU 1.3

The Residential 30 Directive land use designation affords the highest density allowance, permitting a maximum density of up to thirty (30) units per acre, except as otherwise may be provided for within this element. This future land use designation is limited to the Residential Density Rightsizing study areas, including the Avon by the Sea area, the Merritt Island area, and the South Cocoa Beach area. Parameters for this future land use designation include:

Criteria:

FUTURE LAND USE ELEMENT

- A. The Residential 30 Directive land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan.
1. Areas located east of Interstate-95; and
 2. Unincorporated enclaves located within or adjacent to incorporated areas which permit similar or greater density allowance; or
 3. Areas adjacent to existing Residential 30 land use designation; and
 4. Areas with direct access to an arterial or collector roadway, without impacting existing or designated lower density/intensity areas.
- B. In the Merritt Island Redevelopment Area, Brevard County should encourage high density development in clustered patterns that maximize the provision of open space to avoid the impacts of "strip" or "checkerboard" land use patterns and to assist in the development of an urban atmosphere. The Residential 30 Directive land use designation may permit development in excess of 30 units per acre, provided that one of the following applies:
1. Residential density of up to 37.5 dwelling units per acre, may be considered if approved as part of a redevelopment plan; or
 2. Developments which are tied to a binding development plan and propose a mixture of residential and commercial uses may permit the residential portion of the project with density of up to 50 dwelling units per acre.
- C. A 25% density bonus to permit up to 37.5 dwelling units per acre may be considered, ~~except in the Coastal High Hazard Area (CHHA);~~ where the Planned Unit Development concept is utilized, where deemed compatible by the County with adjacent development, provided that minimum infrastructure requirements set forth in Policy FLU 1.2 are available. Such higher densities should be relegated to interior portions of the PUD tract, away from perimeters, to enhance blending with adjacent areas and to maximize the integration of open space within the development and promote inter-connectivity with surrounding uses. ~~This density bonus shall not be utilized for properties within the CHHA.~~
- D. The Residential 30 Directive land use designation shall not be applied to lands within the Coastal High Hazard Area (CHHA).

Residential 15 (maximum of 15 units per acre)

Policy FLU 1.4

The Residential 15 land use designation affords the second highest density allowance, permitting a maximum density of up to fifteen (15) units per acre, except as otherwise may be provided for within this element. The Residential 15 land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan:

FUTURE LAND USE ELEMENT

Criteria:

- A. Areas located east of Interstate-95, except in instances where they are adjacent to existing or designated residential densities of an equal or higher density allowance; and
- B. Unincorporated areas which are adjacent to incorporated areas and may be considered a logical transition for Residential 15 area;
- C. Areas adjacent to an existing Residential 15 land use designation; and
- D. Areas which have access to an arterial or collector roadway, without impacting existing or designated lower density/intensity areas.
- E. Up to a 25% density bonus to permit up to 18.75 dwelling units per acre may be considered where the Planned Unit Development concept is utilized, where deemed compatible by the County with adjacent development, provided that minimum infrastructure requirements set forth in Policy FLU 1.2 are available. Such higher densities should be relegated to interior portions of the PUD tract, away from perimeters, to enhance blending with adjacent areas and to maximize the integration of open space within the development and promote inter-connectivity with surrounding uses. This density bonus shall not be utilized for properties within the CHHA.

Residential 12 Directive (maximum of 12 dwelling units per acre)

Policy FLU 1.5

The Residential 12 Directive land use designation affords a transition in density between highly urbanized areas and lower intensity residential uses within the Port St. John Small Area Plan study area. This land use designation permits a maximum density of up to twelve (12) units per acre.

Residential 10 (maximum of 10 dwelling units per acre)

Policy 1.5 FLU 1.6

The Residential 10 land use designation affords a transition in density between highly urbanized areas and lower intensity residential uses. This land use designation permits a maximum density of up to ten (10) units per acre, except as otherwise may be provided for within this element. The Residential 10 land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan:

Criteria:

- A. Areas adjacent to existing Residential 10 or higher land use designations; or
- B. Areas which serve as a transition between existing land uses or land use designations with density greater than ten (10) units per acre and areas with density of less than ten (10) units per acre; or

FUTURE LAND USE ELEMENT

- C. Unincorporated areas which are adjacent to incorporated areas and may be considered a logical transition for Residential 10; and
- D. Areas which have access to an arterial or collector roadway, without impacting existing or designated lower density/intensity areas.
- E. Up to a 25% density bonus to permit up to 12.5 dwelling units per acre may be considered where the Planned Unit Development concept is utilized, where deemed compatible by the County with adjacent development, provided that minimum infrastructure requirements set forth in Policy FLU 1.2 are available. Such higher densities should be relegated to interior portions of the PUD tract, away from perimeters, to enhance blending with adjacent areas and to maximize the integration of open space within the development and promote inter-connectivity with surrounding uses. This density bonus shall not be utilized for properties within the CHHA.

Residential 8 Directive (maximum of 8 dwelling units per acre)

Policy FLU 1.7

The Residential 8 Directive land use designation affords a transition in density between higher urbanized areas and lower intensity residential uses within the Port St. John, Canaveral Groves, and South Beaches Small Area Plan study areas. This land use designation permits a maximum density of up to eight (8) units per acre.

Residential 6 (maximum of 6 dwelling units per acre)

Policy 1-6 FLU 1.8

The Residential 6 land use designation affords a transition in density between higher urbanized areas and lower intensity land uses. This land use designation permits a maximum density of up to six (6) units per acre, except as otherwise may be provided for within this element. The Residential 6 land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan:

Criteria:

- A. Areas adjacent to existing Residential 6 land use designation; or
- B. Areas which serve as a transition between existing land uses or land use designations with density greater than six (6) units per acre and areas with density of less than six (6) units per acre; or
- C. Unincorporated areas which are adjacent to incorporated areas and may be considered a logical transition for Residential 6.
- D. Up to a 25% density bonus to permit up to 7.5 dwelling units per acre may be considered where the Planned Unit Development concept is utilized, where deemed compatible by the County with adjacent development, provided that

FUTURE LAND USE ELEMENT

minimum infrastructure requirements set forth in Policy FLU 1.2 are available. Such higher densities should be relegated to interior portions of the PUD tract, away from perimeters, to enhance blending with adjacent areas and to maximize the integration of open space within the development and promote inter-connectivity with surrounding uses. This density bonus shall not be utilized for properties within the CHHA.

Residential 6 Directive (maximum of 6 dwelling units per acre)

Policy FLU 1.9

The Residential 6 Directive land use designation affords a transition in density between higher urbanized areas and lower intensity land uses within the Canaveral Groves and South Beaches Small Area Plan study areas. This land use designation permits a maximum density of up to six (6) units per acre.

Residential 5 Directive (maximum of 5 dwelling units per acre)

Policy FLU 1.10

The Residential 5 Directive land use designation affords an additional step down in density from more highly urbanized areas within the Canaveral Groves Small Area Plan study area. This land use designation permits a maximum density of up to five (5) units per acre.

Residential 4 (maximum of 4 dwelling units per acre)

Policy ~~1.7~~ FLU 1.11

The Residential 4 land use designation affords an additional step down in density from more highly urbanized areas. This land use designation permits a maximum density of up to four (4) units per acre, except as otherwise may be provided for within this element. The Residential 4 land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan:

Criteria:

- A. Areas adjacent to existing Residential 4 land use designation; or
- B. Areas which serve as a transition between existing land uses or land use designations with density greater than four (4) units per acre and areas with density of less than four (4) units per acre; or
- C. Unincorporated areas which are adjacent to incorporated areas and may be considered a logical transition for Residential 4.
- D. Up to a 25% density bonus to permit up to five (5) units per acre may be considered with a Planned Unit Development where deemed compatible by the County with adjacent development, provided that minimum infrastructure requirements set forth in Policy FLU 1.2 are available. Such higher densities should be relegated to interior portions of the PUD tract, away from perimeters, to enhance blending with adjacent areas and to maximize the integration of open space within the development and promote inter-

FUTURE LAND USE ELEMENT

connectivity with surrounding uses. This density bonus shall not be utilized for properties within the CHHA.

Residential 4 Directive (maximum of 4 dwelling units per acre)

Policy FLU 1.12

The Residential 4 Directive land use designation affords a transition in density between higher urbanized areas and lower intensity land uses within the North Merritt Island and South Beaches Small Area Plan study areas. This land use designation permits a maximum density of up to four (4) units per acre.

Residential 3 Directive (maximum of 3 units per acre)

Policy FLU 1.13

The Residential 3 Directive land use designation serves as a transition between more highly urbanized and lower density residential development within the Canaveral Groves and Central and South Merritt Island Small Area Plan study areas. This land use designation permits a maximum density of up to three (3) units per acre.

Residential 2 (maximum of 2 units per acre)

Policy ~~1.8~~ FLU 1.14

The Residential 2 land use designation permits lower density residential development with a maximum density of up to two (2) units per acre, except as otherwise may be provided for within this element. The Residential 2 land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan:

Criteria:

- A. Areas adjacent to existing Residential 2 land use designation; or
- B. Areas which serve as a transition between existing land uses or land use designations with density greater than two (2) units per acre and areas with density of less than two (2) units per acre; or
- C. Unincorporated areas which are adjacent to incorporated areas and may be considered a logical transition for Residential 2.
- D. Up to a 25% density bonus to permit up to 2.5 dwelling units per acre may be considered where the Planned Unit Development concept is utilized, where deemed compatible by the County with adjacent development, provided that minimum infrastructure requirements set forth in Policy FLU 1.2 are available. Such higher densities should be relegated to interior portions of the PUD tract, away from perimeters, to enhance blending with adjacent areas and to maximize the integration of open space within the development and promote inter-connectivity with surrounding uses. This density bonus shall not be utilized for properties within the CHHA.

FUTURE LAND USE ELEMENT

Residential 2 Directive (maximum of 2 units per acre)

Policy FLU 1.15

The Residential 2 Directive land use designation permits lower density residential development within the North Merritt Island Small Area Plan study area. This land use designation permits a maximum density of up to two (2) units per acre.

Residential 1 (maximum of 1 unit per acre)

Policy ~~1-9~~ FLU 1.16

The Residential 1 land use designation permits low density residential development with a maximum density of up to one (1) unit per acre, except as otherwise may be provided for within this element. The Residential 1 land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan:

Criteria:

- A. Areas adjacent to existing Residential 1 land use designation; or
- B. Areas which serve as a transition between existing land uses or land use designations with density greater than one (1) unit per acre and areas with lesser density; or
- C. Unincorporated areas which are adjacent to incorporated areas and may be considered a logical transition for Residential 1.
- D. Up to a 25% density bonus to permit up to 1.25 dwelling units per acre may be considered with a Planned Unit Development where deemed compatible by the County with adjacent development, provided that minimum infrastructure requirements set forth in Policy FLU 1.2 are available. Such higher densities should be relegated to interior portions of the PUD tract, away from perimeters, to enhance blending with adjacent areas and to maximize the integration of open space within the development and promote inter-connectivity with surrounding uses. This density bonus shall not be utilized by properties within the CHHA.

Residential 1:2.5 (maximum of 1 unit per 2.5 acres)

Policy ~~1-10~~ FLU 1.17

The Residential 1:2.5 land use designation, which establishes the lowest density of all the residential future land use designations, permits a maximum density of up to one (1) unit per 2.5 acres, except as otherwise may be provided for within this element. Development in the Residential 1:2.5 land use designation should seek to maximize the integration of open space within the development and promote inter-connectivity with surrounding uses. The Residential 1:2.5 land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan:

Criteria:

- A. Areas adjacent to existing Residential 1:2.5 land use designation; or

FUTURE LAND USE ELEMENT

- B. Areas which serve as a transition between existing land uses or land use designations with density greater than 1:2.5 units per acre and areas with lesser density or lower intensity uses; or
- C. Unincorporated areas which are adjacent to incorporated areas and may be considered a logical transition for Residential 1:2.5.

Density in Coastal High Hazard Areas (CHHA)

Policy ~~1-11~~ FLU 1.18

The construction of additional infrastructure intended to remedy existing deficiencies, such as any new bridges or improvements to existing causeways over the Indian River Lagoon, shall not serve as a basis for increasing residential densities nor allowing residential density bonuses within the Coastal High Hazard Area (CHHA) above those programmed on the Future Land Use Map.

Protection of Residential Riverside Lands

Policy ~~1-12~~ FLU 1.19

Brevard County shall identify lineal land use patterns which parallel the U.S. 1 corridor and the Indian River in order to promote the protection of residential designated lands lying easterly of U.S. 1 and to discourage the expansion and encroachment of non-residential designated lands into such lineal residential areas. These lineal land use patterns shall generally be identified in, but not limited to, the following areas of Brevard County:

- 1) Generally from the southern Titusville city limits (~~Section 26 Township 22 Range 35~~) (Section 1 Township 23 Range 35) to SR 528 (Section 8 Township 24 Range 36).
- 2) Generally from south of Gus Hipp Boulevard (Section 23 Township 25 Range 36) to Pineda Causeway (Section 19 Township 26 Range 37).
- 3) Generally south of the southern Malabar city limits (~~Section 17 Township 29 Range 38~~) southern Grant-Valkaria city limits (Section 11 Township 30 Range 38) to the south Brevard County line (Section 23 Township 30 Range 38).

Promotion of Linear Parks in Residential Subdivisions

Policy ~~1-13~~ FLU 1.20

Brevard County ~~shall~~ may prepare and implement development incentives to encourage the inclusion of linear parks which promote the integration of open space within residential subdivisions and interconnectivity with adjacent development.

Breezeway/Visual Corridor

Policy FLU 1.21

Brevard County shall maintain minimum breezeway and visual corridor requirements in its land development regulations for oceanfront and riverfront development, in coordination with the Recreation and Open Space Element.

FUTURE LAND USE ELEMENT

Commercial Land Uses

Objective FLU 2

Brevard County shall provide for adequate and appropriate lands for the location of commercial land uses, through the Land Development Regulations, to serve the needs of the projected residents and visitors to the County. Brevard County shall direct new commercial land use designations to areas which are determined to be appropriate based upon a suitability analysis, a market analysis, character of the area, compatibility with surrounding land uses, and public facilities and services. These uses shall be directed to sites where there are sufficient uplands for the intended use and for all other measures to ensure wetland function. During the review of proposed amendments to the Future Land Use Map, which would allow commercial uses, Brevard County shall ensure that the site is suitable for the proposed use with regard to environmental features. The proposed designation shall be consistent with the following suitability criteria:

Criteria:

- A. Floodplain policies contained within Conservation Objective CON 4;
- B. Aquifer protection policies contained within Conservation Objective ~~44~~ CON 10;
- C. Types, values, conditions, functions, and locations of wetlands, and wetlands protection policies contained in Conservation Objective CON 5.
- D. Availability of centralized potable water and wastewater treatment concurrent with the impacts of development.

Role of the Comprehensive Plan in the Designation of Commercial Lands

Policy FLU 2.1

The Comprehensive Plan takes into consideration broad criteria for evaluating requests for commercial land use designations within Brevard County. At a minimum, these criteria address the following:

Criteria:

- A. Overall accessibility to the site;
- B. Compatibility and inter-connectivity with adjacent adopted Future Land Use designations and land uses;
- C. Existing and anticipated commercial development trend trends in the area as shown in a market analysis;
- D. Fundamental changes in the character of an area prompted by infrastructure improvements undertaken by the County;
- E. Availability of required infrastructure at/above adopted levels of service;
- F. Spacing from other commercial activities;

FUTURE LAND USE ELEMENT

- F. Size of proposed commercial designation compared with current need for commercial lands;
- G. Adherence to the objectives/policies of the Conservation Element and minimization of impacts upon natural resources and systems; and
- H. ~~Integration of open space; and~~
- ~~F. I.~~ Impacts upon strip commercial development.

Role of Zoning Regulations in the Designation of Commercial Lands

Policy FLU 2.2

The zoning process regulates the types and intensities of uses for a parcel of land. Criteria which aid in assessing zoning compatibility shall include consideration of the following standards:

Criteria:

- A. Permitted/prohibited uses;
- B. Existing commercial zoning trends in the area;
- C. Compatibility of the proposed use with the area, pursuant to Administrative Policy 3;
- D. Impact upon Level of Service (LOS) standards for roads, potable water service, sanitary sewer service, drainage, and solid waste disposal;
- E. Impact upon natural resources, including wetlands, floodplains, and endangered species; and
- F. Other issues which may emerge specific to a particular property which may be addressed through performance based zoning criteria.

Role of Land Development Regulations in the Designation of Commercial Lands

Policy FLU 2.3

Land development regulations provide performance standards for evaluating the acceptability of proposed commercial development activities, including:

Criteria:

- A. Integration of vehicular and non-vehicular access into the site and access management features of site in terms of driveway cuts and cross access between adjacent sites, including use of frontage roads and/or shared access, where feasible, as determined by Brevard County;
- B. Buffering from adjacent existing/potential uses;

- C. Open space provisions, breezeway/visual corridor requirements, and balance of proportion between gross floor area and site size;
- D. Adequacy of pervious surface area in terms of drainage requirements;
- E. Placement of signage;
- F. Adequacy of site lighting and intrusiveness of lighting upon the surrounding area;
- G. Safety of on-site circulation patterns (patron, employee and delivery vehicles), including parking layout and drive aisles, and points of conflict;
- H. Landscaping, as it relates to the requirements of the Comprehensive Plan and Land Development Regulations;
- I. Unique features and resources which may constrain site development, such as soils, existing vegetation and historic significance; and
- J. Performance based zoning requirements which may serve as a substitute for or accompany land development regulations in attaining acceptable site design.

Public Facilities and Services Requirements

Policy FLU 2.4

Minimum public facilities and services are required for commercial uses. The following criteria shall serve as guidelines for approving new commercial land use designations:

Criteria:

- A. Adequate roadways, solid waste disposal, hazardous waste disposal, potable water, wastewater treatment, and drainage facilities to serve the needs of the development shall be available concurrent with development in all commercial land use designations in accordance with policies set forth in the “Service Delivery, Concurrency, and Growth” section of this Future Land Use Element.
- B. Adequate fire protection, police protection, and emergency medical services to serve the needs of the development should be available concurrent with the impacts of development in all commercial land use designations.
- C. Where public potable water service is available, commercial development proposals shall be required to connect to the public potable water system.
- D. Where public sewer facilities are available, commercial development proposals shall be required to connect to the public sewer system.

FUTURE LAND USE ELEMENT

- E. Where public reclaimed water service is available, commercial development proposals shall be required to connect to the public reclaimed water system.
- F. The County shall not extend public utilities and services outside of established service areas to accommodate new development in commercial land use designations, unless an overriding public benefit can be demonstrated. This criterion is not intended to preclude acceptance of dedicated facilities and services by the County through MSBU's, MSTU's and other means through which the recipients pay for the service or facility.

Commercial Future Land Use Designations

Policy 2-4 FLU 2.5

The following two (2) commercial land use designations are adopted as part of the Future Land Use Map:

- Neighborhood Commercial (NC)
- Community Commercial (CC)

Activities Permitted in Neighborhood Commercial (NC) Future Land Use Designations

Policy 2-5 FLU 2.6

Neighborhood Commercial (NC) development activities are intended to be low-impact in nature and serve the needs of the immediate residential area. Intrusion of these land uses into surrounding residential areas shall be limited. Existing BU-1-A uses, which were established as of the adoption date of this provision shall be considered consistent with this policy. Development activities which may be considered within Neighborhood Commercial (NC) Future Land Use designation, provided that listed criteria are met, include the following:

- a) Professional offices (no drive through lanes permitted);
- b) Personal Services (no drive through lanes permitted);
- c) Convenience stores (no drive through lanes permitted);
- d) Residential uses;
- e) Institutional uses;
- f) Recreational uses;
- g) Public facilities; and
- h) ~~Transitional uses pursuant to Policy 2-12:~~ Resiliency Facilities, as defined by section 163.3210, F.S.

Zoning classifications that may be considered in Neighborhood Commercial as transitional uses are: RA-2-4, RA-2-6, RA-2-8, RA-2-10, RU-2-4, RU-2-6, RU-2-8, RU-2-10, RU-2-12, RU-2-15, RU-2-30, BU-1-A, and IN(L).

Locational and Development Criteria for Neighborhood Commercial Uses

Policy 2-6 FLU 2.7

Locational and development criteria for neighborhood commercial land uses are as follows:

FUTURE LAND USE ELEMENT

Criteria:

- A. Neighborhood commercial clusters should be located at collector/collector or collector/arterial intersections, except as otherwise provided for in this Comprehensive Plan.
- B. Due to the linear nature and lack of intersections along SR A1A south of Melbourne Beach, new neighborhood commercial uses may not be considered along those roadways ~~if there is sufficient infrastructure to support commercial development; if the area has an established commercial character; and if they are consistent with the other applicable policies of this Comprehensive Plan.~~
- C. New neighborhood commercial land use sites should incorporate no more than two acres maximum at each corner of an intersection, as set forth in Criterion A of this policy. Neighborhood commercial land uses at such intersections should not exceed eight (8) acres total.
- D. Neighborhood commercial development clusters should be spaced at least 1/2 mile apart, ~~except in the south beaches where neighborhood commercial clusters should be spaced at least three (3) miles apart.~~
- E. The gross floor area of neighborhood commercial complexes should not exceed a Floor Area Ratio (FAR) of 0.75 unless zoned PUD and adequate roadways, solid waste disposal, hazardous waste disposal, potable water, wastewater treatment, and drainage facilities to serve the needs of the development are available concurrent with its impacts.
- F. Recreational vehicle parks shall be located in areas which serve the needs of tourists and seasonal visitors to Brevard County. The location of recreational vehicle parks shall have access to interstate interchanges via arterial and principal collector transportation corridors or the property shall be located on a major multi-county transportation corridor.

In summary, Table 2.1 reiterates the specific development parameters and issues for consideration discussed in Policies FLU 2.1 and ~~2.6~~ 2.7 when evaluating requests for NC land use designations. This table also outlines issues which affect decision making for rezoning requests and for site plan review, as described in Policies FLU 2.2 and 2.3.

**Activities Permitted in Community Commercial (CC) Future Land Use Designations
Policy ~~2.7~~ FLU 2.8**

Community Commercial (CC) development activities are intended to serve several neighborhoods, sub-regional and regional areas and provide an array of retail, personal and professional uses. Development activities which may be considered within the Community

FUTURE LAND USE ELEMENT

Commercial (CC) Future Land Use designation, provided that the guidelines listed in Table 2.2 are met, include the following:

- a) Existing strip commercial;
- b) Transient commercial uses;
- c) Tourist commercial uses;
- d) Professional offices;
- e) Personal service establishments;
- f) Retail establishments;
- g) Non-retail commercial uses;
- h) Residential uses;
- i) Institutional uses;
- j) Recreational uses;
- k) Public facilities; and
- l) Transitional uses pursuant to Policy 2.1; and Resiliency Facilities, as defined by section 163.3210, F.S.
- m) ~~Planned Industrial Park development (as permitted by PIP zoning).~~

Locational and Development Criteria for Community Commercial Uses

Policy 2.8 FLU 2.9

Locational and development criteria for community commercial land uses are as follows:

Criteria:

- A. Community Commercial clusters of up to ten (10) acres in size should be located at arterial/arterial intersections. Collector/arterial intersections are acceptable for clusters of up to ten (10) acres in size, however, the collector roadways must serve multiple residential areas. Intrusion of these land uses into the surrounding residential areas shall be limited. For Community Commercial clusters greater than ten (10) acres in size, they must be located at principal arterial/principal arterial intersections.
- B. Community commercial complexes should not exceed 40 acres at an intersection.
- C. Community commercial clusters up to 10 acres in size should be spaced at least 2 miles apart and community commercial clusters up to 40 acres in size should be spaced at least five (5) miles apart.
- D. The gross floor area of community commercial complexes should not exceed 150,000 square feet for commercial clusters up to 10 acres in size and shall not exceed 400,000 square feet for commercial clusters greater than 10 acres but less than 40 acres in size unless within a Planned Unit Development (PUD) zoning classification. The square footage may be increased if it is located within a PUD zoning classification.

FUTURE LAND USE ELEMENT

- E. Floor Area Ratio (FAR) of up to 1.00 will be permitted for Community Commercial sites unless ~~accompanies~~ accompanied with a PUD zoning classification wherein the FAR may be increased up to 1.75.
- F. Recreational vehicle parks shall be located in areas which serve the needs of tourists and seasonal visitors to Brevard County. The location of recreational vehicle parks shall have access to interstate interchanges via arterial and principal collector transportation corridors or the property shall be located on a major multi-county transportation corridor.

In summary, Table 2.2 reiterates the specific development parameters and issues for consideration, as discussed in Policies FLU 2.1 and ~~2.8~~ 2.9, when evaluating requests for CC land use designations. This table also outlines issues which affect decision making for rezoning requests and for site plan review, as described in Policies FLU 2.2 and 2.3.

TABLE 2.1 THREE LAYER DEVELOPMENT REVIEW PROCESS FOR EVALUATING NEW NEIGHBORHOOD COMMERCIAL (NC) FUTURE LAND USES		
FIRST LEVEL OF REVIEW CONSISTENCY WITH COMPREHENSIVE PLAN ¹	SECOND LEVEL OF REVIEW CONSISTENCY WITH ZONING REGULATIONS ²	THIRD LEVEL OF REVIEW CONSISTENCY WITH LAND DEVELOPMENT REGULATIONS ³
Issues for Evaluation	Issues for Evaluation	Issues for Evaluation
Overall accessibility to the proposed NC site. (Policy 2.1.A)	Permitted/prohibited uses. (Policy 2.2.A)	Integration of vehicular and non-vehicular access into the site plan. (Policy 2.3.A)
Compatibility and inter-connectivity of proposed NC site with adjacent adopted Future Land designations and uses. (Policy 2.1.B)	Proposed zoning is consistent with zoning trends for the area. (Policy 2.2.B)	Access management features of the site design. (Policy 2.3.A)
Existing commercial development trend in the area as shown in a market analysis. (Policy 2.1.C)	Compatibility of proposed zoning with surrounding land uses. (Policy 2.2.C)	Adequacy of buffering provided. (Policy 2.3.B)
Changes in character of an area due to infrastructure improvements. (Policy 2.1.D)	Availability of public facilities to accommodate proposed zoning at or above adopted Level of Service standards. (Policy 2.2.D)	Open space provisions and balance of proportion between gross floor area and site size. (Policy 2.3.C)
Availability of public facilities to accommodate proposed NC Future Land Uses at or above adopted Level of Service standards. (Policy 2.1.E)	Impacts upon natural resources, including wetlands, floodplains and endangered species. (Policy 2.2.E)	Adequacy of pervious surface area in terms of drainage requirements of Land Development Code. (Policy 2.3.D)
Minimum Spacing from Nearest Commercial Land Use: .5 (one half) mile, with exceptions. (Policies 2.1.F and 2.6-D 2.7.D)	Other issues which may emerge specific to a particular property. (Policy 2.2.F)	Placement of signage on site. (Policy 2.3.E)
Size of proposed NC designation compared with current need. (Policy 2.1.G)	Development Parameters Addressed by BU-1A Zoning Regulations	Adequacy of site lighting and intrusiveness of lighting upon the surrounding area. (Policy 2.3.F)
Adherence of proposed NC land use to objectives/policies of the Conservation Element and the minimization of impacts upon natural systems. (Policy 2.1.H)	Listing of permitted/prohibited uses.	Safety of on site circulation patterns and points of conflicts. (Policy 2.3.G)
Integration of open space. ⁴ (Policy 2.1.I)	Minimum building setbacks requirements.	Landscaping conforms with policies of the Comprehensive Plan and the Land Development Code. (Policy 2.3.H)
Effect upon strip commercial development as a result of approving NC Future Land Use. (Policy 2.1-J 2.1.I)	Minimum lot size requirements.	Site plan sensitivity to protecting unique natural features. (Policy 2.3.I)
Location: Limited to intersections of Collector/Collector or Collector/Arterial roadways. (Policy 2.6-A 2.7.A)	Minimum floor area requirements.	Other performance based requirements. (Policy 2.3.J)
NC Future Land Use Site Size: 2 acres maximum (Policy 2.6-G 2.7.C)	Maximum building height allowances.	³ This table serves as a summary. Refer to Policies 2.3 and 2.6 2.7 for full details.
Maximum Floor Area Ratio (FAR): .75 ⁴ (Policy 2.6-E 2.7.E)	Buffering requirements.	
¹ This table serves as summary. Refer to Policies 2.1 and 2.6 2.7 for full details.	Traffic impact allowances.	
⁴ These parameters will be applied during the plan review process.	² This table is a summary. Refer to Policies 2.2 and 2.8 2.9 for full details.	

FUTURE LAND USE ELEMENT

TABLE 2.2 THREE LAYER DEVELOPMENT REVIEW PROCESS FOR EVALUATING NEW COMMUNITY COMMERCIAL (CC) FUTURE LAND USES		
FIRST LEVEL OF REVIEW CONSISTENCY WITH COMPREHENSIVE PLAN ¹	SECOND LEVEL OF REVIEW CONSISTENCY WITH ZONING REGULATIONS ²	THIRD LEVEL OF REVIEW CONSISTENCY WITH LAND DEVELOPMENT REGULATIONS ³
Issues for Evaluation	Issues for Evaluation	Issues for Evaluation
Overall accessibility to the proposed CC site. (Policy 2.1.A)	Permitted/prohibited uses. (Policy 2.2.A)	Integration of vehicular and non-vehicular access into the site plan. (Policy 2.3.A)
Compatibility and inter-connectivity of proposed CC site with adjacent adopted Future Land designations and uses. (Policy 2.1.B)	Proposed zoning is consistent with zoning trends for the area. (Policy 2.2.B)	Access management features of the site design. (Policy 2.3.A.)
Existing commercial development trend in the area as shown in a market analysis. (Policy 2.1.C)	Compatibility of proposed zoning with surrounding land uses. (Policy 2.2.C)	Adequacy of buffering provided. (Policy 2.3.B)
Changes in character of an area due to infrastructure improvements. (Policy 2.1.D)	Availability of public facilities to accommodate proposed zoning at or above adopted Level of Service standards. (Policy 2.2.D)	Open space provisions and balance of proportion between gross floor area and site size. (Policy 2.3.C)
Availability of public facilities to accommodate proposed CC Future Land Uses at or above adopted Level of Service standards. (Policy 2.1.E)	Impacts upon natural resources, including wetlands, flood plains, and endangered species. (Policy 2.2.E)	Adequacy of pervious surface area in terms of drainage requirements of Land Development Code. (Policy 2.3.D)
Minimum Spacing from Nearest CC Land Use: 2 miles for sites up to 10 acres and 5 miles for sites >10 acres. (Policies 2.1.F and 2-8-G 2.9.C)	Other issues which may emerge specific to a particular property. (Policy 2.2.F)	Placement of signage on site. (Policy 2.3.E)
Size of proposed CC designation compared with current need. (Policy 2.1.G)	Development Parameters Addressed by BU-1 & BU-2 Zoning Regulations	Adequacy of site lighting and intrusiveness of lighting upon the surrounding area. (Policy 2.3.F)
Adherence of proposed CC land use to objectives/policies of the Conservation Element and the minimization of impacts upon natural systems. (Policy 2.1.H)	Listing of permitted/prohibited uses.	Safety of on site circulation patterns and points of conflicts. (Policy 2.3.G)
Integration of open space. ⁴ (Policy 2.1-I)	Minimum building setbacks requirements.	Landscaping conforms with policies of the Comprehensive Plan and the Land Development Code. (Policy 2.3.H)
Effect upon strip commercial development as a result of approving CC Future Land Use. (Policy 2-1-J 2.1.I)	Minimum lot size requirements.	Site plan sensitivity to protecting unique natural features. (Policy 2.3.I)
Locations: Limited to intersections of Arterial/Arterial or Collector/Arterial roadways for sites up to 10 acres (with exceptions) and limited to Principal Arterial/Principal Arterial intersections for sites >10 acres. (Policy 2-8-A 2.9.A)	Minimum floor area requirements.	Other performance based requirements. (Policy 2.3.J)
CC Future Land Use Site Size: >2 acres and <40 acres. (Policy 2-8-B 2.9.B)	Maximum building height allowances.	³ This table serves as a summary. Refer to Policies 2.3 and 2-8 2.9 for full details.
Minimum spacing from nearest CC land use: 2 miles for sites up to 10 acres and 5 miles for sites > 10 acres. (Policy 2-8-C)	Buffering requirements.	
Maximum Building Size: up to 150,000 square feet for sites up to 10 acres and up to 400,000 square feet for sites > 10 acres unless within an approved PUD, then a maximum of 76,230 GFA per acre. ⁴ (Policy 2-8-D 2.9.D)	² This table is a summary. Refer to Policies 2.2 and 2-8 2.9 for full details.	
Maximum Floor Area Ratio (FAR): 1.0 for sites up to 10 acres and 1.0 for sites >10 acres unless with PUD zoning classification wherein the FAR is up to 1.75. ⁴ (Policy 2-8-E 2.9.E)		
¹ This table serves as summary. Refer to Policies 2.1 and 2-8 2.9 for full details.		
⁴ These parameters will be applied during the plan review process.		

FUTURE LAND USE ELEMENT

Regional Commercial Centers

Policy 2-9 FLU 2.10

Regional commercial centers are those which meet the standards for Developments of Regional Impact, as defined by Chapter 380, F.S. that exceed 40 acres in size and/or 400,000 square feet of gross leasable area. Such land uses shall only be located within the Development of Regional Impact (DRI) future land use designation. Project design and review standards shall be in accordance with the requirements of Chapter 380, F.S. FLU Policies 2.2, 2.3, 2.4, 2.8, and 2.9 of this element.

Residential Development in Neighborhood Commercial and Community Commercial Land Use Designations

Policy 2-10 FLU 2.11

Residential development or the integration of residential development with commercial development shall be permitted in the Neighborhood Commercial and Community Commercial land use designations, provided that the scale and intensity of the residential/mixed use development is compatible with abutting residential development and areas designated for residential use on the Future Land Use Map. Residential development is permissible in these commercial land use designations at a density as follows. ~~of up to one category higher than the closest residentially designated area on the Future Land Use Map (FLUM) which is on the same side of the street. residential designation within one-quarter mile on the same side of the street. If there are no residential designations within one-quarter mile on the same side of the street and along the street, then the property is limited to the adjacent residential designation on the same side of the street, or as designated in public hearing.~~

1. Density of one category higher than the closest residential designation within one-quarter mile on the same side of the street with frontage on the street.

2. If criteria (1) of this section cannot be satisfied, then the development is limited to the adjacent residential designation on the same side of the street.

3. If criteria (1) and (2) of this section cannot be satisfied, then the density shall be determined through a public hearing provided that public facilities to serve the proposed development will be available concurrent with its impact.

~~Increases in density beyond this allowance may be considered through a public hearing the provisions of 125.01055, F.S., for affordable housing and only when public facilities to serve the proposed development will be available concurrent with its impacts.~~ In the CHHA, however, residential development is strictly limited to the density of the closest residentially designated area on the FLUM that is on the same side of the street. Such residential development, as described above, shall be allowed to utilize the following characteristics:

Criteria:

- A. Residential uses within Neighborhood Commercial and Community Commercial designations shall be encouraged to utilize ~~neo-traditional neighborhood development techniques, such as narrower road rights-of-way, mid-block pedestrian pass-throughs, alleys, smaller lot sizes, on-street~~

FUTURE LAND USE ELEMENT

~~parking, reduced lot line setbacks~~ PUD zoning or open space subdivision techniques and public transit facilities.

- B. Residential density bonuses as set forth in Policy FLU 11.2 may be considered in addition to the bonus stated in the above policy within Neighborhood Commercial and Community Commercial designations in redevelopment districts as an incentive for redevelopment and regentrification if the proposed development will address serious incompatibility with existing land uses, is adequately buffered from other uses, is located along major transportation corridors, and meets the concurrency requirements of this Comprehensive Plan.

Transitional Commercial Activities

Policy ~~2-11~~ FLU 2.12

As a result of their intrinsic nature and scale of intensity, offices, non-retail and neighborhood commercial activities may be utilized as transitional activities to afford buffering between higher and lower intensity uses, including transportation corridors. Due to their intrinsic nature and intensity of scale, offices, non-retail, neighborhood commercial, and multifamily residential uses may serve as a transition to buffer lower intensity uses from the impacts of higher intensity uses. The criteria listed below, ~~as summarized by Table 2-3,~~ should serve as locational guidelines for ~~employing such development as~~ approving transitional uses. Projects ~~which~~ that are approved as transitional uses may be subject to special requirements by the County, such as buffers, lighting, hours of operation, access/egress points, etc. in order to minimize impact upon adjacent lower intensity uses. In residential land use designations, strict adherence to development parameters outlined in Policies ~~2-6~~ FLU 2.7 and ~~2-8~~ FLU 2.9 must be maintained to qualify for consideration as a transitional activity under this policy. Once a transition is achieved between a higher and lower intensity land use, this policy should not be construed to justify the extension or enlargement of such uses onto adjacent lower intensity lands.

Criteria:

- A. Non-retail commercial land uses shall be limited to those areas where non-retail commercial or industrial characteristics are established or planned so as to protect residential areas from their influence. Non-retail uses, including wholesaling, contracting, heavy repair services, paint and body shops, storage and warehousing uses, may serve as a transitional use between the following higher intensity and lower intensity uses, in the following listed Future Land Use designations:

Higher Intensity Uses:

Heavy Industrial or Light Industrial activities.

Lower Intensity Uses:

Community Commercial, Planned Industrial Park or Planned Business Park uses.

FUTURE LAND USE ELEMENT

Future Land Use designations:	Community Commercial, Heavy/Light Industrial or Planned Industrial (Planned Industrial permits PIP zone uses only).
Roadway Access Requirements:	Convenient access to a major transportation corridor or along a railroad corridor with visual buffering from such corridors.

B. Professional Office uses may serve as a transition between the following higher intensity and lower intensity uses, in the following listed Future Land Use designations:

Higher Intensity Uses:	Light Industrial, Heavy Industrial, Planned Industrial Park, Planned Business Park, Neighborhood Commercial or a transportation corridor.
Lower Intensity Uses:	<u>Residential 3 Directive</u> , Residential 4, <u>Residential 5 Directive</u> , Residential 6, <u>Residential 8 Directive</u> , Residential 10, <u>Residential 12 Directive</u> , or Residential 15
Future Land Use Designations:	Neighborhood Commercial, Community Commercial, <u>Residential 3 Directive</u> , Residential 4, <u>Residential 5 Directive</u> , Residential 6, <u>Residential 8 Directive</u> , Residential 10, <u>Residential 12 Directive</u> , Residential 15. These residential land use designations permit RP zone uses only.
Roadway Access Requirements:	Direct access to collector or higher roadway.

C. Neighborhood Commercial uses may serve as a transition between the following higher intensity and lower intensity uses, in the following listed Future Land Use designations:

Higher Intensity Uses:	Any higher intensity uses listed in Criteria A and B above.
Lower Intensity Uses:	Professional Offices (RP and BU-1-A zone uses only) and any residential.

FUTURE LAND USE ELEMENT

Future Land Use Designations: Neighborhood Commercial and all Residential designations.
Roadway Access Requirements: Direct access to collector or higher roadway.

D. Residential uses as authorized by section 125.01055, F.S., for affordable housing with densities higher than 10 units per acre may serve as a transition between higher intensity and lower intensity uses, in the following listed Future Land Use designations:

Higher Intensity Uses: Non-residential uses.

Lower Intensity Uses: Residential 1:2.5, Residential 1, Residential 2, Residential 2 Directive, Residential 3 Directive, Residential 4, Residential 4 Directive, Residential 5 Directive.

Future Land Use Designations: Neighborhood Commercial, Community Commercial, Heavy/Light Industrial, Planned Industrial.

Future Land Use Designations: Direct access to collector or higher roadway.

FUTURE LAND USE ELEMENT

TABLE 2.3				
LOCATIONAL CRITERIA FOR TRANSITIONAL COMMERCIAL & INDUSTRIAL LAND USES ¹				
TRANSITIONAL ¹ USE	TRANSITION FROM...	TRANSITION TO...	PERMITTED FUTURE LAND-USE DESIGNATION	ROADWAY ACCESS REQUIREMENTS
Non-retail ² Uses	Light Industrial or Heavy Industrial	Community Commercial; Planned Industrial Park; or Planned Business Park	Community Commercial; Heavy/Light Industrial; or Planned Industrial ⁴	Convenient access to a major transportation corridor or along a railroad corridor, but must be visually buffered from such corridors.
Professional Office	Light Industrial, Heavy Industrial, Planned Industrial Park, Planned Business Park, Neighborhood Commercial, or Transportation Corridors	Residential (4 units per acre or higher density)	Neighborhood Commercial; Community Commercial; Residential 4 ³ ; Residential 6 ³ ; Residential 10 ³ ; Residential 15 ³ ; or Residential 30 ³	Direct access to collector or higher.
Neighborhood Commercial	Any of the above uses, plus Community Commercial	Professional Offices ³ Residential	Neighborhood Commercial and all Residential Designations	Direct access to collector or higher.
¹ -This table serves as a summary. Refer to Policy 2.11 for full details. ² -Generally includes wholesaling, contracting, heavy repair services, paint and body shops, storage and warehousing uses. ³ -Permits RP and BU-1-A zoning uses only. ⁴ -Permits PIP zoning uses only.				- - - -

FUTURE LAND USE ELEMENT

Strip Commercial Development

Policy ~~2-12~~ FLU 2.13

The creation/promotion of strip pattern of commercial development shall be discouraged. Infill within established strip commercial areas is preferred over extension of a strip commercial pattern. Extension of a commercial land use designation may be considered in circumstances where the proposed commercial parcel is located within a block in which at least fifty percent (50%) of the block face (in linear feet) is either currently developed with commercial land uses or is designated for commercial use. In either case, the proposed commercial land use extension shall not constitute an encroachment into a residential area. ~~Refer to Figure 1 in the Appendix, "Illustrative Examples of Commercial Infill vs. Extension of Strip Development."~~ Judging the suitability of a location for an extension of strip commercial development activities shall be based upon the following minimum criteria:

Criteria:

- A. Impacts upon traffic circulation should be anticipated and mitigated through the reservation of right-of-way for road widening and marginal access streets. Access points for strip commercial complexes shall seek to minimize points of conflict by utilizing frontage roads, providing cross access between parcels or installing shared use curb cuts for access driveways to the maximum extent feasible, as determined by Brevard County.
- B. Setbacks and landscaped or other appropriate buffers shall be established to mitigate the visual impacts of strip commercial development.
- C. A sidewalk or bicycle path shall be required where appropriate, as encouraged by ~~Tables 2.1 and 2.2~~ Policies FLU 2.1, 2.2, and 2.3 to provide convenient access to surrounding residents and to reduce traffic volumes on the roadways.
- D. Adequacy of off-street parking, off-street loading facilities and stormwater facilities.

Periodic Review of Commercial Area Allocations

Policy ~~2-13~~ FLU 2.14

As part of each Evaluation and Appraisal Report (EAR), Brevard County shall analyze the allocation of commercial acreage in the Future Land Use Map. The evaluation of said allocation shall be based upon the following minimum criteria:

Criteria:

- A. Commercial development trends;
- B. The types, intensities, locations, and land areas of commercial land use designations; and
- C. Commercial acreage allocations shall consider all commercial development, whether within or outside of commercial land use designations.

FUTURE LAND USE ELEMENT

Institutional Future Land Use Designations

Policy 2.14 FLU 2.15

Because of the contrasting nature of institutional activities, two types of institutional land uses are identified below. Institutional uses shall be evaluated according to the following location and development criteria:

Criteria:

- A. Low Intensity Institutional Uses
 - 1. Permitted in all Residential Land Use Designations and in the Neighborhood Commercial Land Use Designation
 - 2. Access to a roadway classified as a local street or higher
 - 3. Pedestrian access required
 - 4. Building scale and design compatible with the surrounding neighborhood
- B. High Intensity Institutional Uses
 - 1. Permitted in the Community Commercial Land Use Designation
 - 2. Access to a roadway classified as an arterial or higher
 - 3. Access to a roadway classified as a collector or higher in established Community
 - 4. Commercial areas' intrusion into residential areas shall be limited. High Intensity Institutional Uses shall be located in areas where commercial development is planned or established.

Industrial Land Uses

Objective FLU 3

Brevard County shall provide for adequate and appropriate lands for the location of industrial land uses to support the role of these uses in the County's economy. Brevard County shall direct new industrial land use designations to areas which are determined to be appropriate based upon a suitability analysis, character of the area, compatibility with surrounding land uses, and public facilities and services. These uses shall be directed to sites where there are sufficient uplands for the intended use and for all other measures to ensure wetland function. During the review of proposed amendments to the Future Land Use Map, which would allow industrial uses, Brevard County shall ensure that the site is suitable for the proposed use with regard to environmental features. The proposed designation shall be consistent with the following suitability criteria:

Criteria:

- A. Floodplain policies contained within Conservation Objective CON 4.
- B. Aquifer protection policies contained within Conservation Objective ~~11~~ CON 10.

- C. Types, values, conditions, functions, and locations of wetlands, and wetland protection policies contained in Conservation Objective CON 5.

Role of the Comprehensive Plan in the Designation of Industrial Lands

Policy FLU 3.1

The Comprehensive Plan shall impose broad criteria for consideration in evaluating proposals for new industrial designated lands within Brevard County. At a minimum, these criteria shall address the following:

Criteria:

- A. Compatibility with adjacent adopted Future Land Use designations and land uses;
- B. Existing industrial development trend in the area;
- C. Availability of required infrastructure at/above adopted levels of service;
- D. Size of proposed industrial designation compared with current need for industrial lands;
- E. Accessibility to major transportation corridors, as well as air, water, and rail transportation facilities;
- F. Adherence to the objectives/policies of the Solid Waste and Hazardous Materials Element and the Conservation Element and minimization of impacts upon natural resources and systems; and
- G. Accessibility to labor, raw materials and markets.

Role of Zoning Regulations in the Designation of Industrial Lands

Policy FLU 3.2

Zoning regulates the specific types and intensities of uses. Criteria which aid in assessing zoning compatibility shall consider the following standards:

Criteria:

- A. Permitted/prohibited uses;
- B. Existing industrial zoning trends in the area;
- C. Compatibility of proposed use with area;
- D. Impact upon Level of Service (LOS) standards for roads, potable water service, sanitary sewer service, and solid waste disposal; and
- E. Impact upon natural resources, including air and water, wetlands, floodplains, and endangered species.

FUTURE LAND USE ELEMENT

- F. Other issues which may emerge specific to a particular property which may be addressed through performance based zoning criteria.

Role of Land Development Regulations in the Designation of Industrial Lands

Policy FLU 3.3

Once a proposed project is designed, site plan/land development regulations provide the final level of review for evaluating the acceptability of proposed industrial development activities. Criteria include:

Criteria:

- A. Accessibility of site for vehicular and non-vehicular modes;
- B. Buffering from adjacent existing/potential uses in terms of set backs, landscaping, and open space as well as the arrangement of access and parking for the site;
- C. Open space provisions and balance of proportion between gross floor area and site size;
- D. Adequacy of pervious surfaces in terms of drainage requirements;
- E. Safety of on site vehicular circulation patterns (patrons, employees, and delivery vehicles) including loading facilities, truck parking, and points of conflict;
- F. Storage locations and buffering from the surrounding area;
- G. Adequacy of site lighting and intrusiveness of lighting upon the surrounding area;
- H. Building placement/arrangement on the site;
- I. Provision of breezeway/visual corridor for riverfront and oceanfront properties;
- J. Placement of signage;
- K. Unique features and resources which may constrain site development, such as soils, existing vegetation and historic significance.
- L. Performance based zoning requirements which may serve as a substitute for or accompany Land Development Regulations in attaining acceptable site design;
- M. Suitability of mixture of uses (if multiple uses proposed);

- N. Blending of the project with the character of the area; and
- O. Landscaping conforms with the policies of the Comprehensive Plan and land development code.

Public Facilities and Services Requirements

Policy FLU 3.4

Minimum public facilities and services are required for industrial uses. The following criteria shall serve as guidelines for approving new industrial land use designations:

Criteria:

- A. Adequate roadways, solid waste disposal, hazardous waste disposal, potable water, wastewater treatment, and drainage facilities to serve the needs of the development shall be available concurrent with development in all industrial land use designations in accordance with policies set forth in the “Service Delivery, Concurrency, and Growth” section of this Future Land Use Element.
- B. Adequate fire protection, police protection, and emergency medical services to serve the needs of the development should be available concurrent with the impacts of development in all industrial land use designations.
- C. Where public potable water service is available, industrial development proposals shall be required to connect to the public potable water system.
- D. Where public sewer facilities are available, industrial development proposals shall be required to connect to the public sewer system.
- E. Where public reclaimed water service is available, industrial development proposals shall be required to connect to the public reclaimed water system.
- F. The County shall not extend public utilities and services outside of established service areas to accommodate new development in industrial land use designations, unless an overriding public benefit can be demonstrated. This criterion is not intended to preclude acceptance of dedicated facilities and services by the County through MSBU’s, MSTU’s and other means through which the recipients pay for the service or facility.

Industrial Future Land Use Designations

Policy ~~3.4~~ FLU 3.5

The two (2) industrial land use designations adopted as part of the Future Land Use Map are:

- Planned Industrial
- Heavy/Light Industrial

Planned Industrial Land Use Designation

Policy 3.5 FLU 3.6

The Planned Industrial land use designation is intended to accommodate the clustering of light industrial and business uses in settings which provide special attention to the integration of infrastructure, such as circulation, parking, and utilities, while placing emphasis upon aesthetics of the project and compatibility with abutting properties and properties within the industrial park. These parks shall be designed to limit intrusion into residential areas. Appropriate uses are those that operate within enclosed buildings such as manufacturing, assembling, fabricating, warehousing, and retailing activities. Hotel and motel accommodations that serve the travel needs of employees or clients associated with firms within the planned industrial or business parks are also appropriate. Marinas may also be considered within this land use designation. Resiliency Facilities, as defined by section 163.3210, F.S. shall be a permitted use in this land use designation. Appropriate locations for planned industrial parks shall be based upon the criteria listed below. Table 3.1 summarizes the specific development parameters listed below as well as issues that affect decision making for rezoning requests and for site plan review, as described in Policies FLU 3.2 and FLU 3.3.

Criteria:

- A. Planned industrial park project sites shall incorporate at least three (3) acres.
- B. Planned industrial parks must be within 660 feet of the major transportation corridors. Major transportation corridors include such roadways as Interstate 95, U.S. Highways 1 and 192, and State Roads 3, 46, 50, 528, 524, 520, 518, and 516.

TABLE 3.1 THREE LAYER DEVELOPMENT REVIEW PROCESS FOR EVALUATING NEW PLANNED INDUSTRIAL FUTURE LAND USES		
FIRST LEVEL OF REVIEW CONSISTENCY WITH COMPREHENSIVE PLAN ¹	SECOND LEVEL OF REVIEW CONSISTENCY WITH ZONING REGULATIONS ²	THIRD LEVEL OF REVIEW CONSISTENCY WITH LAND DEVELOPMENT REGULATIONS ³
Issues for Evaluation	Issues for Evaluation	Issues for Evaluation
Compatibility of proposed Planned Industrial Future Land Use with adjacent adopted Future Land designations and uses. (Policy 3.1.A)	Permitted/prohibited uses. (Policy 3.2.A)	Accessibility of site. (Policy 3.3.A)
Existing Planned Industrial development trend in the area. (Policy 3.1.B)	Proposed zoning is compatible with zoning trends for the area. (Policy 3.2.B)	Buffering of adjacent existing/potential uses. (Policy 3.3.B)
Availability of public facilities to accommodate proposed Planned Industrial Future Land Uses at or above adopted Level of Service standards. (Policy 3.1.C)	Proposed zoning is compatible with surrounding land uses. (Policy 3.2.C)	Open space provisions and balance of proportion between gross floor area and site size. (Policy 3.3.C)
Size of proposed Planned Industrial designation compared with current need for such lands. (Policy 3.1.D)	Availability of public facilities to accommodate the proposed zoning at or above adopted Level of Service standards. (Policy 3.2.D)	Adequacy of pervious surface area in terms of drainage requirements. (Policy 3.3.D)
Accessibility to major transportation corridors, as well as air, water and rail transportation facilities. (Policy 3.1.E)	Impacts upon natural resources, including wetlands, flood plains and endangered species. (Policy 3.2.E)	Safety of on site vehicular circulation, loading facilities and truck parking. (Policy 3.3.E)
Adherence to objectives/policies of the <u>Solid Waste and Hazardous Materials Element</u> and Conservation Element and the minimization of impacts upon natural systems. (Policy 3.1.F)	Other issues which may emerge specific to a particular property. (Policy 3.2.F)	Storage locations and buffering from surrounding area. (Policy 3.3.F)
Planned Industrial Park land use designation minimum acreage: 3 acres (Policy 3-5-A 3.6.A)	Development Parameters Addressed by PIP & PBP Zoning Regulations	Arrangement of site lighting and intrusiveness of lighting upon the surrounding area. (Policy 3.3.G)
Planned Industrial Park land use designation must be within 660' of a major transportation corridor. (Policy 3-5-B 3.6.B)	Listing of permitted/prohibited uses.	Building placement/arrangement. (Policy 3.3.H)
¹ This table serves as a summary. Refer to Policies 3.1 and 3-5 3.6 for details. ² This table serves as a summary. Refer to Policies 3.2 and 3-5 3.6 for full details. ³ This table serves as a summary. Refer to Policies 3.3 and 3-5 3.6 for full details.	Minimum parks size requirements.	Provision of breezeway/visual corridor for riverfront properties. (Policy 3.3.I)
	Minimum buffering requirements.	Location of signage. (Policy 3.3.J)
	Minimum lot size requirements.	Site plan sensitivity to protecting unique natural features. (Policy 3.3.K)
	Minimum building setback requirements.	Other performance based requirements. (Policy 3.3.L)
	Maximum lot coverage requirements.	Suitability of mixture of uses (if multiple uses proposed). (Policy 3.3.M)
	Maximum building height allowances.	Blending with the character of the area. (Policy 3.3.N)
	Loading facility requirements.	Landscaping conforms with policies of the Comprehensive Plan and land development code. (Policy 3.3.O)
	Lighting standards.	

FUTURE LAND USE ELEMENT

Heavy/Light Industrial Land Use Designation

Policy 3.6 FLU 3.7

The Heavy/Light Industrial land use designation is intended to accommodate an array of industrial activities ranging from those which involve indoor manufacturing to those which utilize prepared materials in the outdoor production of goods. Resiliency Facilities, as defined by section 163.3210, F.S. shall be a permitted use in this land use designation. IU and IU-1 uses may be permitted only within an area designated for Heavy/Light Industrial uses, ~~unless treated as a transitional use pursuant to Policy 2.2.~~ Heavy/Light industrial land uses shall be deemed appropriate provided that the generalized locational factors listed below are satisfied. Table 3.1 summarizes the specific development parameters listed below as well as issues that affect decision making for rezoning requests and for site plan reviews, as described in Policies FLU 3.2 and FLU 3.3.

Criteria:

- A. Industrial development shall be located with ~~convenient~~ resilient access to major transportation corridors, as well as air, water, and rail transportation facilities when such access is required for logistical purposes. Major transportation corridors include such roadways as Interstate 95, U.S. Highways 1 and 192, and State Roads 3, 46, 50, 528, 524, 520, 518, and 516.
- B. Industrial land uses should be located with ~~convenient~~ resilient access to the labor supply, raw material sources and market areas.
- C. Natural vegetative and other appropriate buffers, ~~potentially primarily~~ in the form of performance based standards, shall be employed as part of industrial site development to minimize the nuisance effects of industrial land uses, including noise, odor, and visual effects, and to provide aesthetically pleasing settings for such uses.

Light Industrial Uses in the Heavy/Light Industrial Designation

Policy 3.7 FLU 3.8

Light industrial land uses involve manufacturing, assembling, fabricating, and warehousing activities which are generally conducted indoors. Such uses have the potential to adversely affect surrounding land uses; therefore, light industrial development proposals shall be reviewed for compatibility with surrounding land uses. Locations for light industrial land uses shall be based upon the following minimum criteria:

Criteria:

- A. Light industrial land uses shall not be located within 660 feet of major transportation corridors, unless such uses are located west of railroad right-of-way along U. S. Highway 1 and are served by a spur or other connection to the rail line or are water-dependent or water-dependent uses or meet the criteria below.
- C. Light industrial land uses may also be considered within 660 feet of the major transportation corridors if they are located contiguous to an established

FUTURE LAND USE ELEMENT

industrial park (lands separated by roads are considered contiguous), and if such lands have existing IU (light industrial) zoning and such zoning has existed for at least ten years, provided that such lands contain natural vegetation affording sufficient visual screening from the transportation corridor. Under these circumstances, all natural vegetation shall be retained within a minimum 15 foot roadway buffer area unless it is determined by the County that such vegetation needs to be replaced due to the poor health or viability of the vegetation. Drainage works and all other improvements shall not be permitted within the 15 foot roadway buffer area. The landscaping requirements of this provision shall be carried out in addition to the requirements of Brevard County Landscaping Regulations. Major transportation corridors include such roadways as Interstate 95, U.S. Highways 1 and 192, and State Roads 3, 46, 50, 528, 524, 520, 518, and 516.

- C. Sites for light industrial land uses shall be at least 20,000 square feet in size.
- D. Floor Area Ratio (FAR) for a light industrial land use project ~~should~~ shall not exceed 2.48.

Heavy Industrial Uses in the Heavy/Light Industrial Land Use Designation
Policy 3-8 FLU 3.9

Heavy industrial land uses include indoor and outdoor activities such as cement and concrete production, chemicals and fertilizer processing, lumber mills, foundries and forge works, and paint and plastics production. Heavy industrial land uses have the potential to adversely affect surrounding land uses; therefore, such development proposals shall be reviewed for compatibility with surrounding land uses. Locations for heavy industrial land uses shall be based upon the following minimum criteria:

Criteria:

- A. Heavy industrial land uses shall not be located within 660 feet of major transportation corridors, unless such uses are existing or are located west of the railroad right-of-way along U.S. Highway 1 and are served by a spur or other connection to the rail line or are water-dependent or water-related uses. Major transportation corridors include such roadways as Interstate 95, U.S. Highways 1 and 192, and State Roads 3, 46, 50, 528, 524, 520, 518, and 516.
- B. Sites for heavy industrial land uses shall ~~incorporate~~ be at least 40,000 square feet in size.
- C. Floor Area Ratio (FAR) for a heavy industrial land use project ~~should~~ shall not exceed 1.76.

TABLE 3.2 THREE LAYER DEVELOPMENT REVIEW PROCESS FOR EVALUATING NEW HEAVY/LIGHT INDUSTRIAL FUTURE LAND USES

FIRST LEVEL OF REVIEW CONSISTENCY WITH COMPREHENSIVE PLAN ¹	SECOND LEVEL OF REVIEW CONSISTENCY WITH ZONING REGULATIONS ²	THIRD LEVEL OF REVIEW CONSISTENCY WITH LAND DEVELOPMENT REGULATIONS ³
Issues for Evaluation	Issues for Evaluation	Issues for Evaluation
Compatibility of proposed Heavy/Light Industrial Future Land Use with adopted Future Land Uses in the surrounding area. (Policy 3.1.A)	Permitted/prohibited uses. (Policy 3.2.A)	Accessibility of the site. (Policy 3.3.A)
Existing Heavy/Light Industrial development trend in the area. (Policy 3.1.B)	Proposed zoning is consistent with zoning trends for the area. (Policy 3.2.B)	Buffering of adjacent existing/potential uses. (Policy 3.3.B)
Availability of public facilities to accommodate proposed Heavy/Light Industrial Future Land Uses at or above adopted Level of Service standards. (Policy 3.1.C)	Proposed zoning is compatible with surrounding land uses. (Policy 3.2.C)	Open space provisions and balance of proportion between gross floor area and site size. (Policy 3.3.C)
Size of proposed Heavy/Light Industrial designation compared with current need for Heavy/Light Industrial lands. (Policy 3.1.D)	Availability of public facilities to accommodate proposed zoning at or above LOS standards. (Policy 3.2.D)	Adequacy of pervious surface areas in terms of drainage requirements (Policy 3.3.D)
Accessibility to major transportation corridors, air, water and rail transportation facilities. (Policies 3.1.E and 3.6-A 3.7.A)	Adherence of proposed zoning to the objectives/policies of the Conservation Element and minimization of impacts upon natural systems. (Policy 3.2.E)	Safety of on site vehicular circulation, loading facilities and truck parking. (Policy 3.3.E)
Minimization of impacts upon natural systems. (Policy 3.1.F)	Development Parameters Addressed by IU and IU-1 Zoning Regulations	Storage locations and buffering from rights of way and the surrounding area. (Policies 3.3.F and 3.7-B 3.8.B)
Convenient access to labor, raw materials and market areas. (Policies 3.1.G and 3.6-B 3.7.B)	Permitted/prohibited uses.	Arrangement of site lighting and intrusiveness of lights upon the surrounding area. (Policy 3.3.G)
Provision of natural vegetative or other appropriate buffers to minimize nuisance effects. ⁴ (Policy 3.6-G 3.7.C)	Minimum lot size requirements.	Building placement/arrangement. (Policy 3.3.H)
Other performance based standards to minimize nuisance effects. ⁴ (Policy 3.6-G 3.7.C)	Minimum building setback requirements.	Provision of breezeway/visual corridor for riverfront properties. (Policy 3.3.I)
Light Industrial uses should not be located within 660' of major transportation corridors, unless contiguous with the railroad along US 1 or are water dependent/related uses. (Policies 3.7-A 3.8.A and 3.7-B 3.8.B)	Floor Area Ratio requirements.	Location of signage. (Policy 3.3.J)
Minimum Lot Size for Light Industrial Uses: 20,000 s.f. ⁴ (Policy 3.7-G 3.8.C)	Maximum building height allowances.	Site plan sensitivity to the protection of unique natural features. (Policy 3.3.K)
Maximum Floor Area Ratio (FAR) for Light Industrial use: 2.48 ⁴ (Policy 3.7-D 3.8.D)	Minimum buffering requirements.	Other performance based requirements. (Policy 3.3.L)
Heavy Industrial uses should not be located within 660' of major transportation corridors, unless contiguous with the railroad, adjacent to US 1, or are water related/dependent uses. (Policies 3.8-A 3.9.A)	Traffic impacts associated with the proposed use(s).	Suitability of mixture of uses (if multiple uses proposed). (Policy 3.3.M)
Minimum Lot Size for Heavy Industrial Uses: 40,000 s.f. ⁴ (Policy 3.8-B 3.9.B)		Provision of natural vegetative buffers, fencing materials or other buffers to minimize nuisance effects such as noise, odor, visual impacts. (Policies 3.3.B and 3.3.N)
Maximum Floor Area Ratio (FAR) for Heavy Industrial use: 1.76 ⁴ (Policy 3.8-G 3.9.C)		Landscaping conforms with policies of the Comprehensive Plan and land development code. (Policy 3.3.O)
¹ This table serves as a summary. Refer to Policies 3.1, 3.6, 3.7 and 3.8 3.7, 3.8, and 3.9 for full details. ² This table serves as a summary. Refer to Policies 3.2 and 3.6, 3.7 and 3.8 3.7, 3.8, and 3.9 for full details.		
³ This table serves as a summary. Refer to Policies 3.3 and 3.6, 3.7 and 3.8 3.7, 3.8, and 3.9 for full details. ⁴ These parameters will be applied during the plan review process.		

FUTURE LAND USE ELEMENT

Water-Related and Water-Dependent Industrial Uses

Policy ~~3.9~~ FLU 3.10

Waterfront parcels may be designated for Heavy/Light Industrial land use to satisfy unique locational needs for water-dependent and water-related industrial activities, provided that such activity is compatible with surrounding existing and programmed development and is consistent with these Industrial land use policies. Appropriate locations for water-dependent and water-related industrial land uses shall be based upon the following minimum criteria:

Criteria:

- A. Only water-dependent industrial land uses, which must be carried out only on, in, or adjacent to water areas, may be considered for location along the Indian River ~~lagoon~~ Lagoon system.
- B. Water-related industrial land uses shall be considered only on the uplands adjacent to Class III waters of the Indian River ~~lagoon~~ Lagoon system. Water-related uses are those which are not directly dependent upon access to a water body but which provide goods and services to uses which are water-dependent.
- C. Directives, policies and criteria in the Coastal Management and Conservation elements of this Comprehensive Plan which address water-dependent and water-related land uses shall be utilized in the location of industrial uses adjacent to water bodies.

Agricultural Land Uses

Objective FLU 4

Brevard County recognizes the importance of agricultural lands to the community as the industry benefits the economy, reduces the extent of urban sprawl; and the costs of providing public facilities and services, provides environmental benefits, and provides open space and visual beauty. The County shall enhance and protect agricultural lands; and provide for the continuing viability of the agricultural industry in the County's economy.

Permitted Uses in Agricultural Land Use Designation

Policy FLU 4.1

Appropriate and adequate lands shall be designated Agricultural on the Future Land Use Map. Agricultural activities include, but are not limited to, row, vegetable, and fruit crop production; dairy, poultry, and livestock production; and aquaculture, silviculture, horticulture, and apiariculture. Solar facilities, per section 163.3205, F.S., shall be permitted in this land use designation. Large lot residential development which does not impede the use of lands for agricultural purposes

FUTURE LAND USE ELEMENT

shall be permitted in this land use designation. The following minimum criteria shall govern activities in this land use designation:

Criteria:

- A. Residential densities shall not exceed one dwelling unit per five (5) acres.
- B. The County shall not extend public utilities and services outside of the service areas to Agricultural areas for new development, unless there is an overriding public benefit which accrues to an area larger than the specific Agricultural area. However, the County will accept facilities through dedication, and provide services and utilities through MSBU's, MSTU's and other means through which the recipients pay for the service or facility.
- C. The County shall actively promote Transfer of Development Rights from Agricultural Lands and restrict Open Space Subdivisions and corresponding density bonuses in those areas designated as Agricultural on the Future Land Use Map.
- D. The County may allow agritourism activities, per section 570.85, F.S., on land classified as agricultural land under section 193.461, F.S.

Maintenance of Agricultural Designated Lands

Policy FLU 4.2

Brevard County shall support voluntary federal, state, and private acquisition and incentive programs for the maintenance of agricultural lands ~~as opposed to eminent domain procedures.~~

Policy FLU 4.3

Agricultural lands which are unique to Brevard County should be identified and programs for the protection of such lands should be evaluated as part of each Evaluation and Appraisal Report.

Criteria:

- A. Unique agricultural lands would be those lands in Brevard County which possess the physical and chemical conditions for a high level of production with a low level of input. Other factors to be used in defining these lands would include the location, growing season, climate, moisture supply, or technique utilized.
- B. Programs to be considered for protection of these agricultural lands should include, but not be limited to voluntary agricultural districts, time-certain dedications, purchase or transfer of development rights, and voluntary fee simple purchase of agricultural lands.

FUTURE LAND USE ELEMENT

Policy FLU 4.4

Brevard County shall support the Florida Greenbelt Law, Chapter 193 Part II, F.S., in an effort to provide incentives for agricultural property owners to maintain their lands in ~~agriculture~~ bona fide agricultural use.

Policy FLU 4.5

~~Brevard County shall encourage the use of cost-sharing programs and technical assistance offered through agencies such as the Soil & Water Conservation District to assist in the application of technology to conserve water and land resources.~~

Brevard County seeks to promote the application of technology that facilitates the conservation of water and land resources by partnering with state and federal agencies that offer cost-sharing and technical assistance.

Conservation Land Uses

Objective FLU 5

Brevard County shall protect the natural and historic resources in the County from the adverse impacts of development; and coordinate development with appropriate topography and soil conditions.

Conservation Future Land Use Designations

Policy FLU 5.1

The following two (2) conservation land use designations are adopted as part of the Future Land Use Map:

- Public Conservation
- Private Conservation

Public Conservation Lands

Policy FLU 5.2

The Future Land Use Map shall designate lands as Public Conservation to provide for the protection of publicly held environmentally sensitive areas. The Public Conservation future land use designation is intended to accommodate lands and facilities which are managed by federal, state, and local governments within unincorporated Brevard County for conservation or preservation uses. Such uses shall conform to the following minimum criteria:

Criteria:

- A. The Public Conservation land use designation should include lands under the ownership of Brevard County, the St. Johns River Water Management District, or other such agencies, for the purpose of environmental protection, publicly owned lands within the Environmental Area (EA) zoning classification, and publicly owned areas in which it is demonstrated that the preservation of

FUTURE LAND USE ELEMENT

environmentally sensitive resources will provide an overriding public benefit.

- B. Development activities within lands designated as Public Conservation shall be consistent with the specific policies in the Conservation Element related to natural resources; and the intent of this Comprehensive Plan. Specifically, activities that are conducted on Public Conservation lands that enhance, protect, or manage such lands for nature-based recreation, conservation, or preservation purposes for the benefit of the public shall be considered as consistent with this criterion.
- C. Other environmentally sensitive lands (i.e., floodplains, wetlands, or aquifer recharge areas) which are located outside of the Public Conservation land use designation are protected through the policies of the Conservation Element of this Comprehensive Plan.
- D. Privately owned land shall not be designated as Public Conservation. If privately owned lands are acquired by state, regional, or local agencies for conservation or preservation purposes, the participating agencies should provide such information to the County so that the Future Land Use Map may be amended pursuant to ~~Florida Statute section 163.3187, F.S.~~, as may be amended. The County shall annually request such information from the applicable agencies so that any necessary amendments can be made to the Future Land Use Map.

Residential Uses in Public Conservation Areas

Policy FLU 5.3

Residential densities for Public Conservation lands should not exceed one (1) dwelling unit per fifty (50) acres. Dwelling units on publicly held lands, including those zoned EA which are in public ownership, are limited to accommodating park rangers or other authorized personnel as deemed appropriate in order to manage or protect such Public Conservation lands.

Private Conservation Lands

Policy FLU 5.4

This land use designation is related to privately owned lands with significant environmental features. The land use designation applies to privately held lands that were designated Conservation on the Future Land Use Map prior to adoption of the Future Land Use Element on May 16, 2000 regardless of their zoning classification. Any land uses designated Private Conservation after May 16, 2000 are lands which are privately owned and zoned Environmental Area (EA) or so designated by an approved binding development plan and shall be designated as

FUTURE LAND USE ELEMENT

Private Conservation. Such privately owned parcels shall permit a maximum residential density of one (1) unit per ten (10) acres.

Public Facilities Land Uses

Objective FLU 6

Brevard County shall provide for adequate lands to meet the existing and future needs for public facilities and services, consistent with the Capital Improvements Program and the policies and the criteria of this Comprehensive Plan.

Designation of Public Facilities Lands

Policy FLU 6.1

Brevard County shall adopt a Public Facility land use designation as part of the Future Land Use Map.

Locational Criteria for Public Facilities

Policy FLU 6.2

Appropriate locations for public facility land uses should be based upon the following minimum criteria:

Criteria:

- A. Public facilities are those uses which, at a minimum, relate to government-managed transportation, sanitary sewer, potable water, solid waste, drainage, conservation, education, government service systems, and other utilities such as gas, electric, telephone, and cable. An exception should be made for transmission or collection facilities, rights-of-ways, and easements. Public facilities are also those uses classified as scientific research and technology development activities conducted by non-governmental organizations (NGOs) in formal partnership with governmental entities. Such NGOs shall provide economic, environmental, and/or quality of life benefits to Brevard County. Specific land-use activities include either: life science research, ocean, coastal and marine research and technology development, or environmental science research. Public Facilities that are NGOs in formal partnership with governmental entities shall not exceed a FAR of .25
- B. Public facilities land uses may be considered for locations within all land use designations on the Future Land Use Map provided such uses are compatible with adjacent land uses consistent with this Comprehensive Plan.

- C. Following the purchase, lease or dedication of property for public facility purposes, the Comprehensive Plan shall be amended to depict the property as Public Facility on the Future Land Use Map.
- D. Brevard County shall encourage the use of common corridors for utility systems, including sanitary sewer, potable water, re-use, electricity, gas, and other utilities.

Co-location of Public Facilities with Public School Sites

Policy FLU 6.3

In order to maximize the efficiency of public facilities and resources, Brevard County and ~~the Brevard County School Board~~ Brevard Public Schools should strive to coordinate use of existing school facilities for public use. In addition, development of new libraries, parks and recreation facilities, children's services facilities, and other appropriate public uses on properties adjoining school sites should also be coordinated.

Recreation Land Uses

Objective FLU 7

Brevard County ~~shall~~ should acquire or dedicate adequate public lands for parks and recreation to meet the County's existing and future recreational needs consistent with the objectives and policies in the Recreation and Open Space Element of this Comprehensive Plan.

Locational Criteria for Recreation Lands

Policy FLU 7.1

The Recreation land use designation ~~shall~~ may be adopted as part of the Future Land Use Map to identify appropriate locations for public recreation land uses, based upon the following minimum criteria:

Criteria:

- A. Recreation land uses may be considered within all land use designations on the Future Land Use Map, provided such uses are compatible with adjacent land uses. The County shall consider compatibility parameters including, but not limited to, hours of operation, anticipated traffic volumes, and landscaping and buffering.
- B. Following ~~determination by Brevard County to utilize~~ acquisition by Brevard County of the property for public recreational purposes, the Future Land Use Map shall be amended to depict said property as Recreation on the Future Land Use Map.

FUTURE LAND USE ELEMENT

Developments of Regional Impact (DRIs)

Objective FLU 8

Brevard County shall review and regulate ~~Developments of Regional Impact (DRIs)~~ the Viera Development of Regional Impact pursuant to the requirements of Chapter 380, Florida Statutes, ~~Chapters 91-2~~ and Chapter 28-24 Florida Administrative Code and applicable local ordinances.

Designation of Development of Regional Impact on the Future Land Use Map Policy FLU 8.1

Brevard County shall adopt a Development of Regional Impact (DRI) land use designation which depicts approved DRIs on the Future Land Use Map. Each DRI shall adhere to the conditions contained within its adopted Development Order as amended from time to time. The approved development amounts for each land use type are listed below for each DRI and may be exceeded by amending the approved Development Order only if the approved changes do not represent a Substantial Deviation pursuant to the requirements of ~~Subparagraph (b) of Subsection (19);~~ Chapter section 380.06, Florida Statutes.

1. The Viera Development of Regional Impact

The following shall guide land use and development of the Viera New Town:

Viera is planned as a mixed use community that incorporates smart growth principles with the functional integration of uses including residential, retail, office, attraction, theater, hotel, institutional, hospital, light industrial, educational, medical and recreation uses and supporting infrastructure. The residential uses will provide for a full range of housing types including single family ownership and rental units supporting a broad range of family sizes and incomes and will be linked by pedestrian/bicycle friendly pathways to the various non-residential components. The town will also have interconnected systems of open space that provide recreational opportunities and provide for the conservation of natural resources. The overall approximate acreage of the DRI is 20,500 acres.

The Future Land Use Map Designation for Viera is Development of Regional Impact (DRI). The DRI area west of I-95 is a New Town as described in Objective FLU 9. Map ~~7~~ 2 identifies the location of the New Town Land Use Areas/Districts of Viera including: Community; Regional Commerce; Town Center; Village; Interchange; Rural; and Conservation. These “Areas/Districts” (as defined in Policy FLU 9.1) are not separate future land use designations, but are intended to further guide the form and design of the development that is permitted within Viera. Viera is distinct from existing urban areas and surrounding land uses and is generally situated between Wickham Road and Barnes Boulevard on the east side of I-95 and between Post Road and Barnes Boulevard on the west side of I-95.

FUTURE LAND USE ELEMENT

A. Viera DRI: Allowable Uses

The following land uses and substantially similar land uses and corresponding densities and intensities are allowable in the ~~Viera New Town~~ West Viera Area:

Land Use		Maximum Density/Intensity
•	Single Family Residential	7 units per net acre*
•	Multi Family Residential, including Nursing Home, ALF and ILF	20 units per net acre*
•	Rural Residential (within the Rural Development District)	1 unit per 2.5 gross acres*
•	Retail; Office including Medical Office and Clinic; Hotel; Movie Theaters, Attractions in Town Center**	3.0 FAR
•	Retail; Office including Medical Office and Clinic; Hospital Hotel; Movie Theaters, Attractions Outside Town Center	2.0 FAR
•	Institutional/Civic/Education	.5 FAR
•	Light Industrial/Office Warehouse	.5 FAR
•	Educational Campus	2.0 FAR
•	Sports Stadium	9,000 seats
•	Parks and Recreation	Not Applicable
•	Agricultural Use (as defined in Policy <u>FLU</u> 9.1) is permitted within the Rural Area and the Conservation Area prior to the transition of such areas to the Rural District and the Conservation District, respectively, in accordance with an approved staging plan set forth in the DRI Development Order. Upon transitioning to such districts, Agricultural Use is permitted within the Rural District and the Conservation District only in a manner consistent with the Habitat Management Plan and applicable conservation easements and regulatory permits. Agricultural Use is permitted within any district in which development is occurring up to and until approval of a Site Plan or Subdivision Plat applicable to land which is subject to Agricultural Use.	Not Applicable
•	Land excavation for the creation or enhancement of lakes, water bodies, or drainage facilities and removal of materials in association or connection therewith are allowable uses.	Not Applicable

Notes:

FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025

- * Maximum Density/Intensity is based on net developable acreage, which does not include additional acreage needed for storm water management, roads, parks and recreation and conservation areas. Maximum Density/Intensity relates to the overall net density of the entire DRI, except as applied to Rural Residential which relates to the overall gross density of the Rural Development District, and is not intended to apply as a site specific maximum density limitation during sketch plan or site plan review.
- ** The Town Center is generally located in an area north of Wickham Road, west of I-95; east of Stadium Parkway and south of Viera Boulevard. (See Map 7 2). Town Center uses within the Viera Town Center shall include government facilities as well as a full mix of other land uses such as office, retail, civic and residential.
- ***Agricultural Use within the Rural Area includes a limited number of temporary housing units for agricultural workers, not to exceed 50 total units.
- **** Within the Conservation District and the Rural District no residential development will be permitted. Only that non-residential development which is consistent with an approved Habitat Management Plan (as part of the DRI Development Order) shall be permitted in the Conservation and Rural District.

(1) Special Standards for the Rural District

The following land uses and substantially similar land uses and corresponding densities and intensities are allowable in the Rural District:

Land Use	
•	Habitat Protection
•	Agricultural Use
•	Recreation

Notes:

1. These uses are only permitted to the extent that they are consistent with the provisions of the approved Habitat Management Plan.

B. Viera: Mix of Uses

The mix of uses for Viera (gross acreage) is as follows:

Table 8.1: Viera DRI Development Program (2009 2019 Development Order)

*		
	Land Use (See Notes)	Totals
	Residential (units)	29,945 31,619
	Office Development (s.f.)	3,569,702 3,504,467
	- General Office (s.f.)	3,391,702 3,318,327
	- Government Office (s.f.)	178,000 186,140
	Hospital, Health Clinic (beds and s.f.)	
	- VA Clinic (s.f.)	137,500
	- Hospital Beds	322
	- ACLF Nursing Home (beds)	1,060
	Industrial Plants or Parks Distribution, Warehousing or Wholesaling Facilities	302,518 522,500
	- Office/Warehouse (s.f.)	22,500
	- Light Industrial (s.f.)	280,018 500,000
	Retail and Service Development (s.f.)	3,438,127
	Hotel or Motel Development (rooms)	1,000 750
	Attractions and Recreation Facilities	
	- Stadium (seats)	7,500
	- Theaters (screens/seats)	16 Screens/ 3,600 Seats
	-Golf Course	72 Holes

Government Office for Phases 1 and 2A is included in General Office

Notes:

1. Office use includes medical office uses. Medical offices may include physician offices, medical clinics, labs, and diagnostic centers, ambulatory facilities, surgery centers, urgent care centers, rehabilitation centers, medical equipment sales and service, hospice, home health, pharmacies, cancer centers, hospitals or other similar medical office or specialty medical services or uses.
2. Medical uses may include but are not limited to physician offices, medical clinics, labs, diagnostic centers, ambulatory facilities, surgery centers, urgent care centers,

FUTURE LAND USE ELEMENT

rehabilitation centers, medical equipment sales and service, pharmacies, cancer centers, hospitals, health fitness, hospice or home health care or other similar medical or health care uses, so long as they are consistent with the terms of the Viera DRI Development Order.

3. Retail service use includes fitness center/health club uses.
4. Residential use includes independent living uses.
5. Land uses such as elementary and secondary schools (public and private), churches, libraries, post offices, fire or police stations, golf courses and other public/civic uses are allowable in any development district, in addition to other designated uses shown on the DRI Map H.

New Town Overlay West Viera Area

Objective FLU 9

Brevard County shall maintain development standards for ~~large scale mixed use New Town projects~~ the West Viera Area and provide incentives for ~~large-scale~~ environmental design.

Definitions

Policy FLU 9.1

Agricultural Use: Any use of land for bona fide agricultural purposes as described in Section 193.461(3)(b), Florida Statutes, or for activities of a farm operation as described in Section 823.14(3), Florida Statutes, or for Agriculture as defined in Section 570. 02(1), Florida Statutes, including, but not limited to, temporary housing for agricultural workers ~~not to exceed a total of 50 units.~~

Community District: That portion of the ~~New Town Overlay West Viera Area~~ promoting mixed-use development in both infill and redevelopment scenarios. Allowed uses include residential, office, retail, light industrial, and institutional.

Conservation Area: That portion of the ~~New Town Overlay West Viera Area~~ to be dedicated to conservation purposes as mitigation for impacts related to development within subsequent phases of the DRI. Portions of the Conservation Area shall be dedicated to conservation purposes and designated as part of the Conservation District pursuant to an approved staging plan set forth in the DRI Development Order. Prior to designation as part of the Conservation District, Agricultural Use is permitted within the Conservation Area.

Conservation District: That portion of the ~~New Town Overlay West Viera Area~~ dedicated to conservation purposes and providing mitigation for impacts to wetlands and listed species habitat resulting from development within the ~~New Town Overlay West Viera Area~~. Land Uses and Agricultural Use within the Conservation District will be permitted only in a manner consistent with the Habitat Management Plan and applicable conservation easements specifically imposed on lands within the Conservation District.

FUTURE LAND USE ELEMENT

Neighborhood: Neighborhoods are predominantly residential areas, the collection of which constitutes a Village. They are designed around a centrally located park or other public space (a Neighborhood Center) and are characterized by a mix of residential housing and local services that include schools, parks, and churches. ~~(For more specific standards see Policy 9.7.)~~

Habitat Management Plan: Guidelines and practices for maintaining, enhancing, and managing listed species habitat and conducting Agricultural Use within the Rural District and the Conservation District which shall be attached as an exhibit to the DRI Development Order. ~~(For more specific provisions see Policy 9.9.1)~~

Interchange District: That portion of the ~~New Town Overlay~~ West Viera Area dedicated to providing opportunities for development compatible with adjacency to a major I-95 interchange. Potential uses include multi-family residential, office, retail, light industrial, and institutional.

Neighborhood Center: The required public focal point of a Neighborhood. Uses may include parks, open space, or public type facilities such as churches, community centers, or recreational facilities.

Public/Civic: A class of land uses that includes government service centers, public parks and recreational space, educational institutions, libraries, museums, and religious institutions.

Recreational Space: The lands within the Developed area of the ~~New Town~~ West Viera Area that are required to meet the recreational needs of residents; may include both active and passive parks.

Regional Commerce: That portion of the ~~New Town Overlay~~ West Viera Area dedicated to providing employment opportunities. Allowed uses include office, retail, light industrial, and higher density residential.

Rural Area: That portion of the ~~New Town Overlay~~ West Viera Area to be dedicated to listed species habitat enhancement and management as mitigation for impacts to listed species habitat within the ~~New Town Overlay~~ West Viera Area related to subsequent phases of the DRI. Rural Areas shall be dedicated to habitat enhancement and management purposes and designated as part of the Rural District pursuant to an approved phasing plan set forth in the DRI Development Order. Prior to designation as part of the Rural District, Agricultural Use (including temporary housing units for agricultural workers, ~~not to exceed 50 total units~~) is permitted within the Rural Area.

Rural District: That portion of the ~~New Town Overlay~~ West Viera Area dedicated to providing listed species habitat as mitigation for impacts arising from development within the ~~New~~

FUTURE LAND USE ELEMENT

~~Town Overlay West Viera Area~~ and accommodating long-term Agricultural Use in a manner consistent therewith in accordance with the Habitat Management Plan. Listed species habitat will be enhanced and managed, and Land Uses and Agricultural Use are only permitted within the Rural District in a manner consistent with the Habitat Management Plan.

Rural Development District: That portion of the ~~New Town Overlay West Viera Area~~ designated for low-impact rural residential development. Rural residential development occurring within the Rural Development District shall be designed in a context sensitive manner to minimize impacts on the adjoining Rural District and/or Rural Area.

Sketch Plan: An illustration that demonstrates the specific requirements for development areas that further support and implement the baseline standards established as part of the PUD zoning. This is a required component of development approval within the Village District. ~~(For more specific standards, see Policy 9.9.2)~~

Town Center: That portion of the ~~New Town Overlay West Viera Area~~ designated as the central, mixed-use core for an entire ~~New Town West Viera Area~~; emphasizes Traditional Neighborhood Design (TND) or Transit Oriented Design (TOD) development form ~~as specified in Objective 8, Section 3.D. Special Provisions~~. Allowed uses include higher density residential, office, light industrial, retail, and institutional. ~~(For more specific standards see Policy 9.6.)~~

Village: That portion of the ~~New Town Overlay West Viera Area~~ designated to provide a sustainable mixed-use development form. Villages are a collection of Neighborhoods, offering a diverse mix of housing types, of which at least 50 percent are within ½ mile of a Village or Neighborhood Center. Villages shall be supported by centrally located, mixed-use Village Centers (designed specifically to serve the daily needs of Village residents). Residential densities transition from high within and around the Village Center to lower densities on the edges of each village. ~~(For more specific standards see Policy 9.7.)~~

Village Center: A centrally located and required mixed-use component of a Village designed to provide a sufficient mixture of non-residential uses so as to provide for the daily commercial needs of Village residents and residential uses of various densities, intensities, and types. This development form promotes walking between uses and a variety of transportation modes such as bicycles, transit, and automobiles. Allowed uses includes residential, retail, office, and civic uses including a park and/or school. ~~(For more specific development standards see Policy 9.5)~~

New Town West Viera Area: General Principles **Policy FLU 9.2**

~~Brevard County adopts, as part of the Future Land Use Map, a New Town Overlay to include those areas having the characteristics of a new town community. Brevard County may approve Alternative Development Standards to guide development in the West Viera Area.~~

FUTURE LAND USE ELEMENT

Criteria:

- A. ~~A New Town Overlay~~ The West Viera Area shall consist of and be regulated by the following:
1. ~~Size of 1,500 acres at a minimum.~~ The Viera Company shall establish and maintain the Viera Stewardship District to provide the necessary funding for the West Viera Area.
 2. ~~All new town communities~~ The West Viera Area shall provide acceptable funding mechanisms such as Community Development Districts, Special Districts formed pursuant to Florida Law, other private funding and developers' agreements to the County that ensure all services and facilities proposed by the applicant will be funded, operated, and maintained, through the acceptable funding mechanism, for the utilization of the ~~new town's~~ West Viera Area's citizenry.
 3. ~~A full and balanced mix of all major future land use categories set forth in Rule 9J-5, F.A.C. shall be provided, with the possible exception of agriculture, with a goal of planning land uses that will result in a balance of jobs to households.~~ The West Viera Area shall provide a balanced mix of residential and non-residential uses with a goal of planning land uses with a balance of jobs to households.
 4. ~~Initial control by a master developer of the land within the new town area.~~
 5. ~~4.~~ Development based on shall be guided by a master development plan for the new town area detailed in Sketch Plans for each Village, as well as, the Alternate Development Standards adopted through the Planned Unit Development zoning process.
 6. ~~Development that is clearly functionally distinct or geographically separated from existing urban areas and surrounding land uses.~~
 7. ~~5.~~ Central potable water and sewer service and availability of other public facilities and services including roads, storm water management, parks and recreation, police and fire protection, emergency medical services, schools, and solid waste service shall be planned and provided in accordance with applicable policies of the Capital Improvements Element, if not already available.
 8. ~~6.~~ It shall be clearly demonstrated The master development plan shall clearly demonstrate in a conceptual manner how future land uses will function as an interrelated community.
 9. ~~All New Town Overlay areas shall be evaluated as part of the Evaluation and Appraisal Report (EAR) process.~~
- B. Maximum allowable ~~residential~~ densities and non-residential intensities ~~within a New Town Overlay area~~ shall be established as provided by ~~other policies of this element in the Viera DRI Amended and Restated Development Order, the master development plan for the West Viera Area, and other~~

FUTURE LAND USE ELEMENT

policies established in the Comprehensive Plan.

- C. A full range of housing types meeting the Standard Housing Code, including single family ownership and rental units that are considered affordable to all income levels, shall be allowed within ~~a new town~~ the West Viera Area. Provision of this range of housing shall be supported by cooperative developer/government efforts to provide opportunities for affordable single family home ownership. Specifically, opportunity for development of a variety of affordable housing units shall be made available which reflect the incomes of persons employed within the ~~new town area~~ West Viera Area.
- D. ~~A New Town Overlay~~ The West Viera area shall have interconnected systems of open space that provide recreational opportunities and provide for the conservation of natural resources
- ~~E. All New Town Overlay areas should have similar land use designations, directives, policies, and criteria. The new town developer shall assist local governments in developing uniform new town designations, policies, directives, and criteria. Brevard County shall, as part of its Evaluation and Appraisal Report (EAR) process, initiate appropriate amendments to fulfill this requirement.~~
- ~~F. The establishment of a New Town Overlay area on the Future Land Use Map is not intended to imply, nor does it express an intent by the Board of County Commissioners, that development is being directed to a New Town Overlay area, and to guide development away from other areas of Brevard County. Nor does Brevard County plan to reduce development potential in other areas of the County. Brevard County will always support additional development elsewhere in the County wherever appropriate.~~
- ~~G.~~ E. The County recognizes that prevention of urban sprawl and the creation of compact, mixed-use development support an important public purpose. The County also recognizes the value of regional resource protection and accepts that wetland protection and enhancement measures shall be addressed as a part of established mitigation managed pursuant to a Habitat Management Plan.
- ~~H.~~ F. ~~New Towns~~ The West Viera Area shall conserve, appropriately use, and protect native vegetative communities, including forests as appropriate, through the protection of regionally valuable ecological resources adjacent to publicly-owned lands, located wholly within Brevard County, and managed pursuant to an approved Habitat Management Plan.

FUTURE LAND USE ELEMENT

~~I. G.~~ In order to provide community green space and clustering developments, all development shall comply with environmental design criteria in the form of alternative land clearing, tree protection, and landscaping standards included in applicable PUD zoning (approved by the Natural Resources Management Department).

~~J. Landscaping, Land Clearing & Tree Protection~~
~~In order to facilitate development consistent with the objectives, principles and standards of the New Town Overlay, development shall follow alternative standards for landscape, land clearing and tree protection as set forth in applicable PUD zoning.~~

~~K. H.~~ Brevard County shall continue to implement regulations for land excavation operations within a ~~New Town Overlay~~ the West Viera Area. The regulations ~~which~~ shall include the following:

1. Provisions to prevent adverse effects on water quality and quantity.
2. Depiction of stormwater ponds and recreational lakes, including approximate locations and configurations, with details of side slopes, pond depths, normal water levels, and any required planting areas.
3. Material removed from recreational lakes and stormwater ponds, or other excavation areas approved and consistent with the requirements as listed in Policy FLU 9.2 (K)(4), may be utilized for fill material inside and outside of a ~~New Town~~ the West Viera Area.
4. Construction and operation of Stormwater ponds and recreational lakes and associated facilities that are part of a Stormwater Management system approved by the County Engineer and included within an approved subdivision, sketch plan, site plan, or plat shall not be considered a Land Alteration activity and shall not be subject to the regulations titled or pertaining to Land Alteration or Private Lakes.

~~L. I.~~ ~~New Town West Viera Area~~ developments require central water, wastewater, and irrigation services except in the Rural Development District. ~~The New Town West Viera Area~~ development shall identify, through the Zoning Approval Process, the method for the provision of infrastructure for the water, wastewater, and irrigation systems for the development.

~~M. J.~~ All subsequent development submittals within a ~~New Town~~ the West Viera Area shall demonstrate that the integrity of the mixed-use district is not compromised by allowing extensive single-uses. The land use mix shall be phased to provide an adequate mix of non-residential uses to serve residential development within each development phase.

FUTURE LAND USE ELEMENT

**New Town West Viera Area: Commercial and Industrial Location Standards in
Community District
Policy FLU 9.3**

If consistent with other criteria in this policy and the master development plan, uses within the ~~New Town Overlay~~ West Viera Area Community District ~~area~~ need not be consistent in all cases with commercial and industrial locational criteria, due to the integrated nature and large scale of ~~New Town~~ development, if they comply with the following:

Criteria:

A. Commercial Land Uses

Regional commercial uses shall be located in proximity to Interstate highways or other existing or planned arterial roadways. Sites for regional commercial centers shall be a minimum of 50 acres in size and should consist of 500,000 square feet of gross leasable area. A major component of the regional center may be a mall with at least two anchor stores. The site plan for the center shall ~~ensure for~~ include a pedestrian circulation system that is integrated with the ~~new town's~~ West Viera Area's overall pedestrian system. ~~The site plan~~ Site plans for all regional commercial development in close proximity to the center shall ~~ensure that a pedestrian circulation system is provided that is provide~~ pedestrian facilities that are integrated into the Town Center's center's overall pedestrian system, ~~where such regional commercial development is in close proximity to the Town Center.~~ The regional commercial center shall be compatible with adjacent uses, provided however such use shall be deemed compatible where it is consistent with an applicable Preliminary Development Plan.

1. Tourist commercial uses shall be located in proximity to other tourist uses such as sports facilities, entertainment facilities, and other tourist-related uses. These uses shall be accessed from an existing or planned arterial street. Tourist commercial uses shall be compatible with adjacent uses, provided however such use shall be deemed compatible where it is consistent with an applicable Preliminary Development Plan.
2. Local commercial centers shall be integrated with residential uses and shall be accessible from the ~~New Town's~~ West Viera Area's pedestrian/bicycle pathway system and an additional transit corridor. The minimum acreage of a local commercial center is 10 acres with a gross leasable area to 125,000 square feet or less. Local centers may be spaced from 1 to 1.5 miles apart within the community. The centers are intended to serve the shopping needs of the residents living within the community and the immediate surrounding neighborhood. Sub-regional uses shall be permitted within local commercial centers, they shall have a minimum acreage of 20 acres and may have a gross leasable area of 500,000 square feet or less. Sub-regional uses shall be located adjacent to existing or planned arterial roadways. Local

FUTURE LAND USE ELEMENT

commercial centers shall be compatible with adjacent uses, provided however such use shall be deemed compatible where it is consistent with an applicable Preliminary Development Plan.

3. Convenience commercial shall consist of a minimum of 1 to 5 acres in size, and shall provide access to residential neighborhoods via the ~~New Town's~~ West Viera Area's pedestrian/bicycle pathway system. The gross leasable area shall be up to 50,000 square feet. The convenience commercial center shall be compatible with adjacent uses, provided however such use shall be deemed compatible where it is consistent with an applicable Preliminary Development Plan.

B. Office Uses

Office uses may be located in regional commercial centers, local commercial centers, convenience commercial centers, or serve as a transitional use between residential uses and more intense non-residential uses and between residential uses and transportation facilities. Office uses shall be compatible with adjacent uses, provided however such use shall be deemed compatible where it is consistent with an applicable Preliminary Development Plan.

C. Industrial Uses

The negative impacts of industrial land uses on the functions of the natural systems shall be minimized. Sites for industrial development shall be accessible to essential public and private facilities and services including transportation, potable water, an appropriate sewage treatment facility, solid waste, and drainage. Sites for industrial development shall be located with access from existing planned arterial streets or highways. Industrial use shall be compatible with adjacent uses, provided however such use shall be deemed compatible where it is consistent with an applicable Preliminary Development Plan.

New Town West Viera Area: Regional Commerce District Standards

Policy FLU 9.4

For those areas within a ~~New Town~~ the West Viera Area that are designated as "Regional Commerce District", the following standards shall apply:

Criteria:

- A. Regional Commerce Districts should be developed with the goal of increasing full-time employment opportunities through office uses. Retail, light industrial, and high density residential uses are also allowed.
- B. Regional Commerce Districts shall include a mixture of uses wherein the residential uses are integrated with the non-residential uses through an interconnected network of streets. This street network shall also be interconnected and accessible from the ~~New Town's~~ West Viera Area's pedestrian/bicycle pathway system and a transit corridor. Site plans for

FUTURE LAND USE ELEMENT

development shall ensure that the pedestrian circulation system for the Regional Commerce development is integrated with the ~~New Town's~~ West Viera Area's overall pedestrian system.

New Town West Viera Area: Urban Design Principles

Policy FLU 9.5

Districts within a ~~New Town~~ the West Viera Area that are designated as either “Town Center”; or “Village” shall ~~exhibit elements of the following Traditional Neighborhood Design principles:~~ adhere to the Alternative Development Standards that have been approved through the Planned Unit Development zoning process.

Criteria:

- A. Village or Town Centers with Mixed Uses. Village Center and Town Centers shall be designed to insure a mixture of non-residential and residential uses of various densities, intensities, and types designed to promote walking between uses and a variety of transportation modes such as bicycles, transit, and automobiles.
- B. Pedestrian Scale Commercial Development. Commercial areas shall be designed to a pedestrian scale and orientation served by an urban street network with a block structure and urban building frontages along street faces.
- C. Functional Neighborhoods. Residential areas shall be located and designed as neighborhoods, which embrace a full range of urban facilities including neighborhood retail centers, a variety of housing types, public/civic space and a variety of open space amenities, schools, central water and sewer, and fire/safety accessibility.
- D. Walkable Streets. Neighborhoods shall be designed to reinforce reasonable walking distances from Village or Neighborhood Centers and the location of parking, and the design of streetlights, signs, and sidewalks shall respect the pedestrian orientation of the development.
- E. Interconnected Circulation Network. The Villages and Town Center shall be designed along an interconnected street system that accommodates pedestrians and bicycle features and links neighborhoods to shopping areas, civic uses, and parks and other recreational features.

New Town West Viera Area: Town Center Standards

Policy FLU 9.6

For those Districts within a ~~New Town~~ the West Viera Area that are designated as a Town Center, the additional following standards shall apply:

Criteria:

FUTURE LAND USE ELEMENT

- A. The Town Center is a strong core of higher density residential, employment, and commercial uses, which shall be interconnected and accessible by pedestrians to surrounding areas and shall be designed to encourage and accommodate regional transit.
- B. The quantity of non-residential development permitted in the Town Center will be related to the demand for community commercial, office, civic, and government use development within the ~~New Town~~ West Viera Area.

~~New Town~~ West Viera Area: Village Standards

Policy ~~FLU~~ 9.7

For those Districts within a ~~New Town~~ the West Viera Area that are designated as a Village, the additional following standards shall apply:

Criteria:

- A. The planning principles that shall guide the development of all Villages shall include the following:
- B. The development pattern of all Villages shall respect the environment by reinforcing the consolidated, connected open space systems of the ~~New Town~~ West Viera Area which ~~enhances~~ enhance regional environmental systems ~~where appropriate~~ whenever possible and mitigated according to the terms of the Viera DRI Amended and Restated Development Order when adverse impacts to environmental systems occur;
- C. The development shall create self-sufficient communities that provide a fully connected system of streets and roads that encourage alternative means of transportation such as pedestrians, bicycle, and transit; and
- D. The development shall be formed around the Village Center and Neighborhoods which, collectively, shall include a diversity of housing types.
- E. Villages shall be a minimum of 1000 acres and shall be designed as a collection of Neighborhoods where a majority of the housing units are within a half mile walking distance of a Village or Neighborhood Center with higher densities closer to the Village Center. Villages shall be supported by internally designed, mixed-use Village Centers (designed specifically to serve the daily needs of Village residents).
- F. Villages shall include a mix of uses, including residential, commercial, office, Public/Civic, schools, and Recreational Space, that serve the daily needs of residents;

- G. Villages shall include a Village Center with sufficient non-residential uses to provide for the daily needs of Village residents, by phase of development, in a form that can be conveniently served by regional bus service;
- H. Villages shall include a range of housing types that supports a broad range of family sizes and incomes.
- I. Villages shall include compact design that includes a system of land subdivision and development which links one Neighborhood to another;
- J. Villages shall include interconnected streets that are designed to balance the needs of all users, including pedestrians, bicyclists, and motor vehicles, and which are built with design speeds that are appropriate. Villages shall include alternatives for pedestrians and bicyclists through the provision of sidewalks, street trees, and on-street parking which provide distinct separation between pedestrians and traffic; and provide adequate lighting that is designed for safe walking and signage which has a pedestrian orientation. Within Village Centers, ~~spatially define~~ primary streets and sidewalks should be spatially defined by arranging commercial and multi-family buildings in a regular pattern ~~that are~~ unbroken by parking lots;
- K. Villages shall provide Recreational Spaces that meet the recreational needs of the community, reinforce the design of the development by providing a variety of Recreational Space amenities that serve a range of interests, and distribute Recreational Space amenities throughout the development.
- L. Villages shall have a system of connected open space which includes elements of public edge throughout the neighborhoods that connect each village.

New Town West Viera Area: Rural Development Standards

Policy FLU 9.8

~~For those Districts within a New Town that are designated as Rural Development, the additional following standards shall apply:~~ Within the West Viera Area, the following additional standards shall apply within the Rural Development District:

Criteria:

- A. Residential development within the Rural Development District shall be limited to ~~a specified acreage~~ an overall density of 1 unit per 2.5 acres.
- B. The development design shall be context-sensitive in order to minimize adverse impacts to adjacent lands.
- C. Residential development should promote rural character when viewed from public roads and from abutting properties.

FUTURE LAND USE ELEMENT

- D. Low-density residential development and rural residential clusters shall both be considered compatible forms of development.
- E. At the request of an applicant, the boundary of the Rural Development District (as shown on ~~an overlay~~ the West Viera Area map) may be changed administratively by Brevard County provided that the change does not create a development enclave, does not exceed the overall approved acreage of the Rural Development District, or reduce the existing overall acreage of the Rural District.

New Town West Viera Area: Standards for Rural and Conservation Districts
Policy FLU 9.9

The Rural District and the Conservation District shall accommodate and provide mitigation for impacts to wetlands and/or listed species habitat resulting from development within the ~~New Town Overlay~~ West Viera Area. The transition of land into either the Rural District or the Conservation District shall occur in accordance with a phasing plan set forth in the DRI Development Order. Such transition shall be implemented by the conveyance of either (1) fee simple title to such lands or (2) a conservation easement over such lands, to an independent special district formed under Chapter 189 or Chapter 190 of the Florida Statutes or other governmental entity, which may include, but not be limited to, the Viera Stewardship District, Brevard County, the St. Johns River Water Management District, the Florida Fish and Wildlife Conservation Commission, or the U.S. Fish and Wildlife Service. The following criteria apply to the Rural District and the Conservation District within the ~~New Town Overlay~~ West Viera Area:

Criteria:

- A. Agricultural Use is only permitted within the Rural District and the Conservation District in a manner consistent with the Habitat Management Plan and applicable conservation easements and regulatory permits.
- B. Passive recreational uses are allowed within the Rural District and the Conservation District in a manner consistent with the Habitat Management Plan and applicable conservation easements and regulatory permits.
- C. The Rural District and the Conservation District shall be administered by an independent special district formed under Chapter 189 or Chapter 190 of the Florida Statutes or other governmental entity satisfactory to Brevard County, ~~which the administrator of which~~ shall provide for the long term management of such districts and the implementation of all management, enhancement and preservation activities required in accordance with the Habitat Management Plan and applicable conservation easements and regulatory permits.

Habitat Management Plan

Policy FLU 9.10

A Habitat Management Plan shall be submitted to and approved by Brevard County Natural Resources Management Department, as a part of the DRI approval process and compliance with said plan shall become a condition of the development approval. The specific requirements listed below shall be defined through the subsequent permitting process and incorporated into the Habitat Management Plan in accordance with the DRI Development Order.

Criteria:

- A. Resource protection and conservation will occur through the legal protection of Conservation and Rural Districts;
- B. Specific responsibilities for the regular and periodic operation and maintenance of the area including the identification of on-going management strategies for conservation and/or restoration of native habitats to meet mitigation requirements;
- C. Standards and timelines for monitoring that will evaluate listed species behavior and productivity, enhancement activities, and ongoing land management;
- D. Operational standards, including the standards for regular maintenance of infrastructure, and providing wildlife management, to ensure the long-term success of natural resource management in a mitigation area.
- E. Operational standards to ensure the continuation of Agricultural Use in a manner compatible with long-term natural resource management goals.

Review and Approval Process

Policy FLU 9.11

Criteria:

- A. Standards for Review
Development within the ~~New Town Overlay~~ West Viera Area Village, Town Center, Regional Commerce, and Interchange Districts must demonstrate the following:
 - 1. That the development complies with all applicable County environmental preservation regulations provided, however, that the development shall also separately comply with applicable federal and state environmental preservation regulations.
 - 2. That the location of the developed areas on the site respects existing adjacent development patterns;
 - 3. Permits the most density and intensity in areas that are most proximate to Town Centers and Village Centers;

FUTURE LAND USE ELEMENT

4. That, where applicable, the integrity of the mixed-use district is not compromised by allowing extensive single-uses. The land use mix shall be phased to provide an adequate mix of non-residential uses to serve residential development within each development phase.
-
- B. **Approval Process**
Development within the ~~New Town Overlay~~ West Viera Area includes the approval of a Planned Unit Development Zoning District rezoning and a more specific Sketch Plan approval process for each Village within the Village District. As part of the Planned Unit Development Zoning, each Village must be master planned as shown on a Preliminary Development Plan before an individual neighborhood can proceed through the Sketch Plan Process. The applicant may submit more than one Village Sketch Plan at a time for review and approval.
 - C. **Approval Process: Zoning Standards**
The Planned Unit Development Zoning District rezoning shall establish the general baseline regulation for the development including standards for physical design, development approval processing, proposed phasing, and the identification and definition of the types of major modifications to the Zoning District approval that shall require the review and approval of the County Commission and minor modifications that shall require only the review and approval of county staff. The Planned Unit Development Zoning shall include a Preliminary Development Plan as required by Brevard County Land Development Code Section 62 Subdivision V.
 - D. **Approval Process: Sketch Plan Standards**
The Sketch Plan review and approval process shall establish the specific requirements for Village development that further support and implement the baseline standards established as a part of the Planned Unit Development Zoning and shall include the following information:
 - Location of each Neighborhood, Neighborhood Center, Village, and a block layout of a Village Center or Town Center where applicable
 - Recreational Space
 - Land Use Mix
 - Density and intensity of land uses proposed
 - Circulation routes for auto, transit (where applicable), pedestrian, and bicycles modes
 - Design Criteria for landscaping and signage
 - Transportation Network Connections

FUTURE LAND USE ELEMENT

- Preserved wetland areas, associated upland buffers, impacted wetland areas, and a quantification of wetland impacts within the Sketch Plan area.

A Sketch Plan shall be considered an integrated site plan or commercial subdivision ~~as referenced in Chapter 1 Policy 5.2 (5) (a) (iii).~~ The approval of a Sketch Plan and modifications thereto shall only require the review and approval of county staff.

- E. Approval Process: Site Plan or Subdivision Plan
Site Plan or Subdivision Plan review for individual sites within an approved Sketch Plan shall follow the procedures outlined in Articles VII and VIII of the Brevard County Land Development Regulations, provided that Site Plans and Subdivision Plans for individual sites within any Sketch Plan area shall be consistent with such Sketch Plan.
- F. Appeals related to any administrative decision or determination concerning implementation or application of Policy FLU 9.9 provisions shall follow the established appeal procedures as included in the Brevard County Code of Ordinances (Sec. 62-506. Appeals generally.)

Transfer of Development Rights (TDRs)

Objective FLU 10

Brevard County shall encourage preservation of unique aspects of the natural environment by recognizing Transfer of Development Rights (TDRs) which permit more intense activity in areas deemed suitable for development.

Criteria for Transfer of Development Rights

Policy FLU 10.1

Transfer of development rights (TDRs) may be obtained through the ~~Conditional Use Permit or DRI~~ Planned Unit Development (PUD) or Open Space Subdivision process to direct residential development to areas which are deemed suitable for growth with the intent of furthering County goals related to preservation of the physical (including historic) and/or natural environment. TDRs may be transferred: (1) to an approved offsite location which is designated a receiving district; or (2) internally within a project from an approved sending district. In either circumstance, the utilization of TDRs must adhere to the following minimum criteria:

Criteria:

- A. TDRs may be utilized in a project via Planned Unit Development (PUD), ~~DRI~~ Open Space Subdivision process, or ~~binding development agreements~~ Binding Development Plans with binding development restrictions.

FUTURE LAND USE ELEMENT

- B. The density of a project receiving TDRs shall not exceed 150% of the density permitted in the designated land use category. The maximum allowable density of a development shall take into consideration all other requirements of the Comprehensive Plan.
- C. The density assigned to a wetland area on the Future Land Use Map series may be transferred to an upland area within the same project. The transfer shall be subject to the provisions contained in Criterion B above.
- D. Compatibility with surrounding development patterns within receiving areas shall be ensured.
- E. TDRs may be considered due to environmental considerations; for the protection of historic resources; to encourage the preservation of Agricultural lands, to encourage urban infill development; to provide additional open space; and to encourage development within specified area(s).
- F. Applications for projects proposing to utilize TDRs shall include an analysis of the impacts that the increased density will have on public facilities and infrastructure as well as the school system.
- G. The CHHA is considered a sending district for TDRs, but cannot be a receiving district, except for intra-area transfers.
- H. To promote the protection of Agricultural lands, the transfer of development rights from Agricultural land will receive a 25% density bonus. Example: A TDR of 4 dwelling units from an Agricultural sending district will be 5 dwelling units to the non-Agricultural receiving district.

Receiving Districts for Transfer of Development Rights
Policy FLU 10.2

The following land use designations may be considered receiving districts for Transfer of Development Rights:

- Residential 30 Directive
- Residential 15
- Residential 10
- Residential 6
- Residential 4
- ~~Neighborhood Commercial~~
- ~~Community Commercial~~

Sending Districts for Transfer of Development Rights

Policy FLU 10.3

The following land use designations may be considered as sending districts for Transfer of Development Rights:

- Agricultural (25% bonus applicable)
- Conservation
- Coastal High Hazard Areas

Redevelopment & Regentrification

Objective FLU 11

Brevard County ~~shall~~ should alleviate the impacts of inadequate public facilities and services; and substandard structures and lot configurations in blighted or other affected areas in the County through redevelopment initiatives.

Criteria for Redevelopment Plans

Policy FLU 11.1

Brevard County ~~shall~~ should continue to identify areas that are candidates for redevelopment, such as those addressed in the Merritt Island Redevelopment Plan, and adopt redevelopment plans in order to improve traffic circulation and parking; and to provide for aesthetically pleasing and environmentally sound commercial, office, and residential opportunities, consistent with this Comprehensive Plan. At a minimum, the following criteria ~~shall~~ should apply:

Criteria:

- A. Redevelopment plans shall be coordinated with the availability of the following public facilities and services at levels of service adopted in this Comprehensive Plan: roadways, potable water, sanitary sewer, drainage, solid waste, public schools, fire protection, and emergency medical services.
- B. Redevelopment plans shall be coordinated with transportation improvements including marginal access, existing roadway networks in the study area, limitation of access points, parking, pedestrian and bicycle facilities, and mass transit.
- C. Redevelopment plans shall address the impacts of redevelopment activities on the natural systems. Redevelopment activities shall be conducted consistent with the Conservation, Coastal Management, and Surface Water Management elements of this Comprehensive Plan.
- D. Redevelopment plans shall address appropriate development patterns in the study area. Primary emphasis shall be given to compatible retail commercial, high density residential, professional office, and mixed-use projects.

FUTURE LAND USE ELEMENT

Clustered development patterns shall be preferred over strip development patterns.

- E. Redevelopment plans shall provide for the visual continuity of the study area through landscaping, signage, and architectural and design requirements.
- F. Redevelopment plans shall address economic development strategies such as business recruitment, commercial revitalization, and marketing campaigns.
- G. Redevelopment plans shall identify structures which are substandard and shall address measures for rehabilitation or replacement.
- H. Redevelopment plans shall include relocation strategies for residents and businesses displaced by implementation of said Plan. These strategies shall ensure that those displaced are provided adequate notice, equitable compensation, and assistance in locating comparable relocation accommodations.

Policy FLU 11.2

Redevelopment Districts may be established consistent with criteria set forth in Chapter 163, Part III, F.S. Such districts may receive special attention and flexibility, in accordance with current or new land development regulation which may be adopted by the Board of County Commissioners in accordance with Criterion C, in order to assure the elimination of factors contributing to economic debilitation. To that end, Redevelopment Districts shall be developed according to the following minimum criteria:

Criteria:

- A. A Redevelopment District shall be developed in accordance with its adopted Redevelopment Plan.
- B. Redevelopment Districts shall be permitted in any land use designation.
- C. Redevelopment agencies shall promulgate land development regulations, design standards, rehabilitation and maintenance standards, and other regulatory or planning programs to establish performance standards, guide growth, or implement the adopted Redevelopment Plan, as may be amended and adopted by the Brevard County Board of County Commissioners.
- D. Allowable non-residential development activities shall reflect the character and nature of the District. If a Redevelopment District has the potential to become an urban central business district, then adequate opportunities should be provided for pedestrian movement, activity centers, urban spaces, and other characteristics of urban core areas.

- E. Residential development activities shall be encouraged to complement the types, styles, and ranges of residential development standards assigned through the respective Redevelopment Agency's Land Development Regulations.
- F. A density bonus program that provides developer incentives for the rehabilitation and reconstruction of housing should be implemented in appropriate Redevelopment Districts, as follows:

Land Use Designation	Maximum Number of Units Permitted
Residential 30 Directive	37.5 du/ac.
Residential 15	18.75 du/ac.
Residential 10	12.5 du/ac.
Residential 6	7.5 du/ac.
Residential 4	5 du/ac.
Residential 2	2.5 du/ac.
Residential 1	1.25 du/ac.

Density bonuses in the CHHA shall be approved by the Board of County Commissioners and shall be subject to environmental constraints, availability of public facilities, land use compatibility, and level of service requirements set forth in this Plan. Residential densities, of up to 37.5 dwelling units per acre, may be considered in the Merritt Island Redevelopment Area and shall be incorporated if approved by the Board of County Commissioners as part of a redevelopment plan.

- G. Appropriate areas shall be set aside within each Redevelopment District for conservation, open space, recreation, or public facility usage.

Platted Lands with Development Limitations

Policy ~~FLU 11.3~~

Brevard County ~~shall continue to~~ may support State and local initiatives that seek to address those lands which are platted but possess limitations to development based upon inadequate public facilities and services, substandard lot configurations, or environmental constraints.

Property Rights

Policy ~~FLU 11.4~~

Brevard County shall address all constitutional and statutory property rights considerations in the evaluation of applications for development orders and permits, in coordination with the Property Rights Element, and shall maintain a process for appeals.

~~Policy 11.5~~

~~Brevard County shall encourage private redevelopment projects which are not regulated under Chapter 163, Part III, F.S. through the establishment of the Planned~~

FUTURE LAND USE ELEMENT

Redevelopment District Future Land Use designation. This land use designation is intended to enable the County to consider preliminary redevelopment proposals in which only maximum thresholds for buildout and other general development information are provided. Under this approach, the identification of specific land use tracts may be reserved until rezoning (if required) or the site plan approval process. The following minimum criteria must be met in order to request the Planned Redevelopment District land use designation:

Criteria:

- A. — Parcels seeking this designation must currently be substantially improved and proposed for redevelopment ; and
- B. — The minimum land assemblage requirement for this future land use designation is twenty-five (25) acres, all of which is held under one ownership, consolidated under a Unity of Title or similarly bound by other legal instrument, to ensure that the site remains undivided and that the project is built out and maintained in a manner contemplated at the time of the FLUM amendment approval; and
- C. — A property utilizing this future land use designation must abut one or more improved arterial roadways at the time of the FLUM amendment request.

Policy 11.6

Since the Planned Redevelopment District land use designation is based upon broad conceptual information rather than specific details relating to the proposed layout/arrangement of use(s) on site, such amendment requests shall, at a minimum, be accompanied by the following information:

Criteria:

- A. — Project description explaining the intent/scope of the project; and
- B. — Listing of the types of general land uses proposed (i.e., residential, commercial, industrial, etc.) and potential zoning classifications in the project; and
- C. — Details of each residential component, if proposed, including acreage breakdown(s), maximum number of dwelling units, density caps, and types of housing styles for each residential component of the project; and
- D. — Details of each non-residential component, if proposed, including acreage breakdown(s) and type(s) of non-residential uses; and

- E. ~~Description of special amenities proposed for the project to promote a cohesive character and encourage alternative transportation modes. Such amenities may include, but are not limited to the following:~~
 - 1. ~~Greenbelts;~~
 - 2. ~~Sidewalks;~~
 - 3. ~~Bikepaths;~~
 - 4. ~~Features to accommodate mass transit services.~~
- F. ~~Analysis of the compatibility of the proposed project with surrounding land uses and the Future Land Use designations in the area; and~~
- G. ~~Anticipated time limit for build out of the project (time extensions may be considered by the Board and shall require amendment to the Comprehensive Plan); and~~
- H. ~~Relocation plan for displaced residents/business, if applicable; and~~
- I. ~~At the time of adoption for a particular parcel, the developer must proffer a fully executed development agreement which specifies the nature of the approved development, as outlined by the above criteria.~~

Policy 11.7

~~When reviewing a request for Planned Redevelopment District, the County shall consider the following factors:~~

Criteria:

- A. ~~Future land use designations and residential density guideline allowance for the subject parcel and surrounding area;~~
- B. ~~Development trends in the area;~~
- C. ~~Compatibility and interconnectivity with adjacent adopted future land use designations and existing land uses;~~
- D. ~~Accessibility of the site;~~
- E. ~~Availability of required infrastructure at or above adopted level of service standards;~~
- F. ~~Adherence to the objectives/policies of the Conservation Element and minimization of impacts upon natural resources and systems;~~
- G. ~~Integration of open space and interconnectivity within the proposed project area; and~~

FUTURE LAND USE ELEMENT

- H. ~~Promotion of alternative transportation modes, including pedestrian movement, bicycles and mass transit within the project.~~

Policy 11.8

During the zoning process for projects designated Planned Redevelopment District, the County shall consider the following factors:

Criteria:

- A. ~~Types of permitted/prohibited uses associated with the requested zoning;~~
- B. ~~Impact of anticipated land use mix in maximizing trip capture within the project;~~
- C. ~~Existing zoning trends in the area;~~
- D. ~~Compatibility of requested zoning with the area;~~
- E. ~~Impact upon Level of Service (LOS) standards for roads, potable water service, sanitary sewer service and solid waste disposal;~~
- F. ~~Impact upon natural resources, including wetlands, floodplains and endangered species; and~~
- G. ~~Other issues which may emerge specific to a particular property which may be addressed through performance based zoning criteria.~~

Policy 11.9

Development within the Planned Redevelopment District land use designation shall be designed to encourage a cohesive arrangement of interdependent land uses which promote internal interconnectivity and support the use of alternative circulation modes within the project boundaries. At the time of site plan review, the County shall consider the following, at a minimum:

Criteria:

- A. ~~Buffering from adjacent existing/potential uses;~~
- B. ~~Arrangement of land uses in terms of maximizing trip capture within the development;~~
- C. ~~Provision of open space, as defined by Section 62-1102 of the Zoning Code, as set forth in applicable zoning districts and in this Comprehensive Plan;~~
- D. ~~Adequacy of pervious areas in terms of drainage requirements;~~
- E. ~~Unique features and resources which may constrain site development, such as soils, existing vegetation, and historic significance;~~

FUTURE LAND USE ELEMENT

- ~~F. — Safety of on-site circulation patterns and interconnectivity within the project area to encourage alternative transportation modes, such as pedestrian movement, bicycling, and mass transit options;~~
- ~~G. — Landscaping, as it relates to applicable land development regulations and the Comprehensive Plan;~~
- ~~H. — Performance based zoning requirements which may serve as a substitute for or accompany land development regulations in attaining acceptable site design.~~

Policy 11.10

~~Once a Planned Redevelopment District future land use designation is adopted for a parcel, the specific development criteria approved by the County shall be incorporated into the Future Land Use Element. Modifications to approved development criteria shall require amendment to the Comprehensive Plan.~~

Service Delivery, Concurrency, and Growth

Objective FLU 12

Through concurrency management, Brevard County shall oversee development activities in order to assure that existing and future needs for public facilities and services are available consistent with the ~~Capital Improvements Program~~ Capital Improvements Element Schedule of Improvements and the policies of this Comprehensive Plan. Brevard County shall utilize a 5 year short range, ~~and 10 year mid range, and 20 year long range planning periods.~~

Public Facilities Siting and Capacity Needs

Policy FLU 12.1

Public facilities and services ~~shall~~ should be designed with capacities sufficient to support the needs of the projected population and the intensity of future development.

Policy FLU 12.2

Planning for public facility and service expansions should consider the area's suitability for urbanization based upon environmental constraints, existing and future land uses, the availability of potable water, and the availability of other facilities and services. The provision of public facilities and services shall be encouraged within existing or future service areas as designated in this Comprehensive Plan, unless an overriding public benefit can be demonstrated, in an effort to limit urban sprawl. Plans for the expansion of existing facilities, services, and corridors or the construction of new facilities, services, and corridors should include measures to mitigate negative impacts upon the surrounding area during construction.

FUTURE LAND USE ELEMENT

Policy FLU 12.3

Future public facility sites and corridors should be identified in currently undeveloped areas to anticipate and plan for the needs of future development.

Rights of Way Needs**Policy FLU 12.4**

Brevard County should coordinate with appropriate authorities including, but not limited to, the Florida Department of Transportation, the Space Coast TPO, and affected municipalities in defining right-of-way needs for proposed roadway improvements, extensions, or new corridors and establishing mechanisms for right-of-way acquisition and protection, as identified in the Transportation Element of this Comprehensive Plan.

Public Drainage Facilities Needs**Policy FLU 12.5**

The provision of public drainage facilities should be contingent upon the ~~Master Stormwater Management Plan~~, stormwater area studies recommended in the Surface Water Management Element of this Comprehensive Plan, which will identify deficiencies and establish priorities for facility improvements.

Community Facilities Needs (Fire and Police Stations, Libraries, Schools, Water Facilities, and Prisons)**Policy FLU 12.6**

Brevard County ~~shall~~ should designate, acquire, or dedicate adequate and appropriate lands for community facilities, such as ~~public schools~~, water system facilities, fire protection and emergency medical services, police protection, and libraries as established in the Capital Improvements Element of this Comprehensive Plan based upon the following minimum criteria:

Criteria:

- A. Fire and emergency medical service stations should be ~~located so as to~~ sited at locations that provide a level of service consistent with the response time goals adopted by the Emergency Medical Services Advisory Council. Access should be available to roadways of sufficient capacity to allow for emergency vehicle accessibility.
- B. Sheriff offices should be ~~located so as to~~ sited at locations that minimize the response time within the districts to be served. Districts should be comprised of a homogeneous area, not limited by natural or physical barriers such as water bodies, major transportation corridors, or railroads. Stations should be located near concentrations of commercial or industrial uses and the areas with the highest crime rates. Access should be available to roadways of sufficient capacity to allow for vehicle accessibility.
- C. New public library sites should be located at least five miles from existing public libraries.

FUTURE LAND USE ELEMENT

- D. Sites for correctional facilities should be of sufficient size, ~~no less than 50 acres,~~ to allow for a secure compound and to limit the impacts upon the surrounding community. The site should be located within 15 miles of the communities which provide staff or other support and at least 1/2 mile from the nearest residential area. The population within a two-mile radius of the site should not exceed 1,000.
- E. To the extent allowed by law, the construction of a new Community Water System (per ~~62-550.200(12)~~ 62-550.200, F.A.C.) located within the unincorporated area of Brevard County which is designed to serve at least 15 service connections used by year-round residents or regularly serves at least 25 year-round residents, shall be reviewed and approved by Brevard County. This review shall be limited to those construction activities which increase existing or create new supply, treatment, or storage facilities. Brevard County review shall be consistent with the provisions of Brevard County Ordinance No. 2003-32 and the consents recited therein.

Public School Needs

Policy FLU 12.7

Brevard County should encourage ~~the School Board~~ Brevard Public Schools to locate public schools in accordance with the following criteria:

Criteria:

- A. School facilities should be centrally located within the residential areas to be served and should be of sufficient size to accommodate the projected enrollment.
- B. Convenient pedestrian access to school sites is desirable.
- C. Locations on major roadways, in commercial or industrial areas should be avoided to limit the hazards of vehicular traffic, and to minimize disturbances from noise, odors, or fumes.
- D. Joint locations with recreational facilities should be encouraged.
- E. The general location of school facilities should be consistent with the comprehensive plan of the appropriate local governing body developed pursuant to provisions of Chapter 163, F.S.

Concurrency Evaluation Practices

Policy FLU 12.8

Brevard County shall periodically update its Land Development Regulations regarding concurrency and proportionate share contributions to maintain consistency with Florida Statutes and continue to utilize a concurrency evaluation system to review the impacts of all development proposals on existing public facilities to ensure that service levels are not

FUTURE LAND USE ELEMENT

degraded below acceptable level of service standards as adopted in this Comprehensive Plan.

Policy FLU 12.9

Brevard County shall continue to implement a concurrency evaluation system using ~~Best Evaluation Practices~~ professionally accepted methods for evaluating impacts to the adopted levels of service, and ~~shall~~ should conduct and apply the system, and any subsequent system, in accordance with the following criteria:

Criteria:

- A. The concurrency evaluation system shall measure the potential impact of any development order or permit proposal upon the established minimum acceptable level of service for a roadway, solid waste, potable water, drainage, sanitary sewer, or ~~park~~ public school facility or service.
- B. The most current available information and data regarding the above public facilities or services operating levels of service ~~shall~~ should be utilized for concurrency evaluations.
- C. If the result of the concurrency evaluation ~~test~~ finds that any development order proposal will cause a deficiency on any public facility or service serving the proposed development site for which a minimum acceptable level of service has been established, Brevard County reserves the authority to deny or defer the development proposal, to cause the development order proposal to be modified to achieve consistency with the minimum acceptable levels of service, or to process it as a conditional development order proposal pursuant to Policy FLU 12.10.
- D. A non-deficiency finding for a development order proposal by a concurrency evaluation ~~test~~ shall remain valid for the following prescribed time-frames, provided the permit application is submitted within 180 days after the date of the test results:
 - 1. For a site development plan approval, the finding shall remain valid for a period not to exceed 18 months, except where the intensiveness of the approved use is exceeded. In the latter instances, another concurrency evaluation test shall be required.
 - 2. For a residential subdivision, or phase or unit thereof, including residential subdivision phases of planned unit developments, the finding shall remain valid for a period not to exceed 36 months from the date of the construction permit's approval, providing the work authorized proceeds in a timely manner.
 - 3. For a commercial, industrial, or multi-family building permit, the finding shall remain valid until construction has been completed and a certificate of occupancy issued; or for the life of the permit until it is

revoked or suspended for failure to proceed in a timely manner as prescribed.

- E. A non-deficiency finding for an individual single-family development proposal shall remain valid for 24 months, provided a construction building permit is obtained within that timeframe, and work authorized proceeds in a timely manner.
- F. Concurrency evaluation tests for commercial and industrial subdivisions, for the purpose of approving a final development order, shall be conducted as a component of a development agreement, and if concurrency is found or guaranteed, the timeframe for the finding's validity shall be set forth in the agreement.
- G. Property owners shall have the option of pursuing a development agreement with Brevard County as provided for in Policy FLU 13.2, as opposed to the reliance upon a development permit.
- H. The concurrency evaluation system shall maintain a cumulative record of the level of service allocations permitted by the approval of final development orders relative to the operating levels of service for all applicable public facilities and services which have established levels of service.

Conditional Approval of Development Orders Which May Result in Concurrency Deficiencies

Policy FLU 12.10

If the concurrency evaluation ~~test~~ indicates that the potential impact of a proposed rezoning, site development plan, subdivision, or building development order will cause a deficiency to occur to minimum acceptable level of service, Brevard County may conditionally approve the development order pursuant to the policies of the Capital Improvements Element.

Co-location Opportunities for Aero-Space Related Development

Policy FLU 12.11

Brevard County shall secure long term global economic ~~opportunity~~ opportunities for its residents by maximizing its advantages of unique space-related resources, high tech manufacturing, transportation systems, education strategies, telecommunications industries, and geographic location. The County, in cooperation with the State of Florida, will capitalize on the National Space Policy and growth in this industry by encouraging technology driven development proposals within the boundaries of the County.

Land Development Regulations

Objective FLU 13

Brevard County shall manage growth and development through the preparation, adoption, amendment, implementation, and enforcement of the Land Development Regulations which fulfill the intent of this Comprehensive Plan.

Regulations to Implement the Comprehensive Plan

Policy FLU 13.1

Brevard County shall maintain Land Development Regulations to implement this Comprehensive Plan which, at a minimum, meet the requirements of Chapter 163, F. S. governing County and Municipal Planning and Land Development Regulation.

Regulations to Permit Development Agreements

Policy FLU 13.2

Brevard County shall provide for provisions in the Land Development Regulations that allow Brevard County to enter into development agreements with property owners, consistent with the Comprehensive Plan, pursuant to the requirements set forth in ~~Chapter 163~~ sections 163.3220-163.3243, F.S., the “Florida Local Government Development Agreement Act,” as amended, with the following additional requirements:

Criteria:

- A. A description of the level of service allocations to be permitted by the development agreement;
- B. Specific dates shall be identified that define the development's phasing, if applicable, and the commencement and completion of construction in each phase.
- C. Contrary to the requirement of Chapter 163, F. S., the duration shall not exceed five years, unless extended by mutual agreement according to prescribed due process.

Regulations for Zoning Classifications to be Consistent with the Future Land Use Map

Policy FLU 13.3

The Land Development Regulations shall designate adequate zoning classifications for the location of residential and non-residential development activities which implement the Future Land Use Element, Housing Element, and Future Land Use Map Series.

Regulations to Require Economic and Environmental Impact Assessments

Policy FLU 13.4

As directed by the Board of County Commissioners, all new land development regulations prepared pursuant to this Comprehensive Plan should include an economic and environmental impact assessment for the public and private sectors.

Establishment of Zoning Classifications to Meet Residential Needs

Objective FLU 14

Brevard County shall maintain zoning regulations as part of its Land Development Regulations to establish adequate zoning classifications for residential development in terms of allowing for a variety of housing types while providing residents with choices in terms of residential locations.

General Zoning Regulations Criteria

Policy FLU 14.1

Zoning regulations shall adhere to the following criteria:

Criteria:

- A. Residential zoning classifications shall be designated for single family, multi-family, and mobile home developments to meet the housing needs demonstrated in the Housing Element of this Comprehensive Plan.
- B. The densities of these classifications, as applied, shall not exceed those established for each residential designation as adopted on the Future Land Use Map, unless otherwise provided for by this Element.
- C. Proposed locations for residentially-zoned lands should be consistent with the residential designations shown on the Future Land Use Map and consistent with this Comprehensive Plan.
- D. At a minimum, residential zoning classifications shall provide for a variety of minimum lot sizes, minimum floor areas, setbacks, and residential land use mixes that allow for choice in housing types, designs, and price levels. These residential zoning classifications shall provide for both urban and rural residential environments.

Zoning Regulations to Promote Creative Utilization of Land

Policy FLU 14.2

Zoning regulations should continue to provide for flexibility regarding development patterns and land use mix. The County encourages implementation of innovative residential and commercial development patterns and lot layout techniques which achieve efficient use of public resources, reduced land consumption, and preservation of interconnected open spaces. These techniques include:

Criteria:

- A. The Planned Unit Development concept, where appropriate, to encourage creativity in development design, provision of connected open spaces, protection of environmental features, and an integrated mix of residential and non-residential land uses and employment opportunities.

- B. The use of zero-lot line residential development patterns, shared driveways, and reduced setbacks, where appropriate, to encourage more compact subdivision layouts and to generally provide increased flexibility in the design and use of the lot area.
- C. Designed integration of residential, employment, and commercial uses as permitted in the context of this Element, to promote compact mixed use development patterns within a single structure or complex of structures.
- D. Mixed use developments to promote efficient use of land and public resources by integrating neighborhood support services and employment centers with residential uses. Mixed use patterns should be implemented and achieved through the use of performance standards and other mitigating techniques to ensure compatibility between land uses.
- E. Creative clustering of residential and commercial lots and streets which preserve undisturbed vegetative corridors and consolidate cleared land areas. Innovative techniques may include reduced lot sizes, shared driveways, and other design features. In furtherance of the County's Master Plan of Linear Open Spaces, clustered development schemes which permanently preserve interconnected networks of open space within subdivisions and link same with adjacent subdivisions and parks will be considered for density bonuses or other development incentives ~~(Figure 2 in the Appendix depicts an example of a clustered land development technique in comparison with a conventional subdivision layout).~~

Policy FLU 14.3

Brevard County shall update its Land Development Regulations to expand the use of floating solar facilities and to encourage this use in locations described in section 163.32051, F.S., as amended.

Consistency with Comprehensive Plan, Zoning, and Land Development Regulations

Objective FLU 15

~~Brevard County shall eliminate inconsistencies between the Comprehensive Plan and the zoning regulations of the Land Development Regulations not approve rezoning applications that are inconsistent with the Comprehensive Plan and the Land Development Regulations, and thereafter, shall should reduce the number of existing land uses which are properties with zoning that is non-conforming to the Comprehensive Plan.~~

Authority to Initiate Administrative Actions

Policy FLU 15.1

Brevard County retains the authority to initiate appropriate administrative actions,

FUTURE LAND USE ELEMENT

such as administrative rezonings.

Administrative Rezonings for Consistency with the Future Land Use Map

Policy 15.2

County staff may initiate administrative rezonings for those properties that are found to be inconsistent with the Future Land Use Map at the time of a development permit application.

Criteria:

- A. — Determination of appropriate zoning classifications for these properties shall be pursuant to the policies and criteria which govern the Future Land Use Map and future land use designations established in this element.
- B. — The zoning classifications which are appropriate pursuant to the Future Land Use Element and Maps shall be presented as options to the property owner.

Policy 15.3

Brevard County shall continue to administratively rezone those properties with zoning classifications which are inconsistent with the Future Land Use Map, the acceptable levels of service, and this Comprehensive Plan.

Criteria:

- A. — Administrative rezonings shall not be required for single family or duplex residential lots which meet the requirements of the Brevard County Zoning Code and which are located within Neighborhood Commercial, Community Commercial Agricultural or any residential land use designations.
- B. — Prior to commencement of the administrative rezonings, small area plans shall be completed by the appropriate County staff for each area. These plans shall consider, at a minimum, compatibility issues, character of the area, environmental constraints, hurricane evacuation capabilities, and the availability of public facilities and services. Advisory committees may be appointed by the Commission to work with staff in the development of these plans and public hearings shall be held for the adoption of these plans.

Provisions for Non-conforming Uses

Policy 15.4 FLU 15.2

Brevard County shall maintain procedures that address existing land uses which are non-conforming with this Comprehensive Plan. At a minimum, the following criteria shall apply:

Criteria:

- A. Non-conforming land uses are those existing development activities which were conforming to the zoning and Comprehensive Plan regulations of Brevard County at the time of record but which are inconsistent with this Comprehensive Plan.

- B. Existing non-conforming land uses, damaged beyond 50 percent of their assessed value by natural or man-made causes, shall not be allowed to be reconstructed to a use which is non-conforming to this Comprehensive Plan, except as provided for in the Zoning Code.
- C. The addition, expansion, or re-establishment of existing non-conforming land uses shall be governed by Chapter 62, Article VI, Division 2, Subdivision II, "Non Conforming Uses" of the Brevard County ~~Land Development~~ Zoning Regulations.

Policy ~~15.5~~ FLU 15.3

The following provisions for the development of non-conforming lots to allow for the reasonable use of such properties shall apply. At a minimum, the following criteria shall apply:

Criteria:

- A. Non-conforming lots of record are those properties which meet the non-conforming provisions of the Brevard County Zoning Code but which are non-conforming to this Comprehensive Plan and/or Zoning regulations.
- B. Non-conforming lots of record may be developed to a use permitted by Chapter 62, Article VI, Division 2, Subdivision II, "Non Conforming Uses" of the Brevard County ~~Land Development~~ Zoning Regulations, provided that it is also a use permitted by the Future Land Use Map of this Comprehensive Plan.
- C. The Land Development Regulations should continue to include provisions for minimum lot dimensions and setbacks for non-conforming lots of record to ensure that these uses will be compatible with surrounding land uses.
- D. If an existing non-conforming lot does not meet the minimum lot size established by this element, relief may be obtained in accordance with the Zoning Code of Brevard County.

Provisions for Pre-existing Uses

Policy ~~15.6~~ FLU 15.4

Brevard County should maintain and enforce criteria for Pre-existing Uses, as defined by the County's Land Development Regulations. Applications for Pre-existing Uses shall be reviewed against the requirements found in the Land Development Regulations.

Preclusion of Development

Policy ~~15.7~~ FLU 15.5

If a land use designation in the Comprehensive Plan is determined to preclude all development of such land and an amendment to the Comprehensive Plan is required, an amendment alleviating the preclusion of development may be considered at the next available transmittal or adoption public hearing of the Comprehensive Plan. A development

FUTURE LAND USE ELEMENT

order consistent with the proposed amendment may be submitted for review; however, final approval will not be granted until a finding of compliance and after the appeal period pursuant to Chapter 163, F.S.

Provision for Appeals

Policy ~~15.8~~ FLU 15.6

Brevard County shall provide a method of appeals to address alleged errors in any order, requirement, decision, or determination made in the enforcement of any ordinance, regulation, law, policy, or procedure relative to the Land Use Regulations.

Military Base Land Use Compatibility

Objective FLU 16

Brevard County shall cooperate with Patrick Air ~~Space~~ Force Base (PAFB ~~PSFB~~) to encourage compatible land use, help prevent incompatible encroachment of new development, and facilitate the continued presence of Patrick Air ~~Space~~ Force Base. This Objective and its policies are intended to only apply to new development. Development, including but not limited to buildings and structures, existing on the effective date of this amendment are exempt from the requirements of Objective FLU 16 and its policies, as long as there are no increases in building height or residential density beyond that which is permitted by the applicable zoning classification.

Policy FLU 16.1

Brevard County shall transmit to PAFB ~~PSFB~~ information relating to proposed changes to the Comprehensive Plan, plan amendments, and proposed changes to land development regulations which, if approved, would affect the density, intensity or use of land on Merritt Island south of the Pineda Causeway. Brevard County shall provide PAFB ~~PSFB~~ an opportunity to review and comment on the proposed changes.

Policy FLU 16.2

PAFB ~~PSFB~~ is encouraged to provide comments to the County on the impact such proposed changes may have on the mission of PAFB ~~PSFB~~, whether the proposed changes are compatible with the safety and noise standards in the Air Installation Compatible Use Zone adopted by PAFB ~~PSFB~~, and whether such changes are incompatible with the findings of the Joint Land Use Study for PAFB ~~PSFB~~.

Policy FLU 16.3

Brevard County shall take into consideration any comments provided by PAFB ~~PSFB~~ when such decision regarding comprehensive planning or land development regulation. Brevard County shall include a copy of any such comments to the ~~Florida Dept. of Economic Opportunity or its successor agency~~ state land planning agency.

Policy FLU 16.4

To facilitate the exchange of information, Brevard County shall maintain a representative appointed by PAFB PSFB as an ex officio, nonvoting member of the County's Local Planning Agency as required by Section 62-182, Brevard County Code.

Policy FLU 16.5

The Commanding Officer of PAFB PSFB is encouraged to provide information about any community planning assistance grants that may be available to Brevard County through the Federal Office of Economic Adjustment to facilitate joint community planning efforts.

Policy FLU 16.6

To ensure continuing compatibility with the operations of PAFB PSFB and the existing character of the neighborhood, the Future Land Use designation for properties located on Merritt Island south of the Pineda Causeway shall not exceed the adopted Future Land Use designation of Residential 2.

The Farmton Local Plan**Objective FLU 17**

Establish a long-range, sustainable plan for the Farmton Tract in northern Brevard County based upon permanent conservation of Regional Wildlife Corridors, together with reservation of suitable areas for future compact mixed use development which meet the highest levels of sustainability.

Policy FLU 17.1

The Farmton Local Plan is defined by Objective FLU 17 and implementing policies. It is a flexible and innovative planning strategy to allow the conversion of agricultural lands to other uses while protecting environmentally sensitive areas. The plan uses transfer of development rights and provisions for open space protection, clustering, and mixed use development with high standards of sustainability to preserve environmental resources and reserve suitable areas for sustainable development.

Criteria:

- A. The Farmton Local Plan is the planning framework for the Farmton Tract consisting of approximately 11,500 acres in northern Brevard County. The Farmton Local Plan shall establish land uses, objectives, and policies for resource conservation and sustainable development. The policies are designed to:
 - 1. Provide opportunities for economic development and job growth
 - 2. Preserve lands prioritized by natural resources stakeholders
 - 3. Preserve significant integrated habitat for regional wildlife corridors
 - 4. Provide for a variety of land uses to support residences of diverse ages, incomes, and family sizes
 - 5. Direct population growth and development away from flood plains

FUTURE LAND USE ELEMENT

6. Discourage urban sprawl
 7. Avoid large lot rural subdivisions which fragment natural resources
 8. Create efficiencies in provision for infrastructure
 9. Conserve water and energy
 10. Balance jobs with housing
 11. Continue opportunities for agriculture
 12. Reduce vehicle miles traveled
 13. Reduce greenhouse gas emissions
- B. The Farmton Local Plan is the result of a peer reviewed collaborative stakeholder process designed to holistically address varying community needs in a flexible, yet systematic manner. Land Development Regulations, Mixed Use Zoning provisions, Master Plans, and Development of Regional Impact Development Orders which implement this plan shall utilize innovative land use techniques, creative urban design, highest levels of environmental protection, and the use of sustainable development principles as they may evolve over time.
- C. The overall planning horizon shall be consistent with the County's Comprehensive Plan horizon. There shall be no increases in the number of residential units beyond what is allowed by the future land use plan in effect at the time of adoption of this amendment.
- D. The Farmton Local Plan shall maintain at least 75% of the total area as Agriculture. These lands shall include prioritized conservation lands that have been identified by stakeholders, mitigation banks, and lands adjacent to Buck Lake Conservation Area together with buffers and designated uplands so as to establish interconnected regional wildlife corridors. Such lands shall be subject to a conservation easement and conservation management plan which shall sever all development rights and protect the lands in perpetuity.
- E. The Future Land Use Map shall identify two land uses within the Farmton Local Plan: Agriculture and Farmton Mixed Use Area (FMU). Within FMU are districts with distinct policies as set forth herein. The final shape and acreage for the developable portion of the Farmton Mixed Use Area shall be determined at the time of rezoning, but the total buildable area, exclusive of stormwater management facilities, shall not exceed 1,500 upland acres. In making the determination of which lands are suitable for development, decision support models used in the Greenprint process described in Policy FLU 17.2 A and groundtruthing shall be utilized to identify wetlands, floodplains, mitigation areas, vegetative buffers, specialized habitat for listed species, and under-represented natural communities. Priority shall be given to lands on the perimeter of the FMU which are contiguous to Agriculture lands to promote habitat connectivity. Such lands shall be re-zoned Environmental Area (EA)

FUTURE LAND USE ELEMENT

and made subject to a perpetual conservation easement and conservation management plan.

- F. Maximum development potential: The Farmton Local Plan shall utilize an internal system of transfer of development rights to establish densities. For the purposes of this plan, Agriculture shall be designated Sending Areas and the Farmton Mixed Use (FMU) Area shall be designated as the Receiving Area. The underlying residential densities for the planning area shall be based upon existing Future Land Use. Upon the adoption of the Farmton Local Plan and after the transfer of development rights, the underlying density of Agriculture shall be Zero and the Farmton Mixed Use Area shall have a maximum of 2,306 dwelling units.
1. Maximum Development Potential through buildout: The residential component through buildout of the Farmton Local Plan shall not exceed 2,306 dwelling units.
 2. The maximum non-residential square footage through buildout of the Farmton Local Plan shall not exceed 1.25 million square feet exclusive of public institutional uses (i.e., fire stations, government office, public schools, etc...). The term "Commercial" as referenced in the implementing policies for Objective FLU 17 includes retail, service, restaurants, and other customary business uses. The total maximum and minimum development for Residential and non-residential land uses within the FMU shall be:

	Maximum	Minimum
Residential	2,306 units	2,000 units
Commercial	340,000 SF	200,000 SF
Office	420,000 SF	180,000 SF
Industrial	390,000 SF	192,000 SF
Hotel	200 rooms	120 Rooms
Public Inst	50,000 SF	20,000 SF

- G. Farmton Mixed Use Areas within the Farmton Local Plan shall be located within the areas identified as most suitable for development. The total FMU area shall not exceed 2,800 acres. FMU shall be designed in a compact form including sustainable development planning and building techniques as more fully set forth herein. Densities and intensities for districts within Farmton Mixed Use Area are as set forth in Policy FLU 17.3. The mix of uses shall be in accordance with Policy FLU 17.1F (2) for the Farmton Mixed Use Area.
- H. No development shall take place within Farmton Mixed Use Area until special land development regulations are approved as part of a Mixed Use Zoning (MXD) district or upon approval of a Master Plan as part of a Development of Regional Impact Development Order pursuant to ~~Ch. 380.06, Fl. Stat.~~ section

FUTURE LAND USE ELEMENT

380.06, F.S. No certificate of occupancy may be issued for development within the Farmton Mixed Used Area prior to January 1, 2016. The timing restriction regarding certificates of occupancy shall not apply in the event that a comprehensive plan amendment is adopted and in effect prior to January 1, 2016, which results in a financially feasible capital improvement schedule, taking into account the impacts of the FMU land use change and anticipated development through January 1, 2016 as presented in the supporting analysis for the capital improvement schedule amendment.

- I. This plan shall be consistent with the provisions of the Conservation Element, with particular emphasis on Policy CON 5.2.E.(6) and Policy CON 5.2.E.(7), as amended.

Policy FLU 17.2

Protect Natural Resources of Regional Significance by promoting perpetual preservation of interconnected regional wildlife corridors.

Criteria:

- A. Decision Support Models. The designation of at least 8,700 acres of Agriculture in perpetuity is the result of a Greenprinting process which utilizes recognized decision support models, including but not limited to the Natural Resources of Regional Significance model (NRORS) of the East Central Florida Regional Planning Council (ECFRPC), Critical Lands and Waters Identification Project (CLIP) of the Florida Century Commission, consultation areas of the USFWS, and biodiversity matrix of Florida Natural Areas Inventory, to make preliminary identification of significant habitat. As these areas were identified, the landowner used ground-truthing through scientifically accepted procedures to identify habitats and ecosystems in order to identify regional wildlife corridors, an integrated habitat protection area, and reserve areas for future development. As Farmton Mixed Use Area is planned in the future for development, these decision support models shall be employed to identify additional lands within which can be rezoned to Environmental Area (EA) and made subject to a conservation easement and conservation management plan. Priority shall be given to lands on the perimeter of the FMU which are contiguous to Agriculture lands.
- B. As a result of the process identified in Policy FLU 17.2A, at least eighty percent (80%) of lands within the Farmton Local Plan shall be subject to a conservation easement and conservation management plan and preserved in perpetuity. This will include all lands designated as Agriculture together with those wetlands, mitigation areas, vegetative buffers, specialized habitat for flora or fauna, passive parks, and trails designated as EA within Farmton Mixed Use Area during the rezoning or DRI process.

- C. The identification of areas to be maintained as permanent Agriculture and subject to a conservation management plan shall be approved in consultation with the Florida Fish and Wildlife Conservation Commission, Florida Department of Environmental Protection, St. Johns River Water Management District, the Brevard Environmentally Endangered Lands Program and the Brevard Natural Resources Management Department, and by at least one tax exempt conservation organization, such as the Florida Audubon Society as consistent with Policy FLU 17.6M.
- D. Landowners shall implement an ecological monitoring program to monitor the quality and quantity of habitat type as well as species number and diversity. This information shall be used in preparation of the conservation management plan and the landowner shall not undertake management practices which diminish the quality of habitat within the area.
- E. Agriculture land and land rezoned to EA shall be subject to a conservation management plan which shall provide for ongoing conservation of listed species and other indigenous species which may require special habitat protection. The plan shall include a black bear management plan which shall be developed in consultation with the Florida Fish and Wildlife Conservation Commission consistent with its Black Bear Habitat Management Guidelines.
- F. Any future transportation facilities built across Agriculture land shall be designed to avoid and minimize conflicts between motor vehicles and the movement of wildlife consistent with the Transportation Element. To the greatest extent practicable, the transportation spine network will be within the Farmton Mixed Use Area and cross agricultural lands at suitable locations. Tools to minimize this conflict include locational criteria, landscaping techniques, fencing, speed limits, wildlife underpasses or overpasses, and bridging over known corridors. Transportation facilities shall be designed to avoid the area permitted for mitigation banking.

Policy FLU 17.3

Establish principles of sustainability and land use standards for Agriculture and Farmton Mixed Use Area.

Criteria:

- A. Principles of Sustainability. To ensure that the Farmton Local Plan is truly sustainable, the following principles shall be applied throughout the planning process:
 - 1. The Farmton Local Plan shall preserve regional wildlife corridors and important environmental systems first as part of a holistic approach to sustainability of the land.

FUTURE LAND USE ELEMENT

2. Farmton Mixed Use Area (FMU) shall contain a mixture of uses that provide for a balance of commercial, residential, recreational, open space (active and passive), resource protection, educational, and other supporting uses.
 3. FMU shall be designed with principles of smart growth, traditional neighborhood design (“TND”), New Urbanism or transit oriented development (“TOD”) including walkability, compact development patterns, quality architecture, and urban design, and a hierarchy of street systems to foster connectivity and pedestrian mobility as well as alternate modes of travel, including transit.
 4. FMU shall promote income diversity and choice through a mixture of housing types and price points using higher density, compact development patterns, and variety to limit sprawl.
 5. FMU shall provide opportunities throughout all phases of the development for residents to work in the community they live in, thereby reducing automobile dependence.
- B. FMU shall utilize sustainable development techniques that promote the reduction of greenhouse gases and efficient and effective use of infrastructure.
- C. Permanent designation of Agriculture shall be used as the foundation of land use decisions. Other areas may be reserved for future Mixed Use Zoning which shall demonstrate how the values of the adjacent conservation area will be protected and maintained.
- D. Agriculture shall be subject to a conservation easement approved by the County, and the residential density shall be zero units per acre after the transfer of development rights is completed. Water resource development, stormwater management facilities, or central potable water wellfields shall be allowed within Agriculture and Mixed Use lands after obtaining required permits.
- E. Farmton Mixed Use Areas. Within areas designated on the Future Land Use Map as Farmton Mixed Use Area, the following districts are permitted:
1. WorkPlace. The WorkPlace land use district is intended to provide and promote employment centers as well as provide work force housing in close proximity. Permitted uses include industrial uses, community and regional scale commercial, institutional uses, hotels, and residential uses. The WorkPlace district shall have a minimum density of 10 units per acre and a maximum of 15 units per acre as applied to lands developed with residential use. The maximum overall floor area ratio (FAR) for lands developed with non residential uses is as follows:

FUTURE LAND USE ELEMENT

Commercial	1.0 FAR (0.35 minimum)
Light Industrial	2.48 FAR
Hotel	2.0 FAR

The DRI development order or MXD zoning and/or special land development regulations shall require a mix of uses, including maximums and minimums for the WorkPlace land use district.

2. Villages. Villages are compact residential areas containing a mix of residential housing types to encourage affordability for a wide range of economic levels. Villages shall be supported by internally designed mixed use village centers which provide key goods and services and public facilities at the neighborhood level. Villages shall include interconnected streets that are designed to balance the needs of all users, including pedestrians, bicyclists, and motor vehicles, and which are built with design speeds that are appropriate for neighborhoods. Villages shall be adjacent to large expanses of Agriculture land that are designed to protect the character of the rural landscape.

Villages shall adhere to the following basic guidelines:

- a. Villages shall include compact design that includes a system of land subdivision and development which links one neighborhood to another. No Village shall be greater than 900 acres in size. Preserved wetlands and floodplain within a Village shall be excluded from the calculation of the maximum acreage;
- b. Villages shall include interconnected streets that are designed to balance the needs of all users, including pedestrians, bicyclists, and motor vehicles, and which are built with design speeds that are appropriate for neighborhoods;
- c. Villages shall include alternatives for pedestrians and bicyclists through the provision of sidewalks, street trees, and on-street parking which provide distinct separation between pedestrians and traffic, spatially define streets and sidewalks by arranging buildings in a regular pattern that are unbroken by parking lots, and provide adequate lighting that is designed for safe walking and signage which has a pedestrian orientation;
- d. At least 75% of all housing in a Village shall be within one half mile of the village center to encourage walkability.
- e. Each village shall contain a village center, the purpose of which is to provide key goods and services at the neighborhood level (vs. regional level).
- f. The village center shall be located approximately in the center of a designated village and shall not exceed 90 acres in size (excepting wetlands and school campuses).

FUTURE LAND USE ELEMENT

- g. The target market of a village center shall have a focus towards the residential areas within one mile. In addition to commercial, village centers shall include civic and recreational uses as well as open space in the form of greens, commons, parks, squares, and recreation areas.
- h. The transportation system within a village shall consist of collector and local streets and pedestrian and bike systems that provide linkages to other land use components of the Farmton Mixed Use Area.
- i. Each village center shall be designed to accommodate a transit stop to help facilitate transition from bicycling or walking to bus or trolley. Therefore, the transit stop should include bicycle racks and/or the bus or trolley should include racks.
- j. The village center shall be located near the juncture of two collector roads, but may, depending on environmental constraints, be located near the juncture of a collector and local road.
- k. Each village shall contain a mix of housing types to encourage affordability for a wide range of economic levels.

Approved uses within a Village include single and multi family residential, office, commercial, institutional, open space, and bed and breakfast. Non-residential uses, except for licensed home occupations, are limited to the village center. The maximum overall floor area ratio for non residential developments within a village center shall be as follows:

Commercial: 1.0 FAR (min. 0.3)

The following densities apply to lands developed with residential use within Villages:

	Maximum dupa du du/ac	Minimum dupa du du/ac
Single Family	8 <	4
Multi-family	15	8

The Village Center shall achieve a average density of 7 ~~dupa du~~ du/ac applied to lands developed with residential use.

3. Mixed Use Requirements. To ensure a sustainable mix of uses the minimums and maximums per use are per ~~policy~~ Policy FLU 17.1F.

FUTURE LAND USE ELEMENT

Policy FLU 17.4

Development within Farmton shall incorporate and promote high standards for sustainability, water conservation, energy efficiency, and greenhouse gases.

Criteria:

- A. Farmton Mixed Use Area shall require protection of green infrastructure, natural resource protection, water and energy conservation features, ~~and~~ lower impact development, and compact development. Higher density, mixed use, and compact development shall be required as it is recognized as a more energy efficient land use pattern to reduce trip lengths, promote walking, support regional mass transit, and reduce the development foot print. It also is recognized to provide tangible social and cultural benefits by encouraging more connected social support systems and a stronger sense of community.
- B. Reduction in Greenhouse Gases. By utilizing higher standards of sustainability and the principles of smart growth including traditional neighborhood design and transit oriented development, the Farmton Local Plan seeks to reduce reliance on the automobile; and, therefore, reduce the production of greenhouse gases. Additionally, the Farmton Local Plan desires to lessen the demand for energy utilized to heat and cool houses and commercial structures built in the Farmton Mixed Use Area, not only to reduce the production of greenhouse gases, but to conserve available energy resources.
- C. The Farmton Local Plan shall promote carbon neutrality through energy conservation features such as protecting natural areas, greenways, wetlands, forests, and other natural resources that reduce energy demand; energy efficient land use patterns which reduce energy consumption, promote walkability, and reduce automobile use; water and energy conservation; ; and promotion of solar power and other alternatives to achieve overall reduction in production of greenhouse gases.
- D. Farmton Mixed Use Area shall undertake the physical development of the community using a whole systems approach to the design, development, construction, and operation of the community and to do so in a way where defined benchmarks and metrics can be used to measure its success. The details for these standards will be developed in cooperation with the University of Florida Program for Resource Efficient Communities (PREC) and will be set forth in the Master Plan and DRI Development Order and will implement the following goals of sustainability:
 - 1. Site Design and Land Use shall encourage a walkable transit-ready community with a jobs-to-dwelling-units ratio to create the required synergies for a sustainable community. At build out, all homes shall be within one half (0.5) mile of transit, a village center, workplace, or an institutional or civic use such as a school or government office.

2. Landscape design shall incorporate biodiversity using native vegetation with a goal of reducing water usage and treating groundwater.
 3. Transportation design shall create multi-modal synergies that facilitate a reduction in the use of the automobile; and promote pedestrian and bicycle utilization and the use of mass transit when available.
 4. FMU design shall incorporate water conservation measures so that as nearly as possible it incorporates water neutrality into the construction and operation of the development. Water neutrality shall mean that potable and nonpotable sources of water are provided solely within the boundaries of the Farmton Local Plan and sources outside the boundaries of the Farmton Local Plan are not needed to support development within.
 5. Community design shall incorporate walkability with linkages to employment centers and developing around multi-use compact cores so that the community can coexist harmoniously with the natural, social, and economic environment.
- E. Proposed development shall meet the requirements of a certification program from either USGBC LEED for Neighborhood Development, FGBC Green Development Designation Standard, or another third party program deemed acceptable by Brevard County.
 - F. Outdoor lighting in the community will be encouraged to achieve the standards of the International Dark-Sky Association. Particularly effective best practices established in cooperation with the PREC or other credible agency will be integrated as prerequisites or established as minimum community standards such as solar powered street and pathway lighting.
 - G. Infrastructure within the Farmton Local Plan shall incorporate water and energy conservation standards as part of the land development regulations.
 - H. Individual septic tanks shall be prohibited.
 - I. ENERGY STAR® and Florida Water StarSM standards shall be met for residential development.
 - J. Solar panels shall be permitted on all buildings and in all districts.
 - K. Waterwise and Florida Friendly principles shall be applied in the design of all landscape areas.
 - L. Energy Efficiency Criteria. The Farmton Local Plan shall develop in a manner that establishes energy efficient land use patterns. The specific criteria to be

FUTURE LAND USE ELEMENT

evaluated and incorporated in the implementing land development regulations shall include:

1. Measures to promote walkability;
2. Inclusion of a bike trail system in future development applications that demonstrates connectivity to a larger external system, to include the regional bike trail network, and provision for bicycle racks at all transit stops;
3. A mix of uses that provides residents and employees with opportunities to obtain goods and services utilizing non automotive travel modes;
4. Permitting solar panels on any structure;
5. The provision of at least one recharging station at each Village Center, and WorkPlace for personal electric vehicles (PEV);
6. Demonstration that the application was coordinated with ~~the school board~~ Brevard Public Schools to promote safe, alternative travel modes for school children;

M. Adaptive Management. It is recognized that the standards and protocols which define sustainability are constantly evolving such that what is determined to be acceptable today may be unacceptable in the future and that supportive programs may emerge tomorrow that more adequately accomplish the goal of the Farmton Local Plan. For the purpose of achieving sustainability goals, adaptive management will be employed over the life of the plan so as to ensure that the most current programs, policies, and protocols are used throughout the life of the community.

N. Environmental Education. Proposed development shall provide for an on-site naturalist to provide environmental education and uphold the environmental and sustainability standards for any proposed development within the Farmton Local Plan. Environmental education shall focus on the following and be the responsibility of the Homeowners Association or Community Development District as appropriate:

1. Landscaping activities;
2. Monitoring of environmental conditions and sustainability performance such as energy consumption, greenhouse gas emissions, water consumption, water quality on site, and biodiversity;
3. Analysis and education on community performance standards for energy and water use efficiency and facilitation of carbon credit sales for energy efficiency;
4. Distribution of educational materials for home buyers that include landscape plans/lists of plants installed on their lots and basic maintenance requirements of any home features that received credits under the ENERGY STAR® or Florida Water StarSM certification programs;

FUTURE LAND USE ELEMENT

5. Distribution of educational and interpretive materials on bikeways and trail systems, wildlife and habitat protection issues.
- O. Jobs to housing ratio. The Farmton Local Plan shall develop and implement a program designed to ensure an adequate number of jobs per residential dwelling unit exist in the Farmton Mixed Use Area at buildout. The standard jobs-to-housing balance of 0.65 jobs per residential unit shall be required concurrently with housing development after the first 1,000 dwelling units are permitted.
- P. Diversity of Dwelling Styles. Residential neighborhoods and mixed use areas shall include a variety of dwelling types and lot sizes to provide opportunities for different age and income groups within an integrated and diverse community so as to avoid rigid segregation of dwelling types by price point within the community. Housing types may include, but are not limited to, mid-rise multifamily, single family detached, residential above commercial, townhouses, carriage houses, garden apartments, duplexes, triplexes, zero lot line, owner-occupied, and for rent product. The mix of housing product will vary depending on the section of the community in which the housing is developed.
- Q. Within Farmton, ten (10) percent of residential units shall qualify as “affordable housing” as currently defined by the Comprehensive Plan and Land Development Regulations.
- R. The 10% allocation required by subpolicy Q shall be located within a 1/3 mile of transit stops or on-site employment opportunities.
- S. Institutional uses (e.g. churches, libraries, public and private schools, recreation facilities, government buildings, police/fire/emergency medical services, water and sewer plants) shall be allowed in the FMU land use category, but shall not be allowed in the Agriculture land use category.
- T. Implementing land development regulations of the Farmton Mixed Use Area shall require the early identification of external access locations and a process through which access improvements, if needed, will be guaranteed.
- U. Implementation of appropriate “firewise” community planning practices shall be identified during the subdivision/site plan review process. As part of the development review process, a covenant will be placed on properties near or adjacent to public conservation or preservation land to notify future property owners and residents that the nearby or adjacent public land or conservation areas will be managed by natural resource management practices including prescribed fire and other techniques.

FUTURE LAND USE ELEMENT

- V. A phase I cultural resource assessment survey shall occur prior to initiating any project related land clearing or ground disturbing activities that are not agriculturally related within the project area. The purpose of this survey will be to locate and assess the significance of any historic properties present. The resultant survey report must conform to the specifications set forth in Chapter 1A- 46, Florida Administrative Code, and be forward to the Division of Historical Resources for comment and recommendation in order to complete the process of reviewing the impact of the proposed project on historic resources. Should significant resources be present, additional archaeological testing may be necessary, and/or protection and preservation of significant sites may be required.

Policy FLU 17.5

Adopt general development guidelines and standards for Farmton Mixed Use Areas which provide for delivery of services and provision for infrastructure and fiscal neutrality.

- A. Floodplains. Any development within the Farmton Local Plan shall be consistent with Objective CON 4 of the Brevard County Conservation Element and its implementing land development regulations including those policies promoting clustering of residential densities and non-residential intensities.
- B. Development proposals within Farmton Mixed Use Area shall only be processed with a Master Plan associated with a Development Order reviewed as a development of regional impact (DRI) per Chapter 380 of Florida Statutes or a MXD. As required through the DRI process, financial feasibility of required mitigation to regionally significant off-site transportation facilities will be identified. Recognizing that regionally significant transportation facilities can also be impacted by auto-occupancy factors and transportation mode shifts due to influences such as economic and environmental changes affecting lifestyles, the Farmton Mixed Use Area land use planning and site design must further the goals of trip reduction and vehicle miles of travel reduction, both on- and off-site.
- C. The use of septic tanks is prohibited within Farmton unless preexisting.
- D. Minimum buffers and setbacks
 - 1. Boundary buffer: The purpose of the boundary buffer is to minimize visual and noise impacts on surrounding land owners. The boundary buffer around Farmton Mixed Use Areas shall be a minimum of 200 feet. There shall be no encroachment within the buffer except for bike paths, equestrian, and walking trails, fire lines, existing logging roads, and public roadways.

FUTURE LAND USE ELEMENT

2. Arterial buffer: The purpose of buffers and setbacks on arterial roads shall be to minimize visual intrusion of development activity on the traveling public. A minimum 75 foot “no encroachment” buffer is required on arterials. The no encroachment buffer prohibits intrusion of any kind, excepting intersecting roadways and one monument project signage at such intersections intended for project identification and way finding. Lakes may also encroach into this buffer. However, in such an event, any building setback shall be 200 feet from the arterial right of way.
 3. Collector buffer: For roads that are functionally classified as “collector” by the County, an applicant shall provide a buffer of 50 feet, except that stormwater facilities may be located within this buffer or for roadway segments within the village center(s).
 4. Wetland buffer: All preserved wetlands shall have a minimum 50 foot upland buffer or greater, if required by law or administrative rule.
 5. East Central Regional Rail Trail Buffer: A rail trail corridor ranging in width between 100 and 200 feet extends through the area of the Farmton Local Plan and will ultimately be developed as a public access multi-use trail. A minimum 200 feet wide vegetative buffer shall be maintained on each side of the centerline of the trail right of way so as to minimize encroachments on the trail and enhance the experience of the trail user.
- E. Water Resources. Farmton Water Resources LLC (FWR) is a utility certified by the Florida Public Service Commission and is the authorized water provider to the Farmton Local Plan area. FWR and the City of Titusville have established TIFA LLC which is a joint venture for development of water supply on Farmton which initially reserves 0.6 million(s) of gallons per day (mgd) for the Farmton Mixed Use Area. FWR, through extensive well placement and stress testing, has determined that significant groundwater resources exist within its jurisdictional perimeter that are far in excess of the water needs required by buildout under the Farmton Local Plan. TIFA LLC shall apply for a CUP from SJRWMD to supply groundwater to the area and the proposed development allowed by the Farmton Local Plan. In the event that St. Johns River Water Management District (SJRWMD) deems the existing ground water insufficient to serve buildout of the Farmton Local Plan, then any additional water supply needed shall be provided by an alternative water supply source identified in SJRWMD’s District Regional Water Supply Plan. ~~FWR shall coordinate with the City of Titusville and, County, to revise their 10-year water supply facilities work plans to include FWR’s service area and descriptions of projects needed to provide potable and nonpotable water to the service area. In addition, shall propose additions to the District Water Supply Plan to provide for water resource development and alternative water supply plans including storage of water, and acceptance of reuse or storm water, and augmentation or wetlands~~

FUTURE LAND USE ELEMENT

~~restoration. FWR shall coordinate with Brevard County with respect to updates of the County's Water Supply Facilities Work Plans and other water resources issues as required by Florida Statutes. FWR is responsible for providing onsite and offsite infrastructure improvements necessary to provide potable and nonpotable water and waste water to development within the Farmton Local Plan area. Infrastructure improvements shall include wells, surface water intake facilities, pumps, raw water transmission lines, water treatment plants, wastewater treatment plants (meeting public access reclaimed water standards), finished water transmission lines, reclaimed water transmission lines, and potable and nonpotable water storage facilities. As the infrastructure projects are identified and approved by the County and the SJRWMD, those projects shall be included in the County's Water Supply Facilities Work Plan and Capital Improvements Element during the annual update. At FWR's request, Brevard County will include projects administered by FWR in the annual update of the Capital Improvements Element Schedule of Improvements.~~

- F. The County shall not issue any development orders or development permits for Farmton without first determining that adequate water supplies (potable and nonpotable) exist to serve the new development and will be available no later than the anticipated date of issuance of building permits. The availability of water supply shall be demonstrated through:
1. Before the County issues a DO (except a DO issued under Chapter 380, F.S.), the County shall receive a Concurrency Certificate from the water supplier verifying that it has the facilities and capacity to serve the development;
 2. CUP issued by SJRWMD to TIFA LLC for potable water to site;
 3. The availability of reclaimed water and stormwater for irrigation use within the developments and the quantity of potable water these sources will offset; and
 4. The potential for water conservation practices to reduce demand, such as installation of high-efficiency plumbing fixtures, appliances, and other water conserving devices in households, as well as public and commercial restroom facilities and the use of waterwise and Florida Friendly principles in all landscaped areas, where ecologically viable portions of existing native vegetation shall be incorporated into the landscape design to the greatest extent practicable so as not to require irrigation. The Farmton Local Plan shall comply with the Aquifer Recharge policies of the Brevard County Comprehensive Plan (Conservation Element) and its implementing land development regulations. Reuse and water conservation methods shall be implemented in accordance with the applicable requirements of ~~policy~~ Policy FLU 17.4 to reduce water demand.

FUTURE LAND USE ELEMENT

- G. The owner shall also reserve and dedicate at no expense to the County a 200 foot right of way to allow the for future extension of an arterial roadway from the SR 5A interchange with I-95 through the FMU to the County line to connect with Williamson Road Extension in Volusia County in the event that road is established. The developer shall also reserve and dedicate a utility easement along any transportation facilities that connects to the SR 5A interchange with I-95 to the FMU. The alignment of the transportation and utility facilities shall be as generally depicted on the “Farmton Local Plan Boundary & Arterial Transportation Network” Map ~~13~~ 3, but the final alignment shall be after groundtruthing to avoid, to the greatest extent practicable, impacts to wetlands and flood plains within the Agriculture lands.

Policy FLU 17.6

Agriculture within Farmton shall be managed for natural resource protection and conserved in perpetuity.

Criteria:

- A. Lands designated as Agriculture together with lands rezoned EA within FMU shall be subject to a conservation management plan and protected by a perpetual conservation easement.
- B. The initial conservation easement severing development rights for the area designated as Agriculture on the Future Land Use Map shall be recorded by the owner with the ~~Clerk of the Circuit Court~~ Brevard County Clerk of the Court and Comptroller within 30 days of effective date of the Ordinance adopting the Farmton Local Plan which is subject to the final determination of compliance and the expiration of any and all deadlines for appeal. Additional areas designated as EA within Farmton Mixed Use shall be recorded prior to the issuance of certificate of occupancy(ies) for the associated development. Conservation easements shall be conveyed to the County and combination of other public agencies or qualified conservation organizations experienced in holding and maintaining conservation easements (such as the Florida Audubon Society) subject to their acceptance after review and approval of the easement as to form and content.
- C. The conservation easement(s) shall accommodate a limited number of crossings of the easements for arterial roads, utilities, and trails. Roads and utilities shall share crossings unless the utility is pre-existing. The conservation easement(s) shall also accommodate potable wellfields or other water resource development to supply water to the FMU(s) subject to required permitting. No new roads or new utility crossings shall be allowed in the area permitted for mitigation banking.
- D. The conservation easement(s) shall incorporate provisions for a conservation management plan which shall include agriculture, silviculture, and

FUTURE LAND USE ELEMENT

conservation objectives and outcomes and a financial plan for meeting the obligations of the program over time.

- E. Areas set aside for Agriculture may be accessed by walkways, boardwalks, trails, and bikeways where such access is consistent with the maintenance of the ecological resource, its habitat values, and the bone fide commercial agricultural operation, as well as consistent with the Conservation Management Plan. Agriculture may include facilities for environmental education and research and potable wellfields subject to required permitting.
- F. Uses within Agriculture designated areas may include agriculture, conservation, and passive recreation.
- G. Agriculture land shall have the highest level of protection and conservation management plans shall protect natural resource values identified within those areas consistent with agriculture.
- H. Agriculture land shall be designed to eliminate or minimize fragmentation and promote the formation of linked networks to adjacent properties managed for conservation purposes.
- I. To the extent that transportation and utility facilities are necessary for access to the Farnton Mixed Use Area, they shall be designed to avoid wetlands and other ecological resources except as allowed by policy and as necessary, and shall avoid the area permitted for mitigation banking.
- J. Conservation Management Plan. A conservation management plan shall be adequately funded to meet the requirements of the plan over time. The conservation management plan shall set resource protection standards and management protocols designed to ensure the long-term maintenance of the ecology of the areas subject to a conservation easement. The plan shall be developed within one year of the recording of the initial conservation easement. The County and the owner shall establish an advisory committee made up of representatives of the owner and grantees under the conservation easement and the community stewardship organization and others with special expertise to develop the management plan which, upon approval of the landowner, and owner of the conservation easements, shall be incorporated into the conservation easement and made enforceable. The intent of the conservation management plan is to prevent the quality of habitat in the Farnton Local Plan from being diminished and encourage the improvement of habitat quality which may include habitat restoration.

Areas which have been formally opened as a mitigation bank shall be managed subject to the permit conditions, financial responsibility provisions,

FUTURE LAND USE ELEMENT

and terms of the conservation easement pertaining to the mitigation bank. The conservation management plan shall establish conservation goals and objectives for diversified habitats within the Farmton Local Plan which are consistent with respective habitat requirements, ecological communities, and other natural resource requirements, as well as conditions associated with public access, hunting, and passive recreational use. The conservation management plan shall address at a minimum, the following matters:

1. A prioritized list of natural resource management objectives for the site and implementation methods that protect and enhance ecosystem integrity, function, and biodiversity.
2. Identification of special areas, including but not limited to the Maytown Flatwoods Florida Forever Project and USFWS consultation areas.
3. Identification of natural and cultural resources in need of protection and discussion on how those resources will be protected.
4. Description of natural communities and establish desired future conditions by specific habitat type.
5. Identification of known threatened or endangered plants and animals occurring on site and strategies and habitat management plans as identified in the best available scientific literature.
6. Identification of exotic species and a plan for treatment/control .
7. Forestry stewardship provisions consistent with Best Management Practices for silviculture, including location and logging road access management plan.
8. Provisions for significant water resources (such as streams, creeks, natural drainage ways, floodplains, and wetlands) protection, enhancement, and restoration and planned hydrological restoration.
9. Provisions for protection of habitat of listed or imperiled species and other indigenous species which may require special habitat protection.
10. Provisions for water resource development, well fields, and protection of wellfields
11. Erosion control.
12. Fencing, appropriate public access, hunting, and, if consistent with maintenance of the ecological resource, its habitat values and the bone fide commercial agricultural operation, possible development of trails, boardwalks, and interpretive facilities.
13. Provisions for elevated roadways or wildlife crossings.
14. Prescribed fires specific to habitat types, Division of Forestry criteria, and addressing flexibility associated with climatic conditions and catastrophic events.
15. Coordination of management plans with adjacent conservation lands and mitigation banks.
16. Identification of ownership and management responsibilities including financial responsibility.

FUTURE LAND USE ELEMENT

17. Establishment of a timetable for implementation of the conservation management plan and development of a monitoring and reporting program to track the implementation.
 18. Provisions for passive recreational use, environmental education, and public access where appropriate.
 19. Provisions for security and maintenance.
 20. Coordination of conservation management plans with the management plan of the East Central Florida Regional Trail.
- K. To the extent that transportation and utility facilities are necessary for access to the Farmton Mixed Use Area, they shall be designed to avoid wetlands and other ecological resources except as allowed by policy and as necessary, and shall avoid the area permitted for mitigation banking.
1. bicycle, pedestrian, and equestrian trails, trailheads and rest areas for trails to include restrooms, water fountains, government initiated parking facilities for trail users, shelters to provide protection/ relief from the weather
 2. utility lines
 3. solar energy facilities to provide all, or portions of, the power source for illumination of on-site signage or on-site security
 4. stormwater retention facilities only when required for public infrastructure projects
 5. roads, rights of way, or transportation facilities which cross Agriculture land.
 6. fencing if specifically directed by appropriate public agency
 7. agricultural or silvicultural activities using BMPs and which do not require irrigation.
 8. replacement of existing structures.
 9. environmental education or interpretation facilities.
 10. well fields, water storage and water reservoirs and other water resource development projects.
 11. Maintenance or replacement of existing hunting camp facilities
- L. The maximum impervious surface ratio for uses identified in Policy FLU 17.6K shall not exceed those established in the County's Land Development Regulations.
- M. Agriculture land shall be permanently protected by conservation easement such that areas are and remain undeveloped in perpetuity. The applicant shall draft a conservation easement agreement in a format acceptable to the County. The easement shall be conveyed to the County and combination of other public agencies or qualified conservation organizations experienced in holding and maintaining conservation easements subject to their acceptance after review and approval of the easement as to form and content.

FUTURE LAND USE ELEMENT

- N. A Community Stewardship Organization or other tax exempt not for profit conservation organization (CSO) pursuant to Sec. 170(h)(3) I.R.C. shall have perpetual existence and be established for the purpose of conservation of areas of significant ecological integrity through fee acquisition of natural sites, acceptance or creation of conservation easements, or development of managed and interpretive public access to areas of special ecological, aesthetic, and educational value. The owner/applicant shall fund and facilitate the creation of the CSO, but its governance shall be independent from the owner/applicant. The CSO shall be governed by a board of directors of seven individuals. At least four of the members of the board shall be representatives of statewide or national non-profit environmental/conservation organizations in existence at the time of the adoption of the Farmton Local Plan such as the Nature Conservancy, Florida Audubon Society, Trust for Public Lands, and Florida Wildlife Federation. The owner shall be represented on the board and other board members may include representatives of public agencies, stakeholders, and other interested citizens who participated in the development of the plan. The CSO may take title to designated Agriculture or EA lands, or co-hold a conservation easement over such lands and shall participate in the development of the conservation management plan. The CSO may enter into contracts with the landowner or public agencies to undertake management responsibilities set forth in the conservation management plan and may manage and operate environmental or interpretive facilities associated with the site.

Policy FLU 17.7

The Farmton Local Plan shall promote Sustainable Agriculture.

Criteria:

- A. Unless modified by DRI Development Order or MXD zoning or Conservation Management Plans adopted as part of a Conservation Easement, agricultural activities may continue on Farmton lands.
- B. Future agricultural operations may be provided for within the Farmton Mixed Use Area as may continue in the DRI Development Order or MXD zoning.
- C. Silviculture may continue subject to Best Management Practices approved by the Commissioner of Agriculture and Consumer Services.
- D. Right to Farm. Florida's Right to Farm laws apply to existing and new agricultural uses in the Farmton Local Plan. DRI Development Orders or MXD shall have requirements for purchasers of homes within Farmton to acknowledge, via covenants, conditions, and restrictions that existing silvicultural/agricultural activities are allowed to continue on surrounding lands.

Policy FLU 17.8

The Farmton Local Plan shall promote an efficient transportation system that maximizes on-site traffic capture, mitigates its impacts, and provides for continuous modeling and monitoring to assess the operation of the transportation system. The Farmton Local Plan shall be developed in a manner to promote a transportation system, both on-site and off-site, consistent with the goals of providing mobility that is energy efficient, includes green development principles, and is financially feasible. A key component of the Plan shall be a shift in emphasis from providing for the movement of vehicles to the provision of mobility of people. The Plan shall also identify the procedures for determining transportation needs, identifying funding mechanisms, the protection of transportation facilities, and the monitoring of transportation impacts.

Criteria:

- A. The Farmton Local Plan shall include the concept of transportation mobility in all aspects of the transportation network design. This emphasis is consistent with the concepts of reduced energy requirements, reduced greenhouse emissions, and reduced transportation facility expenditures. All development within the Farmton Local Plan shall implement these design concepts.
 - 1. The Farmton Local Plan shall be developed consistent with walkable community design standards to encourage walking as a means of transportation, recreation, and social interaction.
 - a. A mix of land uses, multi-modal transportation stations, and transit stops shall be provided in close proximity to each other to foster walking as a viable means of transportation.
 - b. Shade shall be provided in the form of tree canopy or man-made structures in the WorkPlace and Villages to accommodate walking by providing relief from direct sunlight and the elements.
 - c. Sidewalks shall be wide enough to accommodate pedestrian activity and shall otherwise comply with the land development regulations.
 - d. Safely lit sidewalks with physical separation from adjacent roadways (via curbing or otherwise adequate spatial separation) shall be provided to encourage night-time use.
 - 2. The Farmton Local Plan shall include a network of interconnected multiuse paths designed to accommodate pedestrian, bicycle, and low speed electric vehicles. The path network shall connect neighborhoods to reasonably proximate destinations including public and commercial land uses. The County shall require the developer to submit to the County both a bicycle routing plan and mobility plan, including a trail plan as part of the MXD master development plan to be reviewed and approved by the County.
 - a. Multi-use paths shall be provided connecting neighborhoods with the WorkPlace, Villages, recreational centers, schools, and parks.
 - i). Multi-use paths shall not be less than 12 ft. in width.

FUTURE LAND USE ELEMENT

- ii). Multi-use paths shall accommodate pedestrians, bicycles, skaters, rollerbladers, skateboarders, and low speed electric vehicles.
 - iii). Rest areas, including parking areas, water fountains, restroom facilities, shelter from the weather, shall be provided for trail users with access from public roads.
 - b. Accommodation of electric vehicles shall be provided in the development of residential units and at significant public, recreational, educational, and commercial destinations.
 - i). Use of low speed electric vehicles on local streets and on multi-use paths shall be permitted.
 - ii). Major public and commercial destinations as well as multimodal stations in the WorkPlace and Village Centers shall provide for parking spaces specifically designed and designated for low speed electric vehicles. The provision of electric vehicle charging stations should be provided where practical.
- 3. The Farmton Local Plan shall incorporate the features of transit-oriented development in the WorkPlace and Villages.
 - a. The WorkPlace shall incorporate a multi-modal station accommodating transit adjacent to the core area.
 - b. Villages shall incorporate transit stops within the Village Center.
 - c. Transit stops shall be designed to provide convenient walking distances for all neighborhoods.
 - d. Bicycle racks for the temporary, secure storage of bicycles shall be provided at all transit stops and at major public facilities, commercial destinations, recreational facilities, and schools.
- 4. FMU within the Farmton Local Plan shall include an efficient road network designed to safely accommodate access to the external road network and the internal road network for all modes of transportation.
 - a. A hierarchy of roads shall be developed that accommodates local transportation needs as well as access to the external road network. An approved plan providing for a hierarchy of transportation facilities will be required to accommodate this goal prior to the development of the FMU.
 - i). Internal access within the WorkPlace and the Villages shall consist of interconnected local streets and collectors meant to disperse traffic and avoid funneling traffic to a reduced number of collectors and arterials. This design requires a pattern of mixed uses, commercial, and residential in proximity to each other. Cul-de-sacs shall be prohibited except in perimeter areas. The interconnected network of local streets shall be posted at lower, bicycle/pedestrian friendly speeds

FUTURE LAND USE ELEMENT

(30 mph or less). On-street bicycle use and on-street parking shall be accommodated on local streets.

- ii). Access between the Workplace and the Villages, as well as access to the external road network, shall be provided by a system of arterial(s).

- 5. The Master Plan shall include a designation of arterial roads identifying approximate alignments, right-of-way widths, path crossings, wildlife corridor crossings, setbacks, and design elements consistent with the needs of access between major uses on-site and access to the external transportation network.
 - a. Concurrency requirements may require improvements, including interchange improvements, which shall be evaluated in determining the use of proportionate share funds and other contributions toward prioritized improvements that will benefit the regional transportation system.
 - b. The owner shall reserve and dedicate at no expense to the County a 200 foot right of way to allow for the future extension of an arterial from the SR 5A interchange with I-95 through the FMU to the County line. All development within the Farmton Local Plan shall provide for, and protect, this corridor and shall include accommodations for multi-modal transportation. Future interchange access to Interstate 95 at the existing SR 5A interchange shall be included in the Master Plan and may be required as mitigation to any over-capacity conditions projected with the development of the Farmton Local Plan. Development shall be setback from the proposed SR 5A interchange and shall be required to protect the traffic-handling capacity of the proposed interchange. Said access to Interstate 95 at the existing SR 5A interchange shall be included in the Traffic Element.
 - c. Designated bicycle lanes shall be provided on all arterial roads.
- 6. The Farmton Local Plan shall accommodate a transit system design within its major transportation facilities connecting on-site transit stops and stations to external transit line routes as may be developed by transit providers in Brevard County.
- 7. Given the potential for innovation in transportation, provision should be made for accommodating state-of-the-art travel modes (both for on-site facilities and access to off-site facilities) as they evolve throughout the development of the Farmton Local Plan to the extent practical.

- B. The transportation mobility focus for the Farmton Local Plan represents a change from the historic approach to providing for mobility which previously focused on the personal automobile. This new focus is on reduction of vehicle miles traveled, increased vehicle occupancy, reduced energy costs, and

FUTURE LAND USE ELEMENT

reduced greenhouse gas emissions while increasing the mobility of the traveling public. A byproduct of this approach will be a reduction in the rate of trip generation on a per vehicle basis. This is a necessary goal given the prevalent and growing deficits in the public's ability to fund new roads. Transportation goals are now focused on reducing travel demand while preserving existing transportation facilities. The County's goal for the Farmton Mixed Use Area is to attain a 30 percent internal traffic capture by encouraging a balanced mix of uses. In order to document the effectiveness of this objective, several policies are proposed that address transportation needs through the build-out.

1. Any proposed development within the Farmton Local Plan shall be required to meet concurrency or mobility standards as may be established by Brevard County. Satisfaction of the standards shall include providing proportionate share funding for off-site transportation improvements. Transportation impact fees and/or mobility fees will be fully-creditable against off-site proportionate share funding of transportation improvements. On-site transportation improvements shall be the sole responsibility of developer(s) of the Farmton Local Plan.
2. Monitoring of the transportation system impacts, both on-site and off-site, will be required at least every seven years after the commencement of construction of the first development in the FMU within the Farmton Local Plan and shall coincide with the County's Evaluation and Appraisal Report Process.
 - a. The monitoring effort shall address transportation impacts for a study area inclusive of transportation facilities impacted by existing approved Farmton Local Plan development at five percent or greater of each facility's capacity at the adopted level of service (significant impacts) as established by the governing body of the facility's jurisdiction.
 - b. The monitoring effort shall be documented in a written report detailing the analysis procedure, results, recommendations, and funding sources necessary to mitigate any transportation deficiencies whereon the trip generation caused by the Farmton Local Plan is significant and results in total traffic volumes exceeding the established capacity (adverse impacts) of the facility.
 - c. The monitoring effort shall document the extent to which external trip generation varies from anticipated industry standards as projected by the Model. The documentation shall address which strategies of travel demand management are being implemented and shall assess the probable effectiveness of each strategy.

FUTURE LAND USE ELEMENT

3. Modeling of future transportation system impacts due to the Farmton Local Plan shall be required at least every seven years following commencement of construction of the first development in the FMU within the Farmton Local Plan and shall coincide with the County's Evaluation and Appraisal Report Process. The modeling period shall address, at a minimum, a 5-year and a 10-year future analysis development period from the date of the biennial modeling effort. The modeling effort shall address transportation impacts for a study area inclusive of transportation facilities impacted by proposed Farmton Local Plan cumulative development at five percent or greater of each facility's capacity at the adopted level of service (significant impacts) as established by the governing body of the facility's jurisdiction. The modeling effort shall be documented in a written report detailing the analysis procedure, results, recommendations, and funding sources necessary to mitigate any transportation deficiencies whereon the trip generation caused by the Farmton Local Plan is significant and results in total traffic volumes exceeding the established capacity (adverse impacts) of the facility.
4. Transportation impact analyses of the Farmton Local Plan shall be coordinated with adjacent jurisdictions including Seminole County as well as significantly impacted municipalities and towns within Brevard and Volusia Counties (significance shall be ~~determine~~ determined consistent with procedures identified in ~~Ch section~~ 380.06, F.S.).

Policy FLU 17.9

Establish a Farmton implementation strategy and development review process.

- A. Contemporaneously with the adoption of the Farmton Local Plan, the Future Land Use Map shall be amended to show Agriculture and Farmton Mixed Use Area. The County shall adopt a Mixed Use Zoning District (MXD) to implement the Farmton Mixed Use Area land uses, land use districts, concurrency management systems, and procedures for development within the Farmton Local Plan.
- B. Land Development Regulations. The County shall adopt amendments to the Zoning Ordinance and Land Development Code to establish the specific requirements for developments within the Farmton Mixed Use Area to ensure consistency with the plan through a Mixed Use Zoning District (MXD). The Zoning Ordinance and Land Development Code will establish a Mixed Use Zoning district and design standards with general baseline regulations including physical design, development approval processing, requirements for the fiscal neutrality plan, the ratio of non-residential to residential development, as well as baseline design guidelines for Workplace and Village development. The general design standards will include, at minimum, architectural standards, street design, transit friendly design requirements,

FUTURE LAND USE ELEMENT

landscaping, lighting, access and circulation, parking, lot development standards, parks, and internal recreational space and facility requirements. In addition, innovative resource conservation measures will also be included to address water conservation, non-potable water usage, and other resource conservation measures including, but not limited to, materials and energy. No development may be approved or permitted until this Mixed Use Zoning District and design standards are adopted.

- C. **FMU Re-Zoning Process:** Development activity within Farmton Mixed Use Area must be approved through a MXD district and/ or Development of Regional Impact process and shall be planned through a master development plan process that integrates development, Agriculture land, and infrastructure. In addition to standard requirements for a MXD or DRI application, the application and development order shall include the following:
1. Master Development Plan
 2. Specific Design Guidelines for the Development
 3. Fiscal Neutrality Plan and Procedure for Monitoring Fiscal Neutrality for on-site improvements and proportionate share mitigation for off-site improvements.
 4. Conservation Management Plan for Agriculture land
 5. Phasing Plan for development (including timing and amount and phasing of residential and non-residential development)
 6. Adequacy of infrastructure including transportation and public schools
 7. Provisions for water and energy conservation measures.
- D. **Master Development Plan Requirements.** The County shall adopt amendments to the Zoning Ordinance and Land Development Code to establish the specific requirements of Master Development Plan submittals and the standards for the review of those Master Development Plans.
- E. **Phasing.** Development within the Farmton Local Plan shall be phased according to a plan approved in the Master Plan and MXD zoning or DRI Development Order which shall establish the timing and conditions upon when future phases will be approved.
- Facilities Capacity.** The phasing conditions of each development shall address at a minimum:
- a. The requirement that adequate public facilities and services be available to accommodate the development and maintain the adopted level of service standards, and
 - b. The availability of water supply to serve the development, and
 - c. The provision of a transportation network within the Farmton Mixed Use Area that is projected to be needed to support the development through buildout.

FUTURE LAND USE ELEMENT

- F. **Monitoring Program.** To ensure efficient planning for public infrastructure, the County shall annually monitor the actual growth within the County, including development within the FMU, and adopt any necessary amendments to the Farmton Local Plan in conjunction with the update of the Capital Improvements Plan. Any amendments to the Capital Improvements Plan will be made consistent with the requirement for Fiscal Neutrality for FMU.
- G. **Fiscal Neutrality.** Development within the Farmton Mixed Use Area shall provide adequate infrastructure that meets or exceeds the levels of service standards adopted by the County and be fiscally neutral or results in a fiscal benefit to the County, ~~School Board~~ Brevard Public Schools, and residents outside that development. The intent of Fiscal Neutrality is that the costs of additional local government services and infrastructure that are built or provided for the Farmton Mixed Use Area shall be funded by properties within the approved FMU.
1. Landowners, developers, or Community Development Districts shall demonstrate fiscal neutrality as part of the master development plan approval process, according to the procedures established by the County. Such procedures shall require that Fiscal Neutrality be determined for development on a case-by-case basis, considering the location, phasing, and development program of the project. For off-site impacts, the procedures will require that the total proportionate share cost of infrastructure be included and not simply the existing impact fee rates. Notwithstanding the provisions of the Concurrency Management System, this shall include, but not be limited to, both localized and Countywide impacts on County, City, State, and Federal transportation facilities (such as roads, intersections, sidewalks, lighting, medians, etc.), public transit, schools, water supply and delivery, sewage transmission and treatment, solid waste, storm and surface water management.
 2. For off-site transportation improvements, if a development needs to pay proportionate fair-share or proportionate share toward a needed improvement to meet concurrency and the remainder of that improvement's cost is not programmed for funding in either the 5 year Capital Improvements Element or the 10-year Concurrency Management System, then the sum of those proportionate share dollars shall be directed to improve specific facilities (pipe-lining) on a priority basis as determined by the county, except as it relates to the Florida Department of Transportation (FDOT) Strategic Intermodal System (SIS) facilities wherein FDOT will determine how funds will be directed. The County will consult and coordinate with all impacted roadway maintaining agencies (including FDOT and the Cities) regarding priorities on other than SIS facilities. The development will be

FUTURE LAND USE ELEMENT

approved if an agreement is executed on how the funds will be directed. The County reserves the right to condition approval of development on the availability of funding for all necessary infrastructure to support and provide capacity for the proposed development. Off-site county roads constructed by the developer with proportionate share dollars may be eligible for transportation impact fee and/or mobility fee credits. However, any said credit shall not exceed the amount of impact fee and/or mobility fees actually paid by the development. The arterial connection from SR 5A interchange to and within the Farmton Mixed Use Area shall be the sole responsibility of the developer(s) of Farmton and not eligible for transportation impact fee and/or mobility fee credits.

3. The County may require that these procedures for measuring fiscal neutrality may be reviewed and certified by independent advisors retained by the County at the expense of the landowner, developer, or Community Development District prior to acceptance by the County.
4. Development within the FMU shall have a financial strategy approved by the County to construct and maintain all required infrastructure. Community Development Districts are identified as the preferred financing technique for infrastructure needs.

- H. Review by State Agencies. The Farmton Local Plan provides no exemption from reviews otherwise required by state and regional agencies.

Sustainability/Energy Efficiency

Objective FLU 18

Brevard County ~~shall~~ should aim at achieving a sustainable/energy efficient environment by minimizing the emission of greenhouse gases and reducing the vehicle miles of travel.

Policy FLU 18.1

LEED Certification. The County ~~shall~~ should encourage new development to be LEED certified by the US Green Building Council or similar program.

Policy FLU 18.2

Reduction of Vehicle Miles of Travel. The County ~~shall~~ should promote walking, bicycle riding and use of public transit by requiring compact design, shared facilities between adjacent or nearby uses, and providing for interconnected walkways, bicycle ways, and parking, and bus stops as part of development approvals, where applicable.

Policy FLU 18.3

Bicycle Parking. The County ~~shall~~ should continue to utilize and enhance bicycle parking standards, including quantity and location of bike racks, to help reduce parking demand and encourage the use of alternative transportation modes.

Policy FLU 18.4

Brevard County shall protect its established and planned greenway network trail facilities by prohibiting ingress and egress crossings to those properties that have alternative access options. Driveway cuts into existing and planned trails shall be avoided whenever possible and only approved where no other option for the private property owner exists.

Working Waterfronts**Objective FLU 19**

~~To manage future growth and development in order to~~ To promote and preserve the recreational and commercial working waterfronts of Brevard County and to provide countywide, Brevard County may consider incentives and criteria to ensure the continued availability of publicly accessible recreational and commercial working waterfronts ~~countywide.~~

Policy FLU 19.1

Brevard County ~~shall provide land-use bonuses or~~ may consider incentives to encourage non-residential development that provides public access to the ~~shorelines and waters of Brevard County~~ provided that such incentives do not result in adverse impacts to the safety of Brevard County residents or diminish the effect of the County's environmental remediation programs. ~~These bonuses or incentives may be granted in the form of increased FAR of twenty percent, a twenty-five percent increase in number of slips, a twenty-five percent increase in area for other uses, or other measure as provided for in the Land Use Regulations. Mixed use developments that include a publically accessible water-dependent, water-related or water-enhanced residential component may be eligible for these incentives.~~

Policy FLU 19.2

Waterfront parcels may be designated for use as water-dependent, water-related as defined in Florida Statutes. Waterfront parcels may also be designated for water enhanced uses as defined in the Glossary. The underlying land-use and unique locational needs for water-dependent and water-related activities ~~shall~~ should be given development priority and be compatible with surrounding existing and programmed development at these sites. In order to ensure appropriate use of the County's waterfront, shoreline development shall be prioritized and based upon the following minimum criteria:

Criteria:**FUTURE LAND USE ELEMENT**

- A. ~~Priority shall be given to water-dependent and water-related land uses, which must be carried out only on, in or adjacent to water areas, may be considered for location along the Indian River lagoon system.~~ Priority should be given to preserving and/or expanding water-dependent and water-related land uses that must be located on or adjacent to water bodies such as the Indian River Lagoon system. Priority may also be given consistent with Coastal Management Element Policy 5.15 CM 5.14 and may also include the expansion of working waterfronts.
- B. Water-related land uses shall be considered only on the uplands adjacent to Class III waters of the Indian River lagoon system. Water-related uses are those which are not directly dependent upon access to a water body but which provide goods and services to uses which are water-dependent.
- C. For Industrial land uses, directives, policies, and criteria in the Coastal Management, Conservation, and Future Land Use elements of this Comprehensive Plan which address water-dependent and water-related shall be utilized in the location of industrial projects adjacent to water bodies utilizing criteria established in Policy ~~3.9~~ FLU 3.10.

Public Airport Land Use Compatibility

Objective FLU 20

Brevard County shall cooperate with the relevant airport authority responsible for the oversight of Merritt Island Airport to discourage incompatible encroachment of new land uses and facilitate the continued presence of the Merritt Island Airport.

Policy FLU 20.1

Brevard County shall transmit to the airport authority information relating to proposed changes to the Comprehensive Plan, plan amendments, and proposed changes to land development regulations which, if approved, would affect the density, intensity, or use of land within a one half mile radius of the airport property.

Policy FLU 20.2

The airport authority is encouraged to provide comments on the impact that such proposed changes may have upon the airport and whether the proposed changes are compatible with the safety, and noise standards as regulated by State and Federal agencies.

Policy FLU 20.3

Brevard County will take into consideration any comments provided by the airport authority or his or her designee when such a decision regarding comprehensive planning or land development regulation is being considered. Brevard County shall include a copy of any such comments to the ~~Florida Department of Community Affairs or its successor agency~~ state land planning agency.

FUTURE LAND USE ELEMENT

Implement Directives from Small Area Studies

Objective FLU 21

Brevard County may establish Citizen Resource Groups, appointive bodies, to evaluate a community's future development needs or desires. This group may be tasked with making recommendation(s) regarding future development trends, evaluating the character of the area, and/or conceptualizing a new vision for previously undeveloped parcels within a study area.

Policy FLU 21.1

Future Development Trends. The Board may create a specialized local plan called a Small Area Study (SAS) be initiated to support a community's desires to participate in its own vision of the future. The outcome of the SAS may culminate with an amendment of the Future Land Use Map, this Element, other Elements of the Comprehensive Plan, and/or update of county land development codes. At a minimum, these criteria address the following:

Criteria:

- A. Identify recent development trends in the area;
- B. Identify changes to the character of an area;
- C. Encourage development or preservation of residential densities in rural areas;
- D. Preservation of existing agricultural areas;
- E. Evaluate commercial expansion techniques for new development areas.

Port St. John Study Area

Policy FLU 21.2

Brevard County shall implement the recommendations of the Port St. John Small Area Study through the following directive:

1. Residential densities east of the Florida East Coast Railroad from Kings Highway to Camp Road will be implemented by the following densities: East of US-1 to the Indian River from Kings Highway to Camp Road, densities may be a maximum of 12 residential dwelling units per acre. This would include portions of Sections 18, 19, and 30, Township 23, Range 36 and a portion of Section 13, Township 23, Range 35, ~~as generally depicted on Map 9.~~ West of US-1 to the Florida East Coast railroad tracks from Kings Highway to Camp Road, densities may be 12 dwelling units per acre with a maximum cap of 8 residential dwelling units per acre. This would include portions of Sections 13, 18, 19, and 30, Township 23, Range 36 and portions of Sections 13 and 24, Township 23, Range 35, ~~as generally depicted on Map 9.~~

Canaveral Groves Study Area

Policy FLU 21.3

Brevard County shall implement the recommendations of the Canaveral Groves Small Area Study through the following directives:

FUTURE LAND USE ELEMENT

1. The maximum density to be considered for the Friday Acres subdivision, located in Section 14, Township 24, Range 35, shall be three dwelling units per acre (3 du/ac). ~~This area is depicted in Map 10.~~
2. The maximum density to be considered in a portion of the northeast quarter of Section 15, Township 24, Range 35 shall be five dwelling units per acre (5 du/ac). ~~This area is depicted in Map 10.~~
3. The maximum density to be considered in the northeastern portion of Section 13, Township 24, Range 35 shall be 6 dwelling units per acre where existing RU-1-9 is designated. ~~The area is depicted on Map 11.~~
4. All types of commercial uses shall be considered in the neighborhood/ community commercial district lying in the portion of Section 27, Township 24, Range 35 north of State Route 524. ~~This area is depicted on Map 11a.~~
5. The maximum density to be considered in the portion of Section 27, Township 24, Range 35 north of State Route 524 shall be eight dwelling units per acre (8 du/ac). ~~This area is depicted on Map 11b.~~

North Merritt Island Study Area

Policy FLU 21.4

Brevard County shall implement the recommendations of the North Merritt Island Small Area Study through the following directives.

1. In the area described as Orange Haven Unrecorded Lots in Section 23, Township 23, Range 36, the residential density designation shall be two (2) dwelling units per acre. ~~This area is depicted on Map 12.~~
2. In the area described as Parcel 17 and Kings Park Unit #3, Lots 9, 10, 11, 12 not to include the east 100 feet parallel to the west right of way of Eagle Way in Section 26, Township 23, Range 36, the residential density designation shall be four (4) dwelling units per acre. ~~This area is depicted on Map 13.~~

South Beaches Study Area

Policy FLU 21.5

~~Brevard County shall implement the recommendations of the South Beaches Small Area Plan Study through the following directives. The recommendations and directives of the South Beaches Study Area have been incorporated into the Brevard Barrier Island Area which has been designated an Area of Critical State Concern by the State of Florida. Please refer to the Brevard Barrier Island Area, Part XVI of the Comprehensive Plan.~~

- ~~1. The property described as Parcel 4, Sections 33 and 34, Township 28 South, Range 38 East shall be designated with a maximum density of six (6) dwelling units per acre. This area is depicted on Map 14.~~
- ~~2. The property described as Parcels 3, 5 and 6, Section 34, Township 28 South, Range 38 East shall be designated with a maximum density of six (6) dwelling units per acre. This area is depicted on Map 15.~~
- ~~3. The property described as Parcels 763 and 776, Sections 10 and 11, Township 29 South, Range 38 East shall be four (4) dwelling units per acre. This area is depicted on Map 16.~~

FUTURE LAND USE ELEMENT

4. ~~The property described as Parcel 3.1, Section 23, Township 29 South, Range 38 East shall be designated as four (4) dwelling units per acre. This area is depicted on Map 17.~~
5. ~~The property described as Lot 32, Block 7, New Melbourne Beach Subdivision Section 3, Township 29 South, Range 38 East shall be designated with a maximum density of six (6) dwelling units per acre. This area is depicted on Map 18.~~
6. ~~The properties described in the south 1260 feet of Section 17, Township 28 South, Range 38 East and the properties described as the north 1280 feet of Sections 20 and 21, Township 28 South, Range 38 East shall be limited to the maximum residential densities as depicted on Map 19. The maximum residential density within this directive is eight (8) dwelling units per acre.~~
7. ~~The properties described in Sections 20 and 21, Township 28 South, Range 38 East, starting 1280 feet from the north section(s) line and ending 3770 feet from the north section(s) line shall be limited to the maximum residential densities range from two (2) dwelling units per acre to eight (8) dwelling units per acre. The area is depicted on Map 20.~~

Central and South Merritt Island Study Area

Policy FLU 21.6

Brevard County shall implement the recommendations of the Central and South Merritt Island Small Area Study through the following directives:

1. ~~Within the area depicted on Map 21 (Sections 11, 12, 13, 24, and 25, of Township 25, Range 36 and the western portions of Sections 18, 19, and a portion of Section 30, Township 25, Range 37), the only residential zoning classifications that may be considered in shall be EU, SR, SEU, RR-1, REU, AU, PA, GU, AGR, RRMH-1, RRMH-2.5, RRMH-5, and TR-2. RP residential professional zoning may be considered on South Courtenay Parkway with a minimum lot size consistent with EU zoning and/or the aforementioned zonings. The maximum density within the described area shall be three (3) dwelling units per acre.~~

Residential Density Rightsizing Study Areas

Objective FLU 22

Brevard County ~~shall~~ should maintain maximum densities in the Residential Density Rightsizing Study Areas.

Avon by the Sea

Policy FLU 22.1

1. The property described as Winslow Reserve Subdivision #27, Lot 13, in Section 26, Township 24, Range 37 ~~shall~~ should have a maximum residential density of 30 dwelling units per acre. ~~This property is depicted on Map 5.~~

FUTURE LAND USE ELEMENT

2. The property described as Avon by the Sea Subdivision #CG, Block 101, Lots 12, 12.01, and 14 ~~shall~~ should have a maximum residential density of 30 dwelling units per acre. ~~This property is depicted on Map 5.~~
3. The property described as Avon by the Sea Subdivision #CG, Block 101, Lots 2, 3, 4, and 5 ~~shall~~ should have a maximum residential density of 30 dwelling units per acre. ~~This property is depicted on Map 5.~~

Merritt Island Area

Policy FLU 22.2

1. The property described as Moore and Catine Subdivision #52, Lot 13, Section 35, Township 24, Range 36 ~~shall~~ should have a maximum residential density of 30 dwelling units per acre. ~~This property is depicted on Map 6.~~

South Cocoa Beach Area

Policy FLU 22.3


1. The property described as Bruner's Resubdivision #25, Block A, Lot 6, Section 26, Township 25, Range 37 and the property described as Birchfield and Bruner's Addition #26, Block B, Lot 1, Section 26, Township 25, Range 37 ~~shall~~ should have a maximum residential density of 30 dwelling units per acre. ~~These properties are depicted on Map 7.~~

APPENDIX

LIST OF MAPS

Map	Name
1	Brevard County 2045 Future Land Use Map
2	Conservation Areas West Viera Area
3	Land Use Planning Areas Farmton Local Plan Boundary & Arterial Transportation Network
4	Viera New Town Overlay Historic Resources
5	Residential Density Rightsizing Study—Avon by the Sea Area Area of Critical State Concern Future Land Use Map (North)
6	Residential Density Rightsizing Study—Merritt Island Area Area of Critical State Concern Future Land Use Map (Central)
7	Residential Density Rightsizing Study—South Cocoa Beach Area Area of Critical State Concern Future Land Use Map (South)
8	Farmton Local Plan Boundary & Arterial Transportation Network
9	St. John Directives
10	Canaveral Groves Directives 1 and 2
11	Canaveral Groves Directive 3
11a and 11b	Canaveral Groves Directives 4 and 5
12	North Merritt Island Study Area Directive 1
13	North Merritt Island Study Area Directive 2
14 and 15	South Beaches Study Area Directives 1 and 2
16	South Beaches Study Area Directive 3
17	South Beaches Study Area Directive 4
18	South Beaches Study Area Directive 5
19 and 20	South Beaches Study Area Directives 6 and 7
21	Central and South Merritt Island Study Area Directive 1
22	Energy Conservation Areas


FUTURE LAND USE ELEMENT



2045 Future Land Use Map


0 5 10 20 Miles

Brevard County Information Technology Department, September 2024
Data Source: BOCC Planning & Development Department



FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025




Future Land Use Element
Conservation Areas



9/29/2017

FUTURE LAND USE ELEMENT


LPA Adoption June 16, 2025



April 7, 2010

FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025



Future Land Use Element
West Viera Area



11/7/2024

FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025

Comprehensive Plan

EAR Amendments 2017



Residential Density Rightsizing Study Map 5
Avon by the Sea
Area Directives



10/2/2017

FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025



**Residential Density Rightsizing Study Map 6
Merritt Island Area Directives**




FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025

Comprehensive Plan

EAR Amendments 2017



Residential Density Rightsizing Study Map 7
South Cocoa Beach Area Directives




10/2/2017

FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025



Map 8




Farmton Local Plan Boundary
& Arterial Transportation Network

December 2010


FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025



FUTURE LAND USE ELEMENT


LPA Adoption June 16, 2025



FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025


XI - 127



FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025

XI - 128




FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025

XI - 129

Comprehensive Plan

EAR Amendments 2017



August 6, 1992 (adoption)

April 25, 2006 (2005B.11)

10/3/2017

FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025

Comprehensive Plan

EAR Amendments 2017




FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025


Comprehensive Plan

EAR Amendments 2011




FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025




Comprehensive Plan

EAR Amendments 2017



FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025




FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025

Comprehensive Plan

EAR Amendments 2011




FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025

Comprehensive Plan

EAR Amendments 2017




FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025

Comprehensive Plan

EAR Amendments 2011




FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025

Comprehensive Plan

EAR Amendments 2017



South Beach Study Area

Map 18

Directive 5

February 17, 1993

April 25, 2006 2005B.11


Residential 6 Directive



10/6/2011

FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025




FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025

Comprehensive Plan

EAR Amendments 2017




FUTURE LAND USE ELEMENT

LPA Adoption June 16, 2025



Brevard County - Comprehensive Plan



Future Land Use Element - Energy Conservation Areas - 2025

June 2, 2010

FUTURE LAND USE ELEMENT


LPA Adoption June 16, 2025

LIST OF FIGURES

Figure	Name
---------------	-------------

- | | |
|---|--|
| 1 | Illustrative Examples of Commercial Infill vs. Extension of Strip Development |
| 2 | Comparative Depiction of Conventional vs. Clustering Land Development Techniques |


FIGURE 1
ILLUSTRATIVE EXAMPLES
OF
COMMERCIAL INFILL vs. EXTENSION OF STRIP DEVELOPMENT



FUTURE LAND USE ELEMENT

FIGURE 2
COMPARATIVE DEPICTION OF
CONVENTIONAL VS. CLUSTERING LAND DEVELOPMENT TECHNIQUES

(See Policy 14.2.E)




Example of a Parcel with a Conventional large Lot Subdivision

Residential Lot Yield	24
Non Residential Lot Yield	0
Open Space Preservation	0%

Example of the Same Parcel with a Clustered, Mixed Use Subdivision

Residential Lot Yield	28*
Non Residential Lot Yield	2
Open Space Preservation	50%

* assumes a theoretical density bonus for creation and clustering of smaller lots; integration of non-residential uses; connection of undisturbed linear open spaces.



FUTURE LAND USE ELEMENT

CHAPTER PART XII

INTERGOVERNMENTAL COORDINATION ELEMENT

TABLE OF CONTENTS

Comprehensive Plan Coordination..... 1

Development Approval Processes..... 6

Coordination of Essential Services 8

GOALS, OBJECTIVES, AND POLICIES

GOAL IC

Brevard County shall initiate and/or participate in intergovernmental coordination efforts necessary to establish governmental relationships which improve the coordination, effectiveness, and efficiency of public policy-making bodies within Brevard County.

Comprehensive Plan Coordination

Objective IC 1

Brevard County shall coordinate the Comprehensive Plan and its implementation with the State, the region, adjacent municipalities and counties, as well as with ~~the Brevard County School Board~~ Brevard Public Schools, and special districts.

Policy IC 1.1

Brevard County shall encourage the State, the region, adjacent municipalities and counties, ~~Brevard County School Board~~ Brevard Public Schools, and special districts to review their proposed public facility improvement plans and plan amendments with Brevard County for consistency with the policies and criteria of this Comprehensive Plan.

Criteria:

- A. Public facility and service needs within and affecting the County shall be identified and regularly updated.
- B. Identified public facility and service needs should be included in the Capital Improvements Program of Brevard County and encouraged to appear within the Capital Improvements Program of all Brevard County local governments.
- C. Facility needs shall be based on a projection of proposed development intensity.
- D. The appropriate County departments shall participate in the evaluations of potential development impacts.

Policy IC 1.2

Brevard County shall establish and maintain a repository of the comprehensive plans or other master plans of the State, region, and adjacent municipalities and counties, as well as those of ~~the Brevard County School Board~~ Brevard Public Schools and special districts.

Policy IC 1.3 (~~Coordinated Public School Facility Siting~~)

Brevard County shall encourage ~~the Brevard County School Board~~ Brevard Public Schools to mutually agree on, promote, and support high-quality community and neighborhood development by coordinating site searches, planning, and design of public

INTERGOVERNMENTAL COORDINATION ELEMENT

educational facilities as well as assuring the consistency of those facilities with the Comprehensive Plan and Land Development Regulations.

Criteria:

- A. The intergovernmental bikeway/pedestrian plan and schedule of improvements should be mutually maintained by ~~the School Board~~ the Space Coast Transportation Planning Organization (TPO), Brevard Public Schools, and Brevard County for new schools within Brevard County. The Plan should include identification of bicycle and pedestrian access deficiencies on school sites and within any designated access corridors within two (2) miles of school sites.
- B. In order to maximize the use of public facilities and resources, ~~the School Board~~ Brevard Public Schools and Brevard County should strive to coordinate development of properties adjoining school sites into libraries, parks, children's services, recreation, and other appropriate related facilities.

Policy IC 1.4

Brevard County shall implement all other policies of this comprehensive plan which address intergovernmental coordination.

Criteria:

- A. During reviews of the Comprehensive Plan ~~as set forth in the resolution adopted pursuant to 9J-5.004~~ and as a part of the Evaluation and Appraisal Reports required by Chapter 163, Florida Statutes, an assessment shall be made of the effectiveness of the Intergovernmental Coordination Element and any deficiencies in the element shall be identified.
- B. The applicable planning staff shall coordinate the review.

Policy IC 1.5

Brevard County shall pursue the use of interlocal agreements to identify and quantify the potential impacts of proposed public facility improvements upon historic resources and to ensure the protection of such resources if discovered during associated ground disturbing activities. At a minimum, the interlocal agreements should include provisions provided for in the Historic Preservation element policies as cited below.

Criteria:

- A. Policy HP 1.4 Local Register of Historic Places
- B. Policy HP 1.6 Provide information for Florida Master Site File and prepare nominations for National Register of Historic Places and Local Register of Historic Places
- C. Policy HP 2.11 Encourage ~~cities~~ municipalities to adopt Historic Preservation ordinances

INTERGOVERNMENTAL COORDINATION ELEMENT

- D. Policy HP 2.3 Review of public/private projects
- E. Policy HP 2.4 Discovery procedures
- F. Policy HP 3.1 Distribute information and materials
- G. Policy HP 3.2 Historic landmark program

Policy IC 1.6

Brevard County shall maintain active coordination and cooperation with all water service providers to the public, and continue to coordinate the provision of potable water with the St. Johns River Water Management District, the Brevard County Utility Services Department, the Cities of Titusville, Cocoa, Palm Bay, West Melbourne, and Melbourne, and the other water suppliers within the County.

Policy 1.7

~~Brevard County shall continue to participate in meetings of the Brevard County Planning Coordination Committee (PCC).~~

Criteria:

- ~~A. The Planning Coordination Committee should have authority to advise all local governments on planning issues.~~
- ~~B. Membership should be comprised of planning staff representatives of the County, each municipality, a School Board representative and other appropriate representatives as necessary.~~

Policy 1.8 IC 1.7

If necessary, Brevard County may use an informal mediation process involving the East Central Florida Regional Planning Council (ECFRPC) to assist in resolving conflicts between the County's Comprehensive Plan and the comprehensive plans of adjacent municipalities and counties.

Policy 1.9 IC 1.8

Brevard County shall cooperate with the ~~East Central Florida Regional Planning Council (ECFRPC)~~ during the preparation of any Regional Development Guides which identify potential urban and rural service areas, and conservation areas to be used as a basis for determining the expansion of regionally significant public facilities.

Policy 1.10 IC 1.9

Brevard County shall continue to coordinate with municipalities to establish and maintain interlocal agreements and joint planning areas for use in coordinating public service delivery and facility maintenance subsequent to municipal annexation procedures. Interlocal planning, annexation, and maintenance agreements should, at a minimum, address the topics set forth in the criteria below:

Criteria:

INTERGOVERNMENTAL COORDINATION ELEMENT

- A. Existing and future service areas for public services and facilities.
- B. Methodology for advance notification to the County by municipalities conducting annexation procedures and hearings pursuant to Chapter 171, Florida Statutes.
- C. Issues of land use compatibility and consistency with the Brevard County Comprehensive Plan.
- D. Public participation and notification of all affected land owners of the land to be annexed.
- E. Notification of affected adjoining properties in the unincorporated areas.
- F. Available level of services and facilities and identification of the provider of those services.

Policy ~~1.11~~ IC 1.10

Brevard County shall maintain a geographic information system (GIS) which will, among other operations, store, retrieve, and display data related to evaluating and managing land use and growth, and assist in implementation of the Comprehensive Plan.

Criteria:

- A. The geographic information system should be capable of reading data from the County's municipalities as well as special districts, and regional, state, and federal sources.
- B. Information and products generated by this system should be made available to both public and private sector entities consistent with available fiscal and time resources.

Policy ~~1.12~~ IC 1.11

Brevard County and its municipalities shall coordinate their level of service standards and projected sewer service areas for sewer facilities outside their jurisdiction to ensure that enough wastewater treatment plant capacity is available and to ensure that public sewer service is provided to Brevard's citizens in the most efficient manner.

Policy ~~1.13~~ IC 1.12

Brevard County ~~Board of County Commissioners~~ will continue to encourage annual meetings with ~~the Brevard County School Board or their designee~~ Brevard Public Schools to discuss concurrency of infrastructure to serve proposed schools. Pursuant to the requirements of applicable Florida Statutes, the general location of public educational facilities should be consistent with the Public School Facilities Element and other policies within the Comprehensive Plan of Brevard County.

INTERGOVERNMENTAL COORDINATION ELEMENT

Policy ~~1.14~~ IC 1.13

Brevard County shall take steps necessary to coordinate with ~~the Spaceport Florida Authority, Space Florida and the Economic Development Commission of Florida's Space Coast and the Space Coast Development Commission~~ on promotional efforts concerning those areas of the County uniquely suited for the development of space commerce and the National Space Policy.

Criteria:

- A. Support the implementation of previously completed and adopted economic plans.
- B. Continue to work with the City of Titusville, National Aeronautics and Space Administration, ~~Florida~~ Department of Commerce, ~~Department of Economic Opportunity, Florida~~ Department of Education, and other appropriate agencies.

Policy IC 1.14

Prior to the approval process, Brevard County will transmit proposed changes to the comprehensive plan, comprehensive plan amendments, and amendment to the land development regulations to Patrick Space Force Base and Cape Canaveral Space Force Station, providing such entities a reasonable time to provide feedback, particularly when the proposal would impact height limits, lighting restrictions, and/or noise attenuation.

Policy IC 1.15

Brevard County shall provide sewer services to those areas located in proximity to municipal sewer systems if requested and if capacity is available. The cost of providing these services shall be paid for by the property owners that are benefited unless grant funds are available.

Policy IC 1.16

Brevard County should coordinate with the City of Titusville for the provision of public sanitary sewer service from the north limits of the community of Port St. John to the south limits of the City of Titusville.

Policy IC 1.17

Brevard County shall invite all municipalities to participate in class I watershed studies. The criteria set forth within related Conservation Element policies shall provide some guidelines for the study and recommendations for action.

Policy IC 1.18

Brevard County, if requested and feasible, shall cooperate with appropriate federal, state, regional, and local governmental agencies in the aerial photography and topographic mapping of Brevard County.

Policy IC 1.19

Brevard County shall cooperate with the incorporated municipalities within its boundaries and adjacent counties in the development of any regional stormwater management planning efforts.

Development Approval Processes**Objective IC 2**

Brevard County shall strive for increased efficiency in development approval processes including the review of development proposals which impact adjacent municipalities, counties, the region, and the State.

Policy IC 2.1

Annually, with respect to each municipality, Brevard County should establish and maintain interlocal agreements for the purpose of refining the process of:

Criteria:

- A. Reviewing land development proposals pursuant to the following:
 - 1. Rezoning proposals within 660 feet of jurisdictional boundaries.
 - 2. The provision of public facilities and services which are provided by other governmental entities.
- B. Assessing the impact of land development proposals on traffic circulation with respect to:
 - 1. A method of notification of the affected local government regarding traffic impacts must be established providing sufficient time for the affected local government to respond.
 - 2. A method of "recording" or "tracking" projected trips on roadways for mutual use should be established.
 - 3. Resolving any discrepancies in the acceptable levels of service if having different levels of service causes intergovernmental problems.
- C. Standardization of all related land development regulations:
 - 1. Standard format, language, and criteria should be considered, however, modifications should be permitted to address unique local conditions.
 - 2. Workshops should be held between the County and municipalities for the purpose of identifying and resolving problematic inconsistencies.
 - 3. ~~Maintain the Planning Coordination Committee.~~
- D. Annexation and or contraction notification, review, and reporting:
 - 1. Joint planning and interlocal annexation agreements shall be encouraged for all annexation or contractions in order to support a smooth transition and enhanced development coordination.

INTERGOVERNMENTAL COORDINATION ELEMENT

2. Municipalities proposing a voluntary or involuntary annexation or contraction shall be encouraged to notify and coordinate a County review of the proposed annexation or contraction area prior to commencing annexation procedures. The County notification information should include:
 - a) A schedule of any municipal annexation or contraction public hearings including the subject municipality's schedule for amending its Comprehensive Plan.
 - b) The reporting prerequisites stated within Chapter 171.042, Florida Statutes, or, at a minimum, a copy of the municipality's staff annexation report to be considered during municipal public hearing including:
 - A metes and bounds legal description of the property(ies) to be annexed or contracted.
 - The subject property's proposed future land use, zoning designations, and, if possible, the intended use for the proposed annexation area.
 - The limits of post-annexation municipal maintenance of adjacent street right-of-way and drainage facilities.
3. Prior to the adoption of an interlocal enclave annexation agreement between the County and any municipality under F.S. 171.046 (2A), the municipality proposing the annexation should provide written notice to property owners within 500' of the proposed enclave to be annexed no later than 30 days prior to the first public hearing in which the municipality is to consider the enclave annexation interlocal agreement.

Policy IC 2.2

Brevard County shall coordinate with appropriate local governments and Florida Department of Environmental Protection in the maintaining of a Wetland Ordinance for uniform regulation of these valuable resources. Specific guidelines are set forth in the Conservation Element and described in the criteria below.

Criteria:

- A. Policy CON 5.1 Wetlands
- B. Policy CON 5.2 Wetlands
- C. Policy CON 5.4 Wetlands

Policy IC 2.3

Strive to improve the delivery of community services through adoption and implementation of effective records-management, information management, and evaluative procedures.

Criteria:

INTERGOVERNMENTAL COORDINATION ELEMENT

- A. Maintain records management processes utilizing the Geographic Information System (GIS) or other mechanism that can track resources and expenditures in the delivery of community services.
- B. Coordinate the ongoing maintenance of this system with other local governments and service providers in order to achieve a common data base for the delivery of community facilities and services within Brevard County.

Policy IC 2.4

Brevard County's legal relationship with the Port of Canaveral's Port Master Plan is governed by Chapter 163, Florida Statutes. Upon the Port Canaveral Authority's request, Brevard County shall review the Port Master Plan for consistency with the Coastal Management Element of the Brevard County Comprehensive Plan, pursuant to the County's procedure for reviewing plans of other jurisdictions, and ~~Chapter sections~~ 163.3177(6)(g) and 163.3178, F.S. Brevard County shall identify provisions of the Port Master Plan which it considers inconsistent with the Coastal Management Element or any other elements of the County Comprehensive Plan and a meeting shall be established to discuss and rectify the inconsistencies and other issues.

Policy IC 2.5

Brevard County shall coordinate with the municipalities and appropriate state agencies to maintain Evacuation Zone Management Plans as described in the Coastal High Hazard section of the Coastal Management Element as well as the recommendations found within the Brevard County Comprehensive Emergency Management Plan (CEMP).

Coordination of Essential Services

Objective IC 3

Brevard County, in cooperation with the appropriate federal, state, and local governmental agencies, shall achieve coordinated level of service standards for essential public facilities and services.

Policy 3.1

~~Brevard County may maintain a county-wide advisory committee to recommend acceptable levels of service for public facilities and services which are multi-jurisdictional and to advise the respective governing bodies.~~

Criteria:

- ~~A. The public facilities to be addressed should include potable water, sanitary sewer, solid waste, drainage, parks and transportation.~~
- ~~B. Committee members should include County and municipal staff members responsible for planning and coordinating the above public facilities.~~

INTERGOVERNMENTAL COORDINATION ELEMENT

Policy 3.2 IC 3.1

In order to ensure efficient, cost effective, and environmentally sound public facilities and services, Brevard County should initiate and maintain interlocal agreements with the municipalities and other service providers that provide public facilities and services in the unincorporated area, to formalize the designation of facility service areas and acceptable levels of service.

Policy 3.3 IC 3.2

Brevard County shall continue to coordinate with the Florida Department of Transportation for development of permitted connections to the State Highway System with level of service standards adopted by the County and ~~its Transportation Planning Organization (TPO)~~ the TPO.

Policy 3.4 IC 3.3

County-wide uniform level of service standards shall be utilized in the implementation of an impact fee program.

Policy 3.5 IC 3.4

Appropriate County planning staff shall assist the Sheriff's Department in the planning of their facilities and service delivery plans and fiscal programs by coordinating and providing requisite data and planning expertise.

Policy 3.6 IC 3.5

Brevard County shall utilize uniform standards in the provision and operation of community facilities within designated service areas and develop fiscal programs where feasible, for capital and operational needs.

Criteria:

- A. In order to promote greater efficiencies of service through adaptive reuse, joint-use agreements, and rehabilitation of existing structures. These measures may be utilized as an alternative to construction of new community facilities, where economically feasible and consistent with the Future Land Use Element.
- B. In order to eliminate needless duplication of community facilities and services and to promote communication and cooperation in governmental activities and programs within State state, regional, county, city municipal, and other governmental units.

Policy 3.7 IC 3.6

Brevard County shall coordinate with the ~~East Central Florida Regional Planning Council (ECFRPC)~~ regarding strategic and local planning efforts that are relevant to Brevard County. Additional coordination mechanisms shall be established or maintained as required by Florida Statutes.

INTERGOVERNMENTAL COORDINATION ELEMENT

Policy ~~3.8~~ IC 3.7

Brevard County shall continue coordination with ~~the Brevard County School District~~ Brevard Public Schools and municipalities through the Interlocal Agreement for Public School Facility Planning and School Concurrency that ensures the public school facilities level of service is maintained. Brevard County shall continue to be responsive to any legislative changes regarding school facility development and coordination with local governments and agencies.

Policy ~~3.9~~ IC 3.8

Brevard County shall reduce fire loss and personal injury through intergovernmentally coordinated fire prevention programs and early detection systems. Brevard County should support the volunteer fire department efforts by providing data and financial assistance consistent with defined needs and the services provided. Brevard County shall maintain and improve the Fire Insurance Rating for the unincorporated areas of the County, and coordinate with incorporated areas in order to achieve fire rating objectives.


Policy ~~3.10~~ IC 3.9

Brevard County should continue coordination with the ~~Space Coast Transportation Planning Organization (TPO)~~ TPO, Florida Department of Transportation, local governments, and local transportation agencies regarding current and future transportation infrastructure needs and level of service standards. Where appropriate, Brevard County, in cooperation with the ~~Space Coast~~ TPO, may facilitate consideration of alternative land use scenarios as a possible means of addressing transportation infrastructure demands.

LIST OF MAPS

Map	Title
------------	--------------

1.	Brevard County Cities
----	-----------------------



**Intergovernmental Coordination Element
Incorporated Areas within Brevard County**

CHAPTER PART XIII

CAPITAL IMPROVEMENTS ELEMENT

TABLE OF CONTENTS

Objective C1 1

Objective C2 5

Objective C3 6

Objective C4 7

Objective C5 8

Objective C6 11

GOALS, OBJECTIVES, AND POLICIES

GOAL CI

Brevard County shall develop and periodically update a Capital Improvements Plan to coordinate and implement public facility improvements which support the goals, objectives, and policies of the Brevard County Comprehensive Plan and encourage efficient utilization of its public facilities.

Objective CI 1

Where financially feasible, the Capital Improvements Plan shall provide for the construction, expansion, improvement, or replacement of public facilities identified in the various elements of the Comprehensive Plan in order to correct existing deficiencies and accommodate the needs of new growth on a continuing basis.

Policy CI 1.1

As a part of the Capital Improvements Plan (CIP) development process, Brevard County shall utilize the acceptable level of service (LOS) standards for transportation, potable water, sanitary sewer, solid waste, drainage, recreation and open space, and public schools as ~~adopted in other elements of the Comprehensive Plan and~~ shown below to evaluate the need for public facility improvements.

Criteria:

A. Transportation: Acceptable LOS Standards

Brevard County arterial and collector roadways within the urban area boundary: Level of Service E.

Brevard County arterial and collector roadways within the rural area, except as noted above: Level of Service D.

~~State arterial roadways (excluding Florida Intrastate Highway System), Highway System roadways~~ within the urban area boundary: Level of Service ~~E D~~.

~~State arterial roadways (excluding Florida Intrastate Highway System), Highway System roadways~~ outside the urban area boundary (rural area): Level of Service ~~D C~~.

B. Potable Water: Acceptable LOS Standards

POTABLE WATER

SERVICE AREA	LEVEL OF SERVICE STANDARD
BCUSD	200 220 250 gal/ERC/day
Barefoot Bay Water & Sewer District	150 gal/ERC/day
City of Cocoa	340 gal/ERC/day or 122 gal/capita/day
City of Melbourne	100 gal/capita/day
City of Palm Bay	225 gal/ERC/day
City of Titusville	96.4 gal/capita/day
City of West Melbourne	210 gal/ERC/day

CAPITAL IMPROVEMENTS ELEMENT

C. Sanitary Sewer: Acceptable LOS Standards

Brevard County shall provide adequate wastewater treatment plant capacity ~~to maintain the proportion of the permit plant capacity divided by the number of equivalent units as more than 200~~ of at least ~~220~~ 200 gallons per day per equivalent ~~unit~~ residential connection (ERC) countywide and 150 gallons per day per ERC for Barefoot Bay.

D. Solid Waste: Acceptable LOS Standards

1. Collection Twice per week solid waste collection service to residential improved properties
2. Disposal ~~8-32~~ 10.6 pounds/capita/day

E. Drainage: Acceptable LOS Standard

1. Retention and detention requirements shall, at a minimum, meet St. Johns River Water Management District (SJRWMD) Criteria.
2. Retention of the first inch of runoff.
3. Post-development rate of discharge shall not exceed pre-development rate of discharge for a 25 year 24 hour storm event.
4. Stormwater discharge facilities shall be designed so as to not lower receiving water quality or degrade the receiving water body below the minimum conditions necessary to assure the suitability of water for the designated use of its classification as established in Chapter 62-302, F.A.C.

F. Recreation/Open Space: Acceptable LOS Standard

~~3.0 acres of developed park~~ County-managed parks or recreation land per 1,000 people living in the unincorporated areas of each planning area.
Brevard County.

G. Public Schools: Acceptable LOS Standard

~~By December 1 of each year, Brevard County shall adopt as part of its Capital Improvement Element the School Board of Brevard County's Five Year Work Program. Brevard County hereby adopts by reference the School Board of Brevard County's Five Year Work Program for the planning period 2007-8 through 2011-12, the School District Program approved on September 23, 2008 as part of the School District budget, is adopted, including planned facilities and funding sources to ensure a financially feasible capital improvements program and to ensure the level of service standards will be achieved by the end of the five-year period.~~

Brevard County shall maintain the LOS standard for public schools based upon the Interlocal Agreement (ILA) for Public School Facility Planning and

School Concurrency, which established the LOS for Brevard Public Schools at 100% of Florida Inventory of School Houses (FISH) capacity. The LOS is calculated by dividing enrollment by factored FISH total capacity (permanent and relocatable student stations).

TIERED LEVEL OF SERVICE - SCHOOL YEAR 2007-08 to 2011-12					
Facility Type	2007-08	2008-09	2009-10	2010-11	2011-12
Elementary Schools	127%	130%	115%	105%	100%
Middle Schools	122%	120%	100%	100%	100%
Junior / Senior High Schools	133%	135%	110%	105%	100%
High Schools	139%	130%	115%	100%	100%

Policy CI 1.2

Brevard County may establish temporary level of service standards for potable water, sanitary sewer, solid waste disposal, stormwater management, and parks and recreation facilities based on the following criteria:

Criteria:

- A. The health, safety, and welfare of the public shall not be endangered.
- B. Inadequate funding, revenue initiative failures, unforeseen physical constraints affecting construction and its scheduling, and other similar obstacles which may exist or materialize which would prevent the immediate initiation of a service improvement.
- C. The service for which the temporary acceptable level of service is being established shall be given the highest priority pursuant to Objective CI 2.
- D. The temporary level of service for a specific facility or service shall relate to and realistically reflect the minimum timeframe necessary to establish a funding source and/or remove affecting obstacles and proceed with the appropriate improvements to achieve the desired levels of service objectives.
- E. All temporary levels of service shall be established by Comprehensive Plan Amendment.

Policy CI 1.3

As a part of the Capital Improvements Plan development process, Brevard County should utilize the following advisory level of service standards for public libraries, law enforcement, correctional facilities, fire protection, and emergency medical services, ~~and public education~~ shown below as planning guidelines to evaluate the need for public facility improvements.

- A. Public Libraries: 0.6 sq. ft. of library building space per capita;
2.16 volumes per capita;
1.5 titles per capita.

CAPITAL IMPROVEMENTS ELEMENT

- B. Law Enforcement: 2.0 deputies per 1,000 residents;
- C. Correctional Facilities: .003 inmate spaces per capita.
- D. Fire Protection:
1. 6 minute average response time county wide.
 2. 90% of Brevard County within 3 miles of a station.
 3. For 90% of all structural fires, deploy 1 engine company within 5 minutes, and 1 paramedic unit and 1 chief officer within 10 minutes.
 4. For response areas with 5 buildings 3 stories or 35 feet or more in height, or with a needed fire flow greater than 3,500 g.p.m., deploy a ladder company within 5 minutes for 90% of all alarms.
 5. Develop an attack force that can advance 2 standard fire stream hand lines.
 6. Major emergencies: deploy a programmed reserve and automatic aid fire force of 6 engine companies, 3 ladder companies and 3 chief officers within 15 minutes of third alarm.
 7. Petroleum storage and production area fires: deploy within 10 minutes special light water or foam fire fighting equipment and prepare long relays and extended pumping operations.
 8. Water deficient areas: deploy within 10 minutes a pumper-tanker and relay operation of adequate capacity to augment local supplies.
 9. Harbor areas: deploy within 5 minutes adequate marine fire fighting equipment of 500 g.p.m. for 90 percent of all marine oriented incidents.
 10. Light rescue emergencies: deploy 1 engine company within 5 minutes 90% of the time; deploy 1 paramedic unit within 5 minutes 80% of the time. Rescue all trapped persons.
 11. Heavy rescue emergencies: deploy 1 truck company, in addition to an engine and paramedic unit, within 10 minutes 90% of the time. Rescue all trapped persons.
 12. Manpower:

Unincorporated Population	No. Fire Fighters Per 1,000 Residents	% Supervisory Fire Fighters
100,000 - 249,999	1.89	20.4
250,000 - 499,999	1.84	25.5
500,000 +	1.81	21.7

- E. Emergency Medical
- Establish effective Advanced Life Support response within six minutes to 90% of the population.

Policy 1-5 CI 1.4

Brevard County shall include in its CIP all projects identified in its WSFWP Water Supply Facilities Work Plan to commence or continue within the 5-year horizon.

CAPITAL IMPROVEMENTS ELEMENT

Policy 1.6 CI 1.5

Brevard County shall include in its CIP all Water Resource Development, Water Supply Development, and Water Conservation Project Options identified in the SJRWMD RWSP Regional Water Supply Plan assigned to the County as an implementing entity within the 5-year horizon.

Policy CI 1.6

Brevard County shall adopt as part of its CIP the Brevard Public Schools Five-Year District Facilities Work Program.

Policy CI 1.7

Brevard County shall include within its CIP any projects necessary to achieve the pollutant load reductions attributable to the County as established in Basin Management Action Plans that include the County.

Objective CI 2

Brevard County shall establish funding priorities for capital improvements to correct existing public facility deficiencies, provide for facility renewal and replacement, and accommodate the needs of new growth on a continuing basis by implementing a Capital Improvements Plan that is consistent with the Schedule of Improvements in this Element.

Policy CI 2.1

Prioritization for roadway improvements should be based on acceptable level of service standards, improvements required by Development of Regional Impact development orders, and the adopted short-range transportation improvement program developed pursuant to Policies ~~2.1~~ TRA 2.1.1 and ~~2.2~~ TRA 2.1.2 of the Transportation Element.

Policy CI 2.2

Prioritization of potable water improvements should be based on a project's ability to achieve one or more policies found under Objectives 3 PW 4 and 4 PW 5 in the Potable Water Element.

Policy CI 2.3

Prioritization of sanitary sewer improvements should be based on a project's ability to achieve one or more policies found under Objectives SS 2 and SS 3 in the Sanitary Sewer Element.

Policy CI 2.4

Prioritization of drainage improvements should be based on the ~~Master Stormwater Management Plan~~ stormwater area studies developed pursuant to Policies SF 1.1 and SF 1.2 of the Surface Water Management Element.

Policy CI 2.5

Prioritization of recreational facilities should be based upon the project's ability to maintain acceptable levels of service; , ability to maintain the physical integrity and efficient operation of existing facilities; , ability to eliminate access problems for ~~handicapped disabled and special-needs~~ persons, and other applicable criteria.

Criteria:

- A. Acquisition and development of recreational facilities that are needed to eliminate acceptable level of service deficiencies should receive the highest funding priority.

CAPITAL IMPROVEMENTS ELEMENT

- B. Projects related to the maintenance and operation of existing facilities should receive the next highest priority, ~~however, no planning area should be allowed to fall into a deficient status.~~ This should include those projects which provide handicapped Americans with Disabilities Act-compliant and special-needs access to parks and recreational facilities.
- ~~C. Prioritization of improvements should be based on the acceptable level of service and maintenance and operation standards for each individual planning area, as identified in the Recreation and Open Space Element.~~

Policy CI 2.6

Prioritization of capital improvements for solid waste should be based on reduction of level of service deficiencies and enhancement of operational efficiency and environmental quality.

Criteria:

- A. Projects reducing level of service deficiencies or providing additional solid waste disposal capacity should receive the highest priority. Alternative methods of solid waste disposal should be encouraged.
- B. Projects that enhance operational efficiency or environmental quality should receive the next highest priority.

Policy CI 2.7

Those public services and facilities necessary to support industries that provide value-added employment in Brevard County should be given priority for construction.

Policy CI 2.8

Programs and studies necessary to implement policies within the various elements of the Comprehensive Plan shall be included in the Schedule of Improvements and Funding. These programs and studies shall be prioritized based on specified target dates for completion, the availability of revenue to fund these projects, environmental concerns, resiliency, and association with the protection of the public's health, safety, and welfare.

Policy CI 2.9

The Capital Improvements Plan and Annual Capital Budget should be consistent with this Element's Schedule of Improvements and with any element of the Comprehensive Plan which sets standards and policies for the provision of public facilities and programs, shall support the Future Land Use Element, and should be adopted as a part of the annual budgeting process.

Policy CI 2.10

Brevard County shall not extend public facilities and services to Suburban and Rural Density Areas for new development, unless there is an overriding public benefit which accrues to an area larger than the specific Suburban or Rural Density Area. However, the County will accept facilities through dedication, and provide services and facilities through MSBUs, MSTUs, and other means through which the recipients pay for the service or facility.

Objective CI 3

Limit future public expenditures for infrastructure and service facilities which serve to subsidize growth within the coastal high hazard area of Brevard County as described in the

Coastal Management Element and delineated on the Future Land Use Map Series.
Expenditures for public land acquisition or enhancement of natural resources shall be encouraged.

Policy 3.1

~~Brevard County shall designate coastal high hazard areas as defined in Chapter 163, Florida Statutes.~~

Policy 3.2 CI 3.1

Brevard County shall not support or finance new local transportation corridors which lie within the coastal high hazard zone or areas zoned as Environmental Area, except where there are no other cost-feasible alternatives.

Policy 3.3 CI 3.2

Brevard County should not locate sanitary sewer and water transmission lines within the coastal high hazard zone, except where there is no cost-feasible alternative and where practical due to engineering, safety, and cost considerations, or for septic to sewer conversion projects selected specifically to improve ground and surface water quality, and where necessary utilizing existing rights-of-way.

Policy 3.4 CI 3.3

If County utility lines are relocated for any purpose, they should be located outside of the coastal high hazard zone, except where there is no cost-feasible alternative.

Policy 3.5 CI 3.4

Public facilities, except for recreational facilities, shall not be located by Brevard County within of the coastal high hazard zone, except where there are no other cost-feasible alternatives.

Objective CI 4

Brevard County shall maintain adequate fiscal resources and policies to fund necessary public facility improvements, including transportation, potable water, sanitary sewer, surface water management, solid waste, parks and recreation, public libraries, law enforcement, correctional facilities, fire protection, and emergency medical services.

Policy CI 4.1

Brevard County should periodically review the fiscal requirements of needed transportation system improvements and adjust the local option gas tax as may be necessary.

Policy CI 4.2

When adequate funding is not available for a high priority project from existing sources of revenue and the consequences of delaying the project would adversely impact the economy, environment, or public health, safety, and welfare, Brevard County should consider enactment or extension of the infrastructure sales tax by referendum.

Policy CI 4.3

Brevard County should continue to seek funding from State and Federal sources and pursue interlocal agreements with private and public agencies to ensure sufficient money is available to provide necessary public facilities and services.

Policy CI 4.4

Brevard County should periodically readdress its budget and fiscal policies to ensure debt management practices such as limitations on the use of revenue bonds as a percentage of total debt, maximum ratio of total debt service to total revenue, and maximum ratio of outstanding capital indebtedness to property tax base are adequate and effective.

Policy CI 4.5

Brevard County should consider financing needed capital improvements with Municipal Service Benefit Units, Municipal Service Taxing Units, Community Development Districts, impact fees, and other forms of development exactions to ensure that new development pays a pro rata share of infrastructure development costs when it can be determined that these financing methods are not in conflict with Brevard County's economic development and affordable housing goals.

Objective CI 5

Brevard County may approve development orders consistent with the acceptable level of service standards adopted as part of this Comprehensive Plan for public facilities, including transportation, potable water, sanitary sewer, solid waste disposal, and surface water management, ~~and recreation and open space.~~

Policy CI 5.1

Brevard County shall continue to utilize a concurrency management system to review the impacts of all development proposals on existing public facilities to ensure that service levels are not degraded below acceptable level of service standards as adopted in this Comprehensive Plan.

Policy CI 5.2

Brevard County may approve rezoning applications, subdivision plats, site plans, and building permits if the potential impact of the proposed development does not decrease the level of service below acceptable standards for any existing public facility or a facility listed in this Element's Schedule of Improvements. If evaluation of the development application indicates a potential decrease in the level of service below the acceptable standards, approval of a development order may be granted based on the following conditions:

Criteria:

- A. For review of zoning applications, a preliminary concurrency evaluation shall be completed as part of the zoning review process to illustrate the relationship between the proposal and the availability of services and facilities for the Planning and Zoning Board and the Board of County Commissioners. All approvals of zoning applications shall be conditional and shall require a formal concurrency evaluation prior to site plan, subdivision plat, or building permit approval.
- B. Subdivision plats and site plans may be approved if the Schedule of Improvements in the Capital Improvements Element includes a facility improvement that will provide sufficient capacity to accommodate the potential impact of the proposed project based on acceptable level of

service standards. These approvals are subject to the following conditions:

1. All development orders pursuant to this criterion are conditional and shall not be considered vested; they will be revisited upon application for building permits in accordance with Criteria C and D below, to determine their impact upon established or programmed acceptable levels of service.
 2. If the impact evaluation indicated that the conditional development order will cause the level of service of a public facility to fall below the adopted standard, or if the development order will further increase an existing deficiency in the adopted levels of service, Brevard County will maintain the authority to modify the development order to achieve the acceptable levels of service.
- C. Building permits may be approved if the concurrency review determines that the following conditions are met:
1. Potable water supplies and facilities, sanitary sewer, solid waste, and drainage facilities with adequate capacity to accommodate the impacts of the development based on adopted level of service standards will be in place at the time the certificate of occupancy is issued; and
 - ~~2. Parks and recreation facilities with adequate capacity to accommodate the impacts of the development based on adopted level of service standards will be in place or are scheduled to be under actual construction in the Schedule of Recreation and Open Space Improvements in this Element not more than one year after the certificate of occupancy is issued; and~~
 - ~~3.~~ 2. Transportation facilities with adequate capacity to accommodate the impacts of the development based on adopted level of service standards will be in place or are scheduled to be under actual construction in the Schedule of Transportation Improvements in this Element not more than three years after the certificate of occupancy is issued or one of the following conditions is met:
 - a. At the time that a development order or permit is issued, the necessary transportation facilities or services are subject to a binding executed agreement which requires such facilities to be in place or under actual construction not more than three years after the certificate of occupancy is issued; or
 - b. At the time that a development order or permit is issued, the necessary transportation facilities or services are guaranteed in an enforceable development agreement, pursuant to Section 163.3220, Florida Statutes, or development order issued pursuant to Chapter 380, Florida Statutes, to be in place or under actual construction not more than three years

after the certificate of occupancy is issued; or

- c. For the purpose of issuing a development order or permit, a development may be deemed to have a de minimis impact and may not be subject to the concurrency requirements of all applicable State Statutes and Florida Administrative Codes if all of the following conditions are met:
 - i. The development proposal is for an increase in density or intensity of less than or equal to twice the density or intensity of the existing development, or for the development of a vacant parcel of land, at a residential density of less than four dwelling units per acre or, for nonresidential use, at an intensity of less than 0.1 floor area ratio. Isolated vacant lots in predominantly built residential subdivisions where construction of a single family house would be the most suitable use, may be developed for single family residential under the de minimis exception even if smaller than one quarter acre in size; and
 - ii. The transportation impact of the proposed development alone does not exceed 0.1 percent of the maximum service volume at the adopted level of service standard for the peak hour of the affected transportation facility; and
 - iii. The cumulative total transportation impact from the de minimis exceptions does not exceed three percent of the maximum service volume at the adopted level of service standard for the peak hour of the affected transportation facility if the facility does not meet the minimum level of service standard.

~~4.3.~~ A comprehensive plan amendment shall be required to eliminate, defer, or delay construction of any road or public transit facility or service which is needed to maintain the adopted level of service standard and which is listed in the Schedule of Transportation Improvements in this Element.

- D. Building permits may be approved if the developer agrees to construct all improvements necessary to accommodate the specific impacts of the proposed project concurrent with its development.

Policy CI 5.3

Brevard County may approve development orders if the proposed development is

phased to ensure that the necessary public facilities and services are available prior to the completion of the proposed development.

Policy CI 5.4

Brevard County shall coordinate with public and private agencies to identify public facility improvements made necessary by growth in the Viera Development of Regional Impact in order to ensure that needed improvements are incorporated into the Schedule of Improvements and that the developer continues to fund its fair share of the costs of needed infrastructure pursuant to the terms of the DRI Development Order.

Policy CI 5.5

Brevard County shall coordinate the provision of potable water from the Cities of Cocoa, Titusville, Palm Bay, West Melbourne, and Melbourne and any other applicable potable water provider, including the County itself, by requiring development applicants located in unincorporated areas of the County to provide written verification from the applicable potable water provider that the facility capacity and adequate water supply are currently available or will be available at the time of development. Prior to approval of a building permit or its functional equivalent, Brevard County shall consult with the applicable water supplier to determine whether adequate water supplies to serve the new development will be available no later than the anticipated date of issuance by Brevard County of a certificate of occupancy or its functional equivalent. No building or construction permit shall be issued unless the applicable potable water supplier has provided a written statement of committed capacity and water supply availability for the proposed development. Adequate water supplies and potable water facilities shall be in place and available to serve new development no later than issuance by Brevard County of a certificate of occupancy or its functional equivalent.

Objective CI 6

Brevard County shall review and update the Capital Improvements Element annually.

Policy CI 6.1

The annual review of the Capital Improvements Element shall include the following:

Criteria:

- A. Updated forecasts of gross taxable property value, estimated tax rates, revenues, operating expenditures, debt service requirements, reserves, and similar types of financial information; and
- B. Review of project status with updated estimates of project costs, revenue sources, and construction schedules; and
- C. Analysis of infrastructure capacity based on growth trends and acceptable level of service standards, including identification of pending facility deficiencies; and
- D. Review of planned capital improvements by State agencies, water management districts, and other local governments; and

- E. Identification and prioritization of needed facility improvements; and
- F. Recommendations regarding modifications and updates to the Schedule of Improvements.

Policy CI 6.2

The Capital Improvements Plan adopted each year shall be consistent with and serve to implement the Capital Improvements Element. At a minimum, the Capital Improvements Plan should contain those projects listed in the Schedule of Improvements that are scheduled to begin within a five year timeframe. The following information should be provided for each project contained in the Capital Improvements Plan:

Criteria:

- A. Estimated project cost.
- B. Projected funding source(s).
- C. Tentative construction start date.
- D. Project location.
- E. Description and justification for each project.

Policy CI 6.3

The Local Planning Agency shall review all proposed changes to the Capital Improvements Element and updates to the Schedule of Improvements developed pursuant to Policy CI 6.1 and make recommendations to the Board of County Commissioners.

Policy CI 6.4

As part of the annual review of the Capital Improvements Element and the preparation of the Capital Improvements Plan, Brevard County shall review all public facility and infrastructure proposals for their impact upon designated historic resources.

Criteria:

- A. The resources designated as being historically significant are those on the National Register of Historic Places, the Florida Master Site File, the Local Register of Historic Places, and those to be discovered in the future.
- B. If a determination is made that there will be a potentially negative impact to a historic resource, the County shall notify the Florida Division of Historic Resources and the County preservation agent.
- C. Every effort shall be taken to preserve the resource. Where preservation is not a feasible alternative, the resource shall be relocated, information regarding the resource shall be recorded, or elements of the resource shall be salvaged for further study.

Policy CI 6.5

If authorized by Brevard County through implementing amendments to a development of regional impact (DRI) Development Order, a multi-use DRI ~~meeting the criteria of Section 163.3180(12), Florida Statutes,~~ may use the standards and procedures set forth in ~~that statute section 163.3180(5), Florida Statutes,~~ to satisfy the County's transportation concurrency requirements and transportation mitigation requirements under Section 380.06, Florida Statutes, by payment of a proportionate share contribution. Any proportionate share contribution for a DRI pursuant to this policy shall be stated in the

DRI Development Order, as amended, and shall be subject to the conditions stated in the Development Order.

APPENDIX

LIST OF SCHEDULES

<u>Schedule</u>	<u>Title</u>
<u>1</u>	<u>Stormwater, BMAP and Dredging Improvements</u>
<u>2</u>	<u>Parks and Recreation Improvements</u>
<u>3</u>	<u>Potable Water and Sanitary Sewer Improvements</u>
<u>4</u>	<u>Solid Waste and Hazardous Materials Improvements</u>
<u>5</u>	<u>Transportation Improvements</u>
<u>6</u>	<u>Emergency Operations and Fire/Rescue Improvements</u>

Schedule of Stormwater, BMAP and Dredging Improvements

Merritt Island Redevelopment Agency

Program Name: MERRITT ISLAND REDEVELOPMENT AGENCY
Project Name: Mall Area Infrastructure Redevelopment
Project Total: \$1,097,000
Project Timeline: October 1st, 2021 through September 30th, 2027
Funded Program: 519602
District(s): 2

Project Description, Milestones and Service Impact

The purpose of this project is to catalyze a mixed-use commercial core sub-area, ideally creating a Merritt Island Town Centre. There will be several relevant components, including connectivity with Veterans Memorial Park, the phased implementation of a market-based plan, and land and storm water modifications. There is an opportunity for redeveloped properties to connect to the Lakes at Veterans Memorial Park. Additional changes may include relocating Fortenberry Road, and creating mixed-use property fronting on the Lakes at Veterans Memorial Park. Funds may also contribute to plans for a form-based code and planning/zoning overlay to facilitate high-quality redevelopment standards for the mall and surrounding areas. This project will require extensive intergovernment and private-sector collaboration.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Donations Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Incremental Tax Revenue	\$ -	\$ -	\$ -	\$ 1,000,000	\$ 97,000	\$ -	\$ -	\$ 1,097,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Donations Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ -	\$ 1,000,000	\$ 97,000	\$ -	\$ -	\$ 1,097,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 22,000	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ 222,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ 875,000	\$ -	\$ -	\$ 875,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 22,000	\$ -	\$ -	\$ 200,000	\$ 875,000	\$ -	\$ -	\$ 1,097,000

Merritt Island Redevelopment Agency

Program Name: MERRITT ISLAND REDEVELOPMENT AGENCY
Project Name: Fortenberry Stormwater Pipe Extension
Project Total: \$1,120,000
Project Timeline: October 1st, 2023 through September 30th, 2027
Funded Program: 6957216
District(s): 2

Project Description, Milestones and Service Impact

This project will study, engineer, permit, and phase construction of the extension of stormwater piping from properties in the Redevelopment area of Fortenberry Road, S. Plumosa St., Imperial St. Goodwin, S Courtenay Pkwy and properties South of SR 520 to the Lakes at Veterans Memorial Park Stormwater Treatment area.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Donations Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Incremental Tax Revenue	\$ 966,451	\$ 50,000	\$ 103,549	\$ -	\$ -	\$ -	\$ -	\$ 1,120,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 966,451	\$ 50,000	\$ 103,549	\$ -	\$ -	\$ -	\$ -	\$ 1,120,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ 150,000	\$ -	\$ -	\$ 150,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ 970,000	\$ -	\$ -	\$ 970,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ -	\$ -	\$ 1,120,000	\$ -	\$ -	\$ 1,120,000

Merritt Island Redevelopment Agency

Program Name: MERRITT ISLAND REDEVELOPMENT AGENCY
Project Name: S. Courtenay Pkwy Fortenberry to Cone Road Project
Project Total: \$2,003,500
Project Timeline: October 1st 2023 through September 30th 2026
Funded Program: 6931203
District(s): 2

Project Description, Milestones and Service Impact

MIRA is partnering with the County to eliminate traffic, flooding, drainage and blighted gateway issues on South Courtenay Parkway between Fortenberry Road and Cone Road. The development activity on South Courtenay Pkwy area are contributing to unsafe bottlenecking traffic conditions. The County and MIRA will enter into an interlocal agreement to fund and manage the project. The project will be funded primarily by MIRA and Impact Fees.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Donations Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Incremental Tax Revenue	\$ -	\$ -	\$ 900,000	\$ 1,000,000	\$ -	\$ -	\$ -	1,900,000
Sale of Surplus Equipment Revenue	\$ -	\$ 103,500	\$ -	\$ -	\$ -	\$ -	\$ -	103,500
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ -	\$ 103,500	\$ 900,000	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 2,003,500
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Construction Expense	\$ -	\$ 103,500	\$ 900,000	\$ 1,000,000	\$ -	\$ -	\$ -	2,003,500
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ -	\$ 103,500	\$ 900,000	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 2,003,500

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Ditch Outfall Denitrification D1
Project Total: \$2,967,269
Project Timeline: October 01, 2015 through September 30, 2029
Funded Program: 6300131
District(s): 1

Project Description, Milestones and Service Impact

This consists of the modeling, design and installation of denitrification bioreactors and other nutrient removal systems in Brevard County drainage ditches within District 1. Groundwater/stormwater treatment technologies intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. Fiscal Year 19-20 Remodeling/prioritization. Fiscal year 20 Top priority sites designated. Fiscal Year 21-29 Highest priority sites evaluated for feasibility, designed and constructed. Ongoing evaluation of all areas may result in realignment of project priorities. These channel/ditch denitrification bioreactors will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon in stormwater runoff. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 852,269	\$ 365,000	\$ 500,000	\$ 350,000	\$ 300,000	\$ 300,000	\$ 300,000	2,967,269
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 852,269	\$ 365,000	\$ 500,000	\$ 350,000	\$ 300,000	\$ 300,000	\$ 300,000	\$ 2,967,269
Land Expense	\$ 6,600	\$ 300,000	\$ 700,000	\$ 150,000	\$ -	\$ -	\$ -	1,156,600
Planning/Design Expense	\$ 177,954	\$ 40,000	\$ 100,000	\$ 100,000	\$ 75,000	\$ 60,000	\$ 15,000	567,954
Construction Expense	\$ -	\$ -	\$ 350,000	\$ -	\$ 300,000	\$ 300,000	\$ 292,715	1,242,715
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 184,554	\$ 340,000	\$ 1,150,000	\$ 250,000	\$ 375,000	\$ 360,000	\$ 307,715	\$ 2,967,269

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Ditch Outfall Denitrification D3
Project Total: \$1,514,394
Project Timeline: October 01, 2015 through September 30, 2029
Funded Program: 6300317
District(s): 3

Project Description, Milestones and Service Impact

This consists of the modeling, design and installation of denitrification bioreactors and other nutrient removal systems in Brevard County drainage ditches within District 3. Groundwater/stormwater treatment technologies intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. Fiscal Year 19-20 Remodeling/prioritization. Fiscal year 20 Top priority sites designated. Fiscal Year 21-29 Highest priority sites evaluated for feasibility, designed and constructed. Ongoing evaluation of all areas may result in realignment of project priorities. These channel/ditch denitrification bioreactors will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon in stormwater runoff. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 374,394	\$ 350,000	\$ 350,000	\$ 110,000	\$ 110,000	\$ 110,000	\$ 110,000	\$ 1,514,394
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 374,394	\$ 350,000	\$ 350,000	\$ 110,000	\$ 110,000	\$ 110,000	\$ 110,000	\$ 1,514,394
Land Expense	\$ -	\$ -	\$ 200,000	\$ 200,000	\$ -	\$ -	\$ -	\$ 400,000
Planning/Design Expense	\$ 26,428	\$ -	\$ 150,000	\$ 100,000	\$ 50,000	\$ 25,000	\$ 60,000	\$ 411,428
Construction Expense	\$ -	\$ -	\$ -	\$ 200,000	\$ 300,000	\$ -	\$ 202,966	\$ 702,966
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 26,428	\$ -	\$ 350,000	\$ 500,000	\$ 350,000	\$ 25,000	\$ 262,966	\$ 1,514,394

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Ditch Outfall Denitrification D4
Project Total: \$3,283,047
Project Timeline: October 01, 2015 through September 30, 2029
Funded Program: 6300417
District(s): 4

Project Description, Milestones and Service Impact

This consists of the modeling, design and installation of denitrification bioreactors and other nutrient removal systems in Brevard County drainage ditches within District 4. Groundwater/stormwater treatment technologies intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. Fiscal Year 19-20 Remodeling/prioritization. Fiscal year 20 Top priority sites designated. Fiscal Year 21-29 Highest priority sites evaluated for feasibility, designed and constructed. Ongoing evaluation of all areas may result in realignment of project priorities. These channel/ditch denitrification bioreactors will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon in stormwater runoff. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 1,205,047	\$ 388,000	\$ 650,000	\$ 265,000	\$ 275,000	\$ 250,000	\$ 250,000	\$ 3,283,047
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 1,205,047	\$ 388,000	\$ 650,000	\$ 265,000	\$ 275,000	\$ 250,000	\$ 250,000	\$ 3,283,047
Land Expense	\$ -	\$ -	\$ 350,000	\$ 200,000	\$ -	\$ 200,000	\$ -	\$ 750,000
Planning/Design Expense	\$ 157,852	\$ -	\$ 250,000	\$ 75,000	\$ 140,000	\$ 80,000	\$ 120,000	\$ 822,852
Construction Expense	\$ -	\$ -	\$ 600,000	\$ 470,000	\$ -	\$ 260,000	\$ 380,195	\$ 1,710,195
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 157,852	\$ -	\$ 1,200,000	\$ 745,000	\$ 140,000	\$ 540,000	\$ 500,195	\$ 3,283,047

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Ditch Outfall Denitrification D5
Project Total: \$828,490
Project Timeline: October 01, 2015 through September 30, 2029
Funded Program: 6300517
District(s): 5

Project Description, Milestones and Service Impact

This consists of the modeling, design and installation of denitrification bioreactors and other nutrient removal systems in Brevard County drainage ditches within District 5. Groundwater/stormwater treatment technologies intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. Fiscal Year 19-20 Remodeling/prioritization. Fiscal year 20 Top priority sites designated. Fiscal Year 21-29 Highest priority sites evaluated for feasibility, designed and constructed. Ongoing evaluation of all areas may result in realignment of project priorities. These channel/ditch denitrification bioreactors will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon in stormwater runoff. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 428,490	\$ 100,000	\$ 50,000	\$ 100,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 828,490
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 428,490	\$ 100,000	\$ 50,000	\$ 100,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 828,490
Land Expense	\$ 1,845	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 301,845
Planning/Design Expense	\$ 13,032	\$ 25,000	\$ 120,000	\$ 20,000	\$ 20,000	\$ 85,000	\$ 63,613	\$ 346,645
Construction Expense	\$ -	\$ -	\$ -	\$ 180,000	\$ -	\$ -	\$ -	\$ 180,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 14,877	\$ 25,000	\$ 420,000	\$ 200,000	\$ 20,000	\$ 85,000	\$ 63,613	\$ 828,490

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: STORMWATER PROJECTS-NORTH-B1398 SAND DOLLAR CANAL D5
Project Total: \$2,687,449
Project Timeline: October 01, 2021 through September 30, 2026
Funded Program: 6964513
District(s): 5

Project Description, Milestones and Service Impact

This includes modeling and design of a denitrification bioreactor and sediment removal system on County property near the Indian River Lagoon. It will use stormwater treatment technologies to intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. These nutrient removal systems will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. Surveying, planning, and design in Fiscal Years 23-24. Construction in Fiscal Year 25-26. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 663,152	\$ 301,797	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 964,949
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 1,500,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,500,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 198,024	\$ 24,476	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 222,500
Total Revenue	\$ 861,176	\$ 1,826,273	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,687,449
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 124,796	\$ 120,000	\$ 50,000	\$ 50,000	\$ -	\$ -	\$ -	\$ 344,796
Construction Expense	\$ 102	\$ 115,000	\$ 1,985,000	\$ 242,551	\$ -	\$ -	\$ -	\$ 2,342,653
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 124,898	\$ 235,000	\$ 2,035,000	\$ 292,551	\$ -	\$ -	\$ -	\$ 2,687,449

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: STORMWATER PROJECTS-BANANA-B998B HAMPTON HOMES D2
Project Total: \$738,817
Project Timeline: September 30, 2021 through September 30, 2025
Funded Program: 6964228
District(s): 2

Project Description, Milestones and Service Impact

This consists of the modeling, design, and installation of a sediment trap and denitrification bioreactor system in Brevard County right-of-way and easement. It addresses nutrient loading by using groundwater/stormwater treatment technologies to intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. These sediment trap and denitrification bioreactors will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 664,000	\$ -	\$ 7,382	\$ -	\$ -	\$ -	\$ -	\$ 671,382
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 63,618	\$ 3,817	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 67,435
Total Revenue	\$ 727,618	\$ 3,817	\$ 7,382	\$ -	\$ -	\$ -	\$ -	\$ 738,817
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 60,000	\$ 35,000	\$ -	\$ -	\$ -	\$ -	\$ 95,000
Construction Expense	\$ -	\$ -	\$ 643,817	\$ -	\$ -	\$ -	\$ -	\$ 643,817
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 60,000	\$ 678,817	\$ -	\$ -	\$ -	\$ -	\$ 738,817

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: STORMWATER PROJECTS-BANANA-BASIN 1280B FLAMINGO BIOREACTORS
Project Total: \$545,944
Project Timeline: October 01, 2021 through September 30, 2025
Funded Program: 6556401/517580
District(s): 4

Project Description, Milestones and Service Impact

This consists of the modeling, design and installation of a denitrification bioreactors along the side of a Brevard County road. It addresses nutrient loading by using groundwater/stormwater treatment technologies to intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. Fiscal Years 21-24 Project Design and Permitting. Fiscal Year 25 Construction. These denitrification bioreactors will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 200,000	\$ -	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 250,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 220,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 220,000
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 71,645	\$ 4,299	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 75,944
Total Revenue	\$ 271,645	\$ 224,299	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 545,944
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 71,399	\$ 30,000	\$ 20,000	\$ -	\$ -	\$ -	\$ -	\$ 121,399
Construction Expense	\$ -	\$ 50,000	\$ 374,545	\$ -	\$ -	\$ -	\$ -	\$ 424,545
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 71,399	\$ 80,000	\$ 394,545	\$ -	\$ -	\$ -	\$ -	\$ 545,944

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: STORMWATER PERFORMANCE RETROFITS
Project Total: \$500,000
Project Timeline: October 1, 2022 through September 30, 2026
Funded Program: 6556402
District(s): 4

Project Description, Milestones and Service Impact

These retrofits consist of the modeling, design and installation of various nutrient reduction performance enhancements including active control systems, phosphorus filters, and denitrification bioreactors in Brevard County stormwater ponds within District 4. Active controls allow more first flush runoff to be captured and treated and stormwater treatment technologies intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. Fiscal Years 23-24 Modeling, design, and permitting. Fiscal Years 25-26 construction. These stormwater pond retrofits will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon in stormwater runoff. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ 400,000	\$ 100,000	\$ -	\$ -	\$ -	\$ 500,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 400,000	\$ 100,000	\$ -	\$ -	\$ -	\$ 500,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 60,000	\$ 30,000	\$ -	\$ -	\$ -	\$ -	\$ 90,000
Construction Expense	\$ -	\$ -	\$ 310,000	\$ 100,000	\$ -	\$ -	\$ -	\$ 410,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 60,000	\$ 340,000	\$ 100,000	\$ -	\$ -	\$ -	\$ 500,000

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Titusville Causeway WADs
Project Total: \$4,265,520
Project Timeline: October 01, 2021 through September 30, 2025
Funded Program: 515945
District(s): 1

Project Description, Milestones and Service Impact

The project will rebuild and stabilize the southeast shoreline of the Titusville Causeway, the gateway to N.A.S.A./Kennedy Space Center and the Merritt Island National Wildlife Refuge, by constructing an innovative nearshore breakwater reef, living shoreline, planting seagrass, and seeding clams in the lee of the breakwater. Constructing near shore wave attenuation devices in coordination with erosion control and habitat restoration measures will increase water quality, recreational value, long-term stabilization, and resilience against wind-driven wave energy, and reduce erosion in this area of the Indian River Lagoon. Project Design Fiscal Years 21-23. Permitting and Construction Fiscal Years 23-25. This project reduces sediment and the amount of pollution entering the Indian River Lagoon from stormwater runoff and erosion. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure, and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ 64,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 64,000
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 93,983	\$ 3,576,097	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 3,670,080
Other Transfers Revenue	\$ 500,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 500,000
Sales Tax Revenue	\$ -	\$ 31,440	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 31,440
Total Revenue	\$ 593,983	\$ 3,671,537	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 4,265,520
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 259,328	\$ 90,000	\$ 100,085	\$ -	\$ -	\$ -	\$ -	\$ 449,413
Construction Expense	\$ -	\$ 860,000	\$ 2,956,107	\$ -	\$ -	\$ -	\$ -	\$ 3,816,107
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 259,328	\$ 950,000	\$ 3,056,192	\$ -	\$ -	\$ -	\$ -	\$ 4,265,520

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Fay Lake D1
Project Total: \$4,346,000
Project Timeline: October 01, 2015 through September 30, 2028
Funded Program: 6300115
District(s): 1

Project Description, Milestones and Service Impact

This project diverts a West Port St John outfall into a treatment system by Fay Lake. Project implementation was delayed to fund the Chain of Lakes Project and flood control projects in West Cocoa. Construction is divided into three phases with Phase 1 and 2 improving the quality of stormwater discharges into the St. Johns River. Phase 3 will decrease residential flooding. Fiscal Year 22 Phase 1 Permitting and design. Construction: Fiscal Year 23 Phase 1, Fiscal Year 23 Phase 2, and Fiscal Year 25 Phase 3. This water quality/flood control project protects homes, businesses and critical public infrastructure. Each completed flood project increases the level of protection provided in Brevard and reduces risk to people, infrastructure and habitat.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 965,000	\$ 700,000	\$ 2,081,000	\$ 200,000	\$ -	\$ -	\$ -	\$ 3,946,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 400,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 965,000	\$ 1,100,000	\$ 2,081,000	\$ 200,000	\$ -	\$ -	\$ -	\$ 4,346,000
Land Expense	\$ -	\$ 40,000	\$ 200,000	\$ 200,000	\$ -	\$ -	\$ -	\$ 440,000
Planning/Design Expense	\$ 52,450	\$ 25,000	\$ 500,000	\$ 350,000	\$ -	\$ -	\$ -	\$ 927,450
Construction Expense	\$ -	\$ 170,000	\$ -	\$ 1,000,000	\$ 800,000	\$ 1,008,550	\$ -	\$ 2,978,550
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 52,450	\$ 235,000	\$ 700,000	\$ 1,550,000	\$ 800,000	\$ 1,008,550	\$ -	\$ 4,346,000

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: North Merritt Island PUMP STATIONS FLOW METERS RETROFIT
Project Total: \$100,000
Project Timeline: October 01, 2021 through September 30, 2025
Funded Program: 6540209
District(s): 2

Project Description, Milestones and Service Impact

This consists of fitting the existing Pine Island and Hall Road pump stations with flow meters to track pumping rates to more efficiently operate the flood mitigation system. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ 20,000	\$ 80,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 20,000	\$ 80,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: PICA Stormwater Phase III Emergency Outfall Weir D2
Project Total: \$815,000
Project Timeline: October 01, 2018 through September 30, 2026
Funded Program: 6964216
District(s): 2

Project Description, Milestones and Service Impact

Phase 3 of Pine Island Conservation Area Stormwater Management System will include construction of additional improvements to the north impoundment area current system to improve functionality during major storm events. These may include the installation of an emergency outfall weir in the northwest corner to allow to improve discharge flow from the system, raising the eastern berm to allow additional pumping, modifying the intake area of the pumps, and raising the Ransom Road berm. Fiscal Years 24-25 Design and Permitting. Fiscal Year 26 Construction as permits allow. This increases flood protection for homes, businesses and critical public infrastructure. Each completed flood project increases the level of protection provided in Brevard and reduces risk to people, infrastructure and habitat. Delaying the project may continue to subject residences to recurring flooding.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 140,000	\$ -	\$ 55,000	\$ 620,000	\$ -	\$ -	\$ -	\$ 815,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 140,000	\$ -	\$ 55,000	\$ 620,000	\$ -	\$ -	\$ -	\$ 815,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 100,000	\$ 55,000	\$ -	\$ -	\$ -	\$ 155,000
Construction Expense	\$ -	\$ -	\$ -	\$ 660,000	\$ -	\$ -	\$ -	\$ 660,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 100,000	\$ 715,000	\$ -	\$ -	\$ -	\$ 815,000

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Micco Central D3
Project Total: \$2,675,000
Project Timeline: October 01, 2018 through September 30, 2026
Funded Program: 6551302
District(s): 3

Project Description, Milestones and Service Impact

Areas in Micco around Central Avenue have inadequate drainage and treatment which has resulted in flooding. This project consists of the construction of a stormwater pond to alleviate stormwater runoff issues. Denitrification and phosphorus binding systems reduce nutrients in stormwater discharging to the Indian River Lagoon. Fiscal Year 18-23 Voluntary acquisition. Fiscal Year 18-24 Survey, Design and Permitting. Fiscal Year 25-26 Construction as land acquisition proceeds. This increases flood protection for homes and critical public infrastructure. Each completed flood project increases the level of protection provided in Brevard and reduces risk to people, infrastructure, and habitat. Delaying the project may continue to subject the residents to recurring flooding.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 1,010,000	\$ 862,500	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,872,500
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 802,500	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 802,500
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 1,812,500	\$ 862,500	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,675,000
Land Expense	\$ 1,250	\$ 250,000	\$ 350,000	\$ -	\$ -	\$ -	\$ -	\$ 601,250
Planning/Design Expense	\$ 41,024	\$ 75,000	\$ 150,000	\$ 50,000	\$ -	\$ -	\$ -	\$ 316,024
Construction Expense	\$ 37,045	\$ -	\$ 1,100,000	\$ 620,681	\$ -	\$ -	\$ -	\$ 1,757,726
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 79,319	\$ 325,000	\$ 1,600,000	\$ 670,681	\$ -	\$ -	\$ -	\$ 2,675,000

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Breezeway D1
Project Total: \$395,000
Project Timeline: October 01, 2014 through September 30, 2026
Funded Program: 6957105
District(s): 1

Project Description, Milestones and Service Impact

Breezeway is an older development located between U.S. Highway 1 and the Florida East Coast Railroad north of S.R. 528. The area has an inadequate drainage system incapable of preventing flooding of roadways and private property. This project consists of upgrading the existing drainage system to reduce flooding by installing an exfiltration system. Fiscal Year 18-19 Survey completed. Fiscal Years 24-25 Redesign and permitting. Fiscal Year 26 construction completed. This increases flood protection for homes, businesses and critical public infrastructure. Each completed flood project increases the level of protection provided in Brevard and reduces risk to people, infrastructure and habitat. Delaying the project may continue to subject the residents to recurring flooding.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 300,000	\$ -	\$ 75,000	\$ 20,000	\$ -	\$ -	\$ -	\$ 395,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 300,000	\$ -	\$ 75,000	\$ 20,000	\$ -	\$ -	\$ -	\$ 395,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 15,000	\$ 10,000	\$ -	\$ -	\$ -	\$ 25,000
Construction Expense	\$ -	\$ -	\$ -	\$ 370,000	\$ -	\$ -	\$ -	\$ 370,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 15,000	\$ 380,000	\$ -	\$ -	\$ -	\$ 395,000

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Ruby St. - Stormwater Sediment and Treatment System D4
Project Total: \$2,067,036
Project Timeline: October 01, 2018 through September 30, 2026
Funded Program: 6957410
District(s): 4

Project Description, Milestones and Service Impact

Construct a wet pond with denitrification outfall to treat stormwater discharging to the Indian River Lagoon from a commercial & residential basin. Fiscal Year 18-24 Land acquisition and design. Fiscal Year 25-26 Construction. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 520,000	\$ -	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ 1,520,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 547,036	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 547,036
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 1,067,036	\$ -	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ 2,067,036
Land Expense	\$ 140,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 140,000
Planning/Design Expense	\$ -	\$ 75,000	\$ 30,000	\$ -	\$ -	\$ -	\$ -	\$ 105,000
Construction Expense	\$ 38,420	\$ -	\$ 783,616	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 1,822,036
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 178,420	\$ 75,000	\$ 813,616	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 2,067,036

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: NASA DRAINAGE IMPROVEMENT D 2
Project Total: \$2,405,981
Project Timeline: October 01, 2023 through September 30, 2025
Funded Program: 6550200
District(s): 2

Project Description, Milestones and Service Impact

This area of North Merritt Island located north of S.R. Road 528 has experienced significant flooding on multiple occasions. An analysis of potential flood reduction benefits found the most cost effective option is the installation of a permanent electrical hydraulic pump with diesel backup on Hall Road to decrease the duration of flooding. Fiscal Year 17 Planning and initial design. Fiscal Years 17-20 Land acquisition, design, & permitting. Fiscal Years 21-23 Construction. Fiscal Year 25 project closeout. This increases flood protection for homes, businesses and critical public infrastructure. Each completed flood project increases the level of protection provided in Brevard and reduces risk to people, infrastructure and habitat. Delaying the project may continue to subject residences to recurring flooding.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 2,077,733	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	2,077,733
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ 328,248	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	328,248
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 2,405,981	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	2,405,981
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 226,055	\$ -	\$ 50,000	\$ -	\$ -	\$ -	\$ -	276,055
Construction Expense	\$ 1,979,926	\$ -	\$ 150,000	\$ -	\$ -	\$ -	\$ -	2,129,926
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 2,205,981	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	2,405,981

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: W County Stormwater Improvements - D1
Project Total: \$3,100,000
Project Timeline: October 01, 2023 through September 30, 2028
Funded Program: 6964121
District(s): 1

Project Description, Milestones and Service Impact

This project consists of the modeling, design, and installation of a stormwater improvements and securing of drainage rights for the northern District 1 drainage systems west of US 1. The drainage improvements, easements, and land acquisition will reduce flooding and ensure county access to drainage systems leading to the St Johns River. Treatment systems to reduce nutrients to the local lakes and streams will also be included. Fiscal Years 25-26 Land acquisition, design, and permitting. Fiscal Years 26-28 Construction. This project reduces flooding, erosion, sediment, and the amount of pollution entering the local lakes and streams from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ 1,100,000	\$ 1,000,000	\$ 500,000	\$ 500,000	\$ -	3,100,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ -	\$ -	\$ 1,100,000	\$ 1,000,000	\$ 500,000	\$ 500,000	\$ -	3,100,000
Land Expense	\$ -	\$ -	\$ 350,000	\$ 150,000	\$ -	\$ -	\$ -	500,000
Planning/Design Expense	\$ -	\$ -	\$ 500,000	\$ 250,000	\$ 50,000	\$ 50,000	\$ -	850,000
Construction Expense	\$ -	\$ -	\$ -	\$ 850,000	\$ 450,000	\$ 450,000	\$ -	1,750,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ -	\$ -	\$ 850,000	\$ 1,250,000	\$ 500,000	\$ 500,000	\$ -	3,100,000

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: W. COCOA - STORMWATER DRAINAGE IMPROVEMENTS D 1
Project Total: \$8,648,891
Project Timeline: June 28, 2016 through September 30, 2026
Funded Program: 6964102
District(s): 1

Project Description, Milestones and Service Impact

This project consists of improving the drainage channel and upsizing culverts in West Cocoa as recommended in prior studies (including Adamson Rd). This project is a portion of a multiphase regional stormwater improvement plan. Fiscal Year 18-23 Purchase land and easements, complete design, and permitting and initiate construction. Fiscal Year 25 Complete construction. This increases flood protection for homes, businesses and critical public infrastructure. Each completed flood project increases the level of protection provided in Brevard and reduces risk to people, infrastructure and habitat. Delaying the project may continue to subject residences to recurring flooding.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 494,225	\$ 1,435,699	\$ 1,500,000	\$ 1,538,967	\$ -	\$ -	\$ -	4,968,891
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ 850,000	\$ 2,830,000	\$ -	\$ -	\$ -	\$ -	\$ -	3,680,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 1,344,225	\$ 4,265,699	\$ 1,500,000	\$ 1,538,967	\$ -	\$ -	\$ -	8,648,891
Land Expense	\$ 272,112	\$ 500,000	\$ 200,000	\$ -	\$ -	\$ -	\$ -	972,112
Planning/Design Expense	\$ 28,974	\$ 450,000	\$ 300,000	\$ 100,000	\$ -	\$ -	\$ -	878,974
Construction Expense	\$ 384	\$ 200,000	\$ 3,000,000	\$ 3,597,421	\$ -	\$ -	\$ -	6,797,805
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 301,470	\$ 1,150,000	\$ 3,500,000	\$ 3,697,421	\$ -	\$ -	\$ -	8,648,891

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: W Crisafulli Rd - Church Rd Drainage Improvements D2
Project Total: \$1,885,779
Project Timeline: October 01, 2016 through October 30, 2026
Funded Program: 6964204
District(s): 2

Project Description, Milestones and Service Impact

Project design includes diverting stormwater runoff from West Crisafulli Road to an existing outfall that discharges to the west into the Indian River Lagoon to relieve recurring flooding problems on the west side of North Courtenay Parkway. Fiscal Year 24 Easement acquisition. Fiscal Years 24-25 Phase 1 - Improve conveyance systems. Fiscal Year 26, Phase 2, Complete construction. This increases flood protection for homes, businesses and critical public infrastructure. Each completed flood project increases the level of protection provided in Brevard and reduces risk to people, infrastructure and habitat. Delaying the project may continue to subject residences to recurring flooding.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 642,854	\$ 29,925	\$ -	\$ 625,000	\$ -	\$ -	\$ -	1,297,779
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ 588,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	588,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 1,230,854	\$ 29,925	\$ -	\$ 625,000	\$ -	\$ -	\$ -	1,885,779
Land Expense	\$ -	\$ 100,000	\$ 200,000	\$ -	\$ -	\$ -	\$ -	300,000
Planning/Design Expense	\$ 134,676	\$ 60,000	\$ 150,000	\$ 50,000	\$ -	\$ -	\$ -	394,676
Construction Expense	\$ -	\$ -	\$ 600,000	\$ 591,103	\$ -	\$ -	\$ -	1,191,103
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 134,676	\$ 160,000	\$ 950,000	\$ 641,103	\$ -	\$ -	\$ -	1,885,779

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Mud Lake - West Cocoa D2
Project Total: \$2,666,259
Project Timeline: October 01, 2018 through September 30, 2026
Funded Program: 6964227
District(s): 2

Project Description, Milestones and Service Impact

This project improves control structures and creates a regional flood impoundment in West Cocoa. This project is a portion of a multiphase regional stormwater improvement plan. Fiscal Years 20-24 Design and permitting. Fiscal Years 22-25 Land acquisition. Fiscal Year 26 Complete construction. This increases flood protection for homes, businesses and critical public infrastructure. Each completed flood project increases the level of protection provided in Brevard and reduces risk to people, infrastructure and habitat. Delaying the project may continue to subject residences to recurring flooding.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 460,000	\$ 940,000	\$ 450,000	\$ 700,000	\$ -	\$ -	\$ -	2,550,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ -	\$ 116,259	\$ -	\$ -	\$ -	\$ -	\$ -	116,259
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 460,000	\$ 1,056,259	\$ 450,000	\$ 700,000	\$ -	\$ -	\$ -	2,666,259
Land Expense	\$ -	\$ 550,000	\$ 600,000	\$ -	\$ -	\$ -	\$ -	1,150,000
Planning/Design Expense	\$ 161,515	\$ 70,000	\$ 100,000	\$ 75,000	\$ -	\$ -	\$ -	406,515
Construction Expense	\$ -	\$ -	\$ 380,000	\$ 729,744	\$ -	\$ -	\$ -	1,109,744
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 161,515	\$ 620,000	\$ 1,080,000	\$ 804,744	\$ -	\$ -	\$ -	2,666,259

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: W. COCOA - STORMWATER DRAINAGE IMPROVEMENTS D 2
Project Total: \$1,840,000
Project Timeline: October 1, 2024 through September 30, 2026
Funded Program: 6964235
District(s): 2

Project Description, Milestones and Service Impact

This project consists of improving the drainage channel and upsizing culverts along Lake Drive in West Cocoa as recommended in prior studies. This project is a portion of a multiphase regional stormwater improvement plan. Fiscal Year 25 Purchase land and easements, complete design, and permitting and initiate construction. Fiscal Year 26 Complete construction. This increases flood protection for homes, businesses and critical public infrastructure. Each completed flood project increases the level of protection provided in Brevard and reduces risk to people, infrastructure and habitat. Delaying the project may continue to subject residences to recurring flooding.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ 680,000	\$ 125,000	\$ -	\$ -	\$ -	805,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ -	\$ 1,035,000	\$ -	\$ -	\$ -	\$ -	\$ -	1,035,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ -	\$ 1,035,000	\$ 680,000	\$ 125,000	\$ -	\$ -	\$ -	1,840,000
Land Expense	\$ -	\$ -	\$ 25,000	\$ -	\$ -	\$ -	\$ -	25,000
Planning/Design Expense	\$ -	\$ -	\$ 75,000	\$ 25,000	\$ -	\$ -	\$ -	100,000
Construction Expense	\$ -	\$ -	\$ 1,000,000	\$ 715,000	\$ -	\$ -	\$ -	1,715,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ -	\$ -	\$ 1,100,000	\$ 740,000	\$ -	\$ -	\$ -	1,840,000

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Hoover and Ocean Park Stormwater Improvements D5
Project Total: \$930,000
Project Timeline: October 01, 2018 through September 30, 2026
Funded Program: 6964503
District(s): 5

Project Description, Milestones and Service Impact

This project will reduce nutrients in stormwater discharging to the Indian River Lagoon through removal of runoff sediment and debris. Fiscal Year 21-24 Survey, design and permitting. Fiscal Years 25-26 Construction. This project reduces sediment and the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 220,000	\$ 400,000	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 670,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 260,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 260,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 220,000	\$ 660,000	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 930,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 9,926	\$ 100,000	\$ 70,000	\$ -	\$ -	\$ -	\$ -	\$ 179,926
Construction Expense	\$ -	\$ -	\$ 700,074	\$ 50,000	\$ -	\$ -	\$ -	\$ 750,074
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 9,926	\$ 100,000	\$ 770,074	\$ 50,000	\$ -	\$ -	\$ -	\$ 930,000

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Ditch Outfall Denitrification D2
Project Total: \$1,029,843
Project Timeline: October 01, 2015 through September 30, 2029
Funded Program: 6300240 (519361)
District(s): 2

Project Description, Milestones and Service Impact

This consists of the modeling, design and installation of denitrification bioreactors and other nutrient removal systems in Brevard County drainage ditches within District 2. Groundwater/stormwater treatment technologies intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. Fiscal Year 19-20 Remodeling/prioritization. Fiscal year 20 Top priority sites designated. Fiscal Year 21-29 Highest priority sites evaluated for feasibility, designed and constructed. Ongoing evaluation of all areas may result in realignment of project priorities. These channel/ditch denitrification bioreactors will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon in stormwater runoff. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 194,843	\$ 100,000	\$ 25,000	\$ 50,000	\$ 220,000	\$ 220,000	\$ 220,000	\$ 1,029,843
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 194,843	\$ 100,000	\$ 25,000	\$ 50,000	\$ 220,000	\$ 220,000	\$ 220,000	\$ 1,029,843
Land Expense	\$ 15,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 15,000
Planning/Design Expense	\$ 162,479	\$ -	\$ -	\$ 65,000	\$ 32,364	\$ 100,000	\$ 30,000	\$ 389,843
Construction Expense	\$ 50,000	\$ -	\$ -	\$ -	\$ 190,000	\$ -	\$ 385,000	\$ 625,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 227,479	\$ -	\$ -	\$ 65,000	\$ 222,364	\$ 100,000	\$ 415,000	\$ 1,029,843

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: STORMWATER PROJECTS-NORTH-SCOTTSMOOR I - Phase II D1
Project Total: \$100,000
Project Timeline: October 01, 2024 through September 30, 2025
Funded Program: 6964123
District(s): 1

Project Description, Milestones and Service Impact

Phase I constructed denitrification bioreactor will provide water quality treatment for a 525-acre drainage basin currently discharging untreated stormwater to the Indian River Lagoon. The project is located in North Brevard on Aurlantia Road, east of U.S. Highway 1. A denitrification chamber system was installed on Florida Inland Navigation District property to assist in meeting nutrient load reductions. Phase I was completed in FY 23. Phase II, an upgrade to the flow diversion system will be installed to assist in meeting nutrient load reductions. Fiscal Year 25 design and permitting. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 30,000	\$ -	\$ -	\$ -	\$ -	\$ 30,000
Construction Expense	\$ -	\$ -	\$ 70,000	\$ -	\$ -	\$ -	\$ -	\$ 70,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: STORMWATER PROJECTS-NORTH-SCOTTSMOOR C - Phase II D1
Project Total: \$300,000
Project Timeline: October 01, 2024 through September 30, 2025
Funded Program: 6937102
District(s): 1

Project Description, Milestones and Service Impact

Phase I constructed denitrification bioreactor will provide water quality treatment for a 525-acre drainage basin currently discharging untreated stormwater to the Indian River Lagoon. The project is located in North Brevard on Aurlantia Road, east of U.S. Highway 1. A denitrification chamber system was installed on Florida Inland Navigation District property to assist in meeting nutrient load reductions. Phase I was completed in FY 23. Phase II is a revision of the phosphorus binding system due to issues with neighboring properties necessitating a redesign and reconstruction of a portion of the project. Fiscal Year 25 design and permitting. Fiscal Year 25 Construction. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 300,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 300,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 50,000
Construction Expense	\$ -	\$ -	\$ 250,000	\$ -	\$ -	\$ -	\$ -	\$ 250,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 300,000

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: Harvester Facility Building
Project Total: \$480,197
Project Timeline: October 01, 2023 through September 30, 2025
Funded Program: 6501109
District(s): countywide

Project Description, Milestones and Service Impact

This consists of constructing a facility to house additional aquatic vegetation harvesting equipment and office space for harvesting employees. This facility will assist with maintenance and security of the equipment and provide the associated staff with dedicated work spaces. This will allow the staff to more efficiently maintain and operate the harvesting equipment and respond to harvesting needs and requests. Aquatic vegetation harvesting removes nutrients from County stormwater systems in a cost effective manner and will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon by reducing the amount of pollution entering the Indian River Lagoon in stormwater runoff. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 20,000	\$ 160,197	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 480,197
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 20,000	\$ 160,197	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 480,197
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 30,000	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 80,000
Construction Expense	\$ -	\$ 80,000	\$ 320,197	\$ -	\$ -	\$ -	\$ -	\$ 400,197
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 110,000	\$ 370,197	\$ -	\$ -	\$ -	\$ -	\$ 480,197

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: STORMWATER PROJECTS-NORTH- E Main Mlms Nutrient Removal D1
Project Total: \$780,000
Project Timeline: October 01, 2020 through September 30, 2026
Funded Program: 6937101
District(s): 1

Project Description, Milestones and Service Impact

This includes modeling and design of a denitrification bioreactor and sediment removal system on County property near the Indian River Lagoon. It will use groundwater/ stormwater treatment technologies to intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. These nutrient removal systems will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. Surveying, planning, and design in FY 24-25. Construction in FY 25. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 192,800	\$ 100,000	\$ 87,200	\$ -	\$ -	\$ -	\$ -	\$ 380,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ 400,000	\$ -	\$ -	\$ -	\$ 400,000
Total Revenue	\$ 192,800	\$ 100,000	\$ 87,200	\$ 400,000	\$ -	\$ -	\$ -	\$ 780,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 130,000	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 180,000
Construction Expense	\$ -	\$ -	\$ 200,000	\$ 400,000	\$ -	\$ -	\$ -	\$ 600,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 130,000	\$ 250,000	\$ 400,000	\$ -	\$ -	\$ -	\$ 780,000

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: BASIN 958 - PIONEER ROAD DITCH OUTFALL D2
Project Total: \$983,517
Project Timeline: April 01, 2021 through September 30, 2026
Funded Program: 6964229/517290
District(s): 2

Project Description, Milestones and Service Impact

Pioneer Basin Project is to treat stormwater and groundwater base flow conveyed to the Indian River Lagoon. This project will incorporate innovative technologies into traditional BMP treatments to reduce the nutrient loading. Beginning with investigation of treatment opportunities, we will proceed with design, permitting, bidding, and construction. Milestones: Fiscal Years 20-24 Project Design and Permitting. Fiscal Year 25 Construction. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 50,000	\$ -	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ 150,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 100,000	\$ -	\$ 645,000	\$ -	\$ -	\$ -	\$ -	\$ 745,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ 78,780	\$ 9,737	\$ -	\$ -	\$ -	\$ -	\$ 88,517
Total Revenue	\$ 150,000	\$ 78,780	\$ 654,737	\$ 100,000	\$ -	\$ -	\$ -	\$ 983,517
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 73,663	\$ 12,000	\$ 60,000	\$ 28,117	\$ -	\$ -	\$ -	\$ 173,780
Construction Expense	\$ -	\$ -	\$ 100,000	\$ 709,737	\$ -	\$ -	\$ -	\$ 809,737
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 73,663	\$ 12,000	\$ 160,000	\$ 737,854	\$ -	\$ -	\$ -	\$ 983,517

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: STORMWATER PROJECTS-BANANA-BASIN 1304B W ARLINGTON BIOREACTOR
Project Total: \$345,498
Project Timeline: October 01, 2021 through September 30, 2026
Funded Program: 6964407/517426
District(s): 4

Project Description, Milestones and Service Impact

This consists of the modeling, design and installation of a denitrification bioreactor in retention pond at a Brevard County cul-de-sac. It addresses nutrient loading by using groundwater/stormwater treatment technologies to intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. Fiscal Years 20-24 Project Design and Permitting. Fiscal Years 24-25 Construction. This denitrification bioreactor and dry retention system will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 100,000	\$ -	\$ 25,000	\$ -	\$ -	\$ -	\$ -	\$ 125,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ 119,512	\$ -	\$ -	\$ -	\$ 119,512
Sales Tax Revenue	\$ -	\$ 100,986	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 100,986
Total Revenue	\$ 100,000	\$ 100,986	\$ 25,000	\$ 119,512	\$ -	\$ -	\$ -	\$ 345,498
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 50,299	\$ 25,000	\$ 15,638	\$ -	\$ -	\$ -	\$ -	\$ 90,937
Construction Expense	\$ -	\$ 20,000	\$ 115,049	\$ 119,512	\$ -	\$ -	\$ -	\$ 254,561
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 50,299	\$ 45,000	\$ 130,687	\$ 119,512	\$ -	\$ -	\$ -	\$ 345,498

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: BASIN 2258 DITCH OUTFALL DENITRIFICATION D5
Project Total: \$361,113
Project Timeline: October 01, 2019 through September 30, 2025
Funded Program: 6964512/516649
District(s): 5

Project Description, Milestones and Service Impact

This consists of the modeling, design and installation of a denitrification bioreactor in a Brevard County drainage ditch to address nutrient loading by using groundwater/ stormwater treatment technologies to intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. This will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. Land Acquisition, planning, and design in Fiscal Years 19-24. Construction in Fiscal Year 25. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 34,335	\$ 50,000	\$ 119,612	\$ -	\$ -	\$ -	\$ -	\$ 203,947
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 89,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 89,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 50,203	\$ 17,963	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 68,166
Total Revenue	\$ 173,538	\$ 67,963	\$ 119,612	\$ -	\$ -	\$ -	\$ -	\$ 361,113
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 150	\$ 63,000	\$ 30,000	\$ -	\$ -	\$ -	\$ -	\$ 93,150
Construction Expense	\$ -	\$ -	\$ 267,963	\$ -	\$ -	\$ -	\$ -	\$ 267,963
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 150	\$ 63,000	\$ 297,963	\$ -	\$ -	\$ -	\$ -	\$ 361,113

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: STORMWATER PROJECTS-BANANA-B1124 ELLIOT DRIVE CANAL D2
Project Total: \$461,886
Project Timeline: September 30, 2021 through September 30, 2026
Funded Program: 6964230
District(s): 2

Project Description, Milestones and Service Impact

This consists of the modeling, design, and installation of a denitrification bioreactor system in Brevard County right-of-way and easement. It addresses nutrient loading by using groundwater/stormwater treatment technologies to intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. These sediment trap and denitrification bioreactors will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 146,900	\$ -	\$ 79,000	\$ -	\$ -	\$ -	\$ -	\$ 225,900
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 79,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 79,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 148,100	\$ 8,886	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 156,986
Total Revenue	\$ 374,000	\$ 8,886	\$ 79,000	\$ -	\$ -	\$ -	\$ -	\$ 461,886
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 30,000	\$ 49,000	\$ -	\$ -	\$ -	\$ -	\$ 79,000
Construction Expense	\$ -	\$ -	\$ 350,000	\$ 32,886	\$ -	\$ -	\$ -	\$ 382,886
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 30,000	\$ 399,000	\$ 32,886	\$ -	\$ -	\$ -	\$ 461,886

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: STORMWATER PROJECTS-BANANA-B1066-ANGEL AVE D2
Project Total: \$1,275,565
Project Timeline: September 30, 2021 through September 30, 2026
Funded Program: 6964231
District(s): 2

Project Description, Milestones and Service Impact

This consists of the modeling, design, and installation of a wet pond and/or denitrification bioreactor system on Brevard County property. It addresses nutrient loading by using stormwater treatment technologies to intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. The wet pond and denitrification bioreactor will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 210,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 210,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 343,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 343,000
Unfunded	\$ -	\$ -	\$ -	\$ 440,000	\$ -	\$ -	\$ -	\$ 440,000
Sales Tax Revenue	\$ 232,200	\$ 50,365	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 282,565
Total Revenue	\$ 785,200	\$ 50,365	\$ -	\$ 440,000	\$ -	\$ -	\$ -	\$ 1,275,565
Land Expense	\$ 146,433	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 146,433
Planning/Design Expense	\$ -	\$ 100,000	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Construction Expense	\$ -	\$ -	\$ 489,132	\$ 440,000	\$ -	\$ -	\$ -	\$ 929,132
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 146,433	\$ 100,000	\$ 589,132	\$ 440,000	\$ -	\$ -	\$ -	\$ 1,275,565

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: STORMWATER PROJECTS-BANANA-B998 RICHLAND AVE CANAL D2
Project Total: \$1,641,629
Project Timeline: September 30, 2021 through September 30, 2028
Funded Program: 6964232
District(s): 2

Project Description, Milestones and Service Impact

This consists of the replacement of a failing headwall (phase 1) and the modeling, design, and installation of a sediment trap and denitrification bioreactor system in Brevard County right-of-way and easement (phase 2). Phase 1: Fiscal Years 24-25 Design and Permitting, Fiscal Years 25-26 Construction. Phase 2: Fiscal Years 26-27 Design and Permitting, Fiscal Years 27-28 Construction. It addresses nutrient loading by using groundwater/stormwater treatment technologies to intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. These sediment trap and denitrification bioreactors will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 20,000	\$ -	\$ 489,000	\$ 450,000	\$ 460,000	\$ -	\$ -	\$ 1,419,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 84,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 84,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ 138,629	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 138,629
Total Revenue	\$ 104,000	\$ 138,629	\$ 489,000	\$ 450,000	\$ 460,000	\$ -	\$ -	\$ 1,641,629
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 84,000	\$ 70,000	\$ 60,000	\$ 50,000	\$ 10,000	\$ -	\$ 274,000
Construction Expense	\$ -	\$ -	\$ 409,782	\$ 460,000	\$ 200,000	\$ 297,847	\$ -	\$ 1,367,629
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 84,000	\$ 479,782	\$ 520,000	\$ 250,000	\$ 307,847	\$ -	\$ 1,641,629

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: HUNTINGTON POND DENITRIFICATION RETROFIT D1
Project Total: \$599,977
Project Timeline: October 01, 2017 through September 30, 2025
Funded Program: 6964104/517426
District(s): 1

Project Description, Milestones and Service Impact

This consists of the design and installation of a denitrification bioreactor at the outfall of an existing stormwater pond. It addresses nutrient loading by using groundwater/ stormwater treatment technologies to intercept nutrient-laden waters prior to discharge in the Indian River Lagoon. The denitrification bioreactor will assist the county in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. Milestones: Fiscal Year 21-24 Project Redesign. Fiscal Years 24-25 Construction. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 97,373	\$ 236,000	\$ -	\$ -	\$ -	\$ -	\$ -	333,373
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ 139,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	139,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Sales Tax Revenue	\$ 104,720	\$ 22,884	\$ -	\$ -	\$ -	\$ -	\$ -	127,604
Total Revenue	\$ 341,093	\$ 258,884	\$ -	\$ -	\$ -	\$ -	\$ -	599,977
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 13,751	\$ 60,000	\$ 60,000	\$ -	\$ -	\$ -	\$ -	133,751
Construction Expense	\$ -	\$ -	\$ 466,226	\$ -	\$ -	\$ -	\$ -	466,226
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 13,751	\$ 60,000	\$ 526,226	\$ -	\$ -	\$ -	\$ -	599,977

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: FLOUNDER CREEK POND D1
Project Total: \$423,046
Project Timeline: October 01, 2017 through September 30, 2025
Funded Program: 6964105
District(s): 1

Project Description, Milestones and Service Impact

This consists of the design and installation of a denitrification bioreactor at the outfall of an existing stormwater pond. It addresses nutrient loading by using groundwater/ stormwater treatment technologies to intercept nutrient-laden waters prior to discharge in the Indian River Lagoon. This will assist the county in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. Milestones: Fiscal Years 23-24 Project Design. Fiscal Years 23-24 Construction. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ 35,152	\$ -	\$ -	\$ -	\$ -	\$ -	35,152
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ 152,000	\$ -	\$ 157,500	\$ -	\$ -	\$ -	\$ -	309,500
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Sales Tax Revenue	\$ 75,328	\$ 3,066	\$ -	\$ -	\$ -	\$ -	\$ -	78,394
Total Revenue	\$ 227,328	\$ 38,218	\$ 157,500	\$ -	\$ -	\$ -	\$ -	423,046
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 29,980	\$ 15,000	\$ 25,000	\$ -	\$ -	\$ -	\$ -	69,980
Construction Expense	\$ -	\$ 50,000	\$ 303,066	\$ -	\$ -	\$ -	\$ -	353,066
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 29,980	\$ 65,000	\$ 328,066	\$ -	\$ -	\$ -	\$ -	423,046

Natural Resources Management Department

Program Name: STORMWATER UTILITY
Project Name: KINGSMILL AURORA PHASE II
Project Total: \$3,524,249
Project Timeline: May 18, 2017 through September 30, 2026
Funded Program: 6964404/517426
District(s): 4

Project Description, Milestones and Service Impact

This project consists of the modeling, design, and installation of a stormwater pond in the upper end of the Eau Gallie drainage system. The pond addresses nutrient loading by using stormwater technologies to intercept nutrient-laden waters prior to discharge into the Indian River Lagoon and assists the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. Fiscal Year 18-19 Land acquisition. Fiscal Year 19-22 Design. Fiscal Year Permitting 24. Fiscal Years 25-26 Construction. This project reduces sediment in the Eau Gallie River and the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 1,544,615	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 1,844,615
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 1,200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,200,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 367,488	\$ 112,146	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 479,634
Total Revenue	\$ 1,912,103	\$ 1,312,146	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 3,524,249
Land Expense	\$ 842,358	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 842,358
Planning/Design Expense	\$ 64,745	\$ 95,000	\$ 60,000	\$ -	\$ -	\$ -	\$ -	\$ 219,745
Construction Expense	\$ -	\$ 50,000	\$ 1,200,000	\$ 1,212,146	\$ -	\$ -	\$ -	\$ 2,462,146
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 907,103	\$ 145,000	\$ 1,260,000	\$ 1,212,146	\$ -	\$ -	\$ -	\$ 3,524,249

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: BANANA STORMWATER PROJECTS
Project Total: \$25,906,058
Project Timeline: October 01, 2020 through September 30, 2028
Funded Program: 516636
District(s): 2

Project Description, Milestones and Service Impact

This consists of the modeling, design and installation of denitrification bioreactors in 68 Brevard County drainage ditches. It addresses nutrient loading by using groundwater/stormwater treatment technologies to intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. These channel/ditch denitrification bioreactors will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ 9,052,053	\$ 6,213,063	\$ 5,514,375	\$ 5,126,567	\$ -	\$ -	\$ 25,906,058
Total Revenue	\$ -	\$ 9,052,053	\$ 6,213,063	\$ 5,514,375	\$ 5,126,567	\$ -	\$ -	\$ 25,906,058
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Construction Expense	\$ -	\$ -	\$ 8,852,053	\$ 6,213,063	\$ 5,514,375	\$ 5,126,567	\$ -	\$ 25,706,058
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 200,000	\$ 8,852,053	\$ 6,213,063	\$ 5,514,375	\$ 5,126,567	\$ -	\$ 25,906,058

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: NORTH STORMWATER PROJECTS
Project Total: \$42,723,316
Project Timeline: October 01, 2020 through September 30, 2028
Funded Program: 516647
District(s): 3

Project Description, Milestones and Service Impact

This consists of the modeling, design and installation of denitrification bioreactors in 96 Brevard County drainage ditches. It addresses nutrient loading by using groundwater/stormwater treatment technologies to intercept nutrient-laden waters prior to discharge into the Indian River Lagoon. This will assist the County in meeting nutrient load reductions mandated by the state for the Indian River Lagoon. This project reduces the amount of pollution entering the Indian River Lagoon from stormwater runoff. Each completed project increases the level of protection provided in Brevard County and reduces risk to people, infrastructure and habitat. The project aids in satisfying the Federal Clean Water Act.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ 14,747,917	\$ 10,273,903	\$ 8,981,350	\$ 8,720,146	\$ -	\$ -	\$ 42,723,316
Total Revenue	\$ -	\$ 14,747,917	\$ 10,273,903	\$ 8,981,350	\$ 8,720,146	\$ -	\$ -	\$ 42,723,316
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Construction Expense	\$ -	\$ -	\$ 14,547,917	\$ 10,273,903	\$ 8,981,350	\$ 8,720,146	\$ -	\$ 42,523,316
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 200,000	\$ 14,547,917	\$ 10,273,903	\$ 8,981,350	\$ 8,720,146	\$ -	\$ 42,723,316

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: South Brevard Water Reclamation Facility
Project Total: \$1,752,210
Project Timeline: October 1 2023 through September 20 2025
Funded Program: 6520305
District(s): 3

Project Description, Milestones and Service Impact

This project includes the engineering design and construction for the tertiary treatment component of the new South Brevard Water Reclamation Facility, replacing the existing Barefoot Bay Water Reclamation Facility. The new facility is planned to have an increased system capacity enabling additional sewer connections, including septic-to-sewer connections, and have reduced effluent nutrient concentrations providing additional water quality benefits. Shared ARPA Project with Utility

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ 1,752,210	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,752,210
Total Revenue	\$ -	\$ 1,752,210	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,752,210
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 1,752,210	\$ -	\$ -	\$ -	\$ -	\$ 1,752,210
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 1,752,210	\$ -	\$ -	\$ -	\$ -	\$ 1,752,210

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Indialantic Drainage Study
Project Total: \$1,529,337
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 6957511
District(s): 5

Project Description, Milestones and Service Impact

The drainage study is completed and recommendations of maintenance and capital improvement projects were determined based on the drainage study. Due to limited funding, the projects will be phased. Phase I will consist of engineering and permitting of the areas recommended based on the drainage study. This project is funded by the American Rescue Plan Act (ARPA) for Tranche 1 \$625,000 and Constitutional Gas Taxes \$904,337. Public Works staff is working with Natural Resources Management Department (NRMD) to combine the funds to complete this project utilizing ARPA Tranche II \$1.5M funds allocated to NRMD. The service impact for this project will enhance and improve the stormwater system in capture and conveyance capacity.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ -	\$ 458,474	\$ 445,863	\$ -	\$ -	\$ -	\$ -	\$ 904,337
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 625,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 625,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 625,000	\$ 458,474	\$ 445,863	\$ -	\$ -	\$ -	\$ -	\$ 1,529,337
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ 400,000	\$ 1,129,337	\$ -	\$ -	\$ -	\$ -	\$ 1,529,337
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 400,000	\$ 1,129,337	\$ -	\$ -	\$ -	\$ -	\$ 1,529,337

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Oak Park at Suntree Drainage Improvements
Project Total: \$1,411,000
Project Timeline: April 20, 2021 through February 28, 2026
Funded Program: 6957412
District(s): 4

Project Description, Milestones and Service Impact

This project is to assess and improve the drainage and water quality where it seems that the wetlands are staging up. Final engineering includes approximately 1400 LF of new storm infrastructure, environmental mitigation, and easement acquisitions. The service impact for this project will enhance and improve the stormwater system in capture and conveyance capacity.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 950,000	\$ 461,000	\$ -	\$ -	\$ -	\$ -	\$ 1,411,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 950,000	\$ 461,000	\$ -	\$ -	\$ -	\$ -	\$ 1,411,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 366,057	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 366,057
Construction Expense	\$ -	\$ -	\$ 1,044,943	\$ -	\$ -	\$ -	\$ -	\$ 1,044,943
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 366,057	\$ 1,044,943	\$ -	\$ -	\$ -	\$ -	\$ 1,411,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Evans Road at Hibiscus Drainage Improvements
Project Total: \$1,690,390
Project Timeline: January 1, 2022 through September 30, 2025
Funded Program: 6957510
District(s): 5

Project Description, Milestones and Service Impact

This project is to assess and improve drainage and water quality. It consists of replacing approximately 100 LF of existing double barrel metal pipe with a box culvert at the Evans Road M-1 Canal crossing approximately 150 feet south of Hibiscus Blvd. Also includes sidewalk improvements. The service impact for this project will enhance and improve the stormwater system in capture and conveyance capacity.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 300,000
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 1,390,390	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,390,390
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 1,390,390	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 1,690,390
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ 881,429	\$ 808,961	\$ -	\$ -	\$ -	\$ -	\$ 1,690,390
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 881,429	\$ 808,961	\$ -	\$ -	\$ -	\$ -	\$ 1,690,390

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Hield Road Stormwater Improvements
Project Total: \$296,800
Project Timeline: July 2023 through September 30, 2025
Funded Program: 6964514
District(s): 5

Project Description, Milestones and Service Impact

This is a drainage water quality project: the project goal is to evaluate the drainage in this area and determine if the Hield Road runoff can be directed to the MTDD Canal through an improved roadside swale system by way of Powell/Mintod Road. The service impact for this project will enhance and improve the stormwater system in capture and conveyance capacity.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ 296,800	\$ -	\$ -	\$ -	\$ -	\$ 296,800
Total Revenue	\$ -	\$ -	\$ 296,800	\$ -	\$ -	\$ -	\$ -	\$ 296,800
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 296,800	\$ -	\$ -	\$ -	\$ -	\$ 296,800
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 296,800	\$ -	\$ -	\$ -	\$ -	\$ 296,800

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Stormwater Telemetry
Project Total: \$750,000
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 6964426
District(s): Countywide

Project Description, Milestones and Service Impact

Remote rain, wind, and staff gauge telemetry stations for countywide use for hurricane emergency management of stormwater systems.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 750,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 750,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 750,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 750,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 750,000	\$ -	\$ -	\$ -	\$ -	\$ 750,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 750,000	\$ -	\$ -	\$ -	\$ -	\$ 750,000

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: Muck Removal - North - Grand Canal Muck Dredging
Project Total: \$46,719,316
Project Timeline: September 14, 2014 through July 9, 2027
Funded Program: 514982/ 517601/ IO517705
District(s): 4

Project Description, Milestones and Service Impact

The continuation of restoration efforts initiated through the State Legislature and continuing forward through the Save Our Indian River Lagoon Program. Project is targeting the removal of extensive amounts of organic muck deposits created by decades of runoff, erosion and nutrient loading. This project will remove about 600,000 cubic yards of muck sediment from the Indian River Lagoon within the Grand Canal system. This will remove up to 384 tons of nitrogen and 82 tons of total phosphorus contained within the muck deposits. Fiscal Year 16-17 Permitting completed. Fiscal Year 18-19 Project bid. Construction for multiple years through 28. Dredging activities stopped during manatee season from Dec 1 - March 15 each year.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 13,877,929	\$ 9,321,777	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 23,199,706
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 18,020,368	\$ 5,499,242	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 23,519,610
Total Revenue	\$ 31,898,297	\$ 14,821,019	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 46,719,316
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 1,849,835	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,849,835
Construction Expense	\$ 18,572,798	\$ 7,468,200	\$ 8,089,108	\$ 7,048,053	\$ 3,691,322	\$ -	\$ -	\$ 44,869,481
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 20,422,633	\$ 7,468,200	\$ 8,089,108	\$ 7,048,053	\$ 3,691,322	\$ -	\$ -	\$ 46,719,316

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: Muck Removal - North - Eau Gallie Muck Dredging
Project Total: \$19,489,607
Project Timeline: June 12, 2017 through September 30, 2026
Funded Program: 514983 / 517601
District(s): 4

Project Description, Milestones and Service Impact

Project is targeting the removal of extensive amounts of organic muck deposits created by decades of runoff, erosion and nutrient loading. This project will remove 488,057 cubic yards of muck sediment from the Indian River Lagoon system adjacent to the Eau Gallie River area. This will reduce nutrient fluxes to the lagoon from substances contained within the muck deposits by up to 7,972 pounds of nitrogen/year and 1,482 pounds of phosphorus/year. Fiscal Year 16-17 Permitting Initiated under legislative funding. Fiscal Year 23-24 will begin multi-year construction.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 9,284	\$ 7,510,244	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 7,519,528
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 10,020,487	\$ 1,949,592	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 11,970,079
Total Revenue	\$ 10,029,771	\$ 9,459,836	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 19,489,607
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 255,598	\$ 360,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 615,598
Construction Expense	\$ -	\$ 2,000,000	\$ 10,525,560	\$ 6,286,000	\$ -	\$ -	\$ -	\$ 18,811,560
Other Expense	\$ 62,449	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 62,449
Total Expense	\$ 318,047	\$ 2,360,000	\$ 10,525,560	\$ 6,286,000	\$ -	\$ -	\$ -	\$ 19,489,607

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: Muck Removal - Banana - Sykes Creek Muck Dredging
Project Total: \$33,176,990
Project Timeline: August 18, 2014 through September 30, 2027
Funded Program: 514984/ 517601/ IO517704
District(s): 2

Project Description, Milestones and Service Impact

The continuation of restoration efforts initiated through the State Legislature and continuing forward through the Save Our Indian River Lagoon Program. Project is targeting the removal of extensive amounts of organic muck deposits created by decades of runoff, erosion and nutrient loading. This project will remove about 661,000 cubic yards of muck sediment from the Indian River Lagoon within the Sykes Creek system. This will remove up to 384 tons of nitrogen and 82 tons of total phosphorus contained within the muck deposits. Fiscal Year 16-17 Permitting completed. Fiscal Year 17-18 Request for Proposals conducted and all proposals were rejected. Fiscal Year 19-20 Project bid. Fiscal Year 20-21 low bid withdrew. FY 22-23 (August 2022) construction started on Phase 1. Phase 1 was completed in June 2023. Construction for Phase 2 should begin FY 2025 and will continue for several years.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 6,530,164	\$ 5,824,002	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 12,354,166
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 15,954,132	\$ 4,866,692	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 20,820,824
Total Revenue	\$ 22,484,296	\$ 10,690,694	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 33,176,990
Land Expense	\$ 1,037,788	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,037,788
Planning/Design Expense	\$ 1,355,196	\$ 280,157	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,635,353
Construction Expense	\$ 8,373,315	\$ -	\$ 9,093,396	\$ 7,000,000	\$ 6,000,000	\$ -	\$ -	\$ 30,466,711
Other Expense	\$ 37,130	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 37,130
Total Expense	\$ 10,803,437	\$ 280,157	\$ 9,093,396	\$ 7,000,000	\$ 6,000,000	\$ -	\$ -	\$ 33,176,990

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: Muck Removal - Banana - Merritt Island Canals Muck Dredging
Project Total: \$18,674,260
Project Timeline: May 18, 2018 through September 30, 2028
Funded Program: 515493
District(s): 2

Project Description, Milestones and Service Impact

The removal of accumulated muck from 30 canals on central Merritt Island with cost share from District 2 maintenance dredging funds, Ad Valorem \$512,719. This project will remove approximately 200,000 cubic yards of muck, 80 tons of nitrogen, and 16 tons of phosphorus. Fiscal Year 18-19 Permitting initiated. Fiscal Year 19-20 permits issued. Multi-year construction expected to begin Fiscal Year 28-29.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ 512,719	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 512,719
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ 4,732,556	\$ 3,000,961	\$ -	\$ 7,733,517
Sales Tax Revenue	\$ 7,733,517	\$ 2,694,507	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 10,428,024
Total Revenue	\$ 8,246,236	\$ 2,694,507	\$ -	\$ -	\$ 4,732,556	\$ 3,000,961	\$ -	\$ 18,674,260
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 512,719	\$ -	\$ 250,000	\$ -	\$ -	\$ -	\$ -	\$ 762,719
Construction Expense	\$ -	\$ -	\$ 2,444,507	\$ 3,000,961	\$ 7,733,517	\$ 4,732,556	\$ -	\$ 17,911,541
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 512,719	\$ -	\$ 2,694,507	\$ 3,000,961	\$ 7,733,517	\$ 4,732,556	\$ -	\$ 18,674,260

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: Muck Removal - North - Titusville East Muck Dredging
Project Total: \$5,506,238
Project Timeline: August 30, 2014 through September 30, 2026
Funded Program: 515494
District(s): 1

Project Description, Milestones and Service Impact

Restoration efforts through the Save Our Indian River Lagoon Program. Project is targeting the removal of extensive amounts of organic muck deposits created by decades of runoff, erosion and nutrient loading. This project will remove 115,000 cubic yards of muck sediment from the North Indian River Lagoon within the Titusville area. This will remove up to 409 tons of nitrogen and 87 tons of total phosphorus contained within the muck deposits. Fiscal Year 24-25 Engineering and Permitting. Fiscal Year 26 Bidding. Fiscal Year 27 Begin multi-year dredging project.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 1,382,827	\$ 2,279,641	\$ 1,843,770	\$ -	\$ -	\$ -	\$ -	\$ 5,506,238
Total Revenue	\$ 1,382,827	\$ 2,279,641	\$ 1,843,770	\$ -	\$ -	\$ -	\$ -	\$ 5,506,238
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 268,499	\$ 300,000	\$ 500,000	\$ -	\$ -	\$ -	\$ -	\$ 1,068,499
Construction Expense	\$ -	\$ -	\$ 2,437,739	\$ 2,000,000	\$ -	\$ -	\$ -	\$ 4,437,739
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 268,499	\$ 300,000	\$ 2,937,739	\$ 2,000,000	\$ -	\$ -	\$ -	\$ 5,506,238

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: MUCK REMOVAL-NORTH-NASA EAST MUCK DREDGING
Project Total: \$13,645,890
Project Timeline: September 04, 2018 through September 30, 2026
Funded Program: 515980
District(s): 1

Project Description, Milestones and Service Impact

Restoration efforts through the Save Our Indian River Lagoon Program. Project is targeting the removal of extensive amounts of organic muck deposits created by decades of runoff, erosion and nutrient loading. This project will remove 285,000 cubic yards of muck sediment from the North Indian River lagoon within the Titusville area. Fiscal Year 25 Engineering and Permitting. Fiscal Year 26 Bidding. Fiscal Year 27 Begin multi-year dredging project.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 4,569,343	\$ 4,311,752	\$ 2,480,125	\$ 2,284,670	\$ -	\$ -	\$ -	\$ 13,645,890
Total Revenue	\$ 4,569,343	\$ 4,311,752	\$ 2,480,125	\$ 2,284,670	\$ -	\$ -	\$ -	\$ 13,645,890
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 182,059	\$ -	\$ 250,000	\$ -	\$ -	\$ -	\$ -	\$ 432,059
Construction Expense	\$ -	\$ -	\$ 2,222,535	\$ 10,991,296	\$ -	\$ -	\$ -	\$ 13,213,831
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 182,059	\$ -	\$ 2,472,535	\$ 10,991,296	\$ -	\$ -	\$ -	\$ 13,645,890

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: MUCK REMOVAL-NORTH-TITUSVILLE RR WEST MUCK DREDGING
Project Total: \$4,309,228
Project Timeline: August 30, 2018 through September 30, 2026
Funded Program: 515981
District(s): 1

Project Description, Milestones and Service Impact

Restoration efforts through the Save Our Indian River Lagoon Program. Project is targeting the removal of extensive amounts of organic muck deposits created by decades of runoff, erosion and nutrient loading. This project will remove 90,000 cubic yards of muck sediment from the North Indian River Lagoon within the Titusville area. Fiscal Year 20-21 Permitting. Fiscal Year 24 Bidding. Fiscal Year 25 Begin multi-year dredging project.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 1,082,213	\$ 1,784,065	\$ 1,442,950	\$ -	\$ -	\$ -	\$ -	\$ 4,309,228
Total Revenue	\$ 1,082,213	\$ 1,784,065	\$ 1,442,950	\$ -	\$ -	\$ -	\$ -	\$ 4,309,228
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 143,107	\$ 300,000	\$ 500,000	\$ -	\$ -	\$ -	\$ -	\$ 943,107
Construction Expense	\$ -	\$ -	\$ 1,866,121	\$ 1,500,000	\$ -	\$ -	\$ -	\$ 3,366,121
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 143,107	\$ 300,000	\$ 2,366,121	\$ 1,500,000	\$ -	\$ -	\$ -	\$ 4,309,228

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: MUCK REMOVAL-NORTH-ROCKLEDGE A MUCK DREDGING
Project Total: \$5,985,040
Project Timeline: September 15, 2018 through September 30, 2026
Funded Program: 516011
District(s): 1

Project Description, Milestones and Service Impact

Restoration efforts through the Save Our Indian River Lagoon Program. Project is targeting the removal of extensive amounts of organic muck deposits created by decades of runoff, erosion and nutrient loading. Project is removing approximately 125,000 cubic yards of muck sediment from the Indian River Lagoon within the Rockledge A project area. Fiscal Year 20-21 Permitting completed. Fiscal Year 22 project to be bld. Construction to start In Fiscal Year 27.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 2,605,122	\$ 3,379,918	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 5,985,040
Total Revenue	\$ 2,605,122	\$ 3,379,918	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 5,985,040
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 143,331	\$ -	\$ 750,000	\$ -	\$ -	\$ -	\$ -	\$ 893,331
Construction Expense	\$ -	\$ -	\$ -	\$ 5,091,709	\$ -	\$ -	\$ -	\$ 5,091,709
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 143,331	\$ -	\$ 750,000	\$ 5,091,709	\$ -	\$ -	\$ -	\$ 5,985,040

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: MUCK REMOVAL-BANANA-CANAVERAL SOUTH MUCK DREDGING
Project Total: \$20,109,734
Project Timeline: October 01, 2020 through September 30, 2028
Funded Program: 517282
District(s): 2

Project Description, Milestones and Service Impact

Restoration efforts through the Save Our Indian River Lagoon Program. Project is targeting the removal of extensive amounts of organic muck deposits created by decades of runoff, erosion and nutrient loading. This project will remove 195,000 cubic yards of muck sediment from the North Indian River Lagoon within the Banana River. This will reduce annual muck flux by 17.5 tons of nitrogen and 1 ton of total phosphorus. Fiscal Year 25 Engineering and Permitting. Fiscal Year 25 Bidding. Fiscal Year 25-26 Begin multi-year dredging project.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ 3,675,315	\$ 4,208,605	\$ 8,017,209	\$ 4,208,605	\$ -	\$ -	\$ 20,109,734
Total Revenue	\$ -	\$ 3,675,315	\$ 4,208,605	\$ 8,017,209	\$ 4,208,605	\$ -	\$ -	\$ 20,109,734
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 201,572	\$ 400,000	\$ 800,000	\$ 500,000	\$ -	\$ -	\$ -	\$ 1,901,572
Construction Expense	\$ -	\$ -	\$ 4,000,000	\$ 6,000,000	\$ 6,000,000	\$ 2,208,162	\$ -	\$ 18,208,162
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 201,572	\$ 400,000	\$ 4,800,000	\$ 6,500,000	\$ 6,000,000	\$ 2,208,162	\$ -	\$ 20,109,734

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: MUCK REMOVAL-PINEDA BRL MUCK DREDGING
Project Total: \$9,336,662
Project Timeline: October 01, 2022 through September 30, 2027
Funded Program: 517283
District(s): 2

Project Description, Milestones and Service Impact

Restoration efforts through the Save Our Indian River Lagoon Program. Project is targeting the removal of extensive amounts of organic muck deposits created by decades of runoff, erosion and nutrient loading. This project will remove 195,000 cubic yards of muck sediment from the North Indian River Lagoon within the Banana River. This will reduce annual muck flux by 7.5 tons of nitrogen and 0.7 tons of total phosphorus. Fiscal Year 25 Engineering and Permitting. Fiscal Year 26 Bidding. Fiscal Year 26 Begin multi-year dredging project.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 100,000	\$ 5,228,672	\$ 4,007,990	\$ -	\$ -	\$ -	\$ -	\$ 9,336,662
Total Revenue	\$ 100,000	\$ 5,228,672	\$ 4,007,990	\$ -	\$ -	\$ -	\$ -	\$ 9,336,662
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 250,000	\$ 500,000	\$ -	\$ -	\$ -	\$ -	\$ 750,000
Construction Expense	\$ -	\$ -	\$ -	\$ 3,600,000	\$ 4,986,662	\$ -	\$ -	\$ 8,586,662
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 250,000	\$ 500,000	\$ 3,600,000	\$ 4,986,662	\$ -	\$ -	\$ 9,336,662

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: MUCK REMOVAL-BANANA-PATRICK SPACE FORCE BASE (PSFB) MUCK DREDGING
Project Total: \$9,815,466
Project Timeline: October 01, 2022 through September 30, 2027
Funded Program: 517284
District(s): 2

Project Description, Milestones and Service Impact

Restoration efforts through the Save Our Indian River Lagoon Program. Project is targeting the removal of extensive amounts of organic muck deposits created by decades of runoff, erosion and nutrient loading. This project will remove 195,000 cubic yards of muck sediment from the North Indian River Lagoon within the Banana River. This will reduce annual muck flux by 3.5 tons of nitrogen and 0.4 tons of total phosphorus. Fiscal Year 25 Engineering and Permitting. Fiscal Year 26 Bidding. Fiscal Year 26 Begin multi-year dredging project.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ 9,815,466	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 9,815,466
Total Revenue	\$ -	\$ 9,815,466	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 9,815,466
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 250,000	\$ 500,000	\$ -	\$ -	\$ -	\$ -	\$ 750,000
Construction Expense	\$ -	\$ -	\$ -	\$ 4,348,666	\$ 4,716,800	\$ -	\$ -	\$ 9,065,466
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 250,000	\$ 500,000	\$ 4,348,666	\$ 4,716,800	\$ -	\$ -	\$ 9,815,466

Public Works Department

Program Name: ROAD AND BRIDGE
Project Name: Muck Removal - Banana - Merritt Island Canals Muck Dredging
Project Total: \$2,130,163
Project Timeline: October 1, 2019 through September 30, 2030
Funded Program: 517790
District(s): 2

Project Description, Milestones and Service Impact

The removal of accumulated muck from 30 canals on central Merritt Island with cost share from District 2 maintenance dredging funds. This project will remove approximately 200,000 cubic yards of muck, 80 tons of nitrogen, and 16 tons of phosphorus.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 1,135,392	\$ 177,655	\$ 182,985	\$ 188,474	\$ 194,128	\$ 194,128	\$ 57,401	\$ 2,130,163
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 1,135,392	\$ 177,655	\$ 182,985	\$ 188,474	\$ 194,128	\$ 194,128	\$ 57,401	\$ 2,130,163
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ 799,016	\$ 30,000	\$ 480,000	\$ 111,521	\$ 111,521	\$ 93,961	\$ 93,960	\$ 1,719,979
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ 136,728	\$ 136,728	\$ 136,728	\$ 410,184
Total Expense	\$ 799,016	\$ 30,000	\$ 480,000	\$ 111,521	\$ 248,249	\$ 230,689	\$ 230,688	\$ 2,130,163

BREVARD COUNTY CAPITAL IMPROVEMENT PROJECTS

SECTION: PARKS AND RECREATION

Housing and Human Services Department

Program Name: COMMUNITY RESOURCES
Project Name: Multipurpose Fields Bernice Jackson Park
Project Total: \$500,000
Project Timeline: October 1st, 2024 through September 30th, 2025
Funded Program: 6569109
District(s): 1

Project Description, Milestones and Service Impact

Design and phased construction plan for Bernice Jackson park to include 3 multipurpose fields, pavilion, parking, playground and possibly restrooms

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
General Revenue	\$ - \$	- \$	500,000 \$	- \$	- \$	- \$	- \$	500,000 \$
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Finance Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Revenue	\$ - \$	- \$	500,000 \$	- \$	- \$	- \$	- \$	500,000 \$
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	450,000 \$	- \$	- \$	- \$	- \$	450,000 \$
Construction Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Expense	\$ - \$	- \$	50,000 \$	- \$	- \$	- \$	- \$	50,000 \$
Total Expense	\$ - \$	- \$	500,000 \$	- \$	- \$	- \$	- \$	500,000 \$

Merritt Island Redevelopment Agency

Program Name: MERRITT ISLAND REDEVELOPMENT AGENCY
Project Name: Veterans Memorial Park Improvements/Amphitheatre
Project Total: \$6,805,607
Project Timeline: October 1st, 2021 through September 30th, 2025
Funded Program: 6518209
District(s): 2

Project Description, Milestones and Service Impact

This project is the culmination of MIRA's multiple-year efforts beginning with creating the Master Plan for the Veteran's Memorial Park, funding the land acquisition, and making a series of permanent improvements, that will serve the veterans, visitors, and citizens of Brevard County as a quality outdoor park and event venue. The project is a funding partnership with the Tourist Development Council, contributing \$1.27M to the project, and the State of Florida contributing \$1M. The Amphitheatre will support an acoustically-engineered bandshell and seating area designed to accommodate 2,350 attendees with additional overflow lawn seating capacity enabling up to a total of 5,000 attendees for a variety of veterans, visitors and community events.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Grant Revenue	\$ 1,270,833	- \$	1,000,000 \$	- \$	- \$	- \$	- \$	2,270,833 \$
Donations Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Incremental Tax Revenue	\$ 2,102,107	1,312,667 \$	1,120,000 \$	- \$	- \$	- \$	- \$	4,534,774 \$
Other Finance Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Revenue	\$ 3,372,940	1,312,667 \$	2,120,000 \$	- \$	- \$	- \$	- \$	6,805,607 \$
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Construction Expense	\$ 165,607	110,716 \$	6,529,284 \$	- \$	- \$	- \$	- \$	6,805,607 \$
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Expense	\$ 165,607	110,716 \$	6,529,284 \$	- \$	- \$	- \$	- \$	6,805,607 \$

Merritt Island Redevelopment Agency

Program Name: MERRITT ISLAND REDEVELOPMENT AGENCY
Project Name: Merritt Island River Walk
Project Total: \$85,000
Project Timeline: October 1, 2021 through September 30th, 2025
Funded Program: 519603
District(s): 2

Project Description, Milestones and Service Impact

This project will consist of a recreational trail along certain properties adjacent to the Barge Canal, Sea Ray Drive, and N Banana River Drive with connectivity to The 6,000 Acre Ulumay Land Preserve, and Kelly Park on Sykes Creek. The riverwalk would be accessible by trailheads, with pathways linking to other recreational sites, dining, entertainment, scenic river and wetland viewing areas. This will be a designated candidate for the Florida Greenways and Trail system offering statewide access to recreational use and enjoyment of the island's waterfront, open space and natural resources, ultimately extended to Port Canaveral and the Beaches. This would be the only bike and walking path traversing Merritt Island that is unimpeded by motor vehicles and provides safe passage across the island from river to river. There is no other significant public waterfront pedestrian access on the Island. This project will require collaboration with certain commercial property owners, Canaveral Port Authority, Brevard County, FDOT, Florida Greenways and Trails system.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Donations Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Incremental Tax Revenue	\$ 10,000	\$ -	\$ -	\$ 50,000	\$ 25,000	\$ -	\$ -	\$ 85,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 10,000	\$ -	\$ -	\$ 50,000	\$ 25,000	\$ -	\$ -	\$ 85,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 10,000	\$ -	\$ -	\$ 25,000	\$ -	\$ -	\$ -	\$ 35,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ 50,000	\$ -	\$ -	\$ 50,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 10,000	\$ -	\$ -	\$ 25,000	\$ 50,000	\$ -	\$ -	\$ 85,000

Merritt Island Redevelopment Agency

Program Name: MERRITT ISLAND REDEVELOPMENT AGENCY
Project Name: Medal of Honor Tribute Park
Project Total: \$400,000
Project Timeline: October 1st, 2024 through September 30th, 2027
Funded Program: 6578201
District(s): 2

Project Description, Milestones and Service Impact

This Project is the Capstone Project for Veterans Memorial Park. This will be a Medal of Honor Tribute Area set adjacent to the Lake, within viewing distance of the Amphitheatre.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Incremental Tax Revenue	\$ -	\$ -	\$ 100,000	\$ 150,000	\$ 150,000	\$ -	\$ -	\$ 400,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 100,000	\$ 150,000	\$ 150,000	\$ -	\$ -	\$ 400,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 100,000	\$ 150,000	\$ 150,000	\$ -	\$ -	\$ 400,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 100,000	\$ 150,000	\$ 150,000	\$ -	\$ -	\$ 400,000

Parks and Recreation Department

Program Name: ENVIRONMENTALLY ENDANGERED LANDS
Project Name: Environmentally Endangered Lands Trailhead and Parking Improvements
Project Total: \$1,230,250
Project Timeline: May 1, 2024 through September 30, 2025
Funded Program: N/A
District(s): Countywide

Project Description, Milestones and Service Impact

This project is to make trailhead and parking improvements at Scottsmeer Flatwoods, Jordan Scrub Sanctuary, Micco Scrub and Grant Flatwoods along with other facility improvements. Other improvements could include ADA accessible trails and improvements to scout camping areas.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Bond/Referendum Revenue	\$ - \$	1,115,000	115,250	\$ - \$	\$ - \$	\$ - \$	\$ - \$	1,230,250
Charges for Services Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
General Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Grant Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Other Financing Sources Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Total Revenue	\$ - \$	1,115,000	115,250	\$ - \$	\$ - \$	\$ - \$	\$ - \$	1,230,250
Land Expense	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Planning/Design Expense	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Construction Expense	\$ - \$	\$ - \$	1,230,250	\$ - \$	\$ - \$	\$ - \$	\$ - \$	1,230,250
Other Expense	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Total Expense	\$ - \$	\$ - \$	1,230,250	\$ - \$	\$ - \$	\$ - \$	\$ - \$	1,230,250

Parks and Recreation Department

Program Name: ENVIRONMENTALLY ENDANGERED LANDS
Project Name: Construction of Endangered Lands Observation Towers
Project Total: \$450,000
Project Timeline: May 1, 2024 through September 30, 2025
Funded Program: 6300241
District(s): 2, 3

Project Description, Milestones and Service Impact

This project is to construct 30' tall, wooden observation towers at each Pine Island Conservation Area, Ulumay Wildlife Sanctuary and Jordan Scrub Sanctuary. These towers will be a destination for hikers to view the sanctuary property.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Bond/Referendum Revenue	\$ - \$	450,000	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	450,000
Charges for Services Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
General Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Grant Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Other Financing Sources Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Total Revenue	\$ - \$	450,000	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	450,000
Land Expense	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Planning/Design Expense	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Construction Expense	\$ - \$	\$ - \$	450,000	\$ - \$	\$ - \$	\$ - \$	\$ - \$	450,000
Other Expense	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ -
Total Expense	\$ - \$	\$ - \$	450,000	\$ - \$	\$ - \$	\$ - \$	\$ - \$	450,000

Parks and Recreation Department

Program Name: ENVIRONMENTALLY ENDANGERED LANDS
Project Name: Construction of Endangered Lands Pedestrian Bridges
Project Total: \$400,000
Project Timeline: May 1, 2024 through September 30, 2025
Funded Program: 6300133
District(s): 1, 3

Project Description, Milestones and Service Impact

This project is to construct a suspension bridge at Grant Flatwoods Sanctuary over the Sotille Canal and at the Enchanted Forest over the Addison Canal. These bridges would allow for better access to the other side of the canals.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Bond/Referendum Revenue	\$ - \$	400,000	\$ - \$	- \$	- \$	- \$	- \$	400,000
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Revenue	\$ - \$	400,000	\$ - \$	- \$	- \$	- \$	- \$	400,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Construction Expense	\$ - \$	- \$	400,000	\$ - \$	- \$	- \$	- \$	400,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Expense	\$ - \$	- \$	400,000	\$ - \$	- \$	- \$	- \$	400,000

Parks and Recreation Department

Program Name: ENVIRONMENTALLY ENDANGERED LANDS
Project Name: Install Kayak Launch Ramps
Project Total: \$80,000
Project Timeline: May 1, 2024 through September 30, 2025
Funded Program: 6300242
District(s): 2

Project Description, Milestones and Service Impact

This project is to install ADA accessible floating kayak docks at Pine Island Conservation Area and Ulumay Wildlife Sanctuary.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Bond/Referendum Revenue	\$ - \$	80,000	\$ - \$	- \$	- \$	- \$	- \$	80,000
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Revenue	\$ - \$	80,000	\$ - \$	- \$	- \$	- \$	- \$	80,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Construction Expense	\$ - \$	- \$	80,000	\$ - \$	- \$	- \$	- \$	80,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Expense	\$ - \$	- \$	80,000	\$ - \$	- \$	- \$	- \$	80,000

Parks and Recreation Department

Program Name: ENVIRONMENTALLY ENDANGERED LANDS
Project Name: Environmentally Endangered Lands Land Purchases
Project Total: \$3,000,000
Project Timeline: May 1, 2024 through September 30, 2025
Funded Program: N/A
District(s): Countywide

Project Description, Milestones and Service Impact

The purchase of endangered lands that with specific focus on lands that directly benefit the Indian River Lagoon and St. Johns River.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Bond/Referendum Revenue	\$ - \$	3,000,000	\$ - \$	- \$	- \$	- \$	- \$	3,000,000
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	3,000,000	\$ - \$	- \$	- \$	- \$	- \$	3,000,000
Land Expense	\$ - \$	- \$	3,000,000	\$ - \$	- \$	- \$	- \$	3,000,000
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	3,000,000	\$ - \$	- \$	- \$	- \$	3,000,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS
Project Name: Manatee Hammock Campground Pickleball Shade Structure
Project Total: \$71,320
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6538157
District(s): 1

Project Description, Milestones and Service Impact

This project is to install a shade structure over the newly constructed pickleball court. Pickleball has become very popular and providing shade will ensure more use of the court.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ 50,000	\$ 21,320	\$ - \$	- \$	- \$	- \$	- \$	71,320
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ 50,000	\$ 21,320	\$ - \$	- \$	- \$	- \$	- \$	71,320
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	71,320	\$ - \$	- \$	- \$	- \$	71,320
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	71,320	\$ - \$	- \$	- \$	- \$	71,320

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Manatee Hammock Campground Laundry Facility
Project Total: \$1,050,112
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6518118
District(s): 1

Project Description, Milestones and Service Impact

This project is to build an additional laundry facility for use at Manatee Hammock. This new building will house a small restroom and laundry equipment.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Charges for Services Revenue	\$ 876,658	\$ 173,454	- \$	- \$	- \$	- \$	- \$	1,050,112
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Revenue	\$ 876,658	\$ 173,454	- \$	- \$	- \$	- \$	- \$	1,050,112
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ 20,422	\$ 5,588	2,625 \$	- \$	- \$	- \$	- \$	28,635
Construction Expense	\$ - \$	- \$	1,021,477 \$	- \$	- \$	- \$	- \$	1,021,477
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Expense	\$ 20,422	\$ 5,588	1,024,102 \$	- \$	- \$	- \$	- \$	1,050,112

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Manatee Hammock Campground Maintenance Building
Project Total: \$200,000
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 6518120
District(s): 1

Project Description, Milestones and Service Impact

This project is to provide a maintenance facility to secure equipment, mowers and hand tools. The metal building will provide work space for maintenance technicians as well as a breakroom, restroom and office space. The building is replacing a previous manufactured facility that was removed due to age and condition.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Charges for Services Revenue	\$ - \$	100,000 \$	100,000 \$	- \$	- \$	- \$	- \$	200,000
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Revenue	\$ - \$	100,000 \$	100,000 \$	- \$	- \$	- \$	- \$	200,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	25,000 \$	- \$	- \$	- \$	- \$	25,000
Construction Expense	\$ - \$	- \$	175,000 \$	- \$	- \$	- \$	- \$	175,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Expense	\$ - \$	- \$	200,000 \$	- \$	- \$	- \$	- \$	200,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Parrish Park Trailhead
Project Total: \$5,211,766
Project Timeline: May 1, 2019 through September 30, 2025
Funded Program: 6300130
District(s): 1

Project Description, Milestones and Service Impact

This project consists of the design and construction for a trailhead along the Coast to Coast Trail. The trailhead will include a linear parking lot with a one-way aisle, sidewalks, a multi-use path, lighting, landscaping, signage, fencing, pavement markings, and locations for future site amenities.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 40,000	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	140,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
General Revenue	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	200,000
Grant Revenue	\$ 4,271,766	\$ 600,000	\$ -	\$ -	\$ -	\$ -	\$ -	4,871,766
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 4,311,766	\$ 800,000	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 5,211,766
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 290,000	\$ 14,502	\$ -	\$ -	\$ -	\$ -	\$ -	304,502
Construction Expense	\$ 54,217	\$ 2,017,548	\$ 2,835,499	\$ -	\$ -	\$ -	\$ -	4,907,264
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 344,217	\$ 2,032,050	\$ 2,835,499	\$ -	\$ -	\$ -	\$ -	\$ 5,211,766

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Titusville Veteran's Memorial Fishing Pier Electrical Repairs
Project Total: \$140,000
Project Timeline: July 7, 2021 through September 30, 2025
Funded Program: N/A
District(s): 1

Project Description, Milestones and Service Impact

This project is to replace the electrical wiring, junction boxes, lights and receptacles at the Titusville Veterans Memorial Fishing Pier. Due to salt water damage and intrusion, these items are in need of replacement.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 140,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	140,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 140,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 140,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ -	\$ -	\$ 15,000	\$ -	\$ -	\$ -	\$ -	15,000
Construction Expense	\$ -	\$ -	\$ 125,000	\$ -	\$ -	\$ -	\$ -	125,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ -	\$ -	\$ 140,000	\$ -	\$ -	\$ -	\$ -	\$ 140,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Manatee Hammock Campground Corn Hole Courts
Project Total: \$18,000
Project Timeline: October 1, 2024 to September 30, 2025
Funded Program: 6538162
District(s): 1

Project Description, Milestones and Service Impact

This project is to install two corn hole courts at Manatee Hammock Campground. Each court would consist of two 5'x3'x5" concrete pads made solely out of solid polished concrete with vandal resistant fasteners.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	18,000	\$ -	\$ -	\$ -	\$ -	18,000
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	18,000	\$ -	\$ -	\$ -	\$ -	18,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	18,000	\$ -	\$ -	\$ -	\$ -	18,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	18,000	\$ -	\$ -	\$ -	\$ -	18,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: ARPA Capital Improvements for Parks in North Area
Project Total: \$1,368,109
Project Timeline: June 1, 2023 through September 30, 2025
Funded Program: 6300132
District(s): 1

Project Description, Milestones and Service Impact

This project is to invest ARPA revenue replacement funds along with District 1 Recreation MSTU and general revenues to improve infrastructure throughout District 1 parks. Improvements would include construction of a fourth youth softball field at Chain of Lakes softball complex, Asset #2220138. The new softball field will be added to the three plex and have lights to better serve the needs of the community. Other improvements could include, but not limited to, Coast to Coast Trail enhancements and athletic field drainage repairs.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	434,916	\$ -	\$ -	\$ -	\$ -	\$ -	434,916
Grant Revenue	\$ 933,193	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	933,193
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 933,193	\$ 434,916	\$ -	\$ -	\$ -	\$ -	\$ -	1,368,109
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	2,135	\$ -	\$ -	\$ -	\$ -	\$ -	2,135
Construction Expense	\$ -	\$ -	1,365,974	\$ -	\$ -	\$ -	\$ -	1,365,974
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 2,135	\$ 1,365,974	\$ -	\$ -	\$ -	\$ -	1,368,109

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Cuyler Community Center Voice Evacuation Fire Alarm System
Project Total: \$90,000
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 6518119
District(s): 1

Project Description, Milestones and Service Impact

This project is to install a voice evacuation alert system in the Cuyler Community Center. This system will guide patrons out of the building using clear and coherent directions. This is a Fire Rescue mandated item for the safety of patrons.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	90,000	\$ -	\$ -	\$ -	\$ -	\$ -	90,000
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	90,000	\$ -	\$ -	\$ -	\$ -	\$ -	90,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	90,000	\$ -	\$ -	\$ -	\$ -	90,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	90,000	\$ -	\$ -	\$ -	\$ -	90,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Isaac Campbell Sr., Park Enhancements
Project Total: \$130,000
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: N/A
District(s): 1

Project Description, Milestones and Service Impact

This project is to enhance the Isaac Campbell Sr., Park and Community Center by installing new windows, painting the interior of the center and upgrading the restrooms.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	130,000	\$ -	\$ -	\$ -	\$ -	\$ -	130,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	130,000	\$ -	\$ -	\$ -	\$ -	\$ -	130,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	130,000	\$ -	\$ -	\$ -	\$ -	130,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	130,000	\$ -	\$ -	\$ -	\$ -	130,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Blanton Park Renovations
Project Total: \$341,250
Project Timeline: October 27, 2021 through September 30, 2025
Funded Program: 517433
District(s): 1

Project Description, Milestones and Service Impact

This project is to utilize a donation from Parrish Medical Center to enhance amenities at Blanton Park in Titusville. Improvements are to include the demolition and replacement of the existing playground, addition of three exercise stations along the sidewalk, increasing security lighting, adding parking, installing an ADA compliant accessible sidewalk, renovating the basketball court with new adjustable goals, pavilion and restroom upgrades, and fencing and landscape improvements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Donations Revenue	\$ 341,250	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 341,250
Total Revenue	\$ 341,250	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 341,250
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 12,325	\$ 32,700	\$ 7,850	\$ -	\$ -	\$ -	\$ -	\$ 52,875
Construction Expense	\$ -	\$ -	\$ 288,375	\$ -	\$ -	\$ -	\$ -	\$ 288,375
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 12,325	\$ 32,700	\$ 296,225	\$ -	\$ -	\$ -	\$ -	\$ 341,250

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Manatee Hammock Campground Fishing Pier Renovation
Project Total: \$270,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: N/A
District(s): 1

Project Description, Milestones and Service Impact

This project is to replace the aging decking, guardrails and caps on a 185' x 8' fishing pier extending into the Indian River. There is a 30' x 10' fishing platform attached to the end of the pier that will also have the decking, guardrails and caps replaced. This fishing pier is popular with the campground guests.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ 270,000	\$ -	\$ -	\$ -	\$ -	\$ 270,000
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 270,000	\$ -	\$ -	\$ -	\$ -	\$ 270,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 270,000	\$ -	\$ -	\$ -	\$ -	\$ 270,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 270,000	\$ -	\$ -	\$ -	\$ -	\$ 270,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Singleton Tennis Court Facility Improvements
Project Total: \$835,000
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 6573103, 6502120, 6571110
District(s): 1

Project Description, Milestones and Service Impact

The improvements to the Singleton Tennis Court facility would include creating a fenced in, 4 court pickleball facility for public use, create a more stable parking area and install a prefabricated restroom. The current restroom is 56 years old and cannot support the demand at the facility that houses 10 tennis courts, 4 pickleball courts, and 2 racquetball courts. The existing restroom will be converted into a storage area.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 400,000	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 600,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ 235,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 235,000
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 635,000	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 835,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 4,880	\$ 22,402	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 27,282
Construction Expense	\$ -	\$ -	\$ 807,718	\$ -	\$ -	\$ -	\$ -	\$ 807,718
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 4,880	\$ 22,402	\$ 807,718	\$ -	\$ -	\$ -	\$ -	\$ 835,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Wuesthoff Park Improvements
Project Total: \$376,661
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6537118
District(s): 1

Project Description, Milestones and Service Impact

This project is to demolish and remove the Homer Powell Nature Center at Wuesthoff Park and replace it with a pavilion that includes a restroom and small kitchen area.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ 276,661	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 276,661
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 376,661	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 376,661
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 376,661	\$ -	\$ -	\$ -	\$ -	\$ 376,661
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 376,661	\$ -	\$ -	\$ -	\$ -	\$ 376,661

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Manatee Hammock Campground Recreation Hall
Project Total: \$182,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: 6510113
District(s): 1

Project Description, Milestones and Service Impact

This project is to renovate the existing recreation hall to add a kitchen with serving / buffet counter, board game room, media room, restrooms and add a back porch. The renovations will allow campers to have a place to gather.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	182,000	\$ -	\$ -	\$ -	\$ -	182,000
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	182,000	\$ -	\$ -	\$ -	\$ -	182,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	25,000	\$ -	\$ -	\$ -	\$ -	25,000
Construction Expense	\$ -	\$ -	157,000	\$ -	\$ -	\$ -	\$ -	157,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	182,000	\$ -	\$ -	\$ -	\$ -	182,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: North Area Parks Resurfacing Projects
Project Total: \$283,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: N/A
District(s): 1

Project Description, Milestones and Service Impact

This project is to resurface the existing parking lots at the North Brevard Senior Center, Kenney Point Boat Ramp, Scottsmoor Landing and the north parking lot at the Gibson Center.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	283,000	\$ -	\$ -	\$ -	\$ -	283,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	283,000	\$ -	\$ -	\$ -	\$ -	283,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	283,000	\$ -	\$ -	\$ -	\$ -	283,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	283,000	\$ -	\$ -	\$ -	\$ -	283,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: North Area Parks Athletic Field Renovations
Project Total: \$755,395
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: N/A
District(s): 1

Project Description, Milestones and Service Impact

This project is to replace the sod and fencing at the Holder Little League fields, Cuyler softball field, Space Coast Sports Communities Sports Complex Under-12 soccer field and the lit soccer field along with a Gibson football field.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	755,395 \$	- \$	- \$	- \$	- \$	755,395
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	- \$	755,395 \$	- \$	- \$	- \$	- \$	755,395
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	755,395 \$	- \$	- \$	- \$	- \$	755,395
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	755,395 \$	- \$	- \$	- \$	- \$	755,395

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: North Area Parks Playground Replacement
Project Total: \$680,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: 6300134
District(s): 1

Project Description, Milestones and Service Impact

This project is to demolish, remove, and replace the playgrounds at Rotary Park, Asset #641666; Sand Point Park, Asset #723543; Space Coast Community Sports Complex, Asset #641621 and the Tom Statham Park swing set. These new playgrounds and shade structures will provide safe and reliable equipment to meet the needs of the children and families who visit the park.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	680,000 \$	- \$	- \$	- \$	- \$	680,000
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	- \$	680,000 \$	- \$	- \$	- \$	- \$	680,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	680,000 \$	- \$	- \$	- \$	- \$	680,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	680,000 \$	- \$	- \$	- \$	- \$	680,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Manatee Hammock Campground Dog Park Improvements
Project Total: \$30,000
Project Timeline: June 30, 2024 through September 30, 2025
Funded Program: 6563102
District(s): 1

Project Description, Milestones and Service Impact

This project is to install an irrigation system to the existing dog park at Manatee Hammock Campground. The system would include a well, pump and sprinkler system to keep the grass from dying off.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Charges for Services Revenue	\$ - \$	30,000 \$	- \$	- \$	- \$	- \$	- \$	30,000
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Revenue	\$ - \$	30,000 \$	- \$	- \$	- \$	- \$	- \$	30,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Construction Expense	\$ - \$	- \$	30,000 \$	- \$	- \$	- \$	- \$	30,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Expense	\$ - \$	- \$	30,000 \$	- \$	- \$	- \$	- \$	30,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Scottsmoor Community Meeting Hall Generator Replacement
Project Total: \$30,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: 6351113
District(s): 1

Project Description, Milestones and Service Impact

This project is to demolish, remove and replace the 40 year old generator at the Scottsmoor Community Meeting Hall, Asset #562109. The meeting hall is utilized as a shelter for the community during power outages and is a voting precinct.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	30,000 \$	- \$	- \$	- \$	- \$	30,000
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Revenue	\$ - \$	- \$	30,000 \$	- \$	- \$	- \$	- \$	30,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Construction Expense	\$ - \$	- \$	30,000 \$	- \$	- \$	- \$	- \$	30,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Expense	\$ - \$	- \$	30,000 \$	- \$	- \$	- \$	- \$	30,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Parrish Park Restroom Foundation Repairs
Project Total: \$110,000
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: N/A
District(s): 1

Project Description, Milestones and Service Impact

This project will consist of the reinforcement / restabilization to the restroom foundation and sidewalk at Parrish Park in Titusville that were eroded during Hurricane Nicole.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	110,000 \$	- \$	- \$	- \$	- \$	- \$	110,000
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	110,000 \$	- \$	- \$	- \$	- \$	- \$	110,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	110,000 \$	- \$	- \$	- \$	- \$	110,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	110,000 \$	- \$	- \$	- \$	- \$	110,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Chain of Lakes Softball Field Drainage
Project Total: \$30,000
Project Timeline: May 10, 2023 through September 30, 2025
Funded Program: N/A
District(s): 1

Project Description, Milestones and Service Impact

This project is to establish design to increase drainage at the Chain of Lakes softball complex.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	30,000 \$	- \$	- \$	- \$	- \$	- \$	- \$	30,000
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ 30,000 \$	- \$	- \$	- \$	- \$	- \$	- \$	30,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	30,000 \$	- \$	- \$	- \$	- \$	30,000
Construction Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	30,000 \$	- \$	- \$	- \$	- \$	30,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Parrish Park Jet Ski Launch
Project Total: \$50,000
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 6565102
District(s): 1

Project Description, Milestones and Service Impact

This project is to design a concrete jet ski launch area and dock on the west end of Parrish Park in Titusville. The construction of the Florida Local Agency Program (FLAP) Trailhead project only includes non-motorized launch areas. There has been multiple requests to construct a jet ski launch area. The construction of a jet ski launch area would be well received by the jet ski community. This project is contingent in obtaining all applicable permits.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 50,000
Total Revenue	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 50,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 50,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 50,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Fay Park and Sand Point Park Maintenance Sheds
Project Total: \$92,000
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6518122
District(s): 1

Project Description, Milestones and Service Impact

This project is to install two maintenance sheds, one located at Fay Park in Port St John and the other at Sand Point Park. The sheds will be utilized by Parks and Recreation maintenance personnel to store tools and equipment.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 92,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 92,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 92,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 92,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ 6,760	\$ -	\$ 85,240	\$ -	\$ -	\$ -	\$ -	\$ 92,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 6,760	\$ -	\$ 85,240	\$ -	\$ -	\$ -	\$ -	\$ 92,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Sand Point Park Pavilion Replacement
Project Total: \$731,689
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 6537119
District(s): 1

Project Description, Milestones and Service Impact

This project is to demolish, remove, and replace six medium pavilions at Sand Point Park. Three of the six medium pavilions are 14 years old; Asset #641675, Asset #641676, and Asset #641677. The other three are 9 years old and were installed by Florida Department of Transportation in 2013 after the Max Brewer Bridge was completed; Asset #641844, Asset #641845, and Asset #641846. The pavilions are showing damage from the extreme environment and salt water from the intercoastal waterway. New structures will be laminated wood rather than the existing metal frame.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 431,689	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 531,689
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 631,689	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 731,689
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 731,689	\$ -	\$ -	\$ -	\$ -	\$ 731,689
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 731,689	\$ -	\$ -	\$ -	\$ -	\$ 731,689

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Fox Lake Park Boat Ramp Dock Replacement
Project Total: \$450,000
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 6564103
District(s): 1

Project Description, Milestones and Service Impact

This project will replace all pilings, decking, handrails, and side access ramp to the dock at Fox Lake Park. The dock extends from the concrete boat ramp into the navigation canal to allow boaters to board and disembark their vessels. The terminal end of the dock provides fishing opportunities as well as an observation platform.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ 400,000	\$ -	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 450,000
Total Revenue	\$ 400,000	\$ -	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 450,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 50,000
Construction Expense	\$ -	\$ -	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ 400,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 450,000	\$ -	\$ -	\$ -	\$ -	\$ 450,000

Parks and Recreation Department

Program Name: NORTH AREA PARKS OPERATIONS
Project Name: Marina Park Skate Park Lighting
Project Total: \$25,000
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6532109
District(s): 1

Project Description, Milestones and Service Impact

This project is to install light poles and LED lighting at the existing skate park. There is currently no lighting at the skate park and lighting would provide skating activities to extend into evening hours for participants. Patrons have made numerous requests for this improvement. The lighting will be timer controlled to ensure specific hours of operations be maintained.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 15,000	\$ 10,000	\$ -	\$ -	\$ -	\$ -	\$ -	25,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 15,000	\$ 10,000	\$ -	\$ -	\$ -	\$ -	\$ -	25,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Construction Expense	\$ -	\$ -	25,000	\$ -	\$ -	\$ -	\$ -	25,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ -	\$ -	25,000	\$ -	\$ -	\$ -	\$ -	25,000

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: McKnight Family Sports Complex Athletic Facility Renovations
Project Total: \$1,513,606
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 6300420
District(s): 2

Project Description, Milestones and Service Impact

This project is to make renovations at the McKnight Family Sports Complex such as; replace field and dugout fencing, resurface the tennis courts, replace the roof on the tennis building, paving the dirt parking lot and laser grading and laying new sod on the athletic fields.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 200,000	\$ 560,093	\$ 247,316	\$ -	\$ -	\$ -	\$ -	1,007,409
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
General Revenue	\$ -	\$ -	506,197	\$ -	\$ -	\$ -	\$ -	506,197
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 200,000	\$ 560,093	\$ 753,513	\$ -	\$ -	\$ -	\$ -	1,513,606
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Construction Expense	\$ -	224,309	1,289,297	\$ -	\$ -	\$ -	\$ -	1,513,606
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ -	224,309	1,289,297	\$ -	\$ -	\$ -	\$ -	1,513,606

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: Woody Simpson Community Center Voice Evacuation Fire Alarm System
Project Total: \$79,934
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 6518210
District(s): 2

Project Description, Milestones and Service Impact

This project is to install a voice evacuation alert system in the Woody Simpson Community Center. This system will guide patrons out of the building using clear and coherent directions. This is a Fire Rescue mandated item for the safety of patrons.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ 79,934	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 79,934
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 79,934	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 79,934
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 79,934	\$ -	\$ -	\$ -	\$ -	\$ 79,934
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 79,934	\$ -	\$ -	\$ -	\$ -	\$ 79,934

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: Osteen Park Fishing Pier Renovations
Project Total: \$100,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: N/A
District(s): 2

Project Description, Milestones and Service Impact

This project is to restore the fishing pier at Osteen Park by replacing the decking and adding stainless steel hardware to prevent any future damages to the structure.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ 25,000	\$ -	\$ -	\$ -	\$ -	\$ 25,000
General Revenue	\$ -	\$ -	\$ 75,000	\$ -	\$ -	\$ -	\$ -	\$ 75,000
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: McLarty Park Improvements
Project Total: \$595,194
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: 6300419
District(s): 2

Project Description, Milestones and Service Impact

This project is to renovate and improve McLarty Park by constructing a lit pickleball court, paving the dirt section of the parking lot, demolish, remove and replace 34 year old fencing on four of the baseball fields, Asset #2220056 and demolish, remove and replace 23 year old wood light poles at the T-ball fields, Asset #640306.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ 337,613	\$ -	\$ -	\$ -	\$ -	\$ 337,613
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ 25,000	\$ -	\$ -	\$ -	\$ -	\$ 25,000
General Revenue	\$ -	\$ -	\$ 232,581	\$ -	\$ -	\$ -	\$ -	\$ 232,581
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 595,194	\$ -	\$ -	\$ -	\$ -	\$ 595,194
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 595,194	\$ -	\$ -	\$ -	\$ -	\$ 595,194
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 595,194	\$ -	\$ -	\$ -	\$ -	\$ 595,194

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: Kelly Park East Improvements
Project Total: \$1,566,707
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6502209, 6537211
District(s): 2

Project Description, Milestones and Service Impact

This project is to add a new pavilion and a new restroom facility to Kelly Park East. This project will include connecting the park to the sewer line on Banana River Drive, thereby, eliminating the septic system. With the addition of the pavilion to the park, patrons will have more options for shaded cover and therefore, increasing potential revenue for the Central Area Parks Operations. This does not reflect the cost share from a SOIRL grant in the amount of \$143,100.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ 416,092	\$ -	\$ 18,844	\$ -	\$ -	\$ -	\$ -	\$ 434,936
General Revenue	\$ 431,771	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 431,771
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ 500,000	\$ 100,000	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 700,000
Total Revenue	\$ 1,347,863	\$ 100,000	\$ 118,844	\$ -	\$ -	\$ -	\$ -	\$ 1,566,707
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 42,695	\$ 4,950	\$ 19,390	\$ -	\$ -	\$ -	\$ -	\$ 67,035
Construction Expense	\$ -	\$ -	\$ 1,499,672	\$ -	\$ -	\$ -	\$ -	\$ 1,499,672
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 42,695	\$ 4,950	\$ 1,519,062	\$ -	\$ -	\$ -	\$ -	\$ 1,566,707

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: Rotary Park Merritt Island Renovations
Project Total: \$255,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: N/A
District(s): 2

Project Description, Milestones and Service Impact

This project will consist of renovating the restrooms at the park to conform to ADA standards, new fixtures, plumbing and paint. There will also be repairs made to the asphalt on the walking trail along with upgrades at the nature center such as, new cabinets and painting.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	255,000 \$	- \$	- \$	- \$	- \$	255,000
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	- \$	255,000 \$	- \$	- \$	- \$	- \$	255,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	255,000 \$	- \$	- \$	- \$	- \$	255,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	255,000 \$	- \$	- \$	- \$	- \$	255,000

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: Central Area Parks Parking Lot Renovations
Project Total: \$105,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: 6570203
District(s): 2

Project Description, Milestones and Service Impact

This project is to asphalt approximately 1,200 feet of concrete entrance driveway and parking spaces at Osteen Park. The project will asphalt 15 dirt parking spaces on the east and west sides of the entrance driveway and one ADA parking space at the entrance to the sidewalk leading to the park and playground areas. The Cone Road maintenance office parking lot will also be receive an overlay of asphalt.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	105,000 \$	- \$	- \$	- \$	- \$	105,000
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	- \$	105,000 \$	- \$	- \$	- \$	- \$	105,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	105,000 \$	- \$	- \$	- \$	- \$	105,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	105,000 \$	- \$	- \$	- \$	- \$	105,000

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: LeRoy Wright Recreation Area Pavilion
Project Total: \$154,692
Project Timeline: October 1, 2019 through September 30, 2025
Funded Program: 6537210
District(s): 1

Project Description, Milestones and Service Impact

This project is to construct a 20 foot by 28 foot pavilion in the LeRoy Wright recreation area. An ADA compliant sidewalk will also be added leading from the parking lot to the pavilion and restroom. This pavilion will be the only covered structure for patrons to utilize.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 139,692	\$ -	\$ 15,000	\$ -	\$ -	\$ -	\$ -	\$ 154,692
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 139,692	\$ -	\$ 15,000	\$ -	\$ -	\$ -	\$ -	\$ 154,692
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 50,833	\$ -	\$ 2,588	\$ -	\$ -	\$ -	\$ -	\$ 53,421
Construction Expense	\$ -	\$ -	\$ 101,271	\$ -	\$ -	\$ -	\$ -	\$ 101,271
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 50,833	\$ -	\$ 103,859	\$ -	\$ -	\$ -	\$ -	\$ 154,692

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: Don Stradley Memorial Park Softball and Baseball Concession Stand Renovations
Project Total: \$200,000
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: N/A
District(s): 2

Project Description, Milestones and Service Impact

This project is to renovate the current concession stand that is utilized by both the softball and baseball leagues at Don Stradley Memorial Park. Renovations will include updating the ceiling, flooring, restroom fixtures and partitions and painting the facility.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: Merritt Island Athletic Field Fencing Replacement
Project Total: \$661,707
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 6566213 and N/A
District(s): 2

Project Description, Milestones and Service Impact

This project is to replace the chain link field fencing, including backstop and poles, on the baseball and softball fields at Audubon Elementary School, Tropical Elementary School, Woody Simpson fields, and Mitchell Ellington Park. New fencing throughout the athletic fields will allow a safer environment for all users of the facilities.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ 621,707	\$ 40,000	\$ -	\$ -	\$ -	\$ -	\$ 661,707
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 621,707	\$ 40,000	\$ -	\$ -	\$ -	\$ -	\$ 661,707
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ 421,707	\$ 240,000	\$ -	\$ -	\$ -	\$ -	\$ 661,707
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 421,707	\$ 240,000	\$ -	\$ -	\$ -	\$ -	\$ 661,707

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: Don Stradley Memorial Park Football Concession Renovation
Project Total: \$300,000
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 6507400
District(s): 2

Project Description, Milestones and Service Impact

This project is to renovate and modernize the football concession building at Don Stradley Park. The renovations will include the installation of insulation and will expand the footprint of the existing building. The expansion will be approximately 22 feet long by 15 feet wide and will be used for equipment storage.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 200,000	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 300,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 200,000	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 300,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 15,293	\$ -	\$ -	\$ -	\$ -	\$ 15,293
Construction Expense	\$ -	\$ -	\$ 284,707	\$ -	\$ -	\$ -	\$ -	\$ 284,707
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 300,000

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: Leroy Wright Recreation Area Dock Replacement
Project Total: \$261,350
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6564104
District(s): 1

Project Description, Milestones and Service Impact

This project is to replace the existing wood platforms at the entrance to the boat ramp and the adjoining floating docks. With the replacement of the platforms and floating docks, patrons will have a level access point for entering the floating boat launch platforms.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Finance Sources Revenue	\$ 200,000	\$ -	\$ 61,350	\$ -	\$ -	\$ -	\$ -	261,350
Total Revenue	\$ 200,000	\$ -	\$ 61,350	\$ -	\$ -	\$ -	\$ -	261,350
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	\$ 56,250	\$ -	\$ -	\$ -	\$ -	56,250
Construction Expense	\$ - \$	- \$	\$ 205,100	\$ -	\$ -	\$ -	\$ -	205,100
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ -	\$ -	\$ 261,350	\$ -	\$ -	\$ -	\$ -	261,350

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: James G. Bourbeau Memorial Park Floating Dock Renovation
Project Total: \$350,000
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: N/A
District(s): 1

Project Description, Milestones and Service Impact

This project is to replace sections of the Bourbeau Park floating dock. The floating sections are old and are in need of replacement. This will provide a more stable and level area for patrons entering the launch platform.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Finance Sources Revenue	\$ 250,000	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	350,000
Total Revenue	\$ 250,000	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	350,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	\$ 57,250	\$ -	\$ -	\$ -	\$ -	57,250
Construction Expense	\$ - \$	- \$	\$ 292,750	\$ -	\$ -	\$ -	\$ -	292,750
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ -	\$ -	\$ 350,000	\$ -	\$ -	\$ -	\$ -	350,000

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: Canova Beach Park Restroom Replacement
Project Total: \$1,100,000
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6502508
District(s): 5

Project Description, Milestones and Service Impact

This project is to demolish, remove, and replace the current restroom, built in 1990, at the Canova Beach dog park, Asset #620205. This project will include upgrades to the underground plumbing and electrical service. The new restroom will be completely ADA accessible for the busy beach dog park.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 700,000	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,100,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 700,000	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,100,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 12,800	\$ 4,620	\$ 1,824	\$ -	\$ -	\$ -	\$ -	\$ 19,244
Construction Expense	\$ -	\$ -	\$ 1,080,756	\$ -	\$ -	\$ -	\$ -	\$ 1,080,756
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 12,800	\$ 4,620	\$ 1,082,580	\$ -	\$ -	\$ -	\$ -	\$ 1,100,000

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: Wickham Park Improvements
Project Total: \$1,072,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: 6300421
District(s): 4

Project Description, Milestones and Service Impact

Improvements for Wickham Park include the expansion of the playground with additional playground items, sidewalk, shade structure and drop in place restroom. Additional improvements are to the archery range by adding a shade structure and approximately 350' of chain link fencing along the southeast corner of the range.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ 825,000	\$ -	\$ -	\$ -	\$ -	\$ 825,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ 247,000	\$ -	\$ -	\$ -	\$ -	\$ 247,000
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 1,072,000	\$ -	\$ -	\$ -	\$ -	\$ 1,072,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 26,000	\$ -	\$ -	\$ -	\$ -	\$ 26,000
Construction Expense	\$ -	\$ -	\$ 1,046,000	\$ -	\$ -	\$ -	\$ -	\$ 1,046,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 1,072,000	\$ -	\$ -	\$ -	\$ -	\$ 1,072,000

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: Long Point Park Entry Road Repairs
Project Total: \$75,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: N/A
District(s): 3

Project Description, Milestones and Service Impact

This project is to repair the eroding roadway at the entrance to Long Point Park in front of the ranger's station. This repair will keep the roadway wide and safe for large campers and trailers.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Charges for Services Revenue	\$ - \$	- \$	75,000	- \$	- \$	- \$	- \$	75,000
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Revenue	\$ - \$	- \$	75,000	- \$	- \$	- \$	- \$	75,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Construction Expense	\$ - \$	- \$	75,000	- \$	- \$	- \$	- \$	75,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Expense	\$ - \$	- \$	75,000	- \$	- \$	- \$	- \$	75,000

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: South Area Parks Playgrounds
Project Total: \$674,820
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: 6300318
District(s): 4, 5

Project Description, Milestones and Service Impact

This project is to demolish, remove, and replace the existing playgrounds at Max K Rhodes Park, northwest Asset #641781 and southwest Asset #641782, both playgrounds are 14 years old. This new playground and shade structure will provide safe and reliable equipment to meet the needs of the children and families who visit the park. Also included is a new ADA accessible playground and shade structure at the new disabilities building at Wickham Park.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	674,820	- \$	- \$	- \$	- \$	674,820
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Revenue	\$ - \$	- \$	674,820	- \$	- \$	- \$	- \$	674,820
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Construction Expense	\$ - \$	- \$	674,820	- \$	- \$	- \$	- \$	674,820
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Expense	\$ - \$	- \$	674,820	- \$	- \$	- \$	- \$	674,820

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: Wickham Park Restroom Replacement
Project Total: \$1,550,120
Project Timeline: October 1, 2019 through September 30, 2025
Funded Program: 6502412, 6502413
District(s): 4

Project Description, Milestones and Service Impact

This project is to demolish, remove, and replace two Wickham Park restroom, shower, and laundry facilities that were built in the 1960's; Loop A, no existing Asset Number; Loop B, Asset #620442. The current buildings require frequent plumbing, sewer, and electrical repairs. The new facilities will have new underground plumbing and electrical service. The facilities will also be ADA accessible and will provide more reliable showers, restrooms, and laundry facilities for the campground patrons.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 1,550,120	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,550,120
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 1,550,120	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,550,120
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 29,120	\$ 4,980	\$ 57,994	\$ -	\$ -	\$ -	\$ -	\$ 92,094
Construction Expense	\$ -	\$ -	\$ 1,458,026	\$ -	\$ -	\$ -	\$ -	\$ 1,458,026
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 29,120	\$ 4,980	\$ 1,516,020	\$ -	\$ -	\$ -	\$ -	\$ 1,550,120

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: Wickham Park Loop A Pavillion Replacement
Project Total: \$352,900
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6537410
District(s): 4

Project Description, Milestones and Service Impact

This project is to demolish, remove, and replace the current Wickham Park open air pavillion that was built in 1994, Asset #310471, with a new structure on a concrete slab. This new pavillion will provide patrons, especially tent campers, with shelter during high winds, heavy rain, and lightning. Additionally, it will provide a central meeting place for camp activities such as group gatherings, pot luck dinners, and small special events.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ 352,900	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 352,900
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 352,900	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 352,900
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 30,000	\$ -	\$ -	\$ -	\$ -	\$ 30,000
Construction Expense	\$ -	\$ -	\$ 322,900	\$ -	\$ -	\$ -	\$ -	\$ 322,900
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 352,900	\$ -	\$ -	\$ -	\$ -	\$ 352,900

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: South Area Parks Athletic Field Renovations
Project Total: \$740,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: N/A
District(s): 3, 5

Project Description, Milestones and Service Impact

This project is to replace fencing at Suntree little league baseball and softball fields, laser grade four fields at Flutie Sports Complex and strip, grade and sod the baseball fields at Max K. Rodes Park.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	740,000 \$	- \$	- \$	- \$	- \$	740,000
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	- \$	740,000 \$	- \$	- \$	- \$	- \$	740,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	740,000 \$	- \$	- \$	- \$	- \$	740,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	740,000 \$	- \$	- \$	- \$	- \$	740,000

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: South Brevard Beach Crossovers
Project Total: \$1,000,000
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 6300518
District(s): 3, 4, 5

Project Description, Milestones and Service Impact

This project is to demolish, remove, and replace the Canova middle crossover, Asset #2430039, and the Flug Street crossover, Asset #640253, along with any additional crossovers requiring replacement in South Brevard. The Canova crossover is being replaced due to damage by Hurricane Nicole and the Flug Street crossover was destroyed by erosion.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	971,805 \$	28,195 \$	- \$	- \$	- \$	- \$	1,000,000
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	971,805 \$	28,195 \$	- \$	- \$	- \$	- \$	1,000,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	25,000 \$	- \$	- \$	- \$	- \$	25,000
Construction Expense	\$ - \$	- \$	975,000 \$	- \$	- \$	- \$	- \$	975,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	1,000,000 \$	- \$	- \$	- \$	- \$	1,000,000

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: South Area Parks Parking Lot Renovations
Project Total: \$640,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: N/A
District(s): 3, 4, 5

Project Description, Milestones and Service Impact

This project is to repave and stripe the parking lots at North Spessard Holland Park, Canova Park and the Wickham Park loop road.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	640,000 \$	- \$	- \$	- \$	- \$	640,000
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	- \$	640,000 \$	- \$	- \$	- \$	- \$	640,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	640,000 \$	- \$	- \$	- \$	- \$	640,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	640,000 \$	- \$	- \$	- \$	- \$	640,000

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: South Area Parks HVAC Replacements
Project Total: \$425,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: N/A
District(s): 3, 4

Project Description, Milestones and Service Impact

This is to replace the HVAC systems at South Mainland Community Center and the Viera Regional Park baseball building. Both systems have met the end of their service life.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	425,000 \$	- \$	- \$	- \$	- \$	425,000
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	- \$	425,000 \$	- \$	- \$	- \$	- \$	425,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	425,000 \$	- \$	- \$	- \$	- \$	425,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	425,000 \$	- \$	- \$	- \$	- \$	425,000

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: Suntree Rotary Large Pavilion Repairs
Project Total: \$650,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: N/A
District(s): 4

Project Description, Milestones and Service Impact

This project is to repair and renovate the bathrooms and repair and reinforce the concrete block structure at the Suntree Rotary Park large pavilion.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	650,000 \$	- \$	- \$	- \$	- \$	650,000
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	- \$	650,000 \$	- \$	- \$	- \$	- \$	650,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	650,000 \$	- \$	- \$	- \$	- \$	650,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	650,000 \$	- \$	- \$	- \$	- \$	650,000

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: ARPA Capital Improvements for Parks in South Area
Project Total: \$3,500,000
Project Timeline: October 25, 2022 through September 30, 2025
Funded Program: 6300516
District(s): 3, 5

Project Description, Milestones and Service Impact

This project is to invest ARPA revenue replacement funds to improve infrastructure at Hoover Middle School and Flutie Athletic Complex. Potential improvements at Hoover Middle School could include, renovating the soccer fields, demolish and remove softball fields, Asset # 640553 and #640552, and exercise trail, Asset #640301, and replace existing ball field lighting, installing new restroom, relocating irrigation pump and well, installing a new playground with shade structure, perimeter fencing, constructing a new basketball court, installing bleachers and expanding and improving parking. Athletic field lighting to the multi-purpose field at Flutie Athletic Complex is also scheduled.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges for Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ 3,500,000	- \$	- \$	- \$	- \$	- \$	- \$	3,500,000
Other Financing Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ 3,500,000	- \$	- \$	- \$	- \$	- \$	- \$	3,500,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ 1,650	\$ 31,321	- \$	- \$	- \$	- \$	- \$	32,971
Construction Expense	\$ 24,841	\$ 1,697,102	\$ 1,745,086	- \$	- \$	- \$	- \$	3,467,029
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ 26,491	\$ 1,728,423	\$ 1,745,086	- \$	- \$	- \$	- \$	3,500,000

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: Viera Regional Park Outdoor Fitness Trail
Project Total: \$57,625
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 6568406
District(s): 4

Project Description, Milestones and Service Impact

This project is to add ten pieces of outdoor fitness equipment to the current pedestrian trail at Viera Regional Park.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 57,625	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 57,625
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 57,625	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 57,625
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 57,625	\$ -	\$ -	\$ -	\$ -	\$ 57,625
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 57,625	\$ -	\$ -	\$ -	\$ -	\$ 57,625

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: Long Point Park Ranger Station and Maintenance Building
Project Total: \$1,196,770
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6518310
District(s): 3

Project Description, Milestones and Service Impact

This project is to demolish and remove the current ranger station and maintenance buildings, both built in the 1960's. Neither building has Asset numbers. This project is to construct one building that will serve as a combined ranger station and maintenance facility. Combining both buildings into one building will reduce construction costs. The current ranger station is too small to support the needs of the park and due to increased sizes in RV's, the building needs to be relocated. The building will also be used to store equipment and supplies as well as office and workspace for the maintenance staff. The new facility would be set back further from the road and would allow for better traffic flow at the entrance of the park.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 348,959	\$ 97,948	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 446,907
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ 349,863	\$ -	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ 749,863
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 698,822	\$ 97,948	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ 1,196,770
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 28,629	\$ -	\$ 59,500	\$ -	\$ -	\$ -	\$ -	\$ 88,129
Construction Expense	\$ -	\$ -	\$ 1,108,641	\$ -	\$ -	\$ -	\$ -	\$ 1,108,641
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 28,629	\$ -	\$ 1,168,141	\$ -	\$ -	\$ -	\$ -	\$ 1,196,770

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: Long Point Park Pedestrian Bridge Relocation and Boat Ramp / Dock Improvements
Project Total: \$1,218,304
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 6910300
District(s): 3

Project Description, Milestones and Service Impact

This project is to demolish, remove, and relocate the 24 year old pedestrian bridge to Scout Island at Long Point Park, Asset #2220076. The new bridge will be made of composite materials to provide a longer life span. The bridge will be moved north of the boat ramp. This will allow for boat ramp and dock improvements and the public will have easier access to the ramp and docks.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ 1,143,304	\$ 75,000	\$ -	\$ -	\$ -	\$ -	\$ 1,218,304
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 1,143,304	\$ 75,000	\$ -	\$ -	\$ -	\$ -	\$ 1,218,304
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 25,000	\$ -	\$ -	\$ -	\$ -	\$ 25,000
Construction Expense	\$ -	\$ -	\$ 1,193,304	\$ -	\$ -	\$ -	\$ -	\$ 1,193,304
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 1,218,304	\$ -	\$ -	\$ -	\$ -	\$ 1,218,304

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: Police Foundation Park Restroom Installation
Project Total: \$500,000
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 6502511
District(s): 5

Project Description, Milestones and Service Impact

This project is to install a concrete restroom facility at Police Foundation Park. The park does not currently have permanent restroom facilities.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ 500,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 500,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 500,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 500,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 500,000	\$ -	\$ -	\$ -	\$ -	\$ 500,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 500,000	\$ -	\$ -	\$ -	\$ -	\$ 500,000

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: Viera Regional Park Expansion
Project Total: \$1,986,010
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 6300418
District(s): 4

Project Description, Milestones and Service Impact

This project is to develop seven vacant acres adjacent to Viera Regional Park. This project will include 2 new multipurpose fields, a cricket pitch, increased parking, stormwater retention, drop in place restroom and irrigation. With the addition of the expanded athletic space the park will be able to serve more patrons.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 46,010	\$ 1,700,000	\$ 240,000	\$ -	\$ -	\$ -	\$ -	\$ 1,986,010
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 46,010	\$ 1,700,000	\$ 240,000	\$ -	\$ -	\$ -	\$ -	\$ 1,986,010
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 46,010	\$ -	\$ 255,913	\$ -	\$ -	\$ -	\$ -	\$ 301,923
Construction Expense	\$ -	\$ -	\$ 1,684,087	\$ -	\$ -	\$ -	\$ -	\$ 1,684,087
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 46,010	\$ -	\$ 1,940,000	\$ -	\$ -	\$ -	\$ -	\$ 1,986,010

Parks and Recreation Department

Program Name: SOUTH AREA PARKS
Project Name: Viera Regional Park Shade Structures
Project Total: \$71,365
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 6538447, 6538448
District(s): 4

Project Description, Milestones and Service Impact

This project is to provide and install new shade structures for the baseball and soccer playgrounds at Viera Regional Park. The shade structure will allow increased use by patrons and also aid in longevity of the playground structures.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges for Services Revenue	\$ -	\$ 71,365	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 71,365
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 71,365	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 71,365
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 71,365	\$ -	\$ -	\$ -	\$ -	\$ 71,365
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 71,365	\$ -	\$ -	\$ -	\$ -	\$ 71,365

Tourism Development Office

Program Name: TOURISM DEVELOPMENT
Project Name: Mid Reach Beach Access Easement
Project Total: \$1,000,000
Project Timeline: October 1, 2024 to September 30, 2025
Funded Program: N/A
District(s): Multiple

Project Description, Milestones and Service Impact

Expenses associated with resolution of access to properties for the purpose of dune repair and beach (sand) renourishment. Capitalized expense under land general ledger account.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Donations Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Tourist Development Tax Revenue	\$ -	\$ -	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ 1,000,000
Total Revenue	\$ -	\$ -	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ 1,000,000
Land Expense	\$ -	\$ -	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ 1,000,000
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ 1,000,000

Schedule of Potable Water and Sanitary Sewer Improvements

SEPTIC REMOVAL-NORTH-SOUTH BEACHES A

NATURAL RESOURCES DEPARTMENT

NATRES-SOIRL-013

PROGRAM NAME: SAVE OUR INDIAN RIVER LAGOON

PROJECT NAME: SEPTIC REMOVAL-NORTH-SOUTH BEACHES A

Project Total: \$4,411,720.00

Project Timeline: October 01, 2020 through December 31, 2026

Funded Program: 6572504

District(s): 5

Project Description, Milestones and Service Impact

Septic to sewer project for 37 properties. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessment Revenues	\$ -							\$ -
Sales Tax Revenue	\$ 418,000	\$ 1,922,144						\$ 2,340,144
Unfunded	\$ -							\$ -
Grant Revenue	\$ -	\$ 1,165,236						\$ 1,165,236
ARPA Funding	\$ 906,340							\$ 906,340
Total Revenue	\$ 1,324,340	\$ 3,087,380	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 4,411,720
Land Expense	\$ -	\$ 50,000						\$ 50,000
Planning/Design Expense	\$ 80,087							\$ 80,087
Construction Expense		\$ -	\$ 888,000	\$ -		\$ -	\$ -	\$ 888,000
Other Expense	\$ 18,000	\$ 1,328,000	\$ 1,613,236	\$ 234,437	\$ 199,960			\$ 3,393,633
Total Expense	\$ 98,087	\$ 1,378,000	\$ 2,501,236	\$ 234,437	\$ 199,960	\$ -	\$ -	\$ 4,411,720

FY 25 APPROVED BUDGET - INTERNAL CIP SHEETS ONLY

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON

Project Name: SEPTIC REMOVAL-NORTH-SHARPES A

Project Total: \$10,966,513

Project Timeline: October 01, 2021 through December 31, 2028

Funded Program: 6572101

District(s): 1

Project Description, Milestones and Service Impact

Septic to sewer project for 186 properties. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 1,245,000	\$ 3,094,513	\$ 6,627,000	\$ -	\$ -	\$ -	\$ -	\$ 10,966,513
Total Revenue	\$ 1,245,000	\$ 3,094,513	\$ 6,627,000	\$ -	\$ -	\$ -	\$ -	\$ 10,966,513
Land Expense	\$ -	\$ 50,000	\$ 150,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Planning/Design Expense	\$ 205,631	\$ 227,833	\$ 95,841	\$ -	\$ -	\$ -	\$ -	\$ 529,305
Construction Expense	\$ -	\$ -	\$ 3,000,000	\$ 3,000,000	\$ 3,388,095	\$ 849,113	\$ -	\$ 10,237,208
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 205,631	\$ 277,833	\$ 3,245,841	\$ 3,000,000	\$ 3,388,095	\$ 849,113	\$ -	\$ 10,966,513

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-NORTH-SHARPES B
Project Total: \$5,745,779
Project Timeline: October 01, 2021 through December 31, 2026
Funded Program: 6572102
District(s): 1

Project Description, Milestones and Service Impact

Septic to sewer project for 135 properties. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 810,000	\$ 1,838,024	\$ 3,097,755	\$ -	\$ -	\$ -	\$ -	\$ 5,745,779
Total Revenue	\$ 810,000	\$ 1,838,024	\$ 3,097,755	\$ -	\$ -	\$ -	\$ -	\$ 5,745,779
Land Expense	\$ -	\$ 50,000	\$ 80,000	\$ -	\$ -	\$ -	\$ -	\$ 130,000
Planning/Design Expense	\$ 148,420	\$ 200,000	\$ 70,000	\$ -	\$ -	\$ -	\$ -	\$ 418,420
Construction Expense	\$ -	\$ 500,000	\$ 1,777,359	\$ 2,920,000	\$ -	\$ -	\$ -	\$ 5,197,359
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 148,420	\$ 750,000	\$ 1,927,359	\$ 2,920,000	\$ -	\$ -	\$ -	\$ 5,745,779

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-NORTH-COCOA C
Project Total: \$3,960,150
Project Timeline: October 01, 2021 through December 31, 2026
Funded Program: 6572103
District(s): 1

Project Description, Milestones and Service Impact

Septic to sewer project for 61 properties. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 800,000	\$ 3,160,150	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 3,960,150
Total Revenue	\$ 800,000	\$ 3,160,150	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 3,960,150
Land Expense	\$ -	\$ -	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 50,000
Planning/Design Expense	\$ 264,612	\$ 535,388	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 900,000
Construction Expense	\$ -	\$ -	\$ 1,510,150	\$ 1,500,000	\$ -	\$ -	\$ -	\$ 3,010,150
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 264,612	\$ 535,388	\$ 1,660,150	\$ 1,500,000	\$ -	\$ -	\$ -	\$ 3,960,150

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-BANANA-SYKES CREEK T
Project Total: \$8,753,466
Project Timeline: May 18, 2017 through December 31, 2026
Funded Program: 6572203
District(s): 2

Project Description, Milestones and Service Impact

Septic to sewer project for 148 properties in Merritt Island. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	2,732,880	\$ -	\$ -	\$ -	\$ -	\$ -	2,732,880
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 5,040,000	\$ 980,586	\$ -	\$ -	\$ -	\$ -	\$ -	6,020,586
Total Revenue	\$ 5,040,000	\$ 3,713,466	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 8,753,466
Land Expense	\$ 50,480	\$ -	110,000	\$ -	\$ -	\$ -	\$ -	160,480
Planning/Design Expense	\$ 393,810	110,000	\$ -	\$ -	\$ -	\$ -	\$ -	503,810
Construction Expense	\$ -	\$ -	7,017,241	\$ -	\$ -	\$ -	\$ -	7,017,241
Other Expense	\$ -	\$ -	\$ -	1,071,935	\$ -	\$ -	\$ -	1,071,935
Total Expense	\$ 444,290	\$ 110,000	\$ 7,127,241	\$ 1,071,935	\$ -	\$ -	\$ -	\$ 8,753,466

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-BANANA-SYKES CREEK N
Project Total: \$7,591,501
Project Timeline: December 19, 2017 through December 31, 2026
Funded Program: 6572204
District(s): 2

Project Description, Milestones and Service Impact

Septic to sewer project for 91 properties in Merritt Island. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	2,603,016	\$ -	\$ -	\$ -	\$ -	\$ -	2,603,016
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 4,176,000	\$ 812,485	\$ -	\$ -	\$ -	\$ -	\$ -	4,988,485
Total Revenue	\$ 4,176,000	\$ 3,415,501	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 7,591,501
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 278,243	50,000	\$ -	\$ -	\$ -	\$ -	\$ -	328,243
Construction Expense	\$ -	\$ -	6,660,242	238,516	\$ -	\$ -	\$ -	6,898,758
Other Expense	\$ -	\$ -	\$ -	364,500	\$ -	\$ -	\$ -	364,500
Total Expense	\$ 278,243	\$ 50,000	\$ 6,660,242	\$ 603,016	\$ -	\$ -	\$ -	\$ 7,591,501

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-BANANA-SYKES CREEK M
Project Total: \$5,513,666
Project Timeline: May 18, 2017 through December 31, 2027
Funded Program: 6572205
District(s): 2

Project Description, Milestones and Service Impact

Septic to sewer project for 56 properties on East Merritt Island. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 423,936	\$ 1,868,000	\$ -	\$ -	\$ -	\$ -	\$ 2,291,936
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 2,697,000	\$ 524,730	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 3,221,730
Total Revenue	\$ 2,697,000	\$ 948,666	\$ 1,868,000	\$ -	\$ -	\$ -	\$ -	\$ 5,513,666
Land Expense	\$ 429,859	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 429,859
Planning/Design Expense	\$ 381,365	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 431,365
Construction Expense	\$ -	\$ -	\$ 3,860,506	\$ -	\$ -	\$ -	\$ -	\$ 3,860,506
Other Expense	\$ -	\$ -	\$ -	\$ 343,000	\$ 448,936	\$ -	\$ -	\$ 791,936
Total Expense	\$ 811,224	\$ 50,000	\$ 3,860,506	\$ 343,000	\$ 448,936	\$ -	\$ -	\$ 5,513,666

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-BANANA-SOUTH BANANA B
Project Total: \$3,280,287
Project Timeline: October 01, 2021 through December 31, 2026
Funded Program: 6572208
District(s): 2

Project Description, Milestones and Service Impact

Septic to sewer project for 41 properties in Merritt Island. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the State.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 1,368,252	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,368,252
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 1,372,500	\$ 539,535	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,912,035
Total Revenue	\$ 1,372,500	\$ 1,907,787	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 3,280,287
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 88,139	\$ 11,861	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Construction Expense	\$ -	\$ 200,000	\$ 2,830,287	\$ -	\$ -	\$ -	\$ -	\$ 3,030,287
Other Expense	\$ -	\$ -	\$ -	\$ 150,000	\$ -	\$ -	\$ -	\$ 150,000
Total Expense	\$ 88,139	\$ 211,861	\$ 2,830,287	\$ 150,000	\$ -	\$ -	\$ -	\$ 3,280,287

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-BANANA-MERRITT ISLAND C
Project Total: \$2,865,325
Project Timeline: October 01, 2021 through December 31, 2026
Funded Program: 6572209
District(s): 2

Project Description, Milestones and Service Impact

Septic to sewer project for 43 properties in Merritt Island. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	720,000	\$ -	\$ -	\$ -	\$ -	\$ -	720,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 862,500	1,282,825	\$ -	\$ -	\$ -	\$ -	\$ -	2,145,325
Total Revenue	\$ 862,500	2,002,825	\$ -	\$ -	\$ -	\$ -	\$ -	2,865,325
Land Expense	\$ -	50,000	\$ -	\$ -	\$ -	\$ -	\$ -	50,000
Planning/Design Expense	\$ 151,858	61,022	\$ -	\$ -	\$ -	\$ -	\$ -	212,880
Construction Expense	\$ -	\$ -	2,422,445	\$ -	\$ -	\$ -	\$ -	2,422,445
Other Expense	\$ -	\$ -	\$ -	180,000	\$ -	\$ -	\$ -	180,000
Total Expense	\$ 151,858	111,022	2,422,445	180,000	\$ -	\$ -	\$ -	2,865,325

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-BANANA-MERRITT ISLAND F
Project Total: \$2,393,581
Project Timeline: October 01, 2021 through December 31, 2026
Funded Program: 6572210
District(s): 2

Project Description, Milestones and Service Impact

Septic to sewer project for 71 properties in Merritt Island. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	900,000	\$ -	\$ -	\$ -	\$ -	\$ -	900,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 100,000	1,393,581	\$ -	\$ -	\$ -	\$ -	\$ -	1,493,581
Total Revenue	\$ 100,000	2,293,581	\$ -	\$ -	\$ -	\$ -	\$ -	2,393,581
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 116,865	54,135	\$ -	\$ -	\$ -	\$ -	\$ -	171,000
Construction Expense	\$ -	\$ -	1,922,581	\$ -	\$ -	\$ -	\$ -	1,922,581
Other Expense	\$ -	\$ -	\$ -	300,000	\$ -	\$ -	\$ -	300,000
Total Expense	\$ 116,865	54,135	1,922,581	300,000	\$ -	\$ -	\$ -	2,393,581

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-BANANA-SYKES CREEK R
Project Total: \$9,327,120
Project Timeline: October 01, 2021 through December 31, 2027
Funded Program: 6572211
District(s): 2

Project Description, Milestones and Service Impact

Septic to sewer project for 221 properties in Merritt Island. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ 1,500,000	\$ -	\$ -	\$ -	\$ -	\$ 1,500,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 320,000	\$ 3,439,620	\$ 4,067,500	\$ -	\$ -	\$ -	\$ -	\$ 7,827,120
Total Revenue	\$ 320,000	\$ 3,439,620	\$ 5,567,500	\$ -	\$ -	\$ -	\$ -	\$ 9,327,120
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 335,604	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 635,604
Construction Expense	\$ -	\$ -	\$ 5,791,516	\$ 2,500,000	\$ -	\$ -	\$ -	\$ 8,291,516
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ 400,000	\$ -	\$ -	\$ 400,000
Total Expense	\$ 335,604	\$ 300,000	\$ 5,791,516	\$ 2,500,000	\$ 400,000	\$ -	\$ -	\$ 9,327,120

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-BANANA-MERRITT ISLAND G
Project Total: \$21,167,164
Project Timeline: October 01, 2021 through December 31, 2027
Funded Program: 6572212
District(s): 2

Project Description, Milestones and Service Impact

Septic to sewer project for 785 properties in Merritt Island. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ 9,383,000	\$ -	\$ -	\$ -	\$ -	\$ 9,383,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 1,650,000	\$ 7,305,456	\$ 2,828,708	\$ -	\$ -	\$ -	\$ -	\$ 11,784,164
Total Revenue	\$ 1,650,000	\$ 7,305,456	\$ 12,211,708	\$ -	\$ -	\$ -	\$ -	\$ 21,167,164
Land Expense	\$ -	\$ 600,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 600,000
Planning/Design Expense	\$ 1,987,667	\$ 917,759	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,905,426
Construction Expense	\$ -	\$ -	\$ 4,383,000	\$ 5,000,000	\$ 5,878,708	\$ -	\$ -	\$ 15,261,708
Other Expense	\$ 30	\$ -	\$ -	\$ -	\$ 2,400,000	\$ -	\$ -	\$ 2,400,030
Total Expense	\$ 1,987,697	\$ 1,517,759	\$ 4,383,000	\$ 5,000,000	\$ 8,278,708	\$ -	\$ -	\$ 21,167,164

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-BANANA-NORTH MERRITT ISLAND E
Project Total: \$5,104,711
Project Timeline: October 01, 2021 through December 31, 2026
Funded Program: 6572213
District(s): 2

Project Description, Milestones and Service Impact

Septic to sewer project for 223 properties in Merritt Island. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 727,000	\$ 4,377,711	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 5,104,711
Total Revenue	\$ 727,000	\$ 4,377,711	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 5,104,711
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 485,448	\$ 69,552	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 555,000
Construction Expense	\$ -	\$ -	\$ 2,549,711	\$ 2,000,000	\$ -	\$ -	\$ -	\$ 4,549,711
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 485,448	\$ 69,552	\$ 2,549,711	\$ 2,000,000	\$ -	\$ -	\$ -	\$ 5,104,711

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-CENTRAL-MICCO SEWER LINE EXTENSION
Project Total: \$8,153,148
Project Timeline: March 1, 2017 through September 30, 2025
Funded Program: 6572301
District(s): 3

Project Description, Milestones and Service Impact

Septic to sewer project for 29 properties in Micco. Currently in design phase. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 3,674,148	\$ 2,239,500	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 5,913,648
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 2,239,500	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,239,500
Total Revenue	\$ 5,913,648	\$ 2,239,500	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 8,153,148
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 4,060,224	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 4,060,224
Construction Expense	\$ -	\$ 3,004,153	\$ 139,033	\$ -	\$ -	\$ -	\$ -	\$ 3,143,186
Other Expense	\$ -	\$ -	\$ 949,738	\$ -	\$ -	\$ -	\$ -	\$ 949,738
Total Expense	\$ 4,060,224	\$ 3,004,153	\$ 1,088,771	\$ -	\$ -	\$ -	\$ -	\$ 8,153,148

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-CENTRAL-MICCO B
Project Total: \$10,069,652
Project Timeline: October 01, 2021 through December 31, 2026
Funded Program: 6572302
District(s): 3

Project Description, Milestones and Service Impact

Septic to sewer project for 229 properties. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 2,248,125	\$ 6,069,652	\$ 1,751,875	\$ -	\$ -	\$ -	\$ -	\$ 10,069,652
Total Revenue	\$ 2,248,125	\$ 6,069,652	\$ 1,751,875	\$ -	\$ -	\$ -	\$ -	\$ 10,069,652
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 1,780,941	\$ 467,183	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,248,124
Construction Expense	\$ -	\$ -	\$ 4,821,527	\$ 3,000,001	\$ -	\$ -	\$ -	\$ 7,821,528
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 1,780,941	\$ 467,183	\$ 4,821,527	\$ 3,000,001	\$ -	\$ -	\$ -	\$ 10,069,652

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-NORTH-SOUTH CENTRAL C
Project Total: \$14,082,306
Project Timeline: May 18, 2017 through December 31, 2025
Funded Program: 6572403
District(s): 4

Project Description, Milestones and Service Impact

Septic to sewer project for 140 properties. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 4,720,820	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 5,120,820
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 6,600,000	\$ 2,361,486	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 8,961,486
Total Revenue	\$ 11,320,820	\$ 2,761,486	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 14,082,306
Land Expense	\$ 38	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 38
Planning/Design Expense	\$ 390,074	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 390,074
Construction Expense	\$ 8,281,770	\$ 2,596,483	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 10,878,253
Other Expense	\$ -	\$ 850,000	\$ 1,963,941	\$ -	\$ -	\$ -	\$ -	\$ 2,813,941
Total Expense	\$ 8,671,882	\$ 3,446,483	\$ 1,963,941	\$ -	\$ -	\$ -	\$ -	\$ 14,082,306

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-NORTH-SOUTH CENTRAL D (BREVARD)
Project Total: \$7,508,321
Project Timeline: October 01, 2021 through December 31, 2027
Funded Program: 6572405
District(s): 4

Project Description, Milestones and Service Impact

Septic to sewer project for 94 properties. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through ground water migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ 1,025,500	\$ -	\$ -	\$ -	\$ -	\$ 1,025,500
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 4,774,500	\$ 1,708,321	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 6,482,821
Total Revenue	\$ 4,774,500	\$ 1,708,321	\$ 1,025,500	\$ -	\$ -	\$ -	\$ -	\$ 7,508,321
Land Expense	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Planning/Design Expense	\$ 239,365	\$ 412,636	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 652,001
Construction Expense	\$ -	\$ -	\$ 4,556,821	\$ 2,000,000	\$ -	\$ -	\$ -	\$ 6,556,821
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ 199,499	\$ -	\$ -	\$ 199,499
Total Expense	\$ 239,365	\$ 512,636	\$ 4,556,821	\$ 2,000,000	\$ 199,499	\$ -	\$ -	\$ 7,508,321

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-NORTH-SOUTH CENTRAL A
Project Total: \$9,919,750
Project Timeline: October 01, 2021 through December 31, 2028
Funded Program: 6572406
District(s): 4

Project Description, Milestones and Service Impact

Septic to sewer project for 101 properties. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ 3,370,572	\$ -	\$ -	\$ -	\$ -	\$ 3,370,572
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ 5,482,500	\$ 1,066,678	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 6,549,178
Total Revenue	\$ 5,482,500	\$ 1,066,678	\$ 3,370,572	\$ -	\$ -	\$ -	\$ -	\$ 9,919,750
Land Expense	\$ -	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Planning/Design Expense	\$ 30,715	\$ 100,000	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ 530,715
Construction Expense	\$ -	\$ -	\$ -	\$ 2,000,000	\$ 5,370,572	\$ 1,418,463	\$ -	\$ 8,789,035
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 500,000	\$ -	\$ 500,000
Total Expense	\$ 30,715	\$ 100,000	\$ 500,000	\$ 2,000,000	\$ 5,370,572	\$ 1,918,463	\$ -	\$ 9,919,750

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-NORTH-SOUTH BEACHES O
Project Total: \$289,418
Project Timeline: October 01, 2019 through December 31, 2025
Funded Program: 6572502
District(s): 5

Project Description, Milestones and Service Impact

Septic to sewer project for 4 properties. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ -	\$ 103,455	\$ -	\$ -	\$ -	\$ -	\$ -	103,455
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Sales Tax Revenue	\$ 133,488	\$ 52,475	\$ -	\$ -	\$ -	\$ -	\$ -	185,963
Total Revenue	\$ 133,488	\$ 155,930	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 289,418
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 18,243	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	18,243
Construction Expense	\$ -	\$ -	\$ 247,175	\$ -	\$ -	\$ -	\$ -	247,175
Other Expense	\$ -	\$ -	\$ 24,000	\$ -	\$ -	\$ -	\$ -	24,000
Total Expense	\$ 18,243	\$ -	\$ 271,175	\$ -	\$ -	\$ -	\$ -	\$ 289,418

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-NORTH-SOUTH BEACHES P
Project Total: \$539,031
Project Timeline: October 01, 2019 through December 31, 2025
Funded Program: 6572503
District(s): 5

Project Description, Milestones and Service Impact

Septic to sewer project for 15 properties. Consists of design and construction of main sewer line and sewer connection to private residences. This project reduces the amount of nutrient pollution entering the Indian River Lagoon from septic effluent through groundwater migration and will assist the county in meeting nutrient load reductions mandated by the state.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ 120,615	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	120,615
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Sales Tax Revenue	\$ 300,348	\$ 118,068	\$ -	\$ -	\$ -	\$ -	\$ -	418,416
Total Revenue	\$ 420,963	\$ 118,068	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 539,031
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 95,485	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	95,485
Construction Expense	\$ -	\$ -	\$ 443,546	\$ -	\$ -	\$ -	\$ -	443,546
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 95,485	\$ -	\$ 443,546	\$ -	\$ -	\$ -	\$ -	\$ 539,031

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-BANANA-KELLY PARK
Project Total: \$143,100
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6502209
District(s): 2

Project Description, Milestones and Service Impact

This project is to add a new pavilion and a new restroom facility to Kelly Park East. This project will include connecting the park to the sewer line on Banana River Drive, thereby, eliminating the septic system. With the addition of the pavilion to the park, patrons will have more options for shaded cover and therefore, increasing potential revenue for the Central Area Parks Operations.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Fuel Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Sales Tax Revenue	\$ - \$	143,100 \$	- \$	- \$	- \$	- \$	- \$	143,100 \$
Total Revenue	\$ - \$	143,100 \$	- \$	- \$	- \$	- \$	- \$	143,100 \$
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Construction Expense	\$ - \$	- \$	143,100 \$	- \$	- \$	- \$	- \$	143,100 \$
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Expense	\$ - \$	- \$	143,100 \$	- \$	- \$	- \$	- \$	143,100 \$

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-BANANA-ROTARY PARK
Project Total: \$165,360
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6572214
District(s): 2

Project Description, Milestones and Service Impact

This project is to connect Rotary Park Merritt Island Nature Center to the sewer system, thereby, eliminating the use of the septic system. This project will utilize a force main to move the waste approximately 300 yards to a main sewer line on Tropical Trail and allow for the abandonment of the septic system.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Fuel Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Sales Tax Revenue	\$ - \$	165,360 \$	- \$	- \$	- \$	- \$	- \$	165,360 \$
Total Revenue	\$ - \$	165,360 \$	- \$	- \$	- \$	- \$	- \$	165,360 \$
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Construction Expense	\$ - \$	- \$	165,360 \$	- \$	- \$	- \$	- \$	165,360 \$
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Expense	\$ - \$	- \$	165,360 \$	- \$	- \$	- \$	- \$	165,360 \$

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-NORTH-MANATEE COVE
Project Total: \$38,160
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6572215
District(s): 2

Project Description, Milestones and Service Impact

This project is to connect Manatee Cove Park to the sewer system, thereby, eliminating the use of the septic system. This project will utilize a force main to move the waste to a main sewer line and allow for the abandonment of the septic system.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Fuel Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Sales Tax Revenue	\$ - \$	38,160 \$	- \$	- \$	- \$	- \$	- \$	38,160
Total Revenue	\$ - \$	38,160 \$	- \$	- \$	- \$	- \$	- \$	38,160
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	38,160 \$	- \$	- \$	- \$	- \$	38,160
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	38,160 \$	- \$	- \$	- \$	- \$	38,160

Natural Resources Management Department

Program Name: SAVE OUR INDIAN RIVER LAGOON
Project Name: SEPTIC REMOVAL-NORTH-RIVERWALK
Project Total: \$6,360
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6572407
District(s): 2

Project Description, Milestones and Service Impact

This project is to connect Riverwalk Nature Center to the sewer system, thereby, eliminating the use of the septic system. This project will utilize a force main to move the waste approximately 500 yards to a main sewer line and will allow for the abandonment of the septic system.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Fuel Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Sales Tax Revenue	\$ - \$	6,360 \$	- \$	- \$	- \$	- \$	- \$	6,360
Total Revenue	\$ - \$	6,360 \$	- \$	- \$	- \$	- \$	- \$	6,360
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	6,360 \$	- \$	- \$	- \$	- \$	6,360
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	6,360 \$	- \$	- \$	- \$	- \$	6,360

Parks and Recreation Department

Program Name: CENTRAL AREA PARKS
Project Name: Rotary Park Merritt Island Sewer Connection
Project Total: \$249,337
Project Timeline: August 1, 2021 through September 30, 2025
Funded Program: 6572214
District(s): 2

Project Description, Milestones and Service Impact

This project is to connect Rotary Park Merritt Island Nature Center to the sewer system, thereby, eliminating the use of the septic system. This project will utilize a force main to move the waste approximately 300 yards to a main sewer line on Tropical Trail and allow for the abandonment of the septic system. This does not reflect the cost share from a SOIRL grant in the amount of \$165,360.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
General Revenue	\$ 249,337	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	249,337
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Financing Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 249,337	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	249,337
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 42,740	\$ -	\$ 21,350	\$ -	\$ -	\$ -	\$ -	64,090
Construction Expense	\$ -	\$ -	\$ 185,247	\$ -	\$ -	\$ -	\$ -	185,247
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 42,740	\$ -	\$ 206,597	\$ -	\$ -	\$ -	\$ -	249,337

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Mims: Water Main Replacement of Asbestos Cement Pipe
Project Total: \$15,200,802
Project Timeline: October 1, 2013 through September 30, 2028
Funded Program: 6980111, 6980113, 6980114
District(s): 1

Project Description, Milestones and Service Impact

This project will replace the asbestos cement and thin-walled P V C pipe in the Mims water distribution system and includes changing over the water service connections from the existing pipes to the new pipes. This project will take place in seven phases. The Mims water distribution system piping includes asbestos-cement and thin-walled P V C water pipes that were installed in the 1960's. The current pipe material is conducive to breaking thus the replacement of the pipe to better material will improve the integrity of the water system.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 3,544,850	\$ -	\$ 337,912	\$ 7,766,040	\$ -	\$ -	\$ -	11,648,802
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ 3,552,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	3,552,000
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 7,096,850	\$ -	\$ 337,912	\$ 7,766,040	\$ -	\$ -	\$ -	15,200,802
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 469,043	\$ 115,650	\$ 362,348	\$ 313,117	\$ -	\$ -	\$ -	1,260,158
Construction Expense	\$ 3,899,358	\$ 153,692	\$ 2,434,671	\$ 7,452,923	\$ -	\$ -	\$ -	13,940,644
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 4,368,401	\$ 269,342	\$ 2,797,019	\$ 7,766,040	\$ -	\$ -	\$ -	15,200,802

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Mims: Water Treatment Plant Improvements
Project Total: \$7,592,250
Project Timeline: October 1, 2021 through September 30, 2028
Funded Program: 6540116
District(s): 1

Project Description, Milestones and Service Impact

This project consists of improvements to the Mims Water Treatment Plant to rehabilitate existing Infrastructure and restore the plant capacity.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 267,547	\$ 217,575	\$ 3,480,000	\$ 3,627,128	\$ -	\$ -	\$ -	7,592,250
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 267,547	\$ 217,575	\$ 3,480,000	\$ 3,627,128	\$ -	\$ -	\$ -	7,592,250
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 67,547	\$ 217,575	\$ 680,000	\$ 351,043	\$ -	\$ -	\$ -	1,316,165
Construction Expense	\$ -	\$ -	\$ 3,000,000	\$ 3,276,085	\$ -	\$ -	\$ -	6,276,085
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 67,547	\$ 217,575	\$ 3,680,000	\$ 3,627,128	\$ -	\$ -	\$ -	7,592,250

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Mims: Clarifier Replacement
Project Total: \$4,296,426
Project Timeline: October 1, 2022 through September 30, 2027
Funded Program: 6540118
District(s): 1

Project Description, Milestones and Service Impact

Major upgrade that will increase performance/efficiencies of asset 640041 at the Mims Water treatment plant. The clarifier treatment unit was built in the early 1960's and has exceeded its useful life. New turbine, rakes, stilling well and any additional steel components inside the concrete tank will have to be replaced.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 202,739	\$ 5,000	\$ 105,000	\$ 3,983,687	\$ -	\$ -	\$ -	4,296,426
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 202,739	\$ 5,000	\$ 105,000	\$ 3,983,687	\$ -	\$ -	\$ -	4,296,426
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 54,239	\$ 45,621	\$ 212,879	\$ 153,219	\$ -	\$ -	\$ -	465,958
Construction Expense	\$ -	\$ -	\$ -	\$ 3,830,468	\$ -	\$ -	\$ -	3,830,468
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 54,239	\$ 45,621	\$ 212,879	\$ 3,983,687	\$ -	\$ -	\$ -	4,296,426

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Mims: Plant Additional Wells
Project Total: \$2,227,811
Project Timeline: October 1, 2013 through September 30, 2027
Funded Program: 6983105
District(s): 1

Project Description, Milestones and Service Impact

This project consists of installing new water wells to the Mims water system. Current wells have been underperforming in their water withdrawal causing the need for the installation of new wells to meet customer water demand.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 979,811	\$ 1,248,000	\$ -	\$ -	\$ -	\$ -	\$ -	2,227,811
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 979,811	\$ 1,248,000	\$ -	\$ -	\$ -	\$ -	\$ -	2,227,811
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 879,897	\$ 59,584	\$ 65,833	\$ -	\$ -	\$ -	\$ -	1,005,314
Construction Expense	\$ -	\$ -	\$ 1,222,497	\$ -	\$ -	\$ -	\$ -	1,222,497
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 879,897	\$ 59,584	\$ 1,288,330	\$ -	\$ -	\$ -	\$ -	2,227,811

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Mims: Future Projects
Project Total: \$14,664,708
Project Timeline: October 1, 2025 through September 30, 2031
Funded Program: N/A
District(s): 1

Project Description, Milestones and Service Impact

Future Mims Projects: Electrical System Improvements, Site Lighting Improvements, Building and Facility Improvements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ 541,300	\$ 5,705,145	\$ 8,418,263	14,664,708
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ -	\$ -	\$ -	\$ -	\$ 541,300	\$ 5,705,145	\$ 8,418,263	14,664,708
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ 541,300	\$ 392,145	\$ 928,888	1,862,333
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 5,313,000	\$ 7,489,375	12,802,375
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ -	\$ -	\$ -	\$ -	\$ 541,300	\$ 5,705,145	\$ 8,418,263	14,664,708

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: North Brevard: Lift Stations
Project Total: \$15,066,360
Project Timeline: October 1, 2013 through September 30, 2032
Funded Program: 6300128
District(s): 1

Project Description, Milestones and Service Impact

This project consists of the replacement or rehabilitation of lift stations within the North Brevard collection district. Each of the lift stations identified is beyond its useful life. Rehabilitation or replacement will extend the life of the lift station and provide greater integrity of our collection system.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 2,473,520	\$ 1,363,224	\$ 200,000	\$ 1,245,000	\$ -	\$ 832,000	\$ 7,391,000	\$ 13,504,744
Other Finance Sources Revenue	\$ 26,616	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 26,616
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 1,535,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,535,000
Total Revenue	\$ 4,035,136	\$ 1,363,224	\$ 200,000	\$ 1,245,000	\$ -	\$ 832,000	\$ 7,391,000	\$ 15,066,360
Land Expense	\$ 3,583	\$ -	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ 103,583
Planning/Design Expense	\$ 33	\$ -	\$ 553,478	\$ 145,000	\$ -	\$ 32,000	\$ 991,000	\$ 1,721,511
Construction Expense	\$ 896,992	\$ 180,039	\$ 3,964,200	\$ 1,000,000	\$ -	\$ 800,000	\$ 6,400,000	\$ 13,241,231
Other Expense	\$ 35	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 35
Total Expense	\$ 900,643	\$ 180,039	\$ 4,517,678	\$ 1,245,000	\$ -	\$ 832,000	\$ 7,391,000	\$ 15,066,360

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: North Brevard: Plant Dumping Bed
Project Total: \$976,086
Project Timeline: October 1, 2017 through September 30, 2025
Funded Program: 6984108
District(s): 1

Project Description, Milestones and Service Impact

This project consists of the construction of a dumping bed at North Brevard Wastewater Treatment Plant (W W T P) for dewatering of vacuum truck debris. This dumping bed will improve operational logistics resulting in less man hours needed and less mileage to travel and cost efficiency.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 976,086	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 976,086
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 976,086	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 976,086
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 103,334	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 103,334
Construction Expense	\$ -	\$ -	\$ 872,752	\$ -	\$ -	\$ -	\$ -	\$ 872,752
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 103,334	\$ -	\$ 872,752	\$ -	\$ -	\$ -	\$ -	\$ 976,086

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: North Brevard: Headworks Bldg/Plant Improvements
Project Total: \$3,076,000
Project Timeline: October 1, 2023 through September 30, 2027
Funded Program: 6520101
District(s): 1

Project Description, Milestones and Service Impact

New structure (headworks) being added to the existing North Brevard Waste Water Treatment Plant system which will improve system performance. Includes new elevated outdoor structure with bar screen, grit removal system, piping and valving systems, electrical/controls/instrumentation and SCADA system improvements. System built off-line, thereby not affecting existing operations during construction.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 180,000	\$ 5,000	\$ 5,000	\$ 2,886,000	\$ -	\$ -	\$ -	\$ 3,076,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 180,000	\$ 5,000	\$ 5,000	\$ 2,886,000	\$ -	\$ -	\$ -	\$ 3,076,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 190,000	\$ 111,000	\$ -	\$ -	\$ -	\$ 301,000
Construction Expense	\$ -	\$ -	\$ -	\$ 2,775,000	\$ -	\$ -	\$ -	\$ 2,775,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 190,000	\$ 2,886,000	\$ -	\$ -	\$ -	\$ 3,076,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: North Brevard:Future Improvements
Project Total: \$18,837,020
Project Timeline: October 1, 2027 through September 30, 2032
Funded Program: N/A
District(s): 1

Project Description, Milestones and Service Impact

Future North Brevard projects: Electrical System Improvements, Site Lighting Improvements, Building and facility improvements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 421,928	\$ 18,415,092	\$ 18,837,020
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 421,928	\$ 18,415,092	\$ 18,837,020
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 406,928	\$ 1,895,952	\$ 2,302,880
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 16,449,140	\$ 16,449,140
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 15,000	\$ 70,000	\$ 85,000
Total Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 421,928	\$ 18,415,092	\$ 18,837,020

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Port Saint John: Lift Stations
Project Total: \$4,003,459
Project Timeline: October 1, 2019 through September 30, 2032
Funded Program: 6300129
District(s): 1

Project Description, Milestones and Service Impact

This project consists of the replacement or rehabilitation of lift stations within the Port Saint John collection district. Each of the lift stations identified are beyond their useful life. Rehabilitation or replacement will extend the life of the lift station and provide greater integrity of our collection system.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 1,022,462	\$ 61,997	\$ 1,045,000	\$ -	\$ -	\$ -	\$ 1,874,000	\$ 4,003,459
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 1,022,462	\$ 61,997	\$ 1,045,000	\$ -	\$ -	\$ -	\$ 1,874,000	\$ 4,003,459
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 27	\$ 171,690	\$ 87,500	\$ -	\$ -	\$ -	\$ 274,000	\$ 533,217
Construction Expense	\$ 653,007	\$ -	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 1,600,000	\$ 3,253,007
Other Expense	\$ 217,235	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 217,235
Total Expense	\$ 870,269	\$ 171,690	\$ 1,087,500	\$ -	\$ -	\$ -	\$ 1,874,000	\$ 4,003,459

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Port Saint John: Future Improvements
Project Total: \$55,000,000
Project Timeline: October 1, 2026 through September 30, 2031
Funded Program: N/A
District(s): 1

Project Description, Milestones and Service Impact

Future Port Saint John projects: Electrical System Improvements, Site Lighting Improvements, Building and facility improvements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ 5,000,000	\$ 15,000,000	\$ 35,000,000	\$ 55,000,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ -	\$ -	\$ 5,000,000	\$ 15,000,000	\$ 35,000,000	\$ 55,000,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ 5,000,000	\$ -	\$ -	\$ 5,000,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 15,000,000	\$ 35,000,000	\$ 50,000,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ -	\$ -	\$ 5,000,000	\$ 15,000,000	\$ 35,000,000	\$ 55,000,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Beaches: Biosolids Dewatering System
Project Total: \$6,477,912
Project Timeline: October 1, 2023 through September 30, 2026
Funded Program: 6540317
District(s): 3

Project Description, Milestones and Service Impact

Substantial upgrade to Dewatering system asset #640609, will be in the sludge dewatering building and is anticipated to be a substantial improvement to increase performance. Includes: Screw presses, feed pumps, liquid polymer system, piping and valving, conveyors or pumping systems, control panels, associated infrastructure, electrical/controls/instrumentation and SCADA system improvements, rehab of existing dewatering rooms.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 500,000	\$ 5,000	\$ 5,972,912	\$ -	\$ -	\$ -	\$ -	\$ 6,477,912
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 500,000	\$ 5,000	\$ 5,972,912	\$ -	\$ -	\$ -	\$ -	\$ 6,477,912
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 120,344	\$ 307,136	\$ 232,709	\$ -	\$ -	\$ -	\$ -	\$ 660,189
Construction Expense	\$ -	\$ -	\$ 5,817,723	\$ -	\$ -	\$ -	\$ -	\$ 5,817,723
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 120,344	\$ 307,136	\$ 6,050,432	\$ -	\$ -	\$ -	\$ -	\$ 6,477,912

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Beaches: Deep Injection Well Improvements
Project Total: \$22,130,000
Project Timeline: October 1, 2023 through September 30, 2028
Funded Program: 6540318
District(s): 3

Project Description, Milestones and Service Impact

Replacement of existing Deep Injection Well (D I W) pumps, electrical, controls, instrumentation and building improvements and associated infrastructure which is a substantial improvement to increase performance. This will increase the pumping capacity down the deep injection well. Improvements will be made to/for asset 640767.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 100,000	\$ 1,305,000	\$ -	\$ 18,725,000	\$ -	\$ -	\$ -	\$ 20,130,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 2,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,000,000
Total Revenue	\$ 100,000	\$ 3,305,000	\$ -	\$ 18,725,000	\$ -	\$ -	\$ -	\$ 22,130,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 435,000	\$ 2,970,000	\$ 720,000	\$ -	\$ -	\$ -	\$ 4,125,000
Construction Expense	\$ -	\$ -	\$ -	\$ 18,000,000	\$ -	\$ -	\$ -	\$ 18,000,000
Other Expense	\$ -	\$ -	\$ -	\$ 5,000	\$ -	\$ -	\$ -	\$ 5,000
Total Expense	\$ -	\$ 435,000	\$ 2,970,000	\$ 18,725,000	\$ -	\$ -	\$ -	\$ 22,130,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Beaches: Flow Meter Replacement
Project Total: \$75,000
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 6540502
District(s): 3

Project Description, Milestones and Service Impact

This project will change the orientation of the pipe from above ground to below ground and will improve the measuring accuracy of the FDEP required flow meter. The current flow meter configuration allows for inaccurate readings due to air entrapment.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 75,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 75,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 75,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 75,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 75,000	\$ -	\$ -	\$ -	\$ -	\$ 75,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 75,000	\$ -	\$ -	\$ -	\$ -	\$ 75,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Beaches: Future Improvements
Project Total: \$39,058,650
Project Timeline: October 1, 2025 through September 30, 2031
Funded Program: N/A
District(s): 4

Project Description, Milestones and Service Impact

Future South Beaches projects: Electrical System Improvements, Site Lighting Improvements, Building and facility improvements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ 603,200	\$ 8,810,116	\$ 9,364,075	\$ 20,281,259	\$ 39,058,650
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ -	\$ 603,200	\$ 8,810,116	\$ 9,364,075	\$ 20,281,259	\$ 39,058,650
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ 603,200	\$ 1,602,616	\$ 1,525,810	\$ 2,460,697	\$ 6,192,323
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ 7,207,500	\$ 7,838,265	\$ 17,820,562	\$ 32,866,327
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ -	\$ 603,200	\$ 8,810,116	\$ 9,364,075	\$ 20,281,259	\$ 39,058,650

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Beaches: Lift Stations
Project Total: \$22,441,835
Project Timeline: October 1, 2019 through September 30, 2032
Funded Program: 6300415
District(s): 3, 4, 5

Project Description, Milestones and Service Impact

This project consists of the replacement or rehabilitation of lift stations in upcoming fiscal years or others as conditions necessitate. Rehabilitation or replacement will extend the life of the lift station and provide greater integrity of our collection system.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 3,086,281	\$ -	\$ -	\$ 2,605,000	\$ 832,000	\$ 150,250	\$ 12,277,250	\$ 18,950,781
Other Finance Sources Revenue	\$ 72,054	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 72,054
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 3,419,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 3,419,000
Total Revenue	\$ 6,577,335	\$ -	\$ -	\$ 2,605,000	\$ 832,000	\$ 150,250	\$ 12,277,250	\$ 22,441,835
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 199,135	\$ 163,177	\$ 567,492	\$ 105,000	\$ 32,000	\$ 150,250	\$ 1,683,000	\$ 2,900,054
Construction Expense	\$ 4,446,249	\$ 47,486	\$ 1,093,529	\$ 2,900,000	\$ 800,000	\$ -	\$ 10,594,250	\$ 19,481,514
Other Expense	\$ 60,267	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 60,267
Total Expense	\$ 4,705,651	\$ 210,663	\$ 1,661,021	\$ 2,605,000	\$ 832,000	\$ 150,250	\$ 12,277,250	\$ 22,441,835

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Beaches: Plant Blower Improvements
Project Total: \$4,400,000
Project Timeline: October 1, 2019 through September 30, 2026
Funded Program: 6538314
District(s): 3

Project Description, Milestones and Service Impact

This project involves the replacement of the blowers, air piping and associated electrical and controls at the South Beach Wastewater Treatment Facility. The digester blowers will be housed in a new blower building in close vicinity of the digester. This project is needed to address aging equipment and ensure meeting Florida Department of Environmental Protection regulations.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 2,200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,200,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 2,200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,200,000
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 4,400,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 4,400,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 216,017	\$ 253,597	\$ 346,057	\$ -	\$ -	\$ -	\$ -	\$ 815,671
Construction Expense	\$ -	\$ -	\$ 3,584,329	\$ -	\$ -	\$ -	\$ -	\$ 3,584,329
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 216,017	\$ 253,597	\$ 3,930,386	\$ -	\$ -	\$ -	\$ -	\$ 4,400,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Mims: Water Treatment Plant Expansion
Project Total: \$107,000,000
Project Timeline: October 1, 2023 through September 30, 2031
Funded Program: 6984112
District(s): 1

Project Description, Milestones and Service Impact

This project consists of design and permitting of the Mims Water Treatment Plant expansion, new potable water wells, and deep injection wells if needed.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ 104,000,000	\$ -	\$ -	\$ 104,000,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ 1,500,000	\$ -	\$ -	\$ -	\$ -	\$ 1,500,000
Grant Revenue	\$ -	\$ 1,500,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,500,000
Total Revenue	\$ -	\$ 1,500,000	\$ 1,500,000	\$ -	\$ 104,000,000	\$ -	\$ -	\$ 107,000,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 3,000,000	\$ -	\$ 4,000,000	\$ -	\$ -	\$ 7,000,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ 100,000,000	\$ -	\$ -	\$ 100,000,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 3,000,000	\$ -	\$ 104,000,000	\$ -	\$ -	\$ 107,000,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Beaches: Riverside Drive Force Main Improvements
Project Total: \$16,320,000
Project Timeline: October 1, 2023 through September 30, 2026
Funded Program: 6985505
District(s): 4, 5

Project Description, Milestones and Service Impact

Force main improvements and installation of a ground storage tank at lift station B-20 with pumps (a master lift station) to the South Beaches Wastewater Treatment Facility collection system are planned to increase system resiliency and prevent sewage overflows during storm events.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ 520,000	\$ -	\$ -	\$ -	\$ 520,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 15,800,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 15,800,000
Total Revenue	\$ 15,800,000	\$ -	\$ -	\$ 520,000	\$ -	\$ -	\$ -	\$ 16,320,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 1,800,000	\$ 520,000	\$ -	\$ -	\$ -	\$ 2,320,000
Construction Expense	\$ -	\$ -	\$ 14,000,000	\$ -	\$ -	\$ -	\$ -	\$ 14,000,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 15,800,000	\$ 520,000	\$ -	\$ -	\$ -	\$ 16,320,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Integrated fixed film activated sludge (IFAS) Improvements
Project Total: \$670,000
Project Timeline: October 1, 2024 through September 30, 2027
Funded Program: 6538452
District(s): 4

Project Description, Milestones and Service Impact

This project includes an evaluation of the South Central Wastewater Treatment Plant integrated fixed film activated sludge (IFAS) system and improvements to the system performance.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ - \$	- \$	150,000 \$	520,000 \$	- \$	- \$	- \$	670,000
Other Finance Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Permit/Fees Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	- \$	150,000 \$	520,000 \$	- \$	- \$	- \$	670,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	150,000 \$	20,000 \$	- \$	- \$	- \$	170,000
Construction Expense	\$ - \$	- \$	- \$	500,000 \$	- \$	- \$	- \$	500,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	150,000 \$	520,000 \$	- \$	- \$	- \$	670,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Beaches: Wastewater Treatment Facility to (AWT)Advanced Wastewater Treatment Conversion
Project Total: \$12,000,000
Project Timeline: October 1, 2023 through September 30, 2026
Funded Program: 6540319
District(s): 3

Project Description, Milestones and Service Impact

Upgrades/Improvements Included: Plumbing, electrical, and filtration equipment are to be replaced which will be a substantial improvement to increase performance. Chlorine Contact Chamber and Disc Filter are to be relined. All work is intended to resolve hydraulic short-circuiting issues and to comply with FDEP regulations.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Finance Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Permit/Fees Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ 12,000,000 \$	- \$	- \$	- \$	- \$	- \$	- \$	12,000,000
Total Revenue	\$ 12,000,000 \$	- \$	- \$	- \$	- \$	- \$	- \$	12,000,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	30,000 \$	1,602,000 \$	- \$	- \$	- \$	- \$	1,632,000
Construction Expense	\$ - \$	- \$	10,368,000 \$	- \$	- \$	- \$	- \$	10,368,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	30,000 \$	11,970,000 \$	- \$	- \$	- \$	- \$	12,000,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Beaches: West Generator Building Electrical Improvements
Project Total: \$1,454,000
Project Timeline: October 1, 2024 through September 30, 2026
Funded Program: 6518313
District(s): 3

Project Description, Milestones and Service Impact

West Generator Building - Electrical Improvements. The existing generators and associated equipment in this portion of the facility are over thirty (30) years old and have reached the end of their service life. This project includes the installation of the following infrastructure: two new emergency generators, fuel tank(s) and monitoring system; re-feeding of the new ATS's being recommended for the west electrical system; and electrical, controls, instrumentation and SCADA improvements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ 198,200	\$ -	\$ 1,255,800	\$ -	\$ -	\$ -	\$ 1,454,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 198,200	\$ -	\$ 1,255,800	\$ -	\$ -	\$ -	\$ 1,454,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 198,200	\$ 48,300	\$ -	\$ -	\$ -	\$ 246,500
Construction Expense	\$ -	\$ -	\$ -	\$ 1,207,500	\$ -	\$ -	\$ -	\$ 1,207,500
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 198,200	\$ 1,255,800	\$ -	\$ -	\$ -	\$ 1,454,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Drainage Improvements
Project Total: \$3,819,577
Project Timeline: October 1, 2019 through September 30, 2027
Funded Program: 6957411
District(s): 4

Project Description, Milestones and Service Impact

Install underground drainage system for stormwater runoff. This project will allow for the piping of existing waterways, thus allowing for the ditches to be filled in. Existing drainage design inhibits expansion due to numerous open drainage ditches throughout property. This provides greater and more direct access throughout the site, eliminates potential trip/fall hazards, and reduces maintenance (ditch cleaning). Existing wetland equipment is failing and is in need of replacement. Improvements to include a structure to move the equipment out of the elements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 334,577	\$ -	\$ 405,000	\$ 3,080,000	\$ -	\$ -	\$ -	\$ 3,819,577
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 334,577	\$ -	\$ 405,000	\$ 3,080,000	\$ -	\$ -	\$ -	\$ 3,819,577
Land Expense	\$ -	\$ -	\$ -	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 1,000,000
Planning/Design Expense	\$ 34,577	\$ -	\$ 705,000	\$ 80,000	\$ -	\$ -	\$ -	\$ 819,577
Construction Expense	\$ -	\$ -	\$ -	\$ 2,000,000	\$ -	\$ -	\$ -	\$ 2,000,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 34,577	\$ -	\$ 705,000	\$ 3,080,000	\$ -	\$ -	\$ -	\$ 3,819,577

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: WWTP Biosolids Storage Bldg, Roll-Up Door replacement, Vac Truck
Project Total: \$2,074,182
Project Timeline: October 1, 2023 through September 30, 2026
Funded Program: 6525401, 518873
District(s): 4

Project Description, Milestones and Service Impact

This project will consist of constructing a metal storage building and access with either concrete or asphalt floor (TBD) for pressed biosolids in truck containers awaiting to be trucked to the Cocoa landfill. Currently, biosolids stored in truck containers are left in the open atmosphere causing odors. This building will reduce the travel of odors in the vicinity.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ 619,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 619,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 1,455,182	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,455,182
Total Revenue	\$ 1,455,182	\$ 619,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,074,182
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 34,787	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 34,787
Construction Expense	\$ -	\$ -	\$ 1,431,447	\$ -	\$ -	\$ -	\$ -	\$ 1,431,447
Other Expense	\$ -	\$ -	\$ 607,948	\$ -	\$ -	\$ -	\$ -	\$ 607,948
Total Expense	\$ -	\$ 34,787	\$ 2,039,395	\$ -	\$ -	\$ -	\$ -	\$ 2,074,182

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Aerator Replacement
Project Total: \$738,266
Project Timeline: October 1, 2019 through September 30, 2025
Funded Program: 6540424
District(s): 4

Project Description, Milestones and Service Impact

Replace two west aerators of the carousel treatment train. Will be a substantial improvement to increase performance.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 85,000	\$ -	\$ 5,000	\$ 648,266	\$ -	\$ -	\$ -	\$ 738,266
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 85,000	\$ -	\$ 5,000	\$ 648,266	\$ -	\$ -	\$ -	\$ 738,266
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 90,000	\$ 24,933	\$ -	\$ -	\$ -	\$ 114,933
Construction Expense	\$ -	\$ -	\$ -	\$ 623,333	\$ -	\$ -	\$ -	\$ 623,333
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 90,000	\$ 648,266	\$ -	\$ -	\$ -	\$ 738,266

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Lift Stations
Project Total: \$33,050,777
Project Timeline: October 1, 2019 through September 30, 2032
Funded Program: 6300414
District(s): 4

Project Description, Milestones and Service Impact

This project consists of the replacement or rehabilitation of lift stations within the South Central collection system in upcoming fiscal years or others as conditions necessitate. Each of the lift stations identified are beyond their useful life. Rehabilitation or replacement will extend the life of the lift station and provide greater integrity of our collection system.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 5,415,777	\$ -	\$ -	\$ 419,000	\$ 2,496,000	\$ 520,000	\$ 24,200,000	\$ 33,050,777
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 5,415,777	\$ -	\$ -	\$ 419,000	\$ 2,496,000	\$ 520,000	\$ 24,200,000	\$ 33,050,777
Land Expense	\$ 5,600	\$ -	\$ -	\$ -	\$ -	\$ 100,000	\$ -	\$ 105,600
Planning/Design Expense	\$ 26,728	\$ 102,761	\$ 412,737	\$ 319,000	\$ 96,000	\$ 420,000	\$ 3,365,000	\$ 4,742,226
Construction Expense	\$ 2,897,090	\$ -	\$ 1,230,000	\$ 100,000	\$ 2,400,000	\$ -	\$ 20,835,000	\$ 27,462,090
Other Expense	\$ 740,861	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 740,861
Total Expense	\$ 3,670,279	\$ 102,761	\$ 1,642,737	\$ 419,000	\$ 2,496,000	\$ 520,000	\$ 24,200,000	\$ 33,050,777

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Flow Meter Vault Project
Project Total: \$374,500
Project Timeline: October 1, 2022 through September 30, 2026
Funded Program: 6540420
District(s): 4

Project Description, Milestones and Service Impact

This project will change the orientation of the pipe from above ground to below ground and will improve the measuring accuracy of the FDEP required flow meter. The current flow meter configuration allows for inaccurate readings due to air entrapment.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 175,000	\$ -	\$ 199,500	\$ -	\$ -	\$ -	\$ -	\$ 374,500
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 175,000	\$ -	\$ 199,500	\$ -	\$ -	\$ -	\$ -	\$ 374,500
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 74,500	\$ -	\$ -	\$ -	\$ -	\$ 74,500
Construction Expense	\$ -	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 300,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 374,500	\$ -	\$ -	\$ -	\$ -	\$ 374,500

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Replace Plant Reuse Transfer Pumps and Controls
Project Total: \$620,000
Project Timeline: October 1, 2023 through September 30, 2026
Funded Program: 6540421
District(s): 4

Project Description, Milestones and Service Impact

Transfer pumps and controls have exceeded the design service life and are becoming more prone to failure. Replacement parts are hard to find due to age.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 100,000	\$ -	\$ -	\$ 520,000	\$ -	\$ -	\$ -	\$ 620,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 100,000	\$ -	\$ -	\$ 520,000	\$ -	\$ -	\$ -	\$ 620,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 100,000	\$ 20,000	\$ -	\$ -	\$ -	\$ 120,000
Construction Expense	\$ -	\$ -	\$ -	\$ 500,000	\$ -	\$ -	\$ -	\$ 500,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 100,000	\$ 520,000	\$ -	\$ -	\$ -	\$ 620,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Replace W A S and R A S Pump Controls
Project Total: \$2,734,213
Project Timeline: October 1, 2019 through September 30, 2025
Funded Program: 6572401
District(s): 4

Project Description, Milestones and Service Impact

This project involves the replacement of the RAS and WAS pumps and controls at the South Central Wastewater Treatment Plant (W W T P) . The existing pumps are past their life expectancy and are underperforming in their operation. Performing this project will address the age and performance of the pumps along assuring the longevity of maintaining FDEP compliance.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 2,734,213	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,734,213
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 2,734,213	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,734,213
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 211,482	\$ 56,940	\$ 36,165	\$ -	\$ -	\$ -	\$ -	\$ 304,587
Construction Expense	\$ 1,295,457	\$ 828,954	\$ 305,215	\$ -	\$ -	\$ -	\$ -	\$ 2,429,626
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 1,506,939	\$ 885,894	\$ 341,380	\$ -	\$ -	\$ -	\$ -	\$ 2,734,213

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Viera I-95 Extend Reuse Transmission (16-inch)
Project Total: \$2,467,000
Project Timeline: October 1, 2023 through September 30, 2026
Funded Program: 6540428
District(s): 4

Project Description, Milestones and Service Impact

This project extends the reclaimed water main along Viera Blvd between Stadium Pkwy and Star Rush Dr. The new line will be a combination of 16" Ductile Iron Pipe and 20" HDPE and cross under Interstate 95.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Finance Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Permit/Fees Revenue	\$ - \$	2,467,000	- \$	- \$	- \$	- \$	- \$	2,467,000
Unfunded	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	2,467,000	- \$	- \$	- \$	- \$	- \$	2,467,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	98,286	- \$	- \$	- \$	- \$	98,286
Construction Expense	\$ - \$	- \$	2,368,714	- \$	- \$	- \$	- \$	2,368,714
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	2,467,000	- \$	- \$	- \$	- \$	2,467,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Reuse System Optimization Improvements
Project Total: \$1,762,596
Project Timeline: October 1, 2021 through September 30, 2025
Funded Program: 6540409
District(s): 4

Project Description, Milestones and Service Impact

This project involves several projects to improve the level of service, integrity and operation of the South Central reclaimed water system. Performing these projects will increase the level of service to the reuse customers within this service area.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 475,044	\$ 357,146	- \$	- \$	- \$	- \$	- \$	832,190
Other Finance Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Permit/Fees Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ 930,406	- \$	- \$	- \$	- \$	- \$	- \$	930,406
Total Revenue	\$ 1,405,450	\$ 357,146	- \$	- \$	- \$	- \$	- \$	1,762,596
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ 335,044	\$ 140,000	\$ 357,146	- \$	- \$	- \$	- \$	832,190
Construction Expense	\$ 685,883	\$ 118,939	\$ 125,584	- \$	- \$	- \$	- \$	930,406
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ 1,020,927	\$ 258,939	\$ 482,730	- \$	- \$	- \$	- \$	1,762,596

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Septage And Grease Facility
Project Total: \$15,106,990
Project Timeline: October 1, 2019 through September 30, 2027
Funded Program: 6984409
District(s): 4

Project Description, Milestones and Service Impact

Utility Services will relocate the Fats, Oils and Grease Facility (FOGF) from the South Central WWTP to a new location. The process will include the following steps: (1) environmental due diligence which shows no or minimal environmental impacts, (2) a lease agreement for the area to be dedicated for the FOGF, (3) Utility Services contracts with an engineering consultant to design and permit the project, (4) advertise for bid, award, and construct. This project's benefits include (1) the design and size of a FOGF which will accommodate the volume and quality generated within Brevard County, (2) locate the facility where sludge hauling traffic to and from the landfill is reduced, and (3) greatly minimize the wastewater discharges which occur at the South Central WWTP due to the viscosity of fats, oils and grease which disrupt the wastewater treatment components and process.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ 546,990	\$ -	\$ -	\$ 14,560,000	\$ -	\$ -	\$ -	\$ 15,106,990
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 546,990	\$ -	\$ -	\$ 14,560,000	\$ -	\$ -	\$ -	\$ 15,106,990
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 60,740	\$ -	\$ 486,250	\$ 560,000	\$ -	\$ -	\$ -	\$ 1,106,990
Construction Expense	\$ -	\$ -	\$ -	\$ 14,000,000	\$ -	\$ -	\$ -	\$ 14,000,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 60,740	\$ -	\$ 486,250	\$ 14,560,000	\$ -	\$ -	\$ -	\$ 15,106,990

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Suntree Booster Station Rehabilitation
Project Total: \$2,423,958
Project Timeline: October 1, 2019 through September 30, 2025
Funded Program: 6540405
District(s): 4

Project Description, Milestones and Service Impact

This project involves the rehabilitation of the Suntree booster station. This project includes, but is not limited to, the replacement of the vertical turbine pumps, controls and rehabilitation of the storage tank. This booster station has reached the end of its useful life and these improvements will extend its service life.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 192,958	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 192,958
Grant Revenue	\$ 2,231,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,231,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 2,423,958	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,423,958
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 151,654	\$ 28,744	\$ 12,560	\$ -	\$ -	\$ -	\$ -	\$ 192,958
Construction Expense	\$ 948,889	\$ 393,171	\$ 888,940	\$ -	\$ -	\$ -	\$ -	\$ 2,231,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 1,100,543	\$ 421,915	\$ 901,500	\$ -	\$ -	\$ -	\$ -	\$ 2,423,958

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Viera Wetlands - Improvements To Pump Station and Effluent Electrical
Project Total: \$757,928
Project Timeline: October 1, 2019 through September 30, 2027
Funded Program: 6538429
District(s): 4

Project Description, Milestones and Service Impact

This project involves the replacement of the Viera Wetlands pumping station. Not only is this pump station not performing to expectation but is visible to those visiting the wetland. This project will address its performance and esthetics. Current electrical feed to the wetlands pump is insufficient for the pump size/ horse power required for operation. This project brings upgraded power from existing FPL transformers to the pump site. Presently, if the pumps must be operated, they are powered by portable generators. Completion of the project will also reduce the total hours of generator operation and free another generator for use during storm events. Existing wetland equipment is failing and is in need of replacement. Improvements to include a structure to move the equipment out of the elements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 177,928	\$ 5,000	\$ 55,000	\$ 520,000	\$ -	\$ -	\$ -	757,928
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 177,928	\$ 5,000	\$ 55,000	\$ 520,000	\$ -	\$ -	\$ -	757,928
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 117,618	\$ -	\$ 120,310	\$ 20,000	\$ -	\$ -	\$ -	257,928
Construction Expense	\$ -	\$ -	\$ -	\$ 500,000	\$ -	\$ -	\$ -	500,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 117,618	\$ -	\$ 120,310	\$ 520,000	\$ -	\$ -	\$ -	757,928

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: West Pump Room Improvements
Project Total: \$575,000
Project Timeline: October 1, 2023 through September 30, 2026
Funded Program: 6540427
District(s): 4

Project Description, Milestones and Service Impact

This project is to enclose the VFD's (motor control units), adding A/C to the enclosure to keep units cool (within building asset #620624).

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 275,000	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	575,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 275,000	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	575,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ -	\$ 29,000	\$ 50,000	\$ -	\$ -	\$ -	\$ -	79,000
Construction Expense	\$ -	\$ -	\$ 496,000	\$ -	\$ -	\$ -	\$ -	496,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ -	\$ 29,000	\$ 546,000	\$ -	\$ -	\$ -	\$ -	575,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Wickham Road and I-95 Force Main Improvements
Project Total: \$924,152
Project Timeline: October 1, 2023 through September 30, 2026
Funded Program: 6985412
District(s): 4

Project Description, Milestones and Service Impact

This project includes the installation of a new gate valve on the 30" sanitary force main near the intersection of Wickham Rd and I-95 which will increase the functionality of the system and give the ability to better isolate the system. The project will be permitted through Brevard County ROW and FDOT and the scope will include bypassing the 30" force main and the potential relocation of a portion of the adjacent 14" reuse main to allow for construction.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ 87,152	\$ -	\$ 837,000	\$ -	\$ -	\$ -	\$ 924,152
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 87,152	\$ -	\$ 837,000	\$ -	\$ -	\$ -	\$ 924,152
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 10,737	\$ 76,415	\$ 37,000	\$ -	\$ -	\$ -	\$ 124,152
Construction Expense	\$ -	\$ -	\$ -	\$ 800,000	\$ -	\$ -	\$ -	\$ 800,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 10,737	\$ 76,415	\$ 837,000	\$ -	\$ -	\$ -	\$ 924,152

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Additional Plant Reject Pond
Project Total: \$2,495,554
Project Timeline: October 1, 2021 through September 30, 2026
Funded Program: 6540423
District(s): 4

Project Description, Milestones and Service Impact

Install additional reject pond and pumping system north of the two existing storage ponds needed to optimize reclaimed water production at SCWWTP and provide additional capacity. Includes self contained pump equipment with filtering & chlorination.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ 1,600,000	\$ 53,000	\$ -	\$ 842,554	\$ -	\$ -	\$ -	\$ 2,495,554
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 1,600,000	\$ 53,000	\$ -	\$ 842,554	\$ -	\$ -	\$ -	\$ 2,495,554
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 32,234	\$ -	\$ 958,320	\$ -	\$ -	\$ -	\$ -	\$ 990,554
Construction Expense	\$ -	\$ -	\$ 657,446	\$ 842,554	\$ -	\$ -	\$ -	\$ 1,500,000
Other Expense	\$ -	\$ -	\$ 5,000	\$ -	\$ -	\$ -	\$ -	\$ 5,000
Total Expense	\$ 32,234	\$ -	\$ 1,620,766	\$ 842,554	\$ -	\$ -	\$ -	\$ 2,495,554

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Future Improvements
Project Total: \$12,131,700
Project Timeline: October 1, 2025 through September 30, 2031
Funded Program: N/A
District(s): 4

Project Description, Milestones and Service Impact

Future South Central projects: Electrical System Improvements, Site Lighting Improvements, Building and facility improvements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ 453,000	\$ 2,073,200	\$ 60,000	\$ 9,545,500	\$ 12,131,700
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ -	\$ 453,000	\$ 2,073,200	\$ 60,000	\$ 9,545,500	\$ 12,131,700
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ 308,000	\$ 113,200	\$ 60,000	\$ 1,730,500	\$ 2,211,700
Construction Expense	\$ -	\$ -	\$ -	\$ 145,000	\$ 1,960,000	\$ -	\$ 7,815,000	\$ 9,920,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ -	\$ 453,000	\$ 2,073,200	\$ 60,000	\$ 9,545,500	\$ 12,131,700

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Sykes: C03 Force Main Replacement
Project Total: \$178,483
Project Timeline: October 1, 2019 through September 30, 2025
Funded Program: 6985220
District(s): 2

Project Description, Milestones and Service Impact

This project will replace approximately 1575 feet of force main piping along Lucas and Jordan Roads in Merritt Island. The Lift Station C-03 Force Main is planned for replacement because the force main is an asbestos cement pipe (ACP) installed in 1968 beyond its life expectancy. Furthermore, the force main on Lucas Road was determined to encroach on private property and will be relocated through this replacement to be within the right of way.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 178,483	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 178,483
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 178,483	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 178,483
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 28,483	\$ -	\$ 31,975	\$ -	\$ -	\$ -	\$ -	\$ 60,458
Construction Expense	\$ -	\$ -	\$ 118,025	\$ -	\$ -	\$ -	\$ -	\$ 118,025
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 28,483	\$ -	\$ 150,000	\$ -	\$ -	\$ -	\$ -	\$ 178,483

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Central: Headworks Bldg/Plant Improvements
Project Total: \$305,000
Project Timeline: October 1, 2024 through September 30, 2026
Funded Program: 6540426
District(s): 4

Project Description, Milestones and Service Impact

This project consists of evaluating and improving the headworks system at the South Central Regional Wastewater Treatment Facility. This project is anticipated to optimize the pretreatment process for reliable treatment and operational safety.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ - \$	- \$	305,000 \$	- \$	- \$	- \$	- \$	305,000
Other Finance Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Permit/Fees Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Unfunded	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	- \$	305,000 \$	- \$	- \$	- \$	- \$	305,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	305,000 \$	- \$	- \$	- \$	- \$	305,000
Construction Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	305,000 \$	- \$	- \$	- \$	- \$	305,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Sykes: F02 Force Main Replacement
Project Total: \$230,000
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 6985411
District(s): 2

Project Description, Milestones and Service Impact

This force main will go from Lift Station F 02 to the east connecting into the force main on Banana River Drive. This force main will replace the existing force main that connects with LS F 03. This project will eliminate the existing force main located between home property lines in small access areas and relocate it in the road right-of-way providing better accessibility.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 230,000 \$	- \$	- \$	- \$	- \$	- \$	- \$	230,000
Other Finance Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Permit/Fees Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Unfunded	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ 230,000 \$	- \$	- \$	- \$	- \$	- \$	- \$	230,000
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	230,000 \$	- \$	- \$	- \$	- \$	230,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	230,000 \$	- \$	- \$	- \$	- \$	230,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Sykes: Biosolids Walkway
Project Total: \$120,000
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 517992
District(s): 2

Project Description, Milestones and Service Impact

Replacement of the walkway spanning the area between the digester and the biosolids building. This structure is greatly deteriorated and presents a safety risk for operations staff. The platform is currently affixed to both the digester and solids handling building for structural support. The structure will be designed to either repair and replace this connection or to provide independent ground support for the platform with non-structural lateral connections to each structure.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 120,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 120,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 120,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 120,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 120,000	\$ -	\$ -	\$ -	\$ -	\$ 120,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 120,000	\$ -	\$ -	\$ -	\$ -	\$ 120,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Brevard: Wastewater Treatment Plant
Project Total: \$84,010,000
Project Timeline: October 1, 2019 through September 30, 2031
Funded Program: 6520305
District(s): 3

Project Description, Milestones and Service Impact

New Wastewater Treatment Plant to serve South Brevard

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 78,000,000	\$ -	\$ 78,000,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ 1,510,000	\$ -	\$ -	\$ -	\$ -	\$ 1,510,000
Grant Revenue	\$ -	\$ 4,500,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 4,500,000
Total Revenue	\$ -	\$ 4,500,000	\$ 1,510,000	\$ -	\$ -	\$ 78,000,000	\$ -	\$ 84,010,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 6,000,000	\$ -	\$ -	\$ 3,000,000	\$ -	\$ 9,000,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 75,000,000	\$ -	\$ 75,000,000
Other Expense	\$ -	\$ -	\$ 10,000	\$ -	\$ -	\$ -	\$ -	\$ 10,000
Total Expense	\$ -	\$ -	\$ 6,010,000	\$ -	\$ -	\$ 78,000,000	\$ -	\$ 84,010,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Sykes: Replace Plant Generators & Upgrade Electrical System
Project Total: \$2,808,323
Project Timeline: October 1, 2018 through September 30, 2025
Funded Program: 6351205
District(s): 2

Project Description, Milestones and Service Impact

This project involves the replacement of the emergency power generators and its apparatus at Sykes Creek Wastewater Treatment Plant (WWTP). The benefits of this project are to assure that emergency power is available, when needed, for a major treatment plant.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 2,808,323	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	2,808,323
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 2,808,323	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	2,808,323
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 108,323	\$ 520	\$ 90,000	\$ -	\$ -	\$ -	\$ -	198,843
Construction Expense	\$ -	\$ -	\$ 2,609,480	\$ -	\$ -	\$ -	\$ -	2,609,480
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 108,323	\$ 520	\$ 2,699,480	\$ -	\$ -	\$ -	\$ -	2,808,323

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Sykes: Replace Plant Headworks
Project Total: \$7,220,150
Project Timeline: October 1, 2019 through September 30, 2025
Funded Program: 6540203
District(s): 2

Project Description, Milestones and Service Impact

This project involves the replacement of the headworks structures. The headworks is beyond its useful life and a new one is needed in order to comply with FDEP requirements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 7,220,150	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	7,220,150
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 7,220,150	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	7,220,150
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ -	\$ 71,471	\$ -	\$ -	\$ -	\$ -	\$ -	71,471
Construction Expense	\$ 4,820,150	\$ 353,851	\$ 1,974,678	\$ -	\$ -	\$ -	\$ -	7,148,679
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 4,820,150	\$ 425,322	\$ 1,974,678	\$ -	\$ -	\$ -	\$ -	7,220,150

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Sykes: Lift Stations
Project Total: \$26,610,625
Project Timeline: October 1, 2019 through September 30, 2032
Funded Program: 6300238
District(s): 2

Project Description, Milestones and Service Impact

This project consists of the replacement or rehabilitation of lift stations within the Sykes Creek collection system in upcoming fiscal years or others as conditions necessitate. Rehabilitation or replacement will extend the life of the lift station and provide greater integrity of our collection system.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 9,675,069	\$ 4,256,000	\$ 4,679,159	\$ -	\$ -	\$ -	\$ -	\$ 18,610,228
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 8,000,397	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 8,000,397
Total Revenue	\$ 17,675,466	\$ 4,256,000	\$ 4,679,159	\$ -	\$ -	\$ -	\$ -	\$ 26,610,625
Land Expense	\$ 802,390	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 802,390
Planning/Design Expense	\$ 298,766	\$ 1,987,672	\$ 1,026,200	\$ -	\$ -	\$ -	\$ -	\$ 3,312,638
Construction Expense	\$ 3,069,490	\$ 1,808,606	\$ 17,596,597	\$ -	\$ -	\$ -	\$ -	\$ 22,474,693
Other Expense	\$ 20,904	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 20,904
Total Expense	\$ 4,191,550	\$ 3,796,278	\$ 18,622,797	\$ -	\$ -	\$ -	\$ -	\$ 26,610,625

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Brevard: Water Treatment Plant Project
Project Total: \$80,010,000
Project Timeline: October 1, 2023 through September 30, 2031
Funded Program: 6520306
District(s): 3

Project Description, Milestones and Service Impact

New Water Treatment Plant to serve South Brevard

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 78,000,000	\$ -	\$ 78,000,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ 2,010,000	\$ -	\$ -	\$ -	\$ -	\$ 2,010,000
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 2,010,000	\$ -	\$ -	\$ 78,000,000	\$ -	\$ 80,010,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 2,000,000	\$ -	\$ -	\$ 3,000,000	\$ -	\$ 5,000,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 75,000,000	\$ -	\$ 75,000,000
Other Expense	\$ -	\$ -	\$ 10,000	\$ -	\$ -	\$ -	\$ -	\$ 10,000
Total Expense	\$ -	\$ -	\$ 2,010,000	\$ -	\$ -	\$ 78,000,000	\$ -	\$ 80,010,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Sykes: Future Improvements
Project Total: \$21,280,262
Project Timeline: October 1, 2025 through September 30, 2031
Funded Program: N/A
District(s): 2

Project Description, Milestones and Service Impact

Future Sykes projects: Electrical System Improvements, Site Lighting Improvements, Building and facility improvements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ 85,000	\$ 1,265,638	\$ 6,013,948	\$ 13,915,676	\$ 21,280,262
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ -	\$ 85,000	\$ 1,265,638	\$ 6,013,948	\$ 13,915,676	\$ 21,280,262
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ 85,000	\$ 565,638	\$ 457,568	\$ 1,441,846	\$ 2,550,052
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ 700,000	\$ 5,556,380	\$ 12,473,830	\$ 18,730,210
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ -	\$ 85,000	\$ 1,265,638	\$ 6,013,948	\$ 13,915,676	\$ 21,280,262

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: West Cocoa: Sewer Improvements
Project Total: \$12,692,243
Project Timeline: October 1, 2019 through September 30, 2028
Funded Program: 6300127
District(s): 4

Project Description, Milestones and Service Impact

This project will upgrade the collection system in the West Cocoa area which is part of the South Central utility service area. Upgrades include, but are not limited to, the removal and replacement of force mains and gravity sewer lines, as well as replacement or rehabilitation of the area's lift stations. This project will address the age of the infrastructure and will result in the reduction of a large portion of the I&I flows to the treatment plant. Construction for Phase 1 of 5 of this sewer improvement project is funded by a State Revolving Fund loan and includes the redesign and reconstruction of LS W-09 into a master re-pump station. This phase also includes the rehabilitation of LS W-22 to accommodate the force main pressure increases that will result from the W-09 work. Phase 2 of 5 of this sewer improvement project will include the reconstruction of LS W-15. Phase 3 of 5 of this sewer improvement project will include the reconstruction or rehabilitation of lift stations W-01 through W-05 along with the demolition of LS W-06. Phase 4 of 5 of this sewer improvement project includes the relocation of lift stations W-07 and W-08, replacement of the A-C force main from LS W-08 which is subject to frequent breaks/leaks and the rehabilitation of LS W-10. Phase 5 of 5 of this sewer improvement project will include the replacement of the existing LS W-20, the demolition of the current structure, and construction of a driveway.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 1,340,499	\$ 2,076,130	\$ 135,000	\$ 2,184,000	\$ 3,255,000	\$ 1,248,000	\$ -	\$ 10,238,629
Other Finance Sources Revenue	\$ 2,292,885	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,292,885
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ 160,729	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 160,729
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 3,794,113	\$ 2,076,130	\$ 135,000	\$ 2,184,000	\$ 3,255,000	\$ 1,248,000	\$ -	\$ 12,692,243
Land Expense	\$ 2,250	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,250
Planning/Design Expense	\$ -	\$ 53,300	\$ 490,380	\$ 84,000	\$ 255,000	\$ 48,000	\$ -	\$ 930,680
Construction Expense	\$ 3,071,393	\$ -	\$ 2,387,920	\$ 2,100,000	\$ 3,000,000	\$ 1,200,000	\$ -	\$ 11,759,313
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 3,073,643	\$ 53,300	\$ 2,878,300	\$ 2,184,000	\$ 3,255,000	\$ 1,248,000	\$ -	\$ 12,692,243

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: North Brevard: Inflow and Infiltration Prevention
Project Total: \$300,000
Project Timeline: October 1, 2022 through September 30, 2031
Funded Program: 518887
District(s): 1

Project Description, Milestones and Service Impact

This project consists of lining gravity sewers within the North Brevard Utility District. This project will decrease the amount of Inflow and Infiltration and will result in a lower probability of sewer discharge.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 100,000	\$ -	\$ -	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 300,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 100,000	\$ -	\$ -	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 300,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 100,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 300,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 100,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 300,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Port Saint John: Inflow and Infiltration Prevention
Project Total: \$1,300,000
Project Timeline: October 1, 2022 through September 30, 2031
Funded Program: 518819
District(s): 1

Project Description, Milestones and Service Impact

This project consists of lining gravity sewers within the Port Saint John Utility District. This project will decrease the amount of Inflow and Infiltration and will result in a lower probability of sewer discharge.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 100,000	\$ -	\$ -	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 300,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,000,000
Total Revenue	\$ 1,100,000	\$ -	\$ -	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 1,300,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 1,100,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 1,300,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 1,100,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 1,300,000

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: South Beaches: Inflow and Infiltration Prevention
Project Total: \$2,831,236
Project Timeline: October 1, 2022 through September 30, 2031
Funded Program: 518820
District(s): 3

Project Description, Milestones and Service Impact

This project consists of lining gravity sewers within the South Beaches Utility District. This project will decrease the amount of Inflow and Infiltration and will result in a lower probability of sewer discharge.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 1,088,645	\$ -	\$ 100,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 1,588,645
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 1,242,591	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,242,591
Total Revenue	\$ 1,088,645	\$ 1,242,591	\$ 100,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 2,831,236
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ 1,296,264	\$ 1,134,972	\$ 100,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 2,831,236
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 1,296,264	\$ 1,134,972	\$ 100,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 2,831,236

Utility Services Department

Program Name: COUNTY WATER AND WASTEWATER
Project Name: Sykes: Inflow and Infiltration Prevention
Project Total: \$2,400,000
Project Timeline: October 1, 2022 through September 30, 2031
Funded Program: 518821
District(s): 2

Project Description, Milestones and Service Impact

This project consists of lining gravity sewers within the Sykes Utility District. This project will decrease the amount of Inflow and Infiltration and will result in a lower probability of sewer discharge.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 500,000	\$ -	\$ -	\$ 100,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 900,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 1,500,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,500,000
Total Revenue	\$ 2,000,000	\$ -	\$ -	\$ 100,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 2,400,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 2,000,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 2,400,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 2,000,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 100,000	\$ 2,400,000

Utility Services Department

Program Name: BAREFOOT BAY WATER AND WASTEWATER
Project Name: Barefoot Bay Wastewater: Lift Stations
Project Total: \$3,430,332
Project Timeline: October 1, 2019 through September 30, 2032
Funded Program: 6300515
District(s): 3

Project Description, Milestones and Service Impact

This project consists of the replacement or rehabilitation of lift stations within the Barefoot Bay collection system in upcoming fiscal years or others as conditions necessitate. Rehabilitation or replacement will extend the life of the lift station and provide greater integrity of our collection system.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 619,332	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,811,000	\$ 3,430,332
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 619,332	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,811,000	\$ 3,430,332
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ 411,000	\$ 711,000
Construction Expense	\$ 2,530	\$ -	\$ 309,810	\$ -	\$ -	\$ -	\$ 2,400,000	\$ 2,712,340
Other Expense	\$ 6,992	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 6,992
Total Expense	\$ 9,522	\$ -	\$ 609,810	\$ -	\$ -	\$ -	\$ 2,811,000	\$ 3,430,332

Utility Services Department

Program Name: BAREFOOT BAY WATER AND WASTEWATER
Project Name: Barefoot Bay Water: Carbon Dioxide Replacement
Project Total: \$260,000
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 6540316
District(s): 3

Project Description, Milestones and Service Impact

The current CO2 system is undersized and replacement is needed to have better pH control to compensate for variability of lime slaker at the water production plant.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 260,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 260,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 260,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 260,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 260,000	\$ -	\$ -	\$ -	\$ -	\$ 260,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 260,000	\$ -	\$ -	\$ -	\$ -	\$ 260,000

Utility Services Department

Program Name: BAREFOOT BAY WATER AND WASTEWATER
Project Name: Barefoot Bay Wastewater: Plant Equalization Basin Improvements
Project Total: \$3,282,558
Project Timeline: October 1, 2020 through September 30, 2025
Funded Program: 6984316
District(s): 3

Project Description, Milestones and Service Impact

This project will provide the modification / rehabilitation of the headworks of the treatment plant to allow excess flow to be stored in the existing 50 MG ponds on-site. Valve replacement, structural repairs, yard piping and other accessories are involved in this project. Additional equalization volume will minimize potential plant discharges during storm events and allow greater flexibility in daily treatment operations.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 356,522	\$ 1,424,975	\$ 1,501,061	\$ -	\$ -	\$ -	\$ -	\$ 3,282,558
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 356,522	\$ 1,424,975	\$ 1,501,061	\$ -	\$ -	\$ -	\$ -	\$ 3,282,558
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 164,991	\$ 44,416	\$ 137,429	\$ -	\$ -	\$ -	\$ -	\$ 346,836
Construction Expense	\$ -	\$ -	\$ 2,935,722	\$ -	\$ -	\$ -	\$ -	\$ 2,935,722
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 164,991	\$ 44,416	\$ 3,073,151	\$ -	\$ -	\$ -	\$ -	\$ 3,282,558

Utility Services Department

Program Name: BAREFOOT BAY WATER AND WASTEWATER
Project Name: Barefoot Bay Water: Chlorine & Ammonia Feed Systems At The Booster Pump Station And Soft Starters Installation
Project Total: \$1,780,945
Project Timeline: October 1, 2019 through September 30, 2025
Funded Program: 513868
District(s): 3

Project Description, Milestones and Service Impact

This project consists of installing a chlorine and ammonia feed system at the Barefoot Bay water booster station. Included in this project are upgrades to the pumping and electrical systems that would be tied into this project. Doing this project will assure that we continually meet the Clean Water Act requirements associated with potable water.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 317,210	\$ 281,735	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 598,945
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 1,182,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,182,000
Total Revenue	\$ 1,499,210	\$ 281,735	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,780,945
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 222,210	\$ 10,043	\$ 58,928	\$ -	\$ -	\$ -	\$ -	\$ 291,181
Construction Expense	\$ -	\$ -	\$ 1,489,764	\$ -	\$ -	\$ -	\$ -	\$ 1,489,764
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 222,210	\$ 10,043	\$ 1,548,692	\$ -	\$ -	\$ -	\$ -	\$ 1,780,945

Utility Services Department

Program Name: BAREFOOT BAY WATER AND WASTEWATER
Project Name: Barefoot Bay Wastewater: Inflow and Infiltration Prevention
Project Total: \$500,000
Project Timeline: October 1, 2022 through September 30, 2031
Funded Program: 518888.0
District(s): 3

Project Description, Milestones and Service Impact

This project consists of lining gravity sewers within the Barefoot Bay Utility District. This project will decrease the amount of inflow and infiltration and will result in a lower probability of sewer discharge.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 200,000	\$ -	\$ 100,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 500,000
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 200,000	\$ -	\$ 100,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 500,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ 95,338	\$ 54,662	\$ 150,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 500,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 95,338	\$ 54,662	\$ 150,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 50,000	\$ 500,000

Schedule of Solid Waste and Hazardous Materials Improvements

Solid Waste Management Department

Program Name: DISPOSAL
Project Name: U.S. 192 Class III Waste Disposal Facility
Project Total: \$100,650,744
Project Timeline: October 1st, 2004 through September 30, 2027
Funded Program: 6567501
District(s): 5

Project Description, Milestones and Service Impact

The Sarno Road landfill will reach its final capacity in FY24 and therefore additional landfill space is needed to dispose Class III waste generated in the south County areas. The initial phase of the U.S. Hwy 192 Solid Waste Management facility will be to construct a Class III landfill disposal unit and ancillary facilities. Financing of construction is anticipated by bonds issued in FY23, FY25, FY26.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 12,977,218	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 12,977,218
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ 22,940,000	\$ -	\$ -	\$ 35,600,000	\$ 25,640,000	\$ -	\$ -	\$ 84,180,000
Other Finance Sources Revenue	\$ 3,113,820	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 3,113,820
Permit/Fees Revenue	\$ 379,706	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 379,706
Total Revenue	\$ 39,410,744	\$ -	\$ -	\$ 35,600,000	\$ 25,640,000	\$ -	\$ -	\$ 100,650,744
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 14,166,251	\$ 943,378	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 15,109,629
Construction Expense	\$ -	\$ -	\$ 23,676,688	\$ 35,844,721	\$ 25,640,000	\$ -	\$ -	\$ 85,161,409
Other Expense	\$ 379,706	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 379,706
Total Expense	\$ 14,545,957	\$ 943,378	\$ 23,676,688	\$ 35,844,721	\$ 25,640,000	\$ -	\$ -	\$ 100,650,744

Solid Waste Management Department

Program Name: DISPOSAL
Project Name: Titusville Transfer Station Replacement
Project Total: \$22,275,987
Project Timeline: October 1st, 2018 through September 30, 2026
Funded Program: 6525101
District(s): 1

Project Description, Milestones and Service Impact

The aging of the Titusville Transfer Station is such that a replacement of the facility is necessary. The cost to maintain and renovate existing facility is cost prohibitive. The project will provide Solid Waste the ability to enhance the citizens, haulers in the North area of the County and the City of Titusville access to the transfer station. Financing of construction is anticipated by bonds issued in FY23 and FY25.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 597,834	\$ 1,180,000	\$ 4,086,838	\$ 262,000	\$ -	\$ -	\$ -	\$ 6,126,672
Bond/Referendum Revenue	\$ 4,829,000	\$ 4,185,861	\$ -	\$ 7,014,000	\$ -	\$ -	\$ -	\$ 16,028,861
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ 120,454	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 120,454
Total Revenue	\$ 5,547,288	\$ 5,365,861	\$ 4,086,838	\$ 7,276,000	\$ -	\$ -	\$ -	\$ 22,275,987
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 718,288	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 718,288
Construction Expense	\$ -	\$ 6,009,000	\$ 8,534,699	\$ 7,014,000	\$ -	\$ -	\$ -	\$ 21,557,699
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 718,288	\$ 6,009,000	\$ 8,534,699	\$ 7,014,000	\$ -	\$ -	\$ -	\$ 22,275,987

Solid Waste Management Department

Program Name: DISPOSAL
Project Name: CDF Class I Slurry Wall Landfill Closure
Project Total: \$50,102,790
Project Timeline: October 1, 2022 through September 30, 2027
Funded Program: 518110
District(s): 1

Project Description, Milestones and Service Impact

Design and installation of final closure with landfill gas extraction wells at the Slurry Wall landfill as required for compliance with County's Solid Waste Permit for the Central Disposal Facility.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ 50,102,790	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 50,102,790
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 50,102,790	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 50,102,790
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Expense	\$ 29,850,537	\$ 6,712,253	\$ -	\$ 40,000	\$ 7,300,000	\$ 6,200,000	\$ -	\$ 50,102,790
Total Expense	\$ 29,850,537	\$ 6,712,253	\$ -	\$ 40,000	\$ 7,300,000	\$ 6,200,000	\$ -	\$ 50,102,790

Solid Waste Management Department

Program Name: DISPOSAL
Project Name: Sarno Class III Landfill Closure
Project Total: \$19,875,000
Project Timeline: October 1, 2024 through September 30, 2028
Funded Program: 518111
District(s): 5

Project Description, Milestones and Service Impact

Design and installation of final closure of entire Class III landfill as required by State and Federal regulations. Funds for landfill closures are held in an escrow account as required by regulations

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ 16,000,000	\$ 3,875,000	\$ -	\$ -	\$ -	\$ -	\$ 19,875,000
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit/Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 16,000,000	\$ 3,875,000	\$ -	\$ -	\$ -	\$ -	\$ 19,875,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Expense	\$ -	\$ -	\$ -	\$ 320,000	\$ 155,000	\$ 9,700,000	\$ 9,700,000	\$ 19,875,000
Total Expense	\$ -	\$ -	\$ -	\$ 320,000	\$ 155,000	\$ 9,700,000	\$ 9,700,000	\$ 19,875,000

Solid Waste Management Department

Program Name: DISPOSAL
Project Name: Central Disposal Facility Cell 3
Project Total: \$53,181,775
Project Timeline: October 1, 2026 through September 30, 2028
Funded Program: 6938106
District(s): 1

Project Description, Milestones and Service Impact

The development of the southern expansion landfill allows the Department to meet disposal needs of the County. Permitting and construction of the third Class I landfill disposal unit (cell 3) will provide County with additional capacity to meet increased needs.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ 16,000,000	\$ 34,385,000	\$ -	\$ -	\$ 50,385,000
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ 1,500,000	\$ 296,775	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ 2,796,775
Total Revenue	\$ 1,500,000	\$ 296,775	\$ 1,000,000	\$ 16,000,000	\$ 34,385,000	\$ -	\$ -	\$ 53,181,775
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 296,775	\$ 1,125,000	\$ 1,375,000	\$ -	\$ -	\$ -	\$ -	\$ 2,796,775
Construction Expense	\$ -	\$ -	\$ -	\$ 7,819,000	\$ 17,525,000	\$ 25,041,000	\$ -	\$ 50,385,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 296,775	\$ 1,125,000	\$ 1,375,000	\$ 7,819,000	\$ 17,525,000	\$ 25,041,000	\$ -	\$ 53,181,775

Solid Waste Management Department

Program Name: DISPOSAL
Project Name: Central Disposal Facility South Expansion SW Corner Straighten
Project Total: \$2,000,000
Project Timeline: October 1, 2030 through September 30, 2031
Funded Program: Not Applicable
District(s): 1

Project Description, Milestones and Service Impact

Expansion of south landfill footprint to increase Class I landfill capacity.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,000,000	\$ 2,000,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,000,000	\$ 2,000,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 200,000	\$ 200,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,800,000	\$ 1,800,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 2,000,000	\$ 2,000,000

Solid Waste Management Department

Program Name: DISPOSAL
Project Name: U.S. 192 Additional Class III Landfill Cell
Project Total: \$8,000,000
Project Timeline: October 1, 2029 through September 30, 2030
Funded Program: Not Applicable
District(s): 1

Project Description, Milestones and Service Impact

Additional cell to maintain Class III waste capacity for south County.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	8,000,000	8,000,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	8,000,000	8,000,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	300,000	300,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	7,700,000	7,700,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	8,000,000	8,000,000

Solid Waste Management Department

Program Name: DISPOSAL
Project Name: Titusville Transfer Station Entrance Improvements
Project Total: \$1,000,000
Project Timeline: October 1, 2027 through September 30, 2028
Funded Program: Not Applicable
District(s): 1

Project Description, Milestones and Service Impact

Installation of additional lane and scale at the scale house to accommodate automated weigh system.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	1,000,000	1,000,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	1,000,000	1,000,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	200,000	200,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	800,000	800,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	1,000,000	1,000,000

Solid Waste Management Department

Program Name: DISPOSAL
Project Name: CDF Leachate Storage System Expansion
Project Total: \$1,000,000
Project Timeline: October 1, 2028 through September 30, 2029
Funded Program: Not Applicable
District(s): 1

Project Description, Milestones and Service Impact

Expansion of leachate pretreatment system to accommodate higher leachate volumes due to landfill cell expansions.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	1,000,000	1,000,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	1,000,000	1,000,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	200,000	200,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	800,000	800,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	1,000,000	1,000,000

Solid Waste Management Department

Program Name: DISPOSAL
Project Name: CDF Class I South Landfill Cell 4
Project Total: \$10,000,000
Project Timeline: October 1, 2030 through September 30, 2031
Funded Program: Not Applicable
District(s): 1

Project Description, Milestones and Service Impact

Expansion of the Central Disposal Facility Class I landfill to maintain capacity requirements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	10,000,000	10,000,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	10,000,000	10,000,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	300,000	300,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	9,700,000	9,700,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	10,000,000	10,000,000

Solid Waste Management Department

Program Name: DISPOSAL
Project Name: CDF South Landfill Closure
Project Total: \$64,112,757
Project Timeline: October 1, 2047 to September 30, 2048
Funded Program: 518112
District(s): 1

Project Description, Milestones and Service Impact

Design and installation of final closure with landfill gas extraction wells at the Central Disposal Facility as required for compliance with County's Solid Waste Permit for the Central Disposal Facility. Funds for landfill closures are held in an escrow account as required by regulations

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Impact Fees Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Charges for Services Revenue	\$ - \$	- \$	869,186 \$	1,953,067 \$	2,963,484 \$	2,963,484 \$	55,363,536 \$	64,112,757
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Unfunded	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Revenue	\$ - \$	- \$	869,186 \$	1,953,067 \$	2,963,484 \$	2,963,484 \$	55,363,536 \$	64,112,757
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Construction Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Expense	\$ - \$	- \$	800,000 \$	- \$	800,000 \$	- \$	62,512,757 \$	64,112,757
Total Expense	\$ - \$	- \$	800,000 \$	- \$	800,000 \$	- \$	62,512,757 \$	64,112,757

Schedule of Transportation Improvements

Transportation Improvement Plan

5-Year Summary of Funding Source

Funding Source	2025	2026	2027	2028	2029	Total
Federal	211,099,814	114,076,212	55,081,027	20,203,816	11,947,254	414,410,123
Local	57,193,663	75,628,997	73,238,494	8,936,100	4,267,130	219,264,384
State	148,744,948	137,168,818	169,085,467	80,869,741	71,478,497	609,347,491
Total	419,038,425	326,874,047	297,406,988	110,009,657	89,692,881	1,243,021,998

Section A - Highway & Bridge Capacity

Phase	Fund Source	2025	2026	2027	2028	2029	Total
Proj# 4074023	SR 528 FROM E OF SR524(INDUSTRY) TO EAST OF SR 3				Length: 3.719 MI	*SIS*	
Type of Work:	ADD LANES & RECONSTRUCT				Lead Agency: MANAGED BY FDOT		
					LRTP #: Page 33, Goal 2		
Description:	Goes with Project No. 4074021 (PD&E Phase) & 4074024 (Design Phase)						
ROW	DI	3,044,555	0	200,240	0	0	3,244,795
ROW	BNIR	0	2,108,320	0	0	0	2,108,320
ROW	DIH	75,000	75,000	0	0	0	150,000
Total		3,119,555	2,183,320	200,240	0	0	5,503,115
	Prior Years Cost	17,843,318	Future Years Cost		Total Project Cost		23,346,433
Proj# 4074024	SR 528 FROM EAST OF SR 3 TO PORT CANAVERAL INTERCHANGE				Length: 5.091 MI	*SIS*	
Type of Work:	ADD LANES & RECONSTRUCT				Lead Agency: MANAGED BY FDOT		
					LRTP #: Page 33, Goal 2		
Description:	Goes with Project No. 4074021 (PD&E Phase) & 4074023 (Design Phase)						
ROW	BNIR	0	1,241,980	0	0	0	1,241,980
ROW	DI	454,060	0	0	0	0	454,060
ROW	DIH	60,000	20,000	0	0	0	80,000
Total		514,060	1,261,980	0	0	0	1,776,040
	Prior Years Cost	16,048,502	Future Years Cost		Total Project Cost		17,824,542
Proj# 4269052	ST JOHNS HERITAGE PKWY @ ELLIS RD FROM JOHN RHODES TO W OF WICKHAM RD				Length: 1.827 MI	*SIS*	
Type of Work:	ADD LANES & RECONSTRUCT				Lead Agency: MANAGED BY BREVARD COUNTY BOCC		
					LRTP #: Page 33, Goal 2		
Description:							
CST	LF	0	8,000,000	0	0	0	8,000,000
CST	SU	0	6,869,005	0	0	0	6,869,005
CST	TRIP	0	6,101,775	0	0	0	6,101,775
CST	CIGP	0	4,385,051	0	0	0	4,385,051
CST	SA	0	3,996,322	0	0	0	3,996,322
CST	TRWR	0	3,495,563	0	0	0	3,495,563
CST	CM	0	1,307,570	0	0	0	1,307,570
Total		0	34,155,286	0	0	0	34,155,286
	Prior Years Cost	3,302,792	Future Years Cost		Total Project Cost		37,458,078

Proj# 4372101		MALABAR RD FROM ST JOHNS HERITAGE PKWY TO MINTON RD			Length: 3.97 MI		*Non-SIS*	
Type of Work:		PD&E/EMO STUDY			Lead Agency: MANAGED BY CITY OF PALM BAY			
Description:		Off State Highway System			LRTP #: Page 215 & 216			
PE	LF	7,000,000	0	0	0	0	0	7,000,000
PE	ACSU	1,942,634	0	0	0	0	0	1,942,634
PE	TALU	476,000	0	0	0	0	0	476,000
PE	CARU	292,012	0	0	0	0	0	292,012
PE	SU	180,969	0	0	0	0	0	180,969
PE	TALT	147,385	0	0	0	0	0	147,385
Total		10,039,000	0	0	0	0	0	10,039,000
		Prior Years Cost	1,374,667	Future Years Cost		Total Project Cost		
						11,413,667		
Proj# 4379831		SR 524 FROM FRIDAY ROAD TO INDUSTRY ROAD			Length: 3.141 MI		*Non-SIS*	
Type of Work:		PD&E/EMO STUDY			Lead Agency: MANAGED BY FDOT			
Description:		Widening 2 to 4 lanes			LRTP #: Page 171			
PE	LF	5,000,000	0	0	0	0	0	5,000,000
PE	CARU	990,018	0	0	0	0	0	990,018
PE	TALU	608,949	0	0	0	0	0	608,949
PE	SU	404,320	0	0	0	0	0	404,320
PE	ACSU	399,055	0	0	0	0	0	399,055
Total		7,402,342	0	0	0	0	0	7,402,342
		Prior Years Cost	2,058,913	Future Years Cost		Total Project Cost		
						9,461,255		
Proj# 4404241		NASA CAUSEWAY BRIDGE			Length: 3.593 MI		*SIS*	
Type of Work:		BRIDGE REPLACEMENT			Lead Agency: MANAGED BY FDOT			
Description:					LRTP #: Page 142			
INC	GMR	2,000,000	0	0	0	0	0	2,000,000
Total		2,000,000	0	0	0	0	0	2,000,000
		Prior Years Cost	148,310,746	Future Years Cost		Total Project Cost		
						150,310,746		
Proj# 4372101		MALABAR RD FROM ST JOHNS HERITAGE PKWY TO MINTON RD			Length: 3.97 MI		*Non-SIS*	
Type of Work:		PD&E/EMO STUDY			Lead Agency: MANAGED BY CITY OF PALM BAY			
Description:		Off State Highway System			LRTP #: Page 215 & 216			
PE	LF	7,000,000	0	0	0	0	0	7,000,000
PE	ACSU	1,942,634	0	0	0	0	0	1,942,634
PE	TALU	476,000	0	0	0	0	0	476,000
PE	CARU	292,012	0	0	0	0	0	292,012
PE	SU	180,969	0	0	0	0	0	180,969
PE	TALT	147,385	0	0	0	0	0	147,385
Total		10,039,000	0	0	0	0	0	10,039,000
		Prior Years Cost	1,374,667	Future Years Cost		Total Project Cost		
						11,413,667		
Proj# 4379831		SR 524 FROM FRIDAY ROAD TO INDUSTRY ROAD			Length: 3.141 MI		*Non-SIS*	
Type of Work:		PD&E/EMO STUDY			Lead Agency: MANAGED BY FDOT			
Description:		Widening 2 to 4 lanes			LRTP #: Page 171			
PE	LF	5,000,000	0	0	0	0	0	5,000,000
PE	CARU	990,018	0	0	0	0	0	990,018
PE	TALU	608,949	0	0	0	0	0	608,949
PE	SU	404,320	0	0	0	0	0	404,320
PE	ACSU	399,055	0	0	0	0	0	399,055
Total		7,402,342	0	0	0	0	0	7,402,342
		Prior Years Cost	2,058,913	Future Years Cost		Total Project Cost		
						9,461,255		
Proj# 4404241		NASA CAUSEWAY BRIDGE			Length: 3.593 MI		*SIS*	
Type of Work:		BRIDGE REPLACEMENT			Lead Agency: MANAGED BY FDOT			
Description:					LRTP #: Page 142			
INC	GMR	2,000,000	0	0	0	0	0	2,000,000
Total		2,000,000	0	0	0	0	0	2,000,000
		Prior Years Cost	148,310,746	Future Years Cost		Total Project Cost		
						150,310,746		

Proj# 4372101	MALABAR RD FROM ST JOHNS HERITAGE PKWY TO MINTON RD				Length: 3.97 MI	*Non-SIS*
Type of Work:	PD&E/EMO STUDY				Lead Agency: MANAGED BY CITY OF PALM BAY	
Description: Off State Highway System				LRTP #: Page 215 & 216		
PE	LF	7,000,000	0	0	0	7,000,000
PE	ACSU	1,942,634	0	0	0	1,942,634
PE	TALU	476,000	0	0	0	476,000
PE	CARU	292,012	0	0	0	292,012
PE	SU	180,969	0	0	0	180,969
PE	TALT	147,385	0	0	0	147,385
Total		10,039,000	0	0	0	10,039,000
Prior Years Cost		1,374,667	Future Years Cost		Total Project Cost	
					11,413,667	
Proj# 4379831	SR 524 FROM FRIDAY ROAD TO INDUSTRY ROAD				Length: 3.141 MI	*Non-SIS*
Type of Work:	PD&E/EMO STUDY				Lead Agency: MANAGED BY FDOT	
Description: Widening 2 to 4 lanes				LRTP #: Page 171		
PE	LF	5,000,000	0	0	0	5,000,000
PE	CARU	990,018	0	0	0	990,018
PE	TALU	608,949	0	0	0	608,949
PE	SU	404,320	0	0	0	404,320
PE	ACSU	399,055	0	0	0	399,055
Total		7,402,342	0	0	0	7,402,342
Prior Years Cost		2,058,913	Future Years Cost		Total Project Cost	
					9,461,255	
Proj# 4404241	NASA CAUSEWAY BRIDGE				Length: 3.593 MI	*SIS*
Type of Work:	BRIDGE REPLACEMENT				Lead Agency: MANAGED BY FDOT	
Description:				LRTP #: Page 142		
INC	GMR	2,000,000	0	0	0	2,000,000
Total		2,000,000	0	0	0	2,000,000
Prior Years Cost		148,310,746	Future Years Cost		Total Project Cost	
					150,310,746	
Proj# 4372101	MALABAR RD FROM ST JOHNS HERITAGE PKWY TO MINTON RD				Length: 3.97 MI	*Non-SIS*
Type of Work:	PD&E/EMO STUDY				Lead Agency: MANAGED BY CITY OF PALM BAY	
Description: Off State Highway System				LRTP #: Page 215 & 216		
PE	LF	7,000,000	0	0	0	7,000,000
PE	ACSU	1,942,634	0	0	0	1,942,634
PE	TALU	476,000	0	0	0	476,000
PE	CARU	292,012	0	0	0	292,012
PE	SU	180,969	0	0	0	180,969
PE	TALT	147,385	0	0	0	147,385
Total		10,039,000	0	0	0	10,039,000
Prior Years Cost		1,374,667	Future Years Cost		Total Project Cost	
					11,413,667	
Proj# 4379831	SR 524 FROM FRIDAY ROAD TO INDUSTRY ROAD				Length: 3.141 MI	*Non-SIS*
Type of Work:	PD&E/EMO STUDY				Lead Agency: MANAGED BY FDOT	
Description: Widening 2 to 4 lanes				LRTP #: Page 171		
PE	LF	5,000,000	0	0	0	5,000,000
PE	CARU	990,018	0	0	0	990,018
PE	TALU	608,949	0	0	0	608,949
PE	SU	404,320	0	0	0	404,320
PE	ACSU	399,055	0	0	0	399,055
Total		7,402,342	0	0	0	7,402,342
Prior Years Cost		2,058,913	Future Years Cost		Total Project Cost	
					9,461,255	
Proj# 4404241	NASA CAUSEWAY BRIDGE				Length: 3.593 MI	*SIS*
Type of Work:	BRIDGE REPLACEMENT				Lead Agency: MANAGED BY FDOT	
Description:				LRTP #: Page 142		
INC	GMR	2,000,000	0	0	0	2,000,000
Total		2,000,000	0	0	0	2,000,000
Prior Years Cost		148,310,746	Future Years Cost		Total Project Cost	
					150,310,746	

Proj# 4372101		MALABAR RD FROM ST JOHNS HERITAGE PKWY TO MINTON RD		Length: 3.97 MI		*Non-SIS*	
Type of Work:		PD&E/EMO STUDY		Lead Agency: MANAGED BY CITY OF PALM BAY			
				LRTP #: Page 215 & 216			
Description: Off State Highway System							
PE	LF	7,000,000	0	0	0	0	7,000,000
PE	ACSU	1,942,634	0	0	0	0	1,942,634
PE	TALU	476,000	0	0	0	0	476,000
PE	CARU	292,012	0	0	0	0	292,012
PE	SU	180,969	0	0	0	0	180,969
PE	TALT	147,385	0	0	0	0	147,385
Total		10,039,000	0	0	0	0	10,039,000
Prior Years Cost		1,374,667	Future Years Cost		Total Project Cost		11,413,667
Proj# 4379831 SR 524 FROM FRIDAY ROAD TO INDUSTRY ROAD							
Type of Work:		PD&E/EMO STUDY		Length: 3.141 MI		*Non-SIS*	
				Lead Agency: MANAGED BY FDOT			
				LRTP #: Page 171			
Description: Widening 2 to 4 lanes							
PE	LF	5,000,000	0	0	0	0	5,000,000
PE	CARU	990,018	0	0	0	0	990,018
PE	TALU	608,949	0	0	0	0	608,949
PE	SU	404,320	0	0	0	0	404,320
PE	ACSU	399,055	0	0	0	0	399,055
Total		7,402,342	0	0	0	0	7,402,342
Prior Years Cost		2,058,913	Future Years Cost		Total Project Cost		9,461,255
Proj# 4404241 NASA CAUSEWAY BRIDGE							
Type of Work:		BRIDGE REPLACEMENT		Length: 3.593 MI		*SIS*	
				Lead Agency: MANAGED BY FDOT			
				LRTP #: Page 142			
Description:							
INC	GMR	2,000,000	0	0	0	0	2,000,000
Total		2,000,000	0	0	0	0	2,000,000
Prior Years Cost		148,310,746	Future Years Cost		Total Project Cost		150,310,746
Proj# 4372101 MALABAR RD FROM ST JOHNS HERITAGE PKWY TO MINTON RD							
Type of Work:		PD&E/EMO STUDY		Length: 3.97 MI		*Non-SIS*	
				Lead Agency: MANAGED BY CITY OF PALM BAY			
				LRTP #: Page 215 & 216			
Description: Off State Highway System							
PE	LF	7,000,000	0	0	0	0	7,000,000
PE	ACSU	1,942,634	0	0	0	0	1,942,634
PE	TALU	476,000	0	0	0	0	476,000
PE	CARU	292,012	0	0	0	0	292,012
PE	SU	180,969	0	0	0	0	180,969
PE	TALT	147,385	0	0	0	0	147,385
Total		10,039,000	0	0	0	0	10,039,000
Prior Years Cost		1,374,667	Future Years Cost		Total Project Cost		11,413,667
Proj# 4379831 SR 524 FROM FRIDAY ROAD TO INDUSTRY ROAD							
Type of Work:		PD&E/EMO STUDY		Length: 3.141 MI		*Non-SIS*	
				Lead Agency: MANAGED BY FDOT			
				LRTP #: Page 171			
Description: Widening 2 to 4 lanes							
PE	LF	5,000,000	0	0	0	0	5,000,000
PE	CARU	990,018	0	0	0	0	990,018
PE	TALU	608,949	0	0	0	0	608,949
PE	SU	404,320	0	0	0	0	404,320
PE	ACSU	399,055	0	0	0	0	399,055
Total		7,402,342	0	0	0	0	7,402,342
Prior Years Cost		2,058,913	Future Years Cost		Total Project Cost		9,461,255
Proj# 4404241 NASA CAUSEWAY BRIDGE							
Type of Work:		BRIDGE REPLACEMENT		Length: 3.593 MI		*SIS*	
				Lead Agency: MANAGED BY FDOT			
				LRTP #: Page 142			
Description:							
INC	GMR	2,000,000	0	0	0	0	2,000,000
Total		2,000,000	0	0	0	0	2,000,000
Prior Years Cost		148,310,746	Future Years Cost		Total Project Cost		150,310,746

Proj# 4447871		SR 401 BRIDGE REPLACEMENT		Length: 0.686 MI		*SIS*	
Type of Work:		PD&E/EMO STUDY		Lead Agency: MANAGED BY FDOT		L RTP #: Page 33, Goal 2	
Description:							
ENV	DDR	160,000	0	0	0	0	160,000
PE	DRA	0	0	0	1,000,000	0	1,000,000
Total		160,000	0	0	1,000,000	0	1,160,000
Prior Years Cost		4,050,949	Future Years Cost		Total Project Cost		5,210,949
Proj# 4533111		SR 3 N COURTENAY PKWY (CATALINA ISLE DR. TO N OF SR 528 EB RAMP5)		Length: 2.216 MI		*Non-SIS*	
Type of Work:		MEDIAN MODIFICATION		Lead Agency: MANAGED BY FDOT		L RTP #: Page 33, Goal 2	
Description:							
CST	ACSS	0	0	2,619,868	0	0	2,619,868
PE	ACSS	237,500	0	0	0	0	237,500
PE	TALT	237,500	0	0	0	0	237,500
CST	DIH	0	0	127,171	0	0	127,171
PE	DIH	23,750	0	0	0	0	23,750
Total		498,750	0	2,747,039	0	0	3,245,789
Prior Years Cost		0	Future Years Cost		Total Project Cost		3,245,789
Proj# 4534811		NORFOLK PARKWAY EXTENSION		Length: 0.00 MI		*Non-SIS*	
Type of Work:		NEW ROAD CONSTRUCTION		Lead Agency: MANAGED BY CITY OF MELBOURNE		L RTP #: Page 33, Goal 2	
Description:							
PLN	SU	750,000	0	0	0	0	750,000
Total		750,000	0	0	0	0	750,000
Prior Years Cost		0	Future Years Cost		Total Project Cost		750,000
Proj# 4535871		I-95 INTERCHANGE AT MALABAR RD		Length: 1.00 MI		*SIS*	
Type of Work:		INTERCHANGE - ADD LANES		Lead Agency: MANAGED BY FDOT		L RTP #: Page 33, Goal 2	
Description:							
PDE	ACFP	3,529,500	0	0	0	0	3,529,500
Total		3,529,500	0	0	0	0	3,529,500
Prior Years Cost		0	Future Years Cost		Total Project Cost		3,529,500
Proj# 4447871		SR 401 BRIDGE REPLACEMENT		Length: 0.686 MI		*SIS*	
Type of Work:		PD&E/EMO STUDY		Lead Agency: MANAGED BY FDOT		L RTP #: Page 33, Goal 2	
Description:							
ENV	DDR	160,000	0	0	0	0	160,000
PE	DRA	0	0	0	1,000,000	0	1,000,000
Total		160,000	0	0	1,000,000	0	1,160,000
Prior Years Cost		4,050,949	Future Years Cost		Total Project Cost		5,210,949
Proj# 4533111		SR 3 N COURTENAY PKWY (CATALINA ISLE DR. TO N OF SR 528 EB RAMP5)		Length: 2.216 MI		*Non-SIS*	
Type of Work:		MEDIAN MODIFICATION		Lead Agency: MANAGED BY FDOT		L RTP #: Page 33, Goal 2	
Description:							
CST	ACSS	0	0	2,619,868	0	0	2,619,868
PE	ACSS	237,500	0	0	0	0	237,500
PE	TALT	237,500	0	0	0	0	237,500
CST	DIH	0	0	127,171	0	0	127,171
PE	DIH	23,750	0	0	0	0	23,750
Total		498,750	0	2,747,039	0	0	3,245,789
Prior Years Cost		0	Future Years Cost		Total Project Cost		3,245,789
Proj# 4534811		NORFOLK PARKWAY EXTENSION		Length: 0.00 MI		*Non-SIS*	
Type of Work:		NEW ROAD CONSTRUCTION		Lead Agency: MANAGED BY CITY OF MELBOURNE		L RTP #: Page 33, Goal 2	
Description:							
PLN	SU	750,000	0	0	0	0	750,000
Total		750,000	0	0	0	0	750,000
Prior Years Cost		0	Future Years Cost		Total Project Cost		750,000
Proj# 4535871		I-95 INTERCHANGE AT MALABAR RD		Length: 1.00 MI		*SIS*	
Type of Work:		INTERCHANGE - ADD LANES		Lead Agency: MANAGED BY FDOT		L RTP #: Page 33, Goal 2	
Description:							
PDE	ACFP	3,529,500	0	0	0	0	3,529,500
Total		3,529,500	0	0	0	0	3,529,500
Prior Years Cost		0	Future Years Cost		Total Project Cost		3,529,500

Proj# 4447871		SR 401 BRIDGE REPLACEMENT		Length: 0.686 MI		*SIS*	
Type of Work:		PD&E/EMO STUDY		Lead Agency: MANAGED BY FDOT			
				LRTP #: Page 33, Goal 2			
Description:							
ENV	DDR	160,000	0	0	0	0	160,000
PE	DRA	0	0	0	1,000,000	0	1,000,000
Total		160,000	0	0	1,000,000	0	1,160,000
Prior Years Cost		4,050,949	Future Years Cost		Total Project Cost		
					5,210,949		
Proj# 4533111		SR 3 N COURTENAY PKWY (CATALINA ISLE DR. TO N OF SR 528 EB RAMPS)		Length: 2.216 MI		*Non-SIS*	
Type of Work:		MEDIAN MODIFICATION		Lead Agency: MANAGED BY FDOT			
				LRTP #: Page 33, Goal 2			
Description:							
CST	ACSS	0	0	2,619,868	0	0	2,619,868
PE	ACSS	237,500	0	0	0	0	237,500
PE	TALT	237,500	0	0	0	0	237,500
CST	DIH	0	0	127,171	0	0	127,171
PE	DIH	23,750	0	0	0	0	23,750
Total		498,750	0	2,747,039	0	0	3,245,789
Prior Years Cost		0	Future Years Cost		Total Project Cost		
					3,245,789		
Proj# 4534811		NORFOLK PARKWAY EXTENSION		Length: 0.00 MI		*Non-SIS*	
Type of Work:		NEW ROAD CONSTRUCTION		Lead Agency: MANAGED BY CITY OF MELBOURNE			
				LRTP #: Page 33, Goal 2			
Description:							
PLN	SU	750,000	0	0	0	0	750,000
Total		750,000	0	0	0	0	750,000
Prior Years Cost		0	Future Years Cost		Total Project Cost		
					750,000		
Proj# 4535871		I-95 INTERCHANGE AT MALABAR RD		Length: 1.00 MI		*SIS*	
Type of Work:		INTERCHANGE - ADD LANES		Lead Agency: MANAGED BY FDOT			
				LRTP #: Page 33, Goal 2			
Description:							
PDE	ACFP	3,529,500	0	0	0	0	3,529,500
Total		3,529,500	0	0	0	0	3,529,500
Prior Years Cost		0	Future Years Cost		Total Project Cost		
					3,529,500		
Proj# 4447871		SR 401 BRIDGE REPLACEMENT		Length: 0.686 MI		*SIS*	
Type of Work:		PD&E/EMO STUDY		Lead Agency: MANAGED BY FDOT			
				LRTP #: Page 33, Goal 2			
Description:							
ENV	DDR	160,000	0	0	0	0	160,000
PE	DRA	0	0	0	1,000,000	0	1,000,000
Total		160,000	0	0	1,000,000	0	1,160,000
Prior Years Cost		4,050,949	Future Years Cost		Total Project Cost		
					5,210,949		
Proj# 4533111		SR 3 N COURTENAY PKWY (CATALINA ISLE DR. TO N OF SR 528 EB RAMPS)		Length: 2.216 MI		*Non-SIS*	
Type of Work:		MEDIAN MODIFICATION		Lead Agency: MANAGED BY FDOT			
				LRTP #: Page 33, Goal 2			
Description:							
CST	ACSS	0	0	2,619,868	0	0	2,619,868
PE	ACSS	237,500	0	0	0	0	237,500
PE	TALT	237,500	0	0	0	0	237,500
CST	DIH	0	0	127,171	0	0	127,171
PE	DIH	23,750	0	0	0	0	23,750
Total		498,750	0	2,747,039	0	0	3,245,789
Prior Years Cost		0	Future Years Cost		Total Project Cost		
					3,245,789		
Proj# 4534811		NORFOLK PARKWAY EXTENSION		Length: 0.00 MI		*Non-SIS*	
Type of Work:		NEW ROAD CONSTRUCTION		Lead Agency: MANAGED BY CITY OF MELBOURNE			
				LRTP #: Page 33, Goal 2			
Description:							
PLN	SU	750,000	0	0	0	0	750,000
Total		750,000	0	0	0	0	750,000
Prior Years Cost		0	Future Years Cost		Total Project Cost		
					750,000		
Proj# 4535871		I-95 INTERCHANGE AT MALABAR RD		Length: 1.00 MI		*SIS*	
Type of Work:		INTERCHANGE - ADD LANES		Lead Agency: MANAGED BY FDOT			
				LRTP #: Page 33, Goal 2			
Description:							
PDE	ACFP	3,529,500	0	0	0	0	3,529,500
Total		3,529,500	0	0	0	0	3,529,500
Prior Years Cost		0	Future Years Cost		Total Project Cost		
					3,529,500		

Proj# 4447871	SR 401 BRIDGE REPLACEMENT				Length: 0.686 MI	*SIS*
Type of Work:	PD&E/EMO STUDY				Lead Agency: MANAGED BY FDOT	
Description:				LRTP #: Page 33, Goal 2		
ENV	DDR	160,000	0	0	0	160,000
PE	DRA	0	0	0	1,000,000	1,000,000
Total		160,000	0	0	1,000,000	1,160,000
Prior Years Cost		4,050,949	Future Years Cost		Total Project Cost	
					5,210,949	
Proj# 4533111	SR 3 N COURTENAY PKWY (CATALINA ISLE DR TO N OF SR 528 EB RAMPS)				Length: 2.216 MI	*Non-SIS*
Type of Work:	MEDIAN MODIFICATION				Lead Agency: MANAGED BY FDOT	
Description:				LRTP #: Page 33, Goal 2		
CST	ACSS	0	0	2,619,868	0	2,619,868
PE	ACSS	237,500	0	0	0	237,500
PE	TALT	237,500	0	0	0	237,500
CST	DIH	0	0	127,171	0	127,171
PE	DIH	23,750	0	0	0	23,750
Total		488,750	0	2,747,039	0	3,245,789
Prior Years Cost		0	Future Years Cost		Total Project Cost	
					3,245,789	
Proj# 4534811	NORFOLK PARKWAY EXTENSION				Length: 0.00 MI	*Non-SIS*
Type of Work:	NEW ROAD CONSTRUCTION				Lead Agency: MANAGED BY CITY OF MELBOURNE	
Description:				LRTP #: Page 33, Goal 2		
PLN	SU	750,000	0	0	0	750,000
Total		750,000	0	0	0	750,000
Prior Years Cost		0	Future Years Cost		Total Project Cost	
					750,000	
Proj# 4535871	I-95 INTERCHANGE AT MALABAR RD				Length: 1.00 MI	*SIS*
Type of Work:	INTERCHANGE - ADD LANES				Lead Agency: MANAGED BY FDOT	
Description:				LRTP #: Page 33, Goal 2		
PDE	ACFP	3,529,500	0	0	0	3,529,500
Total		3,529,500	0	0	0	3,529,500
Prior Years Cost		0	Future Years Cost		Total Project Cost	
					3,529,500	
Proj# 4538831	I-95 NORTHBOUND REST AREA (MIMS)				Length: 0.31 MI	*SIS*
Type of Work:	REST AREA				Lead Agency: MANAGED BY FDOT	
Description:				LRTP #: Page 33, Goal 2		
PE	DRA	0	0	0	1,900,000	1,900,000
Total		0	0	0	1,900,000	1,900,000
Prior Years Cost		0	Future Years Cost		Total Project Cost	
					1,900,000	
Proj# 4538851	I-95 NORTHBOUND/SOUTHBOUND REST AREA				Length: 0.329 MI	*SIS*
Type of Work:	REST AREA				Lead Agency: MANAGED BY FDOT	
Description:				LRTP #: Page 33, Goal 2		
PE	DRA	0	0	0	1,000,000	1,000,000
Total		0	0	0	1,000,000	1,000,000
Prior Years Cost		0	Future Years Cost		Total Project Cost	
					1,000,000	
Proj# 4344141	SR 514 (MALABAR RD) FROM E OF SR 507 (BABCOCK RD) TO SR 5(US1)DIXIE HW				Length: 3.524 MI	*Non-SIS*
Type of Work:	PAVEMENT ONLY RESURFACE (FLEX)				Lead Agency: MANAGED BY FDOT	
Description:				LRTP #: Page 34, Goal 4		
CST	DDR	0	0	4,243,789	0	4,243,789
PE	DS	666,000	0	0	0	666,000
CST	DIH	0	0	37,783	0	37,783
PE	DIH	33,300	0	0	0	33,300
Total		699,300	0	4,281,572	0	4,980,872
Prior Years Cost		0	Future Years Cost		Total Project Cost	
					4,980,872	

Section C - Maintenance

Phase	Fund Source	2025	2026	2027	2028	2029	Total
Proj# 4438141 SR 5 / US 1 FROM NORTH OF CENTURY OAKS CIRCLE TO NORTH OF MYERS DRIVE							
Type of Work: RESURFACING							
Description:							
Length: 3.706 MI *Non-SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	ACNR	7,619,796	0	0	0	0	7,619,796
CST	DDR	2,888,962	0	0	0	0	2,888,962
CST	DDR	681,432	0	0	0	0	681,432
CST	DIH	10,290	0	0	0	0	10,290
Total		11,200,480	0	0	0	0	11,200,480
Prior Years Cost		1,896,171	Future Years Cost		Total Project Cost		13,096,651
Proj# 4452131 SR 518 FAU GALLE BLV FROM SARNO RD TO WEST OF APOLLO BOULEVARD							
Type of Work: PAVEMENT ONLY RESURFACE (FLEX)							
Description:							
Length: 2.911 MI *Non-SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	DDR	0	7,724,298	0	0	0	7,724,298
CST	DIH	0	10,600	0	0	0	10,600
Total		0	7,734,898	0	0	0	7,734,898
Prior Years Cost		2,065,870	Future Years Cost		Total Project Cost		9,800,768
Proj# 4487851 SR 404 FROM SR 3 TO SR A1A							
Type of Work: RESURFACING							
Description:							
Length: 4.139 MI *SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	DDR	7,887,987	0	0	0	0	7,887,987
CST	DIH	10,290	0	0	0	0	10,290
Total		7,898,277	0	0	0	0	7,898,277
Prior Years Cost		1,019,386	Future Years Cost		Total Project Cost		8,917,663
Proj# 4487871 SR401 RESURFACING FROM SR528 TO CANAVERAL SPACE FORCE STATION							
Type of Work: RESURFACING							
Description:							
Length: 2.196 MI *SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	ACNR	5,659,346	0	0	0	0	5,659,346
CST	DS	2,229,669	0	0	0	0	2,229,669
CST	DDR	570,581	0	0	0	0	570,581
CST	DIH	51,450	0	0	0	0	51,450
Total		8,511,046	0	0	0	0	8,511,046
Prior Years Cost		1,338,931	Future Years Cost		Total Project Cost		9,849,977
Proj# 4487911 SR-405 FROM SR-50 TO E OF US-1							
Type of Work: PAVEMENT ONLY RESURFACE (FLEX)							
Description:							
Length: 4.543 MI *SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	DDR	14,105,194	0	0	0	0	14,105,194
CST	DIH	10,290	0	0	0	0	10,290
Total		14,115,484	0	0	0	0	14,115,484
Prior Years Cost		1,999,028	Future Years Cost		Total Project Cost		16,114,512
Proj# 4487921 SR-513 FROM SR-518 TO PATRICK AIR FORCE BASE							
Type of Work: RESURFACING							
Description:							
Length: 5.253 MI *Non-SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	ACNR	6,430,077	0	0	0	0	6,430,077
CST	SA	5,651,878	0	0	0	0	5,651,878
CST	DDR	1,050,609	0	0	0	0	1,050,609
CST	DIH	10,290	0	0	0	0	10,290
Total		13,142,854	0	0	0	0	13,142,854
Prior Years Cost		2,811,346	Future Years Cost		Total Project Cost		15,954,200

Proj# 4487931		US-1/SR-5 FROM MYERS DR TO CRANE CREEK BRIDGE #70000G		Length: 2.154 MI *Non-SIS*			
Type of Work:		RESURFACING		Lead Agency: MANAGED BY FDOT			
Description:				LRTP #: Page 34, Goal 4			
CST	DDR	4,525,543	0	0	0	0	4,525,543
CST	ACNR	2,217,658	0	0	0	0	2,217,658
CST	SU	1,754,445	0	0	0	0	1,754,445
CST	DDR	338,541	0	0	0	0	338,541
CST	DIH	30,870	0	0	0	0	30,870
Total		8,867,057	0	0	0	0	8,867,057
Prior Years Cost		2,089,560	Future Years Cost		0		Total Project Cost
Proj# 4487941		SR-5 FROM MINNIE LN TO THE VOLUSIA COUNTY LINE		Length: 8.712 MI *Non-SIS*			
Type of Work:		RESURFACING		Lead Agency: MANAGED BY FDOT			
Description:				LRTP #: Page 34, Goal 4			
CST	DDR	22,194,018	0	0	0	0	22,194,018
CST	DIH	154,350	0	0	0	0	154,350
Total		22,348,368	0	0	0	0	22,348,368
Prior Years Cost		2,179,830	Future Years Cost		0		Total Project Cost
Proj# 4488001		SR-5 FROM RAILROAD BRIDGE TO GRACE ST		Length: 1.387 MI *Non-SIS*			
Type of Work:		RESURFACING		Lead Agency: MANAGED BY FDOT			
Description:				LRTP #: Page 34, Goal 4			
CST	DDR	3,291,620	0	0	0	0	3,291,620
CST	DIH	10,290	0	0	0	0	10,290
Total		3,301,910	0	0	0	0	3,301,910
Prior Years Cost		1,118,042	Future Years Cost		0		Total Project Cost
Proj# 4489771		I-95 NB/SB FROM SR514 (MALABAR RD) TO CONCRETE JOINT N OF SR519(FISKE)		Length: 24.085 MI *SIS*			
Type of Work:		RESURFACING		Lead Agency: MANAGED BY FDOT			
Description:				LRTP #: Page 34, Goal 4			
CST	ACNP	111,860,489	0	0	0	0	111,860,489
ENV	DDR	100,000	0	0	0	0	100,000
Total		111,960,489	0	0	0	0	111,960,489
Prior Years Cost		3,713,084	Future Years Cost		0		Total Project Cost
Proj# 4505941		I-95 (SR 9) FROM SR 46 TO NORTH OF SR 46		Length: 3.00 MI *SIS*			
Type of Work:		RESURFACING		Lead Agency: MANAGED BY FDOT			
Description:				LRTP #: Page 34, Goal 4			
CST	ACNP	0	0	12,331,229	0	0	12,331,229
PE	ACNP	1,033,000	0	0	0	0	1,033,000
CST	DIH	0	0	27,325	0	0	27,325
PE	DIH	25,000	0	0	0	0	25,000
Total		1,058,000	0	12,358,554	0	0	13,416,554
Prior Years Cost		0	Future Years Cost		0		Total Project Cost
Proj# 4505951		I-95 / SR 9 FROM INDIAN RIVER COUNTY TO BABCOCK ST		Length: 12.5 MI *SIS*			
Type of Work:		RESURFACING		Lead Agency: MANAGED BY FDOT			
Description:				LRTP #: Page 34, Goal 4			
CST	ACNP	0	44,928,317	0	0	0	44,928,317
CST	DIH	0	155,976	0	0	0	155,976
Total		0	45,084,293	0	0	0	45,084,293
Prior Years Cost		1,550,000	Future Years Cost		0		Total Project Cost

Section C - Maintenance

Phase	Fund Source	2025	2026	2027	2028	2029	Total
Proj# 4506261 SR-406 FROM I-95 TO FORRELL AVE							
Type of Work: PAVEMENT ONLY RESURFACE (FLEX)							
Description:							
Length: 2.022 MI *Non-SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	DS	0	4,768,620	0	0	0	4,768,620
CST	DDR	0	539,822	0	0	0	539,822
CST	DIH	0	10,600	0	0	0	10,600
Total		0	5,319,042	0	0	0	5,319,042
Prior Years Cost		780,718	Future Years Cost	0	Total Project Cost		6,099,760
Proj# 4506271 SR-A1A FROM OAK ST TO US-192							
Type of Work: PAVEMENT ONLY RESURFACE (FLEX)							
Description:							
Length: 3.19 MI *Non-SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	DDR	0	3,803,289	0	0	0	3,803,289
CST	DIH	0	10,600	0	0	0	10,600
Total		0	3,813,889	0	0	0	3,813,889
Prior Years Cost		889,345	Future Years Cost	0	Total Project Cost		4,703,234
Proj# 4507293 SR 514 FROM WEST OF I-95 TO SR 507 / BABCOCK ST							
Type of Work: PAVEMENT ONLY RESURFACE (FLEX)							
Description:							
Length: 0.867 MI *Non-SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	DDR	0	3,475,219	0	0	0	3,475,219
CST	DIH	0	10,600	0	0	0	10,600
Total		0	3,485,819	0	0	0	3,485,819
Prior Years Cost		216,471	Future Years Cost	0	Total Project Cost		3,702,290
Proj# 4507711 I-95/SR9 FROM SOUTH OF SR50 TO SR 46							
Type of Work: RESURFACING							
Description:							
Length: 9.717 MI *SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	ACNP	0	35,715,570	0	0	0	35,715,570
CST	DIH	0	121,807	0	0	0	121,807
Total		0	35,837,377	0	0	0	35,837,377
Prior Years Cost		3,748,444	Future Years Cost	0	Total Project Cost		39,585,821
Proj# 4515941 I-95: CITRUS BLVD. TO ADDISON CANAL							
Type of Work: RESURFACING							
Description:							
Length: 7.736 MI *SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	DI	0	0	35,357,732	0	0	35,357,732
PE	ACNP	2,403,000	0	0	0	0	2,403,000
CST	DIH	0	0	27,325	0	0	27,325
PE	DIH	25,000	0	0	0	0	25,000
Total		2,428,000	0	35,385,057	0	0	37,813,057
Prior Years Cost		0	Future Years Cost	0	Total Project Cost		37,813,057

Section C - Maintenance

Phase	Fund Source	2025	2026	2027	2028	2029	Total
Proj# 4517181 SR 3 OVER BARGE CANAL MOVABLE BRIDGE REHAB							
Type of Work: BRIDGE-REPAIR/REHABILITATION							
Description:							
Length: 0.056 MI *Non-SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	BRRP	6,259,285	0	0	0	0	6,259,285
CST	DIH	2,058	0	0	0	0	2,058
Total		6,261,343	0	0	0	0	6,261,343
Prior Years Cost		809,403					
Future Years Cost			0				
Total Project Cost							7,070,746
Proj# 4526851 SR 524/SR 528 FROM W OF SYKES CREEK TO SR 401							
Type of Work: RESURFACING							
Description:							
Length: 4.315 MI *SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	ACNR	0	0	10,220,598	0	0	10,220,598
CST	SA	0	0	1,290,861	0	0	1,290,861
PE	SA	961,000	0	0	0	0	961,000
CST	DIH	0	0	102,206	0	0	102,206
PE	DIH	48,050	0	0	0	0	48,050
Total		1,009,050	0	11,613,665	0	0	12,622,715
Prior Years Cost		0					
Future Years Cost			0				
Total Project Cost							12,622,715
Proj# 4526881 SR 41A FROM SR 520 TO GEORGE KING BLVD							
Type of Work: PAVEMENT ONLY RESURFACE (FLEX)							
Description:							
Length: 3.109 MI *Non-SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	DDR	0	0	6,403,362	0	0	6,403,362
PE	DS	677,000	0	0	0	0	677,000
CST	DIH	0	0	57,363	0	0	57,363
PE	DIH	33,850	0	0	0	0	33,850
Total		710,850	0	6,460,725	0	0	7,171,575
Prior Years Cost		0					
Future Years Cost			0				
Total Project Cost							7,171,575
Proj# 4528641 SR507 FR S OF LK IN THE WOODS DR/SUN LAKE RD TO SR500(US192)/NEW HAVEN							
Type of Work: PAVEMENT ONLY RESURFACE (FLEX)							
Description:							
Length: 2.628 MI *Non-SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	DS	0	0	5,883,620	0	0	5,883,620
CST	DDR	0	0	684,265	0	0	684,265
PE	DS	660,000	0	0	0	0	660,000
CST	DIH	0	0	58,836	0	0	58,836
PE	DIH	33,000	0	0	0	0	33,000
Total		693,000	0	6,626,721	0	0	7,319,721
Prior Years Cost		0					
Future Years Cost			0				
Total Project Cost							7,319,721
Proj# 4528831 SR 5/US 1 FROM NORTH OF ROCKY POINT RD TO SOUTH OF SR 514/MALABAR RD							
Type of Work: PAVEMENT ONLY RESURFACE (FLEX)							
Description:							
Length: 2.561 MI *Non-SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	DS	0	0	2,989,889	0	0	2,989,889
PE	DS	512,000	0	0	0	0	512,000
CST	DDR	0	0	368,354	0	0	368,354
CST	DIH	0	0	29,899	0	0	29,899
PE	DIH	25,600	0	0	0	0	25,600
Total		537,600	0	3,388,142	0	0	3,925,742
Prior Years Cost		0					
Future Years Cost			0				
Total Project Cost							3,925,742
Proj# 4528851 SR 520 FROM WEST OF 70070031 WB OFF TO TUCKER LANE							
Type of Work: PAVEMENT ONLY RESURFACE (FLEX)							
Description:							
Length: 1.95 MI *Non-SIS*							
Lead Agency: MANAGED BY FDOT							
LRTP #: Page 34, Goal 4							
CST	DDR	0	0	5,349,361	0	0	5,349,361
PE	DS	594,000	0	0	0	0	594,000
CST	DIH	0	0	47,626	0	0	47,626
PE	DIH	29,700	0	0	0	0	29,700
Total		623,700	0	5,396,987	0	0	6,020,687
Prior Years Cost		0					
Future Years Cost			0				
Total Project Cost							6,020,687
Proj# 4384581 BREVARD-MELBOURNE INTL LAND ACQUISITION							
Type of Work: AVIATION ENVIRONMENTAL PROJECT							
Description:							
Length: 0.00 MI *SIS*							
Lead Agency: MANAGED BY CITY OF MELBOURNE							
LRTP #: Page 33, Goal 2							
CAP	DDR	0	1,000,000	0	0	0	1,000,000
CAP	LF	0	1,000,000	0	0	0	1,000,000
Total		0	2,000,000	0	0	0	2,000,000
Prior Years Cost		0					
Future Years Cost			0				
Total Project Cost							2,000,000

Section H - Aviation Projects

Phase	Fund Source	2025	2026	2027	2028	2029	Total
Proj# 4384931 BREVARD-SPACE COAST REG TAXIWAY IMPROVEMENTS							
Type of Work: AVIATION PRESERVATION PROJECT							
Description:							
Length: 0.00 MI *Non-SIS*							
Lead Agency: MANAGED BY TITUSVILLE COCOA AIRPORT							
LRTP #: Page 33, Goal 2							
CAP	FAA	2,880,000	0	0	0	0	2,880,000
CAP	DPTO	235,904	0	0	0	0	235,904
CAP	LF	64,000	0	0	0	0	64,000
CAP	DDR	20,096	0	0	0	0	20,096
Total		3,200,000	0	0	0	0	3,200,000
Prior Years Cost		0	Future Years Cost		Total Project Cost		3,200,000
Proj# 4384942 BREVARD-SPACE COAST REG CONSTRUCT NEW ATCT							
Type of Work: AVIATION SAFETY PROJECT							
Description:							
Length: 0.00 MI *Non-SIS*							
Lead Agency: RESPONSIBLE AGENCY NOT AVAILABLE							
LRTP #: Page 33, Goal 2							
CAP	DDR	700,000	1,000,000	0	0	0	1,700,000
CAP	DPTO	800,000	0	0	0	0	800,000
CAP	LF	375,000	250,000	0	0	0	625,000
Total		1,875,000	1,250,000	0	0	0	3,125,000
Prior Years Cost		3,750,000	Future Years Cost		Total Project Cost		6,875,000
Proj# 4384981 BREVARD-VALKARIA CONSTRUCT AIRPORT ACCESS ROAD							
Type of Work: AVIATION REVENUE/OPERATIONAL							
Description:							
Length: 0.00 MI *Non-SIS*							
Lead Agency: RESPONSIBLE AGENCY NOT AVAILABLE							
LRTP #: Page 33, Goal 2							
CAP	DDR	320,000	0	0	0	0	320,000
CAP	LF	80,000	0	0	0	0	80,000
Total		400,000	0	0	0	0	400,000
Prior Years Cost		0	Future Years Cost		Total Project Cost		400,000
Proj# 4521811 BREVARD-MELBOURNE INTL TAXIWAY IMPROVEMENTS							
Type of Work: AVIATION PRESERVATION PROJECT							
Description:							
Length: 0.00 MI *SIS*							
Lead Agency: RESPONSIBLE AGENCY NOT AVAILABLE							
LRTP #: Page 33, Goal 2							
CAP	FAA	22,590,000	0	0	0	0	22,590,000
CAP	DDR	1,255,000	0	0	0	0	1,255,000
CAP	LF	1,255,000	0	0	0	0	1,255,000
Total		25,100,000	0	0	0	0	25,100,000
Prior Years Cost		1,408,190	Future Years Cost		Total Project Cost		26,508,190
Proj# 4537341 BREVARD-MELBOURNE INTL APRON							
Type of Work: AVIATION PRESERVATION PROJECT							
Description:							
Length: 0.00 MI *SIS*							
Lead Agency: RESPONSIBLE AGENCY NOT AVAILABLE							
LRTP #: Page 33, Goal 2							
CAP	DDR	0	0	0	1,500,000	1,500,000	3,100,000
CAP	LF	0	0	0	1,500,000	1,500,000	3,100,000
Total		0	0	0	3,000,000	3,000,000	6,200,000
Prior Years Cost		0	Future Years Cost		Total Project Cost		6,200,000
Proj# 4540871 BREVARD-VALKARIA AIRFIELD IMPROVEMENT							
Type of Work: AVIATION CAPACITY PROJECT							
Description:							
Length: 0.00 MI *Non-SIS*							
Lead Agency: RESPONSIBLE AGENCY NOT AVAILABLE							
LRTP #: Page 33, Goal 2							
CAP	DDR	0	0	160,000	1,600,000	0	1,760,000
CAP	LF	0	0	40,000	400,000	0	440,000
Total		0	0	200,000	2,000,000	0	2,200,000
Prior Years Cost		0	Future Years Cost		Total Project Cost		2,200,000

Section I - Seaport, Spaceport and Rail

Phase	Fund Source	2025	2026	2027	2028	2029	Total
Proj# 4370701 BREVARD SPACE FL HORIZONTAL LAUNCH/LANDING FACILITIES							
Type of Work: SPACEPORT CAPACITY PROJECT					Length: 0.00 MI *SIS*		
					Lead Agency: MANAGED BY SPACE FLORIDA		
					L RTP #: Page 33, Goal 2		
Description:							
CAP	GMR	0	12,500,000	12,500,000	11,250,000	11,250,000	47,500,000
CAP	LF	9,248,075	18,750,000	17,500,000	0	0	45,498,075
CAP	DPTO	4,248,075	6,250,000	5,000,000	5,000,000	0	20,498,075
CAP	DDR	0	0	0	0	5,000,000	5,000,000
CAP	SIWR	5,000,000	0	0	0	0	5,000,000
Total		18,496,150	37,500,000	35,000,000	16,250,000	16,250,000	123,496,150
Prior Years Cost		25,600,500	Future Years Cost	0	Total Project Cost		149,096,650
Proj# 4403231 BREVARD PORT CANAVERAL NORTH CARGO BERTH IMPROVEMENTS					Length: 0.00 MI *SIS*		
Type of Work: SEAPORT CAPACITY PROJECT					Lead Agency: MANAGED BY CANAVERAL PORT AUTHORITY		
					L RTP #: Page 33, Goal 2		
Description:							
CAP	DIS	0	4,000,000	7,000,000	0	0	11,000,000
CAP	LF	0	5,000,000	2,310,000	0	0	7,310,000
Total		0	9,000,000	9,310,000	0	0	18,310,000
Prior Years Cost		89,683,788	Future Years Cost	0	Total Project Cost		107,993,788
Proj# 4403233 BREVARD PORT CANAVERAL NORTH CARGO BERTH 4 IMPROVEMENTS					Length: 0.00 MI *SIS*		
Type of Work: SEAPORT CAPACITY PROJECT					Lead Agency: Managed by Canaveral Port Authority		
					L RTP #: Page 33, Goal 2		
Description:							
ADM	DIS	0	11,000,000	0	0	0	11,000,000
Total		0	11,000,000	0	0	0	11,000,000
Prior Years Cost		14,666,667	Future Years Cost	0	Total Project Cost		25,666,667
Proj# 4530452 INTERMODAL STATION DEVELOPMENT (Cocoa Multi-modal Station & Rail)					Length: 0.00 MI *Non-SIS*		
Type of Work: MODAL SYSTEMS PLANNING					Lead Agency: MANAGED BY City of Cocoa		
					L RTP #: Page 33, Goal 2, Amendment No. 6		
Description: Cocoa Multimodal Station & Rail Project							
CST	SU	0	0	0	7,073,668	0	7,073,668
PE	SU	0	0	6,373,668	0	0	6,373,668
PE	CARU	0	0	1,026,332	0	0	1,026,332
CST	CARU	0	0	0	1,026,332	0	1,026,332
Total		0	0	7,400,000	8,100,000	0	15,500,000
Prior Years Cost		0	Future Years Cost	0	Total Project Cost		15,500,000
Proj# 4353221 BREVARD-SPACE FL PROCESSING & RANGE FACILITY IMPROVEMENTS					Length: 0.00 MI *SIS*		
Type of Work: SPACEPORT CAPACITY PROJECT					Lead Agency: MANAGED BY SPACE FLORIDA		
					L RTP #: Page 33, Goal 2		
Description:							
CAP	LF	14,250,000	18,750,000	17,500,000	0	0	50,500,000
CAP	GMR	0	12,500,000	12,500,000	11,250,000	11,250,000	47,500,000
CAP	DPTO	4,250,000	6,250,000	4,161,008	3,246,414	0	17,907,422
CAP	DDR	0	0	838,992	1,753,586	5,000,000	7,592,578
CAP	DIS	5,000,000	0	0	0	0	5,000,000
Total		23,500,000	37,500,000	35,000,000	16,250,000	16,250,000	128,500,000
Prior Years Cost		219,100,000	Future Years Cost	0	Total Project Cost		347,600,000
Proj# 4368631 BREVARD-SPACE FLORIDA COMMON USE INFRASTRUCTURE					Length: 0.00 MI *SIS*		
Type of Work: SPACEPORT CAPACITY PROJECT					Lead Agency: MANAGED BY SPACE FLORIDA		
					L RTP #: Page 33, Goal 2		
Description:							
CAP	GMR	0	12,500,000	12,500,000	11,250,000	11,250,000	47,500,000
CAP	DPTO	4,250,000	6,250,000	5,000,000	5,000,000	0	20,500,000
CAP	DDR	0	0	0	0	5,000,000	5,000,000
CAP	SIWR	5,000,000	0	0	0	0	5,000,000
Total		9,250,000	18,750,000	17,500,000	16,250,000	16,250,000	78,000,000
Prior Years Cost		52,932,778	Future Years Cost	0	Total Project Cost		130,932,778
Proj# 4370691 BREVARD-SPACE FL LAUNCH COMPLEX IMPROVEMENTS & PASSENGER/CARGO					Length: 0.00 MI *SIS*		
Type of Work: SPACEPORT CAPACITY PROJECT					Lead Agency: MANAGED BY SPACE FLORIDA		
					L RTP #: Page 33, Goal 2		
Description:							
CAP	GMR	0	12,500,000	12,500,000	11,250,000	11,250,000	47,500,000
CAP	LF	9,250,000	18,750,000	17,500,000	0	0	45,500,000
CAP	DPTO	4,250,000	6,250,000	5,000,000	5,000,000	0	20,500,000
CAP	DDR	0	0	0	0	5,000,000	5,000,000
CAP	SIWR	5,000,000	0	0	0	0	5,000,000
Total		18,500,000	37,500,000	35,000,000	16,250,000	16,250,000	123,500,000
Prior Years Cost		81,700,000	Future Years Cost	0	Total Project Cost		205,200,000

Length: 0.00 MI "515"
Lead Agency: Managed by Canaveral Port Authority
LRTP #: Page 33, Goal 2

	Prior Years Cost		Future Years Cost		Total Project Cost
CAP	IF	1,804,737	0	5,000,000	0
CAP	SWR	0	0	5,000,000	0
CAP	PORT	3,195,263	0	0	0
CAP	DIS	0	0	0	0
Total		5,000,000	0	10,000,000	0
					20,000,000
					20,000,000

TABLE 11.1:
Strategic Intermodal System Projects

[illegible]

TABLE 11.4: Local Funding Projects

2015-2016		2016-2017		2017-2018		2018-2019		2019-2020		2020-2021		2021-2022		2022-2023		2023-2024		2024-2025		2025-2026		2026-2027		2027-2028		2028-2029		2029-2030		2030-2031		2031-2032		2032-2033		2033-2034		2034-2035		2035-2036		2036-2037		2037-2038		2038-2039		2039-2040		2040-2041		2041-2042		2042-2043		2043-2044		2044-2045		2045-2046		2046-2047		2047-2048		2048-2049		2049-2050		2050-2051		2051-2052		2052-2053		2053-2054		2054-2055		2055-2056		2056-2057		2057-2058		2058-2059		2059-2060		2060-2061		2061-2062		2062-2063		2063-2064		2064-2065		2065-2066		2066-2067		2067-2068		2068-2069		2069-2070		2070-2071		2071-2072		2072-2073		2073-2074		2074-2075		2075-2076		2076-2077		2077-2078		2078-2079		2079-2080		2080-2081		2081-2082		2082-2083		2083-2084		2084-2085		2085-2086		2086-2087		2087-2088		2088-2089		2089-2090		2090-2091		2091-2092		2092-2093		2093-2094		2094-2095		2095-2096		2096-2097		2097-2098		2098-2099		2099-2100		2100-2101		2101-2102		2102-2103		2103-2104		2104-2105		2105-2106		2106-2107		2107-2108		2108-2109		2109-2110		2110-2111		2111-2112		2112-2113		2113-2114		2114-2115		2115-2116		2116-2117		2117-2118		2118-2119		2119-2120		2120-2121		2121-2122		2122-2123		2123-2124		2124-2125		2125-2126		2126-2127		2127-2128		2128-2129		2129-2130		2130-2131		2131-2132		2132-2133		2133-2134		2134-2135		2135-2136		2136-2137		2137-2138		2138-2139		2139-2140		2140-2141		2141-2142		2142-2143		2143-2144		2144-2145		2145-2146		2146-2147		2147-2148		2148-2149		2149-2150		2150-2151		2151-2152		2152-2153		2153-2154		2154-2155		2155-2156		2156-2157		2157-2158		2158-2159		2159-2160		2160-2161		2161-2162		2162-2163		2163-2164		2164-2165		2165-2166		2166-2167		2167-2168		2168-2169		2169-2170		2170-2171		2171-2172		2172-2173		2173-2174		2174-2175		2175-2176		2176-2177		2177-2178		2178-2179		2179-2180		2180-2181		2181-2182		2182-2183		2183-2184		2184-2185		2185-2186		2186-2187		2187-2188		2188-2189		2189-2190		2190-2191		2191-2192		2192-2193		2193-2194		2194-2195		2195-2196		2196-2197		2197-2198		2198-2199		2199-2200		2200-2201		2201-2202		2202-2203		2203-2204		2204-2205		2205-2206		2206-2207		2207-2208		2208-2209		2209-2210		2210-2211		2211-2212		2212-2213		2213-2214		2214-2215		2215-2216		2216-2217		2217-2218		2218-2219		2219-2220		2220-2221		2221-2222		2222-2223		2223-2224		2224-2225		2225-2226		2226-2227		2227-2228		2228-2229		2229-2230		2230-2231		2231-2232		2232-2233		2233-2234		2234-2235		2235-2236		2236-2237		2237-2238		2238-2239		2239-2240		2240-2241		2241-2242	
1	2015-2016	2016-2017	2017-2018	2018-2019	2019-2020	2020-2021	2021-2022	2022-2023	2023-2024	2024-2025	2025-2026	2026-2027	2027-2028	2028-2029	2029-2030	2030-2031	2031-2032	2032-2033	2033-2034	2034-2035	2035-2036	2036-2037	2037-2038	2038-2039	2039-2040	2040-2041	2041-2042	2042-2043	2043-2044	2044-2045	2045-2046	2046-2047	2047-2048	2048-2049	2049-2050	2050-2051	2051-2052	2052-2053	2053-2054	2054-2055	2055-2056	2056-2057	2057-2058	2058-2059	2059-2060	2060-2061	2061-2062	2062-2063	2063-2064	2064-2065	2065-2066	2066-2067	2067-2068	2068-2069	2069-2070	2070-2071	2071-2072	2072-2073	2073-2074	2074-2075	2075-2076	2076-2077	2077-2078	2078-2079	2079-2080	2080-2081	2081-2082	2082-2083	2083-2084	2084-2085	2085-2086	2086-2087	2087-2088	2088-2089	2089-2090	2090-2091	2091-2092	2092-2093	2093-2094	2094-2095	2095-2096	2096-2097	2097-2098	2098-2099	2099-2100	2100-2101	2101-2102	2102-2103	2103-2104	2104-2105	2105-2106	2106-2107	2107-2108	2108-2109	2109-2110	2110-2111	2111-2112	2112-2113	2113-2114	2114-2115	2115-2116	2116-2117	2117-2118	2118-2119	2119-2120	2120-2121	2121-2122	2122-2123	2123-2124	2124-2125	2125-2126	2126-2127	2127-2128	2128-2129	2129-2130	2130-2131	2131-2132	2132-2133	2133-2134	2134-2135	2135-2136	2136-2137	2137-2138	2138-2139	2139-2140	2140-2141	2141-2142	2142-2143	2143-2144	2144-2145	2145-2146	2146-2147	2147-2148	2148-2149	2149-2150	2150-2151	2151-2152	2152-2153	2153-2154	2154-2155	2155-2156	2156-2157	2157-2158	2158-2159	2159-2160	2160-2161	2161-2162	2162-2163	2163-2164	2164-2165	2165-2166	2166-2167	2167-2168	2168-2169	2169-2170	2170-2171	2171-2172	2172-2173	2173-2174	2174-2175	2175-2176	2176-2177	2177-2178	2178-2179	2179-2180	2180-2181	2181-2182	2182-2183	2183-2184	2184-2185	2185-2186	2186-2187	2187-2188	2188-2189	2189-2190	2190-2191	2191-2192	2192-2193	2193-2194	2194-2195	2195-2196	2196-2197	2197-2198	2198-2199	2199-2200	2200-2201	2201-2202	2202-2203	2203-2204	2204-2205	2205-2206	2206-2207	2207-2208	2208-2209	2209-2210	2210-2211	2211-2212	2212-2213	2213-2214	2214-2215	2215-2216	2216-2217	2217-2218	2218-2219	2219-2220	2220-2221	2221-2222	2222-2223	2223-2224	2224-2225	2225-2226	2226-2227	2227-2228	2228-2229	2229-2230	2230-2231	2231-2232	2232-2233	2233-2234	2234-2235	2235-2236	2236-2237	2237-2238	2238-2239	2239-2240	2240-2241	2241-2242																																																																																																																																																																																																																																		
2	2015-2016	2016-2017	2017-2018	2018-2019	2019-2020	2020-2021	2021-2022	2022-2023	2023-2024	2024-2025	2025-2026	2026-2027	2027-2028	2028-2029	2029-2030	2030-2031	2031-2032	2032-2033	2033-2034	2034-2035	2035-2036	2036-2037	2037-2038	2038-2039	2039-2040	2040-2041	2041-2042	2042-2043	2043-2044	2044-2045	2045-2046	2046-2047	2047-2048	2048-2049	2049-2050	2050-2051	2051-2052	2052-2053	2053-2054	2054-2055	2055-2056	2056-2057	2057-2058	2058-2059	2059-2060	2060-2061	2061-2062	2062-2063	2063-2064	2064-2065	2065-2066	2066-2067	2067-2068	2068-2069	2069-2070	2070-2071	2071-2072	2072-2073	2073-2074	2074-2075	2075-2076	2076-2077	2077-2078	2078-2079	2079-2080	2080-2081	2081-2082	2082-2083	2083-2084	2084-2085	2085-2086	2086-2087	2087-2088	2088-2089	2089-2090	2090-2091	2091-2092	2092-2093	2093-2094	2094-2095	2095-2096	2096-2097	2097-2098	2098-2099	2099-2100	2100-2101	2101-2102	2102-2103	2103-2104	2104-2105	2105-2106	2106-2107	2107-2108	2108-2109	2109-2110	2110-2111	2111-2112	2112-2113	2113-2114	2114-2115	2115-2116	2116-2117	2117-2118	2118-2119	2119-2120	2120-2121	2121-2122	2122-2123	2123-2124	2124-2125	2125-2126	2126-2127	2127-2128	2128-2129	2129-2130	2130-2131	2131-2132	2132-2133	2133-2134	2134-2135	2135-2136	2136-2137	2137-2138	2138-2139	2139-2140	2140-2141	2141-2142	2142-2143	2143-2144	2144-2145	2145-2146	2146-2147	2147-2148	2148-2149	2149-2150	2150-2151	2151-2152	2152-2153	2153-2154	2154-2155	2155-2156	2156-2157	2157-2158	2158-2159	2159-2160	2160-2161	2161-2162	2162-2163	2163-2164	2164-2165	2165-2166	2166-2167	2167-2168	2168-2169	2169-2170	2170-2171	2171-2172	2172-2173	2173-2174	2174-2175	2175-2176	2176-2177	2177-2178	2178-2179	2179-2180	2180-2181	2181-2182	2182-2183	2183-2184	2184-2185	2185-2186	2186-2187	2187-2188	2188-2189	2189-2190	2190-2191	2191-2192	2192-2193	2193-2194	2194-2195	2195-2196	2196-2197	2197-2198	2198-2199	2199-2200	2200-2201	2201-2202	2202-2203	2203-2204	2204-2205	2205-2206	2206-2207	2207-2208	2208-2209	2209-2210	2210-2211	2211-2212	2212-2213	2213-2214	2214-2215	2215-2216	2216-2217	2217-2218	2218-2219	2219-2220	2220-2221	2221-2222	2222-2223	2223-2224	2224-2225	2225-2226	2226-2227	2227-2228	2228-2229	2229-2230	2230-2231	2231-2232	2232-2233	2233-2234	2234-2235	2235-2236	2236-2237	2237-2238	2238-2239	2239-2240	2240-2241	2241-2242																																																																																																																																																																																																																																		
3	2015-2016	2016-2017	2017-2018	2018-2019	2019-2020	2020-2021	2021-2022	2022-2023	2023-2024	2024-2025	2025-2026	2026-2027	2027-2028	2028-2029	2029-2030	2030-2031	2031-2032	2032-2033	2033-2034	2034-2035	2035-2036	2036-2037	2037-2038	2038-2039	2039-2040	2040-2041	2041-2042	2042-2043	2043-2044	2044-2045	2045-2046	2046-2047	2047-2048	2048-2049	2049-2050	2050-2051	2051-2052	2052-2053	2053-2054	2054-2055	2055-2056	2056-2057	2057-2058	2058-2059	2059-2060	2060-2061	2061-2062	2062-2063	2063-2064	2064-2065	2065-2066	2066-2067	2067-2068	2068-2069	2069-2070	2070-2071	2071-2072	2072-2073	2073-2074	2074-2075	2075-2076	2076-2077	2077-2078	2078-2079	2079-2080	2080-2081	2081-2082	2082-2083	2083-2084	2084-2085	2085-2086	2086-2087	2087-2088	2088-2089	2089-2090	2090-2091	2091-2092	2092-2093	2093-2094	2094-2095	2095-2096	2096-2097	2097-2098	2098-2099	2099-2100	2100-2101	2101-2102	2102-2103	2103-2104	2104-2105	2105-2106	2106-2107	2107-2108	2108-2109	2109-2110	2110-2111	2111-2112	2112-2113	2113-2114	2114-2115	2115-2116	2116-2117	2117-2118	2118-2119	2119-2120	2120-2121	2121-2122	2122-2123	2123-2124	2124-2125	2125-2126	2126-2127	2127-2128	2128-2129	2129-2130	2130-2131	2131-2132	2132-2133	2133-2134	2134-2135	2135-2136	2136-2137	2137-2138	2138-2139	2139-2140	2140-2141	2141-2142	2142-2143	2143-2144	2144-2145	2145-2146	2146-2147	2147-2148	2148-2149	2149-2150	2150-2151	2151-2152	2152-2153	2153-2154	2154-2155	2155-2156	2156-2157	2157-2158	2158-2159	2159-2160	2160-2161	2161-2162	2162-2163	2163-2164	2164-2165	2165-2166	2166-2167	2167-																																																																																																																																																																																																																																																																																																												

TABLE 11.5:
System Operation + Maintenance

[illegible]

TABLE 11.7:
Cost Feasible Plan Summary

[illegible]

TABLE 11.8:
Grant Funded Projects

2015-2016 (2015/16) PROJECTS & SUB-PROJECTS																	
Proj. ID	Project Name	Status	Project Type	Project Manager	2015-2016			2016-2017			2017-2018			2018-2019			Total
					Proj. ID	Proj. Name	Proj. Status	Proj. ID	Proj. Name	Proj. Status	Proj. ID	Proj. Name	Proj. Status	Proj. ID	Proj. Name	Proj. Status	
101	2015-2016 Project A	Active	Project A	John Doe	101	2015-2016 Project A	Active	102	2016-2017 Project B	Active	103	2017-2018 Project C	Active	104	2018-2019 Project D	Active	105
102	2016-2017 Project B	Active	Project B	Jane Smith	102	2016-2017 Project B	Active	103	2017-2018 Project C	Active	104	2018-2019 Project D	Active	105	2019-2020 Project E	Active	106
103	2017-2018 Project C	Active	Project C	Mike Johnson	103	2017-2018 Project C	Active	104	2018-2019 Project D	Active	105	2019-2020 Project E	Active	106	2020-2021 Project F	Active	107
104	2018-2019 Project D	Active	Project D	Sarah Lee	104	2018-2019 Project D	Active	105	2019-2020 Project E	Active	106	2020-2021 Project F	Active	107	2021-2022 Project G	Active	108
105	2019-2020 Project E	Active	Project E	David Kim	105	2019-2020 Project E	Active	106	2020-2021 Project F	Active	107	2021-2022 Project G	Active	108	2022-2023 Project H	Active	109
106	2020-2021 Project F	Active	Project F	Emily White	106	2020-2021 Project F	Active	107	2021-2022 Project G	Active	108	2022-2023 Project H	Active	109	2023-2024 Project I	Active	110
107	2021-2022 Project G	Active	Project G	Frank Green	107	2021-2022 Project G	Active	108	2022-2023 Project H	Active	109	2023-2024 Project I	Active	110	2024-2025 Project J	Active	111
108	2022-2023 Project H	Active	Project H	Grace Brown	108	2022-2023 Project H	Active	109	2023-2024 Project I	Active	110	2024-2025 Project J	Active	111	2025-2026 Project K	Active	112
109	2023-2024 Project I	Active	Project I	Henry Black	109	2023-2024 Project I	Active	110	2024-2025 Project J	Active	111	2025-2026 Project K	Active	112	2026-2027 Project L	Active	113
110	2024-2025 Project J	Active	Project J	Ivy Gray	110	2024-2025 Project J	Active	111	2025-2026 Project K	Active	112	2026-2027 Project L	Active	113	2027-2028 Project M	Active	114
111	2025-2026 Project K	Active	Project K	Jack Blue	111	2025-2026 Project K	Active	112	2026-2027 Project L	Active	113	2027-2028 Project M	Active	114	2028-2029 Project N	Active	115
112	2026-2027 Project L	Active	Project L	Karen Yellow	112	2026-2027 Project L	Active	113	2027-2028 Project M	Active	114	2028-2029 Project N	Active	115	2029-2030 Project O	Active	116
113	2027-2028 Project M	Active	Project M	Leo Purple	113	2027-2028 Project M	Active	114	2028-2029 Project N	Active	115	2029-2030 Project O	Active	116	2030-2031 Project P	Active	117
114	2028-2029 Project N	Active	Project N	Mia Pink	114	2028-2029 Project N	Active	115	2029-2030 Project O	Active	116	2030-2031 Project P	Active	117	2031-2032 Project Q	Active	118
115	2029-2030 Project O	Active	Project O	Noah Orange	115	2029-2030 Project O	Active	116	2030-2031 Project P	Active	117	2031-2032 Project Q	Active	118	2032-2033 Project R	Active	119
116	2030-2031 Project P	Active	Project P	Olivia Green	116	2030-2031 Project P	Active	117	2031-2032 Project Q	Active	118	2032-2033 Project R	Active	119	2033-2034 Project S	Active	120
117	2031-2032 Project Q	Active	Project Q	Peter Blue	117	2031-2032 Project Q	Active	118	2032-2033 Project R	Active	119	2033-2034 Project S	Active	120	2034-2035 Project T	Active	121
118	2032-2033 Project R	Active	Project R	Quinn Yellow	118	2032-2033 Project R	Active	119	2033-2034 Project S	Active	120	2034-2035 Project T	Active	121	2035-2036 Project U	Active	122
119	2033-2034 Project S	Active	Project S	Rachel Purple	119	2033-2034 Project S	Active	120	2034-2035 Project T	Active	121	2035-2036 Project U	Active	122	2036-2037 Project V	Active	123
120	2034-2035 Project T	Active	Project T	Sam Brown	120	2034-2035 Project T	Active	121	2035-2036 Project U	Active	122	2036-2037 Project V	Active	123	2037-2038 Project W	Active	124
121	2035-2036 Project U	Active	Project U	Tina Green	121	2035-2036 Project U	Active	122	2036-2037 Project V	Active	123	2037-2038 Project W	Active	124	2038-2039 Project X	Active	125
122	2036-2037 Project V	Active	Project V	Uma White	122	2036-2037 Project V	Active	123	2037-2038 Project W	Active	124	2038-2039 Project X	Active	125	2039-2040 Project Y	Active	126
123	2037-2038 Project W	Active	Project W	Victor Blue	123	2037-2038 Project W	Active	124	2038-2039 Project X	Active	125	2039-2040 Project Y	Active	126	2040-2041 Project Z	Active	127
124	2038-2039 Project X	Active	Project X	Wendy Yellow	124	2038-2039 Project X	Active	125	2039-2040 Project Y	Active	126	2040-2041 Project Z	Active	127	2041-2042 Project AA	Active	128
125	2039-2040 Project Y	Active	Project Y	Xavier Purple	125	2039-2040 Project Y	Active	126	2040-2041 Project Z	Active	127	2041-2042 Project AA	Active	128	2042-2043 Project AB	Active	129
126	2040-2041 Project Z	Active	Project Z	Yara Green	126	2040-2041 Project Z	Active	127	2041-2042 Project AA	Active	128	2042-2043 Project AB	Active	129	2043-2044 Project AC	Active	130
127	2041-2042 Project AA	Active	Project AA	Zoe White	127	2041-2042 Project AA	Active	128	2042-2043 Project AB	Active	129	2043-2044 Project AC	Active	130	2044-2045 Project AD	Active	131
128	2042-2043 Project AB	Active	Project AB	Adam Blue	128	2042-2043 Project AB	Active	129	2043-2044 Project AC	Active	130	2044-2045 Project AD	Active	131	2045-2046 Project AE	Active	132
129	2043-2044 Project AC	Active	Project AC	Bella Yellow	129	2043-2044 Project AC	Active	130	2044-2045 Project AD	Active	131	2045-2046 Project AE	Active	132	2046-2047 Project AF	Active	133
130	2044-2045 Project AD	Active	Project AD	Charlie Purple	130	2044-2045 Project AD	Active	131	2045-2046 Project AE	Active	132	2046-2047 Project AF	Active	133	2047-2048 Project AG	Active	134
131	2045-2046 Project AE	Active	Project AE	Diana Green	131	2045-2046 Project AE	Active	132	2046-2047 Project AF	Active	133	2047-2048 Project AG	Active	134	2048-2049 Project AH	Active	135
132	2046-2047 Project AF	Active	Project AF	Ethan White	132	2046-2047 Project AF	Active	133	2047-2048 Project AG	Active	134	2048-2049 Project AH	Active	135	2049-2050 Project AI	Active	136
133	2047-2048 Project AG	Active	Project AG	Fiona Blue	133	2047-2048 Project AG	Active	134	2048-2049 Project AH	Active	135	2049-2050 Project AI	Active	136	2050-2051 Project AJ	Active	137
134	2048-2049 Project AH	Active	Project AH	Gavin Yellow	134	2048-2049 Project AH	Active	135	2049-2050 Project AI	Active	136	2050-2051 Project AJ	Active	137	2051-2052 Project AK	Active	138
135	2049-2050 Project AI	Active	Project AI	Hannah Purple	135	2049-2050 Project AI	Active	136	2050-2051 Project AJ	Active	137	2051-2052 Project AK	Active	138	2052-2053 Project AL	Active	139
136	2050-2051 Project AJ	Active	Project AJ	Ian Green	136	2050-2051 Project AJ	Active	137	2051-2052 Project AK	Active	138	2052-2053 Project AL	Active	139	2053-2054 Project AM	Active	140
137	2051-2052 Project AK	Active	Project AK	Jessica White	137	2051-2052 Project AK	Active	138	2052-2053 Project AL	Active	139	2053-2054 Project AM	Active	140	2054-2055 Project AN	Active	141
138	2052-2053 Project AL	Active	Project AL	Kyle Blue	138	2052-2053 Project AL	Active	139	2053-2054 Project AM	Active	140	2054-2055 Project AN	Active	141	2055-2056 Project AO	Active	142
139	2053-2054 Project AM	Active	Project AM	Laura Yellow	139	2053-2054 Project AM	Active	140	2054-2055 Project AN	Active	141	2055-2056 Project AO	Active	142	2056-2057 Project AP	Active	143
140	2054-2055 Project AN	Active	Project AN	Marcus Purple	140	2054-2055 Project AN	Active	141	2055-2056 Project AO	Active	142	2056-2057 Project AP	Active	143	2057-2058 Project AQ	Active	144
141	2055-2056 Project AO	Active	Project AO	Nancy Green	141	2055-2056 Project AO	Active	142	2056-2057 Project AP	Active	143	2057-2058 Project AQ	Active	144	2058-2059 Project AR	Active	145
142	2056-2057 Project AP	Active	Project AP	Oscar White	142	2056-2057 Project AP	Active	143	2057-2058 Project AQ	Active	144	2058-2059 Project AR	Active	145	2059-2060 Project AS	Active	146
143	2057-2058 Project AQ	Active	Project AQ	Pamela Blue	143	2057-2058 Project AQ	Active	144	2058-2059 Project AR	Active	145	2059-2060 Project AS	Active	146	2060-2061 Project AT	Active	147
144	2058-2059 Project AR	Active	Project AR	Quinn Yellow	144	2058-2059 Project AR	Active	145	2059-2060 Project AS	Active	146	2060-2061 Project AT	Active	147	2061-2062 Project AU	Active	148
145	2059-2060 Project AS	Active	Project AS	Rachel Purple	145	2059-2060 Project AS	Active	146	2060-2061 Project AT	Active	147	2061-2062 Project AU	Active	148	2062-2063 Project AV	Active	149
146	2060-2061 Project AT	Active	Project AT	Sam Green	146	2060-2061 Project AT	Active	147	2061-2062 Project AU	Active	148	2062-2063 Project AV	Active	149	2063-2064 Project AW	Active	150
147	2061-2062 Project AU	Active	Project AU	Tina White	147	2061-2062 Project AU	Active	148	2062-2063 Project AV	Active	149	2063-2064 Project AW	Active	150	2064-2065 Project AX	Active	151
148	2062-2063 Project AV	Active	Project AV	Uma Blue	148	2062-2063 Project AV	Active	149	2063-2064 Project AW	Active	150	2064-2065 Project AX	Active	151	2065-2066 Project AY	Active	152
149	2063-2064 Project AW	Active	Project AW	Victor Yellow	149	2063-2064 Project AW	Active	150	2064-2065 Project AX	Active	151	2065-2066 Project AY	Active	152	2066-2067 Project AZ	Active	153
150	2064-2065 Project AX	Active	Project AX	Wendy Purple	150	2064-2065 Project AX	Active	151	2065-2066 Project AY	Active	152	2066-2067 Project AZ	Active	153	2067-2068 Project BA	Active	154
151	2065-2066 Project AY	Active	Project AY	Xavier Green	151	2065-2066 Project AY	Active	152	2066-2067 Project AZ	Active	153	2067-2068 Project BA	Active	154	2068-2069 Project BB	Active	155
152	2066-2067 Project AZ	Active	Project AZ	Yara White	152	2066-2067 Project AZ	Active	153	2067-2068 Project BA	Active	154	2068-2069 Project BB	Active	155	2069-2070 Project BC	Active	156
153	2067-2068 Project BA	Active	Project BA	Zoe Blue	153	2067-2068 Project BA	Active	154	2068-2069 Project BB	Active	155	2069-2070 Project BC	Active	156	2070-2071 Project BD	Active	157
154	2068-2069 Project BB	Active	Project BB	Adam Yellow	154	2068-2069 Project BB	Active	155	2069-2070 Project BC	Active	156	2070-2071 Project BD	Active	157	2071-2072 Project BE	Active	158
155	2069-2070 Project BC	Active	Project BC	Bella Purple	155	2069-2070 Project BC	Active	156	2070-2071 Project BD	Active	157	2071-2072 Project BE	Active	158	2072-2073 Project BF	Active	159
156	2070-2071 Project BD	Active	Project BD	Charlie Green	156	2070-2071 Project BD	Active	157	2071-2072 Project BE	Active	158	2072-2073 Project BF	Active	159	2073-2074 Project BG	Active	160
157	2071-2072 Project BE	Active	Project BE	Diana White	157	2071-2072 Project BE	Active	158	2072-2073 Project BF	Active	159	2073-2074 Project BG	Active	160	2074-2075 Project BH	Active	161
158	2072-2073 Project BF	Active	Project BF	Ethan Blue	158	2072-2073 Project BF	Active	159	2073-2074 Project BG	Active	160	2074-2075 Project BH	Active	161	2075-2076 Project BI	Active	162
159	2073-2074 Project BG	Active	Project BG	Fiona Yellow	159	2073-2074 Project BG	Active	160	2074-2075 Project BH	Active	161	2075-2076 Project BI	Active	162	2076-2077 Project BJ	Active	163
160	2074-2075 Project BH	Active	Project BH	Gavin Purple	160	2074-2075 Project BH	Active	161	2075-2076 Project BI	Active	162	2076-2077 Project BJ	Active	163	2077-2078 Project BK	Active	164
161	2075-2076 Project BI	Active	Project BI	Hannah Green	161	2075-2076 Project BI	Active	162	2076-2077 Project BJ	Active	163	2077-2078 Project BK	Active	164	2078-2079 Project BL	Active	165
162	2076-2077 Project BJ	Active	Project BJ	Ian White	162	2076-2077 Project BJ	Active	163	2077-2078 Project BK	Active	164	2078-2079 Project BL	Active	165	2079-2080 Project BM	Active	166
163	2077-2078 Project BK	Active	Project BK	Jessica Blue	163	2077-2078 Project BK	Active	164	2078-2079 Project BL	Active	165	2079-2080 Project BM	Active	166	2080-2081 Project BN	Active	167
164	2078-2079 Project BL	Active	Project BL	Kyle Yellow	164	2078-2079 Project BL	Active	165	2079-2080 Project BM	Active	166	2080-2081 Project BN	Active	167	2081-2082 Project BO	Active	168
165	2079-2080 Project BM	Active	Project BM	Laura Purple	165	2079-2080 Project BM	Active	166	2080-2081 Project BN	Active	167	2081-2082 Project BO	Active	168	2082-2083 Project BP	Active	169
166	2080-2081 Project BN	Active	Project BN	Marcus Green	166	2080-2081 Project BN	Active	167	2081-2082 Project BO	Active	168	2082-2083 Project BP	Active	169	2083-2084 Project BQ	Active	170
167	2081-2082 Project BO	Active	Project BO	Nancy White	167	2081-2082 Project BO	Active	168	2082-2083 Project BP	Active	169	2083-2084 Project BQ	Active	170	2084-2085 Project BR	Active	171
168	2082-2083 Project BP	Active	Project BP	Oscar Blue	168	2082-2083 Project BP	Active	169	2083-2084 Project BQ	Active	170	2084-2085 Project BR	Active	171	2085-2086 Project BS	Active	172
169	2083-2084 Project BQ	Active	Project BQ	Pamela Yellow	169	2083-2084 Project BQ	Active	170	2084-2085 Project BR	Active	171	2085					

TABLE 11.9:
Tax Based System Operation and Maintenance

[illegible]

Space Coast Area Transit Capital Improvements

Table 9.4: 10-Year Financial Plan (Projected Operating and Capital Expenses)

[illegible]

Table 9-5: 10-Year Financial Plan (Projected Revenues and Annual Funding Balance)

[illegible]

Note: cost and revenue assumptions are detailed in report section text.

Table 9-6: 10-Year TDP Implementation Plan and Unfunded Needs

	Unfunded Expenses	Implementation Year(s)	% Unfunded	Total Amount Unfunded
Operating	Continuous Saturday Service	2024-2032	100%	\$2,989,060
	Add Sunday Service	2025-2032	100%	\$5,128,364
	Extend Weekday Service to 9 pm	2026-2032	100%	\$3,469,993
	Increase Weekday Service to 30-Minutes	2027-2032	100%	\$7,889,002
	Implement MOD Pilot Zones 1-2	2027-2032	50%*	\$2,585,911
	New US 1 Route/MOD Pilot Zones 3-4	2028-2032		
Capital	New Cocoa Transfer Center - Construction	2025	50%*	\$927,000
	New Centralized Facility Design & Construction	2029-2031	100%	\$12,428,950
	Unfunded Replacement/New Vehicles	2024-2032	100%	\$4,486,918
	Estimated Unfunded Expenses**	--	--	\$39,905,199

*Assumes 50% funding through FDOT grant programs, requiring 50% unfunded local match.

**The total amount of unfunded needs in this table vs the 10-year plan detail is slightly higher due to a small funding surplus calculated in FY 2025. The use of those funds towards any unfunded needs would depend on the funding source, local match requirement, and other factors and is therefore not shown as a reduction in the total cost of these unfunded improvements.

Housing and Human Services Department

Program Name: COMMUNITY RESOURCES
Project Name: ADA Bus Stops in Strategy Areas
Project Total: \$300,000
Project Timeline: October 1st, 2024 through September 30th, 2025
Funded Program: 6538164
District(s): 1 & 2

Project Description, Milestones and Service Impact

Installation of ADA compliant bus stops in CDBG Strategy areas. Work to include the design of bus stops, and the construction of bus stops to be concrete pads, if applicable side walk path of travel, if determined to be needed other bus stop fixtures such as trash cans, benches, and shelters. Note: Route of travel path still needs to be approved/accepted by Public Works, if not accepted path or bus stop will not be constructed.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 300,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 300,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Construction Expense	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 300,000

Housing and Human Services Department

Program Name: COMMUNITY RESOURCES
Project Name: Sharpes Sidewalk
Project Total: \$720,294
Project Timeline: October 1st, 2016 through September 30th, 2025
Funded Program: 6911104
District(s): 1

Project Description, Milestones and Service Impact

This project consists of design and installation of ADA accessible sidewalk along the north side of Canaveral Groves Blvd between East Railroad Ave and Morris Ave.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 90,590	\$ -	\$ 629,704	\$ -	\$ -	\$ -	\$ -	\$ 720,294
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 90,590	\$ -	\$ 629,704	\$ -	\$ -	\$ -	\$ -	\$ 720,294
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 76,512	\$ -	\$ 72,458	\$ -	\$ -	\$ -	\$ -	\$ 148,970
Construction Expense	\$ 14,078	\$ -	\$ 500,000	\$ -	\$ -	\$ -	\$ -	\$ 514,078
Other Expense	\$ -	\$ -	\$ 57,246	\$ -	\$ -	\$ -	\$ -	\$ 57,246
Total Expense	\$ 90,590	\$ -	\$ 629,704	\$ -	\$ -	\$ -	\$ -	\$ 720,294

Merritt Island Redevelopment Agency

Program Name: MERRITT ISLAND REDEVELOPMENT AGENCY
Project Name: SR 520; SR3; SR 528 Corridor Improvements
Project Total: \$350,000
Project Timeline: October 1, 2025 through September 30th, 2027
Funded Program: 519601
District(s): 2

Project Description, Milestones and Service Impact

In partnership with the United States Department of Transportation (US DOT), the Florida Department of Transportation (FDOT), Brevard County Public Works, potential donors, and private property owners, MIRA will make safety improvements to Courtenay Parkway (SR3), SR 520, and SR 528. This investment will be based on incident-analysis, field surveys, and citizen participation. It may include the addition of medians, lighting improvements, place markers, traffic signal and pedestrian crossing signal improvements, upgraded sidewalks and pavement markings, and other related improvements.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ 280,000	\$ -	\$ -	\$ -	\$ 280,000
Incremental Tax Revenue	\$ -	\$ -	\$ -	\$ 70,000	\$ -	\$ -	\$ -	\$ 70,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ -	\$ 350,000	\$ -	\$ -	\$ -	\$ 350,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ 120,000	\$ -	\$ -	\$ -	\$ 120,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ 230,000	\$ -	\$ -	\$ 230,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ -	\$ 120,000	\$ 230,000	\$ -	\$ -	\$ 350,000

Merritt Island Redevelopment Agency

Program Name: MERRITT ISLAND REDEVELOPMENT AGENCY
Project Name: S. Courtenay Pkwy Fortenberry to Cone Road Project
Project Total: \$2,003,500
Project Timeline: October 1st 2023 through September 30th 2026
Funded Program: 6931203
District(s): 2

Project Description, Milestones and Service Impact

MIRA is partnering with the County to eliminate traffic, flooding, drainage and blighted gateway issues on South Courtenay Parkway between Fortenberry Road and Cone Road. The development activity on South Courtenay Pkwy area are contributing to unsafe bottlenecking traffic conditions. The County and MIRA will enter into an interlocal agreement to fund and manage the project. The project will be funded primarily by MIRA and Impact Fees.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Donations Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Incremental Tax Revenue	\$ -	\$ -	\$ 900,000	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 1,900,000
Sale of Surplus Equipment Revenue	\$ -	\$ 103,500	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 103,500
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 103,500	\$ 900,000	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 2,003,500
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ 103,500	\$ 900,000	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 2,003,500
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ 103,500	\$ 900,000	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 2,003,500

Natural Resources Management Department

Program Name: Beaches, Boating & Waterways
Project Name: Max Brewer Causeway Hurricane Storm Damage & Restoration
Project Total: \$1,000,000
Project Timeline: June 10, 2022 through September 30, 2025
Funded Program: 517434
District(s): 1

Project Description, Milestones and Service Impact

The Max Brewer Causeway Hurricane and Storm Damage Reduction and Restoration Project will rebuild and restore approximately 2,200 linear feet of shoreline (beach) on the northeast section of the Titusville Max Brewer Causeway for the purpose of fortifying a highly eroded roadway, a high-use public access area and a unique ecological use (Horseshoe Crab) area. The project will place approximately 17,600 cubic yards of sand to restore the northern shoreline of the Max Brewer Causeway.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
General Revenue	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,000,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sales Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,000,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 22,590	\$ 100,000	\$ 77,410	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Construction Expense	\$ -	\$ 500,000	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 800,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 22,590	\$ 600,000	\$ 377,410	\$ -	\$ -	\$ -	\$ -	\$ 1,000,000

Public Works Department

Program Name: TRAFFIC OPERATIONS
Project Name: Traffic ITS Fiber Upgrade Project
Project Total: \$200,000
Project Timeline: October 1, 2024 through September 30, 2025
Funded Program: 518822
District(s): Countywide

Project Description, Milestones and Service Impact

Countywide ATMS (ITS) network communications expansion projects.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000

Public Works Department

Program Name: ROAD AND BRIDGE
Project Name: Five Year Road Resurfacing Plan
Project Total: \$98,534,272
Project Timeline: October 1, 2018 through September 30, 2029
Funded Program: Not Applicable
District(s): Countywide

Project Description, Milestones and Service Impact

In FY 2017-18, the Board of County Commissioners approved a five-year funding plan to resurface a minimum of fifty-five (55) miles of roads countywide. This decreased our current backlog in resurfacing and avoided costly road reconstruction costs, which can be 4 to 6 times greater than the cost to resurface roads. In FY 19-20, an additional \$1,230,000 in General Fund was allocated to the Road Resurfacing plan to increase the annual target from fifty-five (55) miles of road resurfacing to sixty-three (63) miles of road resurfacing for FY 19-20. In FY 20-21 through FY 23-29, an annual projected increase in CPI of three (3) percent is reflected; as well as, to be determined supplemental funding sources to meet the Fifty-five (55) miles of road resurfacing within those fiscal years. In FY 22-23, there was a one-time transfer of Local Option Gas Tax to offset the resurfacing shortage; as well as, the CPI increase associated with resurfacing costs. An anticipated balance forward total of \$1,100,000 will be carried forward for utilization in FY24-25. Furthermore, an additional Ninety (90) miles of road preservation will be completed in FY 24-25. The objective of road preservation is to extend the lifespan of a newly paved asphalt surface which helps reduce future costs.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 1,905,000	\$ 635,000	\$ 635,000	\$ 635,000	\$ 635,000	\$ 635,000	\$ 635,000	\$ 5,715,000
Constitutional Gas Tax Revenue	\$ 8,111,250	\$ 2,920,000	\$ 2,920,000	\$ 2,920,000	\$ 2,920,000	\$ 2,920,000	\$ 2,920,000	\$ 25,631,250
Fuel Taxes Revenue	\$ 9,020,452	\$ 1,600,000	\$ 1,600,000	\$ 1,600,000	\$ 1,600,000	\$ 1,600,000	\$ 1,600,000	\$ 18,620,452
General Revenue	\$ 7,423,591	\$ 3,102,522	\$ 3,195,598	\$ 3,291,466	\$ 3,390,210	\$ 3,491,916	\$ 3,596,673	\$ 27,491,976
Grant Revenue	\$ 220,338	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 220,338
Other Transfers Revenue	\$ 2,544,765	\$ 2,522,011	\$ 3,361,648	\$ 3,106,708	\$ 3,106,708	\$ 3,106,708	\$ 3,106,708	\$ 20,855,256
Total Revenue	\$ 29,225,396	\$ 10,779,533	\$ 11,712,246	\$ 11,553,174	\$ 11,651,918	\$ 11,753,624	\$ 11,858,381	\$ 98,534,272
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Expense	\$ 29,225,396	\$ 10,779,533	\$ 11,712,246	\$ 11,553,174	\$ 11,651,918	\$ 11,753,624	\$ 11,858,381	\$ 98,534,272
Total Expense	\$ 29,225,396	\$ 10,779,533	\$ 11,712,246	\$ 11,553,174	\$ 11,651,918	\$ 11,753,624	\$ 11,858,381	\$ 98,534,272

Public Works Department

Program Name: ROAD AND BRIDGE
Project Name: Five Year Road Reconstruction
Project Total: \$35,615,739
Project Timeline: October 1, 2018 through September 30, 2029
Funded Program: Not Applicable
District(s): Countywide

Project Description, Milestones and Service Impact

In FY 2017-2018, the Board of County Commissioners approved a five-year funding plan to reconstruct roadways as funding was available countywide. In FY 18-19 the Road and Bridge MSTUs were leveraged in order to reconstruct (5.56) miles. In FY 19-20, the General Fund increased funding by \$2.7 million to the County's Road Reconstruction program. This additional funding supports, nine (9) miles of road reconstruction in FY 24-25; in order to continue to decrease our current reconstruction backlog. Additionally, an anticipated balance forward total of \$400,000 will be carried forward for utilization in FY24-25.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 1,019,643	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,019,643
Fuel Taxes Revenue	\$ 296,107	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 296,107
General Revenue	\$ 9,376,389	\$ 5,330,975	\$ 4,236,464	\$ 3,951,558	\$ 4,070,104	\$ 4,192,207	\$ 3,142,291	\$ 34,299,989
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 10,692,139	\$ 5,330,975	\$ 4,236,464	\$ 3,951,558	\$ 4,070,104	\$ 4,192,207	\$ 3,142,291	\$ 35,615,739
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ 10,692,139	\$ 5,330,975	\$ 4,236,464	\$ 3,951,558	\$ 4,070,104	\$ 4,192,207	\$ 3,142,291	\$ 35,615,739
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 10,692,139	\$ 5,330,975	\$ 4,236,464	\$ 3,951,558	\$ 4,070,104	\$ 4,192,207	\$ 3,142,291	\$ 35,615,739

Public Works Department

Program Name: ROAD AND BRIDGE
Project Name: Five Year Road Reconstruction
Project Total: \$35,615,739
Project Timeline: October 1, 2018 through September 30, 2029
Funded Program: Not Applicable
District(s): Countywide

Project Description, Milestones and Service Impact

In FY 2017-2018, the Board of County Commissioners approved a five-year funding plan to reconstruct roadways as funding was available countywide. In FY 18-19 the Road and Bridge MSTUs were leveraged in order to reconstruct (5.56) miles. In FY 19-20, the General Fund increased funding by \$2.7 million to the County's Road Reconstruction program. This additional funding supports, nine (9) miles of road reconstruction in FY 24-25; in order to continue to decrease our current reconstruction backlog. Additionally, an anticipated balance forward total of \$400,000 will be carried forward for utilization in FY24-25.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ 1,019,643	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,019,643
Fuel Taxes Revenue	\$ 296,107	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 296,107
General Revenue	\$ 9,376,389	\$ 5,330,975	\$ 4,236,464	\$ 3,951,558	\$ 4,070,104	\$ 4,192,207	\$ 3,142,291	\$ 34,299,989
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 10,692,139	\$ 5,330,975	\$ 4,236,464	\$ 3,951,558	\$ 4,070,104	\$ 4,192,207	\$ 3,142,291	\$ 35,615,739
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ 10,692,139	\$ 5,330,975	\$ 4,236,464	\$ 3,951,558	\$ 4,070,104	\$ 4,192,207	\$ 3,142,291	\$ 35,615,739
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 10,692,139	\$ 5,330,975	\$ 4,236,464	\$ 3,951,558	\$ 4,070,104	\$ 4,192,207	\$ 3,142,291	\$ 35,615,739

Public Works Department

Program Name: ROAD AND BRIDGE
Project Name: District Maintenance and Capital Projects - District 3
Project Total: \$702,300
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 518093
District(s): 3

Project Description, Milestones and Service Impact

District 3 major maintenance and capital projects; such as drainage, road rehabilitation, sidewalks, and bridge repairs. Project scope may include feasibility studies, survey, design, and construction. The service impact for these projects will improve and enhance the overall infrastructure of: stormwater systems, roadways, sidewalks, and general public safety. District 3 projects are as follows: A1A Bike Path Replacement (Ad Valorem/Constitutional Gas Tax)- \$150,020, Crane Creek Bank restoration (Ad Valorem) \$170,979; Palm Bay & Babcock Intersection Improvement & Hardening Feasibility Study (Constitutional Gas Tax)- \$47,000; Districtwide Roadway Safety Improvements (Ad Valorem)- \$25,000; Main St & Central Ave Drainage Improvement (Ad Valorem)- \$100,000; Midway St Cured in Place Pipe (CIPP) (Ad Valorem)- \$90,101; Sottile Canal Bank Restoration (Ad Valorem)- \$100,000 and Districtwide Sidewalk Repair and Replacement (Local Option Gas Tax)- \$19,200.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	286,080	\$ 300,000	\$ - \$	\$ - \$	\$ - \$	\$ - \$	586,080
Constitutional Gas Tax Revenue	\$ - \$	97,020	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	97,020
Fuel Taxes Revenue	\$ - \$	- \$	19,200	\$ - \$	\$ - \$	\$ - \$	\$ - \$	19,200
Grant Revenue	\$ - \$	- \$	- \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Impact Fees Revenue	\$ - \$	- \$	- \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Total Revenue	\$ - \$	383,100	\$ 319,200	\$ - \$	\$ - \$	\$ - \$	\$ - \$	702,300
Land Expense	\$ - \$	- \$	- \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Planning/Design Expense	\$ - \$	- \$	47,000	\$ - \$	\$ - \$	\$ - \$	\$ - \$	47,000
Construction Expense	\$ - \$	- \$	655,300	\$ - \$	\$ - \$	\$ - \$	\$ - \$	655,300
Other Expense	\$ - \$	- \$	- \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Total Expense	\$ - \$	- \$	702,300	\$ - \$	\$ - \$	\$ - \$	\$ - \$	702,300

Public Works Department

Program Name: ROAD AND BRIDGE
Project Name: District Maintenance and Capital Projects- District 1
Project Total: \$2,785,218
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 518091
District(s): 1

Project Description, Milestones and Service Impact

District 1 major maintenance and capital projects; such as drainage, road rehabilitation, sidewalks, and bridge repairs. Project scope may include feasibility studies, survey, design, and construction. These projects will improve/enhance the overall infrastructure of: stormwater systems, roadways, sidewalks, and general public safety. District 1 projects are as follows: State Road 405 Landscaping (Design & Construction) (Ad Valorem) - \$100,000; Districtwide Sidewalk Repair/Replacement (Ad Valorem, Local Option Gas Tax) - \$257,600; Districtwide Cured in Place Pipe (CIPP) (Ad Valorem) - \$250,000; Feather-Ackerman Drainage Improvement (Ad Valorem) \$75,000; Scottsmoor/Mims Drainage Study (Phase 1) (Ad Valorem)- \$75,000; Ranch Rd Paving and Drainage (Ad Valorem)- \$60,000; Districtwide Roadway Safety Improvements (Ad Valorem)- \$100,000; Westwood Dr Drainage Improvement (Ad Valorem/Local Option Gas Tax)- \$1,242,618; Sunset Ave (Phase 2) (Ad Valorem, Local Option Gas Tax)- \$425,000; Camp Rd Corridor Safety Study (Constitutional Gas Tax)- \$75,000; Grissom Pkwy and Canaveral Groves Blvd Intersection Safety Study (Constitutional Gas Tax)- \$75,000 and Adamson Rd and Coconut Ave Curve Realignment Feasibility Study (Local Option Gas Tax)- \$50,000

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	774,258	\$ 860,000	\$ - \$	\$ - \$	\$ - \$	\$ - \$	1,634,258
Fuel Taxes Revenue	\$ - \$	893,360	\$ 107,600	\$ - \$	\$ - \$	\$ - \$	\$ - \$	1,000,960
Constitutional Gas Tax Revenue	\$ - \$	- \$	150,000	\$ - \$	\$ - \$	\$ - \$	\$ - \$	150,000
Other Transfers Revenue	\$ - \$	- \$	- \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Total Revenue	\$ - \$	1,667,618	\$ 1,117,600	\$ - \$	\$ - \$	\$ - \$	\$ - \$	2,785,218
Land Expense	\$ - \$	- \$	- \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Planning/Design Expense	\$ - \$	- \$	50,000	\$ - \$	\$ - \$	\$ - \$	\$ - \$	50,000
Construction Expense	\$ - \$	- \$	2,735,218	\$ - \$	\$ - \$	\$ - \$	\$ - \$	2,735,218
Other Expense	\$ - \$	- \$	- \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Total Expense	\$ - \$	- \$	2,785,218	\$ - \$	\$ - \$	\$ - \$	\$ - \$	2,785,218

Public Works Department

Program Name: ROAD AND BRIDGE
Project Name: District Maintenance and Capital Projects- District 2
Project Total: \$1,740,320
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 518092
District(s): 2

Project Description, Milestones and Service Impact

District 2 major maintenance and capital projects such as drainage, road rehabilitation, sidewalks, and bridge repairs. Project scope may include feasibility studies, survey, design, and construction. The service impact for these projects will improve and enhance the overall infrastructure of: stormwater systems, roadways, sidewalks, and general public safety. District 2 projects are as follows: Districtwide Roadway Safety Improvements (Ad Valorem)- \$50,000; Oakledge Dr Drainage (Survey & Engineering) (Ad Valorem) - \$25,000; Brentwood Drainage Improvement (Constitutional Gas Tax) - \$150,420; Broad Acres Drainage Improvement (Ad Valorem/Local Option Gas Tax) - \$230,000; Del Sol Drainage Improvement (Ad Valorem/Local Option Gas Tax)- \$130,100; Angel Ave Drainage Improvement (Constitutional Gas Tax)- \$105,800; Teal St Dirt Road Paving (Ad Valorem/Constitutional Gas Tax)-\$176,500; Raven St Dirt Road Paving (Ad Valorem/Constitutional Gas Tax)- \$176,500; Districtwide Sidewalk Repair and Replacement (Local Option Gas Tax)- \$96,000 and Hidden Lakes Dr Cured in Place Pipe (CIPP) (Ad Valorem) \$100,000; Rockledge Dr Paving (Local Option Gas Tax)- \$500,000.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ 205,000	\$ 150,000	\$ -	\$ -	\$ -	\$ -	\$ 355,000
Fuel Taxes Revenue	\$ -	\$ -	\$ 826,100	\$ -	\$ -	\$ -	\$ -	\$ 826,100
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ -	\$ 559,220	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 559,220
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 764,220	\$ 976,100	\$ -	\$ -	\$ -	\$ -	\$ 1,740,320
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 25,000	\$ -	\$ -	\$ -	\$ -	\$ 25,000
Construction Expense	\$ -	\$ -	\$ 1,412,320	\$ -	\$ -	\$ -	\$ -	\$ 1,412,320
Other Expense	\$ -	\$ -	\$ 303,000	\$ -	\$ -	\$ -	\$ -	\$ 303,000
Total Expense	\$ -	\$ -	\$ 1,740,320	\$ -	\$ -	\$ -	\$ -	\$ 1,740,320

Public Works Department

Program Name: ROAD AND BRIDGE
Project Name: District Maintenance and Capital Projects- District 4
Project Total: \$2,311,320
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 518094
District(s): 4

Project Description, Milestones and Service Impact

District 4 major maintenance and capital projects; such as drainage, road rehabilitation, sidewalks, and bridge repairs. Project scope may include feasibility studies, survey, design, and construction. The service impact for these projects will improve and enhance the overall infrastructure of: stormwater systems, roadways, sidewalks, and general public safety. District 4 projects are as follows: Districtwide Roadway Safety Improvements (Ad Valorem)- \$200,000; Districtwide Sidewalk Repair and Replacement (Ad Valorem/Local Option Gas Tax)- \$374,800; Districtwide Cured In Place Pipe (CIPP) (Ad Valorem)- \$300,000; Interlachen Rd Sidewalk (Phase 2) (Ad Valorem)- \$160,000; Oak Park Drainage Improvement (Ad Valorem)- \$461,100; Aurora Rd Sidewalk & Drainage (Ad Valorem/Local Option Gas Tax)- \$504,420; Wickham Rd & Jordan Blass Intersection Signal Hardening (Local Option Gas Tax)- \$107,000; Wickham Rd & Pineda Plaza Intersection Signal Hardening (Local Option Gas Tax)- \$104,000 and South Patrick Area Drainage (Constitutional Gas Tax)- \$100,000.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ 350,000	\$ 1,371,100	\$ -	\$ -	\$ -	\$ -	\$ 1,721,100
Fuel Taxes Revenue	\$ -	\$ 365,420	\$ 124,800	\$ -	\$ -	\$ -	\$ -	\$ 490,220
Constitutional Gas Tax Revenue	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 815,420	\$ 1,495,900	\$ -	\$ -	\$ -	\$ -	\$ 2,311,320
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 211,000	\$ -	\$ -	\$ -	\$ -	\$ 211,000
Construction Expense	\$ -	\$ -	\$ 2,100,320	\$ -	\$ -	\$ -	\$ -	\$ 2,100,320
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 2,311,320	\$ -	\$ -	\$ -	\$ -	\$ 2,311,320

Public Works Department

Program Name: ROAD AND BRIDGE
Project Name: District Maintenance and Capital Projects- District 5
Project Total: \$672,400
Project Timeline: October 1, 2023 through September 30, 2025
Funded Program: 518095
District(s): 5

Project Description, Milestones and Service Impact

District 5 major maintenance repair projects; such as drainage, road rehabilitation, sidewalks, and bridge repairs. Project scope may include feasibility studies, survey, design, and construction. The service impact for these projects will improve and enhance the overall infrastructure of: stormwater systems, roadways, sidewalks, and general public safety. District 5 projects are as follows: Trimble Road Ditch Restoration (Ad Valorem)- \$100,000; Districtwide Roadway Safety Improvements (Ad Valorem)- \$50,000; Districtwide Cured in Place Pipe (CIPP) (Ad Valorem)- \$250,000; Indianalantic Drainage Improvements (Ad Valorem)- \$100,000; Minton Rd Safety and Operational Improvements Feasibility Study (Local Option Gas Tax)- \$150,000 and Districtwide Sidewalk Repair and Replacement (Local Option Gas Tax)- \$22,400.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ 100,000	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ 500,000
Fuel Taxes Revenue	\$ -	\$ 150,000	\$ 22,400	\$ -	\$ -	\$ -	\$ -	\$ 172,400
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 250,000	\$ 422,400	\$ -	\$ -	\$ -	\$ -	\$ 672,400
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 150,000	\$ -	\$ -	\$ -	\$ -	\$ 150,000
Construction Expense	\$ -	\$ -	\$ 522,400	\$ -	\$ -	\$ -	\$ -	\$ 522,400
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 672,400	\$ -	\$ -	\$ -	\$ -	\$ 672,400

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Aurora Road Sidewalk
Project Total: \$1,664,459
Project Timeline: October 1, 2019 through December 31, 2026
Funded Program: 6956510
District(s): 5

Project Description, Milestones and Service Impact

Phase I- Design and permitting completed for approximately 3500 LF of sidewalk on the north side of Aurora Road (Marywood Road to Turtlemound Road); construction anticipated in FY23/24. Phase II- Turtlemound to Wickham South Side survey completion in FY24 and design completion in FY25. The service impact for this project will minimize and/or eliminate safety hazards on this corridor and provide pedestrians a more safe walkway.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ 194,519	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 194,519
Fuel Taxes Revenue	\$ 1,469,940	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,469,940
Total Revenue	\$ 1,664,459	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,664,459
Land Expense	\$ 6,630	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 6,630
Planning/Design Expense	\$ 126,767	\$ 4,603	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 331,370
Construction Expense	\$ -	\$ 462,576	\$ 677,330	\$ 186,553	\$ -	\$ -	\$ -	\$ 1,326,459
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 133,397	\$ 467,179	\$ 877,330	\$ 186,553	\$ -	\$ -	\$ -	\$ 1,664,459

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: St. Johns Heritage Parkway and Ellis Road 4-Lane Project
Project Total: \$92,271,767
Project Timeline: December 1, 2014 through September 30, 2027
Funded Program: 6932504
District(s): 5

Project Description, Milestones and Service Impact

This project consists of widening Ellis Road to four lanes from John Rodes Boulevard to just west of Wickham Road totaling 1.7 miles. Signal plans, pavement marking plans, as well as utility coordination and permitting will be a part of this project. The accepted drainage concept will facilitate a final design which should reduce the right-of-way impacts. Florida Department of Transportation (FDOT) grant funds were used for the design (\$2,960,329) and estimated right-of-way \$37.8M will be funded by FDOT. \$1,760,764 of County ARPA Grant funds in FY22 was used for right-of-way. The \$92M listed above is for design and construction only. The service impact for this project alleviates drainage issues, traffic congestion, and improves the flow of traffic along Ellis Road, a SIS connector roadway to the Melbourne Airport and Ellis I-95 interchange. A Federal INFRA Grant as well as alternative funding sources are being pursued to address the unfunded shortfall.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ 4,186,974	\$ 1,573,389	\$ 2,000,000	\$ -	\$ -	\$ -	\$ -	\$ 7,760,363
Grant Revenue	\$ 4,721,093	\$ -	\$ -	\$ 26,155,446	\$ -	\$ -	\$ -	\$ 30,876,539
Other Finance Sources Revenue	\$ -	\$ 1,208,672	\$ 216,398	\$ 1,600,000	\$ -	\$ -	\$ -	\$ 3,025,070
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ 50,609,795	\$ -	\$ -	\$ 50,609,795
Total Revenue	\$ 8,908,067	\$ 2,782,061	\$ 2,216,398	\$ 27,755,446	\$ 50,609,795	\$ -	\$ -	\$ 92,271,767
Land Expense	\$ 1,760,764	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,760,764
Planning/Design Expense	\$ 2,960,329	\$ 360,569	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 3,520,898
Construction Expense	\$ -	\$ -	\$ -	\$ 15,000,000	\$ 20,000,000	\$ 41,341,725	\$ 10,648,380	\$ 86,990,105
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 4,721,093	\$ 360,569	\$ 200,000	\$ 15,000,000	\$ 20,000,000	\$ 41,341,725	\$ 10,648,380	\$ 92,271,767

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Hollywood Blvd Widening Project
Project Total: \$95,182,303
Project Timeline: August 20, 2007 through September 30, 2030
Funded Program: 6932301
District(s): 3

Project Description, Milestones and Service Impact

Design, permitting, right-of-way acquisition, and construction of widening Hollywood Boulevard from US 192 to Palm Bay Road (3.1 miles). Design underway using Grant funds from Florida Department of Transportation (FDOT). County funds used for right-of-way as parcels and funding becomes available. The service impact for this project will relieve traffic congestion in this surrounding community and promote access management.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Bond/Referendum Revenue	\$ 3,507,484	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 3,507,484
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 85,148,709	\$ 85,148,709
Constitutional Gas Tax Revenue	\$ 1,852,485	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,852,485
Grant Revenue	\$ 3,847,902	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 3,847,902
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Impact Fees Revenue	\$ 825,723	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 825,723
Total Revenue	\$ 10,033,594	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 85,148,709	\$ 95,182,303
Land Expense	\$ 3,404,973	\$ 203,198	\$ 479,078	\$ 100,000	\$ 300,000	\$ 329,000	\$ -	\$ 4,816,249
Planning/Design Expense	\$ 1,887,774	\$ 574,263	\$ 625,000	\$ -	\$ -	\$ -	\$ -	\$ 3,087,037
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 87,279,017	\$ 87,279,017
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 5,292,747	\$ 777,461	\$ 1,104,078	\$ 100,000	\$ 300,000	\$ 329,000	\$ 87,279,017	\$ 95,182,303

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: North Banana River Dr. Bridge #704014
Project Total: \$150,000
Project Timeline: April 5, 2022 through September 30, 2025
Funded Program: 6963201
District(s): 2

Project Description, Milestones and Service Impact

This project consists of consultant services to provide a Feasibility Study for the proposed replacement of the North Banana River Drive Bridge #704014. The service impact will result in a comprehensive report which includes survey, hydraulics analysis, geotechnical investigation, environmental services, and conceptual structure and roadway plans.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ 150,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	150,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 150,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	150,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 134,363	\$ 11,887	\$ 3,750	\$ -	\$ -	\$ -	\$ -	150,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 134,363	\$ 11,887	\$ 3,750	\$ -	\$ -	\$ -	\$ -	150,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: North Banana River Drive Bridge #704015
Project Total: \$150,000
Project Timeline: April 5, 2022 through September 30, 2025
Funded Program: 6963202
District(s): 2

Project Description, Milestones and Service Impact

This project consists of consultant services to provide a Feasibility Study for the proposed replacement of the North Banana River Drive Bridge #704015. The service impact will result in a comprehensive report which includes survey, hydraulics analysis, geotechnical investigation, environmental services, and conceptual structure and roadway plans.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Impact Fees Revenue	\$ 150,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	150,000
Total Revenue	\$ 150,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	150,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 120,571	\$ 11,887	\$ 17,542	\$ -	\$ -	\$ -	\$ -	150,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 120,571	\$ 11,887	\$ 17,542	\$ -	\$ -	\$ -	\$ -	150,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Micco Bridge Replacement
Project Total: \$4,600,000
Project Timeline: April 7, 2020 through September 30, 2025
Funded Program: 6970300
District(s): 3

Project Description, Milestones and Service Impact

This project includes survey, engineering design, and construction to replace the Micco Bridge; constructed in 1938 and at the end of its service life. This service impact will provide citizens a more efficient and safe bridge to travel.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Fuel Taxes Revenue	\$ 2,600,000	\$ 2,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	4,600,000
Total Revenue	\$ 2,600,000	\$ 2,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	4,600,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 40,867	\$ 4,062,190	\$ -	\$ -	\$ -	\$ -	\$ -	4,103,057
Construction Expense	\$ -	\$ -	\$ 496,943	\$ -	\$ -	\$ -	\$ -	496,943
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 40,867	\$ 4,062,190	\$ 496,943	\$ -	\$ -	\$ -	\$ -	4,600,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Girard Boulevard Bridge #704016
Project Total: \$85,000
Project Timeline: April 5, 2022 through September 30, 2025
Funded Program: 6963203
District(s): 2

Project Description, Milestones and Service Impact

This project consists of consultant services to provide a Feasibility Study for the proposed replacement of the Girard Blvd. Bridge #704016. The service impact will result in a comprehensive report which includes survey, hydraulics analysis, geotechnical investigation, environmental services, and conceptual structure and roadway plans.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Impact Fees Revenue	\$ 85,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	85,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 85,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	85,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 63,750	\$ 19,125	\$ 2,125	\$ -	\$ -	\$ -	\$ -	85,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 63,750	\$ 19,125	\$ 2,125	\$ -	\$ -	\$ -	\$ -	85,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Sea Ray Bridge Replacement
Project Total: \$12,991,766
Project Timeline: November 1, 2006 through December 31, 2026
Funded Program: 6970200
District(s): 2

Project Description, Milestones and Service Impact

Replacement of the Sea Ray Bridge over Sykes Creek with Florida I-Beam construction. Prior milestones included completion of the permitting and conceptual plans. Notice to Proceed for final design was issued in May 2022 and is completed. Construction is anticipated to commence in July 2024 due to City of Cocoa waterline removal delays; it is estimated to take 18 months for completion. The service impact will open the closed roadway for vehicular and pedestrian traffic and provide a new bridge with a 75-year service life.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Bond/Referendum Revenue	\$ 805,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 805,000
Constitutional Gas Tax Revenue	\$ 5,905,000	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 6,905,000
Fuel Taxes Revenue	\$ 899,397	\$ 2,226,524	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 3,125,921
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ 780,845	\$ 275,000	\$ 275,000	\$ 275,000	\$ 275,000	\$ 275,000	\$ -	\$ 2,155,845
Total Revenue	\$ 8,390,242	\$ 3,501,524	\$ 275,000	\$ 275,000	\$ 275,000	\$ 275,000	\$ -	\$ 12,991,766
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 1,151,395	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,151,395
Construction Expense	\$ -	\$ 3,865,518	\$ 7,226,524	\$ 748,329	\$ -	\$ -	\$ -	\$ 11,840,371
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 1,151,395	\$ 3,865,518	\$ 7,226,524	\$ 748,329	\$ -	\$ -	\$ -	\$ 12,991,766

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: South Courtenay Parkway Widening
Project Total: \$3,927,026
Project Timeline: August 25, 2020 through September 30, 2026
Funded Program: 6931203
District(s): 2

Project Description, Milestones and Service Impact

This project consists of a three lane widening project from Cone Road to Fortenberry (0.48 miles). Staff has an Interlocal Agreement with Merritt Island Redevelopment Agency to participate in funding this project up to \$2M. The service impact for this project will relieve traffic congestion in this surrounding community and promote access management.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Impact Fees Revenue	\$ 1,927,026	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,927,026
Other Finance Sources Revenue	\$ -	\$ 100,000	\$ 900,000	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 2,000,000
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 1,927,026	\$ 100,000	\$ 900,000	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 3,927,026
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 929,938	\$ 253,285	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,183,223
Construction Expense	\$ -	\$ -	\$ 1,743,803	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 2,743,803
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 929,938	\$ 253,285	\$ 1,743,803	\$ 1,000,000	\$ -	\$ -	\$ -	\$ 3,927,026

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Sheridan Road Sidewalk Phase II
Project Total: \$1,520,000
Project Timeline: October 1, 2019 through April 30, 2026
Funded Program: 6956509
District(s): 5

Project Description, Milestones and Service Impact

Design, permitting, and construction of approximately 4700 LF of sidewalk for Phase II of Sheridan Road sidewalk from Sylvan Dr. West to Wickham Road. Phase I was completed in fiscal year 2018 from John Rodes Boulevard to Sylvan Drive West. Staff is working with W. Melbourne to participate with the County in funding this project. The service impact of this project provides a safe pedestrian corridor.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Fuel Taxes Revenue	\$ 710,000	\$ -	\$ 810,000	\$ -	\$ -	\$ -	\$ -	1,520,000
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ 710,000	\$ -	\$ 810,000	\$ -	\$ -	\$ -	\$ -	1,520,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ 21,623	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	21,623
Construction Expense	\$ -	\$ 2,000	\$ 1,152,578	\$ 343,799	\$ -	\$ -	\$ -	1,498,377
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ 21,623	\$ 2,000	\$ 1,152,578	\$ 343,799	\$ -	\$ -	\$ -	1,520,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Tangerine Street Dirt Road Paving
Project Total: \$71,988
Project Timeline: April 15, 2024 through September 30, 2025
Funded Program: 6930171
District(s): 1

Project Description, Milestones and Service Impact

This project is in Canaveral Groves and would convert Tangerine Street (4200 LF S. of Citrus Ave.) to a paved road. Phase I is fully funded for design and survey. The service impact for this project will enhance and improve stormwater and requires less maintenance due to the paving.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ 71,988	\$ -	\$ -	\$ -	\$ -	\$ -	71,988
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ -	\$ 71,988	\$ -	\$ -	\$ -	\$ -	\$ -	71,988
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Construction Expense	\$ -	\$ -	\$ 71,988	\$ -	\$ -	\$ -	\$ -	71,988
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ -	\$ -	\$ 71,988	\$ -	\$ -	\$ -	\$ -	71,988

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Suntree Blvd and Wickham Road Intersection Improvements
Project Total: \$4,569,250
Project Timeline: December 10, 2019 through September 30, 2027
Funded Program: 6936308
District(s): 4

Project Description, Milestones and Service Impact

This project will upgrade the current Suntree Blvd & Wickham Rd intersection based on the feasibility study completed in FY23. Recommended improvements include intersection signalization updates, roadway widening of Suntree Blvd between Wickham Road & US-1, and turn lane lengthening. The service impact will provide citizens a more efficient and safe roadway to travel.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Impact Fees Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Charges For Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Constitutional Gas Tax Revenue	\$ 400,000	\$ 70,000	- \$	- \$	- \$	- \$	- \$	470,000
Unfunded	\$ - \$	- \$	- \$	- \$	- \$	4,099,250	- \$	4,099,250
Total Revenue	\$ 400,000	\$ 70,000	- \$	- \$	- \$	4,099,250	- \$	4,569,250
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ 150,958	265,042	- \$	- \$	- \$	- \$	- \$	416,000
Construction Expense	\$ - \$	- \$	54,000	- \$	- \$	- \$	- \$	54,000
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	4,099,250	- \$	4,099,250
Total Expense	\$ 150,958	\$ 265,042	\$ 54,000	- \$	4,099,250	- \$	- \$	4,569,250

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Vacaro Avenue Dirt Road Paving
Project Total: \$73,662
Project Timeline: April 15, 2024 through September 30, 2025
Funded Program: 6930172
District(s): 1

Project Description, Milestones and Service Impact

This project is in Canaveral Groves and would convert Vacaro Ave.(2200 LF S. of Citrus Ave.) to a paved road. Phase I is fully funded for design and survey. The service impact for this project will enhance and improve stormwater and requires less maintenance due to the paving.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Impact Fees Revenue	\$ - \$	73,662	- \$	- \$	- \$	- \$	- \$	73,662
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Constitutional Gas Tax Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Fuel Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Revenue	\$ - \$	\$ 73,662	- \$	- \$	- \$	- \$	- \$	73,662
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Planning/Design Expense	\$ - \$	- \$	73,662	- \$	- \$	- \$	- \$	73,662
Construction Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	- \$
Total Expense	\$ - \$	- \$	73,662	- \$	- \$	- \$	- \$	73,662

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Traffic Management Center
Project Total: \$17,828,413
Project Timeline: March 21, 2012 through September 30, 2026
Funded Program: 6500410
District(s): Countywide

Project Description, Milestones and Service Impact

This project consist of the architectural and engineering design of the Traffic Management Center (TMC) facility to support not only the current Intelligent Transportation System (ITS) deployment but all future Transportation Systems Management and Operations (ITSM&O) initiatives. The service impact for the Traffic Management Center, will be a control center that will increase the traffic flow efficiency and safety of Brevard County roads.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Grant Revenue	\$ -	\$ -	\$ 8,100,000	\$ -	\$ -	\$ -	\$ -	\$ 8,100,000
Constitutional Gas Tax Revenue	\$ -	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,000,000
Fuel Taxes Revenue	\$ 8,728,413	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 8,728,413
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Interest Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 8,728,413	\$ 1,000,000	\$ 8,100,000	\$ -	\$ -	\$ -	\$ -	\$ 17,828,413
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 31,047	\$ 639,721	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 670,768
Construction Expense	\$ -	\$ -	\$ 7,721,488	\$ 9,436,157	\$ -	\$ -	\$ -	\$ 17,157,645
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 31,047	\$ 639,721	\$ 7,721,488	\$ 9,436,157	\$ -	\$ -	\$ -	\$ 17,828,413

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Wickham Road and Aurora Pedestrian Improvements
Project Total: \$100,000
Project Timeline: October 1, 2020 through September 30, 2025
Funded Program: 6936411
District(s): 4

Project Description, Milestones and Service Impact

This project will construct new pedestrian improvements at the Aurora Rd & Wickham Rd intersection to include additional pedestrian crosswalks and pedestrian signal poles. The service impact will provide citizens a safer intersection to cross over.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Total Revenue	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ 8,635	\$ 51,465	\$ 39,900	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 8,635	\$ 51,465	\$ 39,900	\$ -	\$ -	\$ -	\$ -	\$ 100,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Wickham Road and Lake Washington Pedestrian Improvements
Project Total: \$100,000
Project Timeline: October 1, 2020 through September 30, 2025
Funded Program: 6936412
District(s): 4

Project Description, Milestones and Service Impact

This project will construct new pedestrian improvements at the Lake Washington Rd and Wickham Rd intersection to include additional pedestrian crosswalks and pedestrian signal poles. The service impact will provide citizens a safer intersection to cross over.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Total Revenue	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 5,900	\$ 50,100	\$ 44,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 5,900	\$ 50,100	\$ 44,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Grissom Parkway Widening
Project Total: \$1,200,000
Project Timeline: July 6th, 2021 through September 30th, 2025
Funded Program: 6932102
District(s): 1

Project Description, Milestones and Service Impact

Preliminary engineering assessment for widening of Grissom Parkway (Port St John Pkwy to Fay Blvd) to a four-lane divided roadway about 5,500 Linear Feet completed in FY23. Design in FY23/24/25. The service impact for this project will relieve traffic congestion in this surrounding community and promote access management.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Impact Fees Revenue	\$ 200,000	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,200,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 200,000	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,200,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 18,481	\$ 181,519	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ 1,200,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 18,481	\$ 181,519	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ 1,200,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Dixie Way Dirt Road Paving
Project Total: \$800,000
Project Timeline: July 6th, 2021 through September 30th, 2025
Funded Program: 6930170
District(s): 1

Project Description, Milestones and Service Impact

Feasibility study and a survey to evaluate converting approximately 5.4 miles of unpaved road along Dixie Way to asphalt paved roadway. The service impact for this project will enhance and improve stormwater and require less maintenance due to the paving.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ 800,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 800,000
Bond/Referendum Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 800,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 800,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 156,586	\$ 573,414	\$ 70,000	\$ -	\$ -	\$ -	\$ -	\$ 800,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 156,586	\$ 573,414	\$ 70,000	\$ -	\$ -	\$ -	\$ -	\$ 800,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: West Central Avenue Bridge #704024
Project Total: \$3,084,000
Project Timeline: April 5, 2022 through September 30th 2027
Funded Program: 6963204
District(s): 2

Project Description, Milestones and Service Impact

This project consists of consultant services to provide a feasibility study and design for the proposed replacement of the West Central Avenue Bridge #70424. A completed comprehensive report includes survey, hydraulics analysis, geotechnical investigation, environmental services, and conceptual structure and roadway plans. Funding allocated for design. The service impact for this project will replace infrastructure beyond its useful service life.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ 84,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 84,000
Unfunded	\$ -	\$ -	\$ -	\$ 2,500,000	\$ -	\$ -	\$ -	\$ 2,500,000
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ -	\$ 500,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 500,000
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ 84,000	\$ 500,000	\$ -	\$ 2,500,000	\$ -	\$ -	\$ -	\$ 3,084,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ 5,000	\$ 279,000	\$ 300,000	\$ -	\$ -	\$ -	\$ -	\$ 584,000
Construction Expense	\$ -	\$ -	\$ -	\$ 1,250,000	\$ 1,250,000	\$ -	\$ -	\$ 2,500,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ 5,000	\$ 279,000	\$ 300,000	\$ 1,250,000	\$ 1,250,000	\$ -	\$ -	\$ 3,084,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Kumquat Street Dirt Road Paving
Project Total: \$77,303
Project Timeline: April 15, 2024 through September 30th, 2025
Funded Program: 6930173
District(s): 1

Project Description, Milestones and Service Impact

This project is in Canaveral Groves and would convert Kumquat St.(2100 LF S. of Citrus Ave.) to a paved road. Phase I is fully funded for design and survey. The service impact for this project will enhance and improve stormwater and requires less maintenance due to the paving.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ - \$	77,303	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	77,303
Bond/Referendum Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Charges For Services Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Constitutional Gas Tax Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Unfunded	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Total Revenue	\$ - \$	77,303	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	77,303
Land Expense	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Planning/Design Expense	\$ - \$	\$ - \$	77,303	\$ - \$	\$ - \$	\$ - \$	\$ - \$	77,303
Construction Expense	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Other Expense	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Total Expense	\$ - \$	\$ - \$	77,303	\$ - \$	\$ - \$	\$ - \$	\$ - \$	77,303

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Navel Street Dirt Road Paving
Project Total: \$22,086
Project Timeline: April 15, 2024 through September 30th, 2025
Funded Program: 6930174
District(s): 1

Project Description, Milestones and Service Impact

This project is in Canaveral Groves and would convert Navel St..(600 LF S. of Citrus Ave.) to a paved road. Phase I is fully funded for design and survey. The service impact for this project will enhance and improve stormwater and requires less maintenance due to the paving.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ - \$	22,086	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	22,086
Bond/Referendum Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Charges For Services Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Constitutional Gas Tax Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Fuel Taxes Revenue	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Total Revenue	\$ - \$	22,086	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	22,086
Land Expense	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Planning/Design Expense	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Construction Expense	\$ - \$	\$ - \$	22,086	\$ - \$	\$ - \$	\$ - \$	\$ - \$	22,086
Other Expense	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	\$ - \$	-
Total Expense	\$ - \$	\$ - \$	22,086	\$ - \$	\$ - \$	\$ - \$	\$ - \$	22,086

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Paddington Street Dirt Road Paving
Project Total: \$22,086
Project Timeline: April 15, 2024 through September 30th, 2025
Funded Program: 6930175
District(s): 1

Project Description, Milestones and Service Impact

This project is in Canaveral Groves and would convert Paddington St. Navel St..(600 LF S. of Citrus Ave.) to a paved road. Phase I is fully funded for design and survey. The service impact for this project will enhance and improve stormwater and requires less maintenance due to the paving.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ - \$	22,086 \$	- \$	- \$	- \$	- \$	- \$	22,086
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges For Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Constitutional Gas Tax Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Unfunded	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	22,086 \$	- \$	- \$	- \$	- \$	- \$	22,086
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	22,086 \$	- \$	- \$	- \$	- \$	22,086
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	22,086 \$	- \$	- \$	- \$	- \$	22,086

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Shadwell Avenue Dirt Road Paving
Project Total: \$77,308
Project Timeline: April 15, 2024 through September 30th, 2025
Funded Program: 6930176
District(s): 1

Project Description, Milestones and Service Impact

This project is in Canaveral Groves and would convert Shadwell Ave. (2100 LF S. of Citrus Ave.) to a paved road. Phase I is fully funded for design and survey. The service impact for this project will enhance and improve stormwater and requires less maintenance due to the paving.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ - \$	77,308 \$	- \$	- \$	- \$	- \$	- \$	77,308
Bond/Referendum Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Charges For Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Fuel Taxes Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	77,308 \$	- \$	- \$	- \$	- \$	- \$	77,308
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	77,308 \$	- \$	- \$	- \$	- \$	77,308
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	77,308 \$	- \$	- \$	- \$	- \$	77,308

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Countywide Bridge Rehabilitation
Project Total: \$1,400,000
Project Timeline: October 1, 2022 through September 30, 2025
Funded Program: 517298
District(s): Countywide

Project Description, Milestones and Service Impact

This project consists of consultant services and repairs and maintenance to bridges across the county. The service impact will provide citizens more efficient and safer bridges to travel.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ 1,400,000	\$ -	\$ -	\$ -	\$ -	\$ 1,400,000
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 1,400,000	\$ -	\$ -	\$ -	\$ -	\$ 1,400,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ 400,000
Construction Expense	\$ -	\$ -	\$ 1,000,000	\$ -	\$ -	\$ -	\$ -	\$ 1,000,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 1,400,000	\$ -	\$ -	\$ -	\$ -	\$ 1,400,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Bamboo Avenue Sidewalk
Project Total: \$162,196
Project Timeline: April 15, 2024 through September 30, 2025
Funded Program: 6911105
District(s): 1

Project Description, Milestones and Service Impact

This project is located in Port St. John installing new sidewalk aprox. 3100 LF. Engineering and survey for phase 1 funded in FY 24. Staff anticipates adding construction funds in FY 26. The service impact of this project provides a safe pedestrian corridor.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ 162,196	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 162,196
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 162,196	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 162,196
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 162,196	\$ -	\$ -	\$ -	\$ -	\$ 162,196
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 162,196	\$ -	\$ -	\$ -	\$ -	\$ 162,196

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Akers Street Sidewalk
Project Total: \$13,080
Project Timeline: April 15, 2024 through September 30, 2025
Funded Program: 6911106
District(s): 1

Project Description, Milestones and Service Impact

This project is located in Port St. John installing new sidewalk aprox. 250 LF. Engineering and survey for phase 1 funded in FY 24. The service impact of this project provides a safe pedestrian corridor.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ 13,080	\$ -	\$ -	\$ -	\$ -	\$ -	13,080
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ -	\$ 13,080	\$ -	\$ -	\$ -	\$ -	\$ -	13,080
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ -	\$ -	\$ 13,080	\$ -	\$ -	\$ -	\$ -	13,080
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ -	\$ -	\$ 13,080	\$ -	\$ -	\$ -	\$ -	13,080

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Aruin Street.Sidewalk
Project Total: \$28,777
Project Timeline: April 15, 2024 through September 30, 2025
Funded Program: 6911107
District(s): 1

Project Description, Milestones and Service Impact

This project is located in Port St. John installing new sidewalk aprox. 550 LF. Engineering and survey for phase 1 funded in FY 24. Staff anticipates adding construction funds in FY 26. The service impact of this project provides a safe pedestrian corridor.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ 28,777	\$ -	\$ -	\$ -	\$ -	\$ -	28,777
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Revenue	\$ -	\$ 28,777	\$ -	\$ -	\$ -	\$ -	\$ -	28,777
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Planning/Design Expense	\$ -	\$ -	\$ 28,777	\$ -	\$ -	\$ -	\$ -	28,777
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	-
Total Expense	\$ -	\$ -	\$ 28,777	\$ -	\$ -	\$ -	\$ -	28,777

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Stadium Parkway and Cuddington Drive Intersection Improvements
Project Total: \$200,000
Project Timeline: October 19, 2024 through September 30, 2025
Funded Program: 6936417
District(s): 4

Project Description, Milestones and Service Impact

This is an intersection improvement project at Stadium Parkway and Cuddington Drive for signalization funding for design. The service impact will provide citizens a more efficient and safe roadway to travel.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Stadium Parkway and Veterans Way Intersection Improvements
Project Total: \$400,000
Project Timeline: October 19th, 2024 through September 30th, 2025
Funded Program: 6936418
District(s): 4

Project Description, Milestones and Service Impact

This is an Intersection Improvement project at Stadium Parkway and Veterans Way. It will consist of widening to add a left turn lane on Veterans Way. Being constructed by Brevard County School Board, Public Works is contributing \$400K to the cost of this project. The service impact will provide citizens a more efficient and safe roadway to travel.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 400,000
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 400,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ 400,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 400,000	\$ -	\$ -	\$ -	\$ -	\$ 400,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Wickham Road and Pineda Boulevard Intersection Improvements
Project Total: \$1,621,000
Project Timeline: October 1st, 2023 through September 30th, 2027
Funded Program: 6936414
District(s): 4

Project Description, Milestones and Service Impact

Project includes survey, design and turn lanes based on a feasibility study completed in FY 23. Due to permitting issues, the project will be split into 2 phases. Phase 1 will include the majority of the turn lane improvements where there are no wetland impacts. Phase 2 will be for the turn lane with wetland impacts. The service impact will provide citizens a more efficient and safe roadway to travel.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ 400,000	\$ 165,000	\$ 667,500	\$ -	\$ -	\$ -	\$ 1,232,500
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ 388,500	\$ -	\$ -	\$ 388,500
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 400,000	\$ 165,000	\$ 667,500	\$ 388,500	\$ -	\$ -	\$ 1,621,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ 106,617	\$ 28,383	\$ -	\$ -	\$ -	\$ -	\$ 135,000
Construction Expense	\$ -	\$ -	\$ 430,000	\$ 667,500	\$ -	\$ -	\$ -	\$ 1,097,500
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ 388,500	\$ -	\$ -	\$ 388,500
Total Expense	\$ -	\$ 106,617	\$ 458,383	\$ 667,500	\$ 388,500	\$ -	\$ -	\$ 1,621,000

Public Works Department

Program Name: TRANSPORTATION CONSTRUCTION
Project Name: Wickham Road and Post Road Intersection Improvements
Project Total: \$200,000
Project Timeline: July 1st, 2024 through September 30, 2025
Funded Program: 6936407
District(s): 5

Project Description, Milestones and Service Impact

This project is for design and construction at the Wickham Rd & Post Rd intersection. Staff is seeking a grant with Florida Department of Transportation (FDOT) for a 50% grant estimated to be in the FY25 FDOT program. Staff is also working with the City of Melbourne to pay for at least 50% of the project in the event it is not awarded a grant. The service impact will provide citizens a more efficient and safe roadway to travel.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Impact Fees Revenue	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Constitutional Gas Tax Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fuel Taxes Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000

Transit Services Department

Program Name: TRANSIT CAPITAL
Project Name: Cocoa Terminal- Fuel Tanks
Project Total: \$646,500
Project Timeline: October 1, 2022 through December 31, 2024
Funded Program: 6538218
District(s): 2

Project Description, Milestones and Service Impact

Replace two existing 1,000 gallon fuel tanks with two 5,000 gallon fuel tanks and replace the damaged concrete surrounding the fuel tanks. This will allow us to meet our existing need for our gas powered buses, and will allow for more growth as we move more of our paratransit fleet from diesel powered vehicles to gasoline. The larger tanks will also be advantageous during declared emergencies when fuel deliveries can not be made.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ - \$	646,500	- \$	- \$	- \$	- \$	- \$	646,500
Other Finance Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ - \$	646,500	- \$	- \$	- \$	- \$	- \$	646,500
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ - \$	- \$	646,500	- \$	- \$	- \$	- \$	646,500
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ - \$	- \$	646,500	- \$	- \$	- \$	- \$	646,500

Transit Services Department

Program Name: TRANSIT CAPITAL
Project Name: Bus Shelters - Countywide
Project Total: \$2,768,846
Project Timeline: Ongoing
Funded Program: 6300010
District(s): 1,2,3,4 and 5

Project Description, Milestones and Service Impact

Space Coast Area Transit will be working with local municipalities to construct and install bus shelters, benches, amenities and signage through the use of inter-local agreements. Space Coast Area Transit will permit, construct and upgrade bus shelters to meet the American with Disabilities Act requirements. Under these agreements, Space Coast Area Transit will own the bus shelters and the municipalities will maintain and clean the shelters.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
General Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Grant Revenue	\$ 1,518,846	250,000	200,000	200,000	200,000	200,000	200,000	2,768,846
Other Finance Sources Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Other Transfers Revenue	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Revenue	\$ 1,518,846	250,000	200,000	200,000	200,000	200,000	200,000	2,768,846
Land Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Planning/Design Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Construction Expense	\$ 517,210	1,032	1,681,574	100,000	100,000	100,000	269,030	2,768,846
Other Expense	\$ - \$	- \$	- \$	- \$	- \$	- \$	- \$	-
Total Expense	\$ 517,210	1,032	1,681,574	100,000	100,000	100,000	269,030	2,768,846

Transit Services Department

Program Name: TRANSIT CAPITAL
Project Name: Cocoa Terminal - Transfer Center
Project Total: \$1,400,000
Project Timeline: October 1, 2024 through September 2026
Funded Program: 6578200
District(s): 2

Project Description, Milestones and Service Impact

Design and construct a transfer center at the Cocoa Terminal.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges For Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ -	\$ 1,400,000	\$ -	\$ -	\$ -	\$ -	\$ 1,400,000
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 1,400,000	\$ -	\$ -	\$ -	\$ -	\$ 1,400,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 1,400,000	\$ -	\$ -	\$ -	\$ -	\$ 1,400,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 1,400,000	\$ -	\$ -	\$ -	\$ -	\$ 1,400,000

Schedule of Emergency Operations and Fire/Rescue Improvements

Emergency Management Office

Program Name: EMERGENCY MANAGEMENT OPERATIONS
Project Name: P25 Radio Frequency Sites Upgrade
Project Total: \$5,151,762
Project Timeline: October 2019 through December 2025
Funded Program: 6351419
District(s): County-wide

Project Description, Milestones and Service Impact

The last necessary step to provide a fully P25 system to the Brevard County public safety agencies and first-responders. P25 is a suite of standards; developed to provide digital, interoperable, and encrypted communication to public safety. Brevard County radio system users are increasingly making the investment to update their radios to P25 standards, but that movement is being hindered by the fact the that Brevard's public safety radio system is not currently P25 capable, which means users cannot utilize their new radios to their full capabilities or benefit from seamless interoperability with other counties.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fines/Fees Revenue	\$ 1,381,792	\$ 628,857	\$ 703,807	\$ -	\$ -	\$ -	\$ -	\$ 2,714,456
Ad Valorem	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ 86,568	\$ 131,480	\$ 1,019,258	\$ -	\$ -	\$ -	\$ -	\$ 1,237,306
Grant Revenue	\$ 1,200,000	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 1,200,000
Total Revenue	\$ 2,668,360	\$ 760,337	\$ 1,723,065	\$ -	\$ -	\$ -	\$ -	\$ 5,151,762
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Expense	\$ 2,668,360	\$ 760,337	\$ 1,723,065	\$ -	\$ -	\$ -	\$ -	\$ 5,151,762
Total Expense	\$ 2,668,360	\$ 760,337	\$ 1,723,065	\$ -	\$ -	\$ -	\$ -	\$ 5,151,762

Fire Rescue Department

Program Name: EMERGENCY MEDICAL SERVICES
Project Name: Station 23 Modular Replacement
Project Total: \$1,300,000
Project Timeline: October 1, 2023 through January 1, 2026
Funded Program: 6506106
District(s): 1

Project Description, Milestones and Service Impact

Station 23 Modular is located on Brevard Government Parkway Complex in Titusville replacing asset #620353. The current facility and has undergone multiple attempts to renovate and repairs to no avail. Funds will be utilized for design, engineering, site preparation, utilities, construction and instillation of a new modular structure funded in FY24 and carried into FY25.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges for Services Revenue	\$ -	\$ -	\$ 1,300,000	\$ -	\$ -	\$ -	\$ -	\$ 1,300,000
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 1,300,000	\$ -	\$ -	\$ -	\$ -	\$ 1,300,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 50,000	\$ -	\$ -	\$ -	\$ -	\$ 50,000
Construction Expense	\$ -	\$ -	\$ 1,250,000	\$ -	\$ -	\$ -	\$ -	\$ 1,250,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 1,300,000	\$ -	\$ -	\$ -	\$ -	\$ 1,300,000

Fire Rescue Department

Program Name: FIRE OPERATIONS
Project Name: Station 42 New Construction
Project Total: \$4,458,890
Project Timeline: October 1st, 2023 through September 30th, 2026
Funded Program: 6506201
District(s): 2

Project Description, Milestones and Service Impact

Demo, remove & replace existing station, asset 620120, that sits on the corner of Sykes Creek and Bananna River Drive (840 Banana River Dr MI). Project includes design, engineering & construction. Existing facility has exceeded life expectancy unable to fit modern apparatus and rescue crew. ARPA funds removed from this project due to project delays.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Assessments Revenue	\$ -	\$ 12,902	\$ 2,959,693	\$ -	\$ -	\$ -	\$ -	\$ 2,972,595
General Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Ad Valorem Taxes Revenue	\$ -	\$ -	\$ 1,486,295	\$ -	\$ -	\$ -	\$ -	\$ 1,486,295
Total Revenue	\$ -	\$ 12,902	\$ 4,445,988	\$ -	\$ -	\$ -	\$ -	\$ 4,458,890
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 200,000	\$ -	\$ -	\$ -	\$ -	\$ 200,000
Construction Expense	\$ -	\$ -	\$ 4,258,890	\$ -	\$ -	\$ -	\$ -	\$ 4,258,890
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 4,458,890	\$ -	\$ -	\$ -	\$ -	\$ 4,458,890

Fire Rescue Department

Program Name: FIRE OPERATIONS
Project Name: Station 44 Major Remodel & Renovation
Project Total: \$1,500,000
Project Timeline: October 1st, 2022 through September 30th, 2024
Funded Program: 6506105
District(s): 1

Project Description, Milestones and Service Impact

Comprehensive renovation of Station 44 including roof, change of interior walls, ceiling, windows, exterior doors. Permitting fees and Planning and Engineering included in the design expense. Scope of project reduced. Construction anticipated to begin FY24.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges for Services Revenue	\$ -	\$ 400,590	\$ 267,060	\$ -	\$ -	\$ -	\$ -	\$ 667,650
Assessments Revenue	\$ -	\$ 499,410	\$ 332,940	\$ -	\$ -	\$ -	\$ -	\$ 832,350
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 900,000	\$ 600,000	\$ -	\$ -	\$ -	\$ -	\$ 1,500,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 100,000	\$ -	\$ -	\$ -	\$ -	\$ 100,000
Construction Expense	\$ -	\$ -	\$ 1,400,000	\$ -	\$ -	\$ -	\$ -	\$ 1,400,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 1,500,000	\$ -	\$ -	\$ -	\$ -	\$ 1,500,000

Fire Rescue Department

Program Name: FIRE OPERATIONS
Project Name: Station 86 Replacement
Project Total: \$5,121,284
Project Timeline: October 1st, 2021 through January 1, 2026
Funded Program: 6506304
District(s): 3

Project Description, Milestones and Service Impact

Replacement station of old asset 620129 and 620134. Permitting fees, Planning and Engineering included in the Design expenses anticipated in FY24. Construction anticipated in FY25. Partial funding from ARPA Revenue Replacement Funds.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges for Services Revenue	\$ -	\$ -	\$ 2,279,484	\$ -	\$ -	\$ -	\$ -	\$ 2,279,484
Assessments Revenue	\$ -	\$ -	\$ 321,357	\$ -	\$ -	\$ -	\$ -	\$ 321,357
Grant Revenue	\$ -	\$ -	\$ 2,520,443	\$ -	\$ -	\$ -	\$ -	\$ 2,520,443
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ -	\$ 5,121,284	\$ -	\$ -	\$ -	\$ -	\$ 5,121,284
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 352,087	\$ -	\$ -	\$ -	\$ -	\$ 352,087
Construction Expense	\$ -	\$ -	\$ 4,769,197	\$ -	\$ -	\$ -	\$ -	\$ 4,769,197
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 5,121,284	\$ -	\$ -	\$ -	\$ -	\$ 5,121,284

Fire Rescue Department

Program Name: FIRE OPERATIONS
Project Name: Station 40 Replacement (Relocated)
Project Total: \$4,576,904
Project Timeline: October 1, 2023 through September 30, 2024
Funded Program: 6506200
District(s): 2

Project Description, Milestones and Service Impact

Planning, engineering and Construction of new station, in a new location, on North Merritt Island (replaces asset 620132 located at 6400 N Trop Trail MI). Construction funded through ARPA Revenue Replacement Funds, less Facilities Fees and contingencies.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges for Services Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Assessments Revenue	\$ -	\$ -	\$ 517,566	\$ -	\$ -	\$ -	\$ -	\$ 517,566
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Grant Revenue	\$ -	\$ 4,059,338	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 4,059,338
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 4,059,338	\$ 517,566	\$ -	\$ -	\$ -	\$ -	\$ 4,576,904
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ 108,892	\$ -	\$ -	\$ -	\$ -	\$ 108,892
Construction Expense	\$ -	\$ -	\$ 4,468,012	\$ -	\$ -	\$ -	\$ -	\$ 4,468,012
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 4,576,904	\$ -	\$ -	\$ -	\$ -	\$ 4,576,904

Fire Rescue Department

Program Name: FIRE OPERATIONS
Project Name: Major Station Renovations
Project Total: \$720,000
Project Timeline: October 1, 2022 to September 30, 2025
Funded Program:
District(s): All

Project Description, Milestones and Service Impact

This project involves reserving funds for unexpected capital repairs that exceed \$35,000 such as various facility improvements and related maintenance items. The funding for this project includes both Fire Rescue and Emergency Medical Services funding which will be utilized as needed depending on the facility that requires renovation.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges for Services Revenue	\$ -	\$ 250,000	\$ 231,393	\$ -	\$ -	\$ -	\$ -	\$ 481,393
Assessments Revenue	\$ -	\$ -	\$ 238,607	\$ -	\$ -	\$ -	\$ -	\$ 238,607
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Revenue	\$ -	\$ 250,000	\$ 470,000	\$ -	\$ -	\$ -	\$ -	\$ 720,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Construction Expense	\$ -	\$ -	\$ 720,000	\$ -	\$ -	\$ -	\$ -	\$ 720,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ 720,000	\$ -	\$ -	\$ -	\$ -	\$ 720,000

Fire Rescue Department

Program Name: FIRE OPERATIONS
Project Name: Station 64
Project Total: \$7,000,000
Project Timeline: October 1, 2026 through January 1, 2029
Funded Program: 6506305
District(s): 3

Project Description, Milestones and Service Impact

Station 64 is a beachside station and scheduled for to have the facility completely replaced. Facility is scheduled to be a 2-story facility due to potential storm surge. Currently reserving funds for future construction obligations.

Revenue or Expense Category	All Prior Fiscal Years	Fiscal Year 2024	Fiscal Year 2025	Fiscal Year 2026	Fiscal Year 2027	Fiscal Year 2028	Fiscal Year 2029 & Future	Total Revenue
Charges for Services Revenue	\$ -	\$ -	\$ 836,088	\$ -	\$ -	\$ -	\$ -	\$ 836,088
Assessments Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Finance Sources Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Other Transfers Revenue	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Unfunded	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 6,163,912	\$ -	\$ 6,163,912
Total Revenue	\$ -	\$ -	\$ 836,088	\$ -	\$ -	\$ 6,163,912	\$ -	\$ 7,000,000
Land Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Planning/Design Expense	\$ -	\$ -	\$ -	\$ -	\$ 250,000	\$ -	\$ -	\$ 250,000
Construction Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ 6,750,000	\$ -	\$ 6,750,000
Other Expense	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Total Expense	\$ -	\$ -	\$ -	\$ -	\$ 250,000	\$ 6,750,000	\$ -	\$ 7,000,000

CHAPTER PART XIV

PUBLIC SCHOOL FACILITIES ELEMENT

TABLE OF CONTENTS

Concurrency Management System	1
School Concurrency Evaluation	3
New Facilities Coordination.....	7
Annual Updates	8

GOAL, OBJECTIVES, AND POLICIES

GOAL PS

To provide a public school system that offers a high quality educational environment, provides accessibility for all of its students, and ensures adequate school capacity to accommodate enrollment demand within a financially feasible school district's ~~five-year capital facilities work program~~ Five-Year District Facilities Work Program.

Concurrency Management System

Objective PS 1

Maintain adequate school facilities in ~~Brevard County Schools~~ Brevard Public Schools by adopting a concurrency management system to address the need for correction of school facility deficiencies through a tiered level of service for the short and long term planning periods.

Policy PS 1.1

Brevard County ~~hereby adopts the following~~ shall maintain Level of Service (LOS) standards for public schools, based upon ~~Florida Inventory of School Houses (FISH)~~ capacity the Interlocal Agreement (ILA) for Public School Facility Planning and School Concurrency.

Table 14-1

LEVEL OF SERVICE					
Facility Type	LOS				
Elementary Schools	100%				
Middle Schools	100%				
Junior / Senior High Schools	100%				
High Schools	100%				

Policy PS 1.2

Brevard County hereby adopts ~~the School Board's~~ Brevard Public Schools' current public school attendance boundaries, as the Concurrency Service Areas (CSA).

Policy PS 1.3

Concurrency shall be measured and applied using a geographic area known as a Concurrency Service Area (CSA) which shall coincide with the school attendance boundaries, as adopted by ~~the School District~~ Brevard Public Schools. The following procedures shall be used for modifying a CSA map:

Criteria:

PUBLIC SCHOOL FACILITIES ELEMENT

A. As future school boundary changes are required for schools programmed in the Five-Year District Facilities Work Program, the CSAs shall be modified to the greatest extent possible to provide maximum utilization. Brevard Public Schools will perform as lead agency for coordination and review of proposed changes to the CSAs. The utilization of school capacity will be maximized to the greatest extent possible, taking into account transportation costs, court approved desegregation plans, and other relevant factors.

~~A. B.~~ Objective criteria shall be adopted by Brevard Public Schools to implement school attendance boundary, and subsequently CSA boundary, changes. When the need for potential attendance boundary changes is identified by the School Board, The School District Brevard Public Schools will transmit a proposed CSA map modification with data and analysis to support the change to the Cities municipalities, the County, and the Capital Outlay Committee (COC). Any proposed change to a CSA shall require a demonstration by the School District that the change complies with the public school LOS standard and that utilization of school capacity is maximized to the greatest extent possible for the purpose of reviewing potential changes a minimum of 30 days prior to the meeting at which an Action Item to consider attendance boundary changes is heard by the School Board.

~~The utilization of school capacity will be maximized to the greatest extent possible, taking into account transportation costs, court approved desegregation plans and other relevant factors.~~

~~B. C.~~ Brevard County and the COC will shall review the proposed modification of the CSA and send their comments to the School District within 30 days of receipt of the proposed change submit consensus recommendations to Brevard Public Schools within a minimum of 10 days prior to the meeting at which the Action Item is heard by the School Board.

~~E. D.~~ The modification of a CSA boundary shall be become effective upon final adoption of the new school boundaries by the School District Brevard Public Schools.

Policy PS 1.4

The Parties shall observe the following process for changes in the use of schools:

Criteria:

A. At such time as the School District Brevard Public Schools determines that a school change is appropriate considering the appropriate use of the school and utilization requirements, the School District Brevard Public Schools shall transmit the proposed school change in use and with data and analysis

PUBLIC SCHOOL FACILITIES ELEMENT

to support the changes to Brevard County and the Capital Outlay Committee and the Staff Working Group.

- B. ~~The Brevard County and the Capital Outlay Committee and the Staff Working Group~~ shall review the proposed changes to the school use and send their comments to the School District within forty five (45) days of receipt.
- C. The change in school use shall become effective upon final approval by the School Board.

School Concurrency Evaluation

Objective PS 2

Brevard County shall ensure a school concurrency evaluation ~~shall be~~ is performed by the ~~School District~~ Brevard Public Schools to review projected residential development in order to accommodate new students at the adopted level of service for adequate school facility capacity.

Policy PS 2.1

Brevard County shall not approve any non-exempt residential development application for a residential land use change, zoning change, or functional equivalent that increases the potential residential development rights until a School Impact Analysis (SIA) has been undertaken resulting in a Capacity Determination Letter issued by ~~the School Board~~ Brevard Public Schools to Brevard County indicating that adequate school facilities exist.

Policy PS 2.2

Brevard County shall not approve any non-exempt residential development application for a new residential preliminary plat, site plan, or functional equivalent until a School Impact Analysis (SIA) has been undertaken resulting in a School Capacity Availability Determination Letter (SCADL) issued by ~~by the School Board~~ Brevard Public Schools to Brevard County indicating that adequate school facilities have been reserved to accommodate the impacts of the development.

Policy PS 2.3

Brevard County shall consider the following criteria to exempt residential uses from the requirements of school concurrency:

Criteria:

- A. All single family lots of record at the time the School Concurrency implementing ordinance became effective.
- B. Any new residential development that has an unexpired preliminary plat or site plan approval or the functional equivalent for a site specific

PUBLIC SCHOOL FACILITIES ELEMENT

development order prior to the commencement date of the School Concurrency Program.

- C. Any amendment to any previously approved residential development, which does not increase the number of dwelling units or change the type of dwelling units (single-family to multi-family, etc.)
- D. Any age restricted community with no permanent residents under the age of eighteen (18). Exemption of an age restricted community will be subject to a restrictive covenant limiting the age of permanent residents to 18 years and older.
- E. The replacement of an existing residential dwelling unit, including those partially or entirely damaged, destroyed, or demolished, with a new unit of the same type and use provided that the existing unit has been occupied at some time during the five year period immediately preceding the construction of the new unit.
- F. De minimis Impact for School Capacity Determination (non-binding):
 - 1. Small Scale Comprehensive Plan Amendment requests which will not increase the maximum allowable residential units by 50 units or more.
 - 2. Preliminary Development Requests (not including Large Scale Comprehensive Plan Amendments) which will not increase the maximum allowable residential units by 50 units or more.
- G. De minimis Impact for Concurrency Determination (binding) – Any residential development request, which based on the Student Generation Rate (SGM) established in ~~this Agreement~~ the ILA will not exceed one (1) student for any type of school.

Policy PS 2.4

Brevard County, through its land development regulations, and in conjunction with ~~the School District Brevard Public Schools~~, shall establish a school concurrency review process for all residential projects that are not exempt under Policy ~~2.2 PS 2.3~~. The minimum process requirements are described below:

Criteria:

- A. A residential development application including a School Facility Planning and Concurrency Application for a School Impact Analysis (SIA) is submitted to Brevard County for review.
- B. Brevard County determines application is complete for processing and transmits the SIA to ~~the School District Brevard Public Schools~~ for review.

PUBLIC SCHOOL FACILITIES ELEMENT

- C. ~~The School District~~ Brevard Public Schools reviews application for available capacity and issues either a preliminary non-binding Capacity Determination Letter (CDL) or a final binding School Capacity Availability Determination Letter (SCADL) to Brevard County:
1. If capacity is available within the affected CSA, ~~the School District~~ Brevard Public Schools shall issue a CDL or SCADL verifying available capacity.
 2. If capacity is not available within the affected CSA, contiguous CSAs are reviewed for available capacity.
 3. If capacity is available in the contiguous CSAs ~~the School District~~ Brevard Public Schools shall issue a CDL or SCADL verifying available capacity in the adjacent CSAs.
 4. If capacity is not available in the contiguous CSAs, ~~the School District~~ Brevard Public Schools shall issue a CDL or SCADL indicating the development is not in compliance with the adopted LOS ~~and offers the developer a 90-day~~ within 10 working days. If the developer has submitted for a SCADL, the applicant will be offered the opportunity to enter into a negotiation period to allow time for the mitigation process. If a proposed mitigation agreement is accepted, Brevard Public Schools shall enter into an enforceable and binding agreement with the affected local government and the developer pursuant to the ILA.

Policy PS 2.5

Brevard County in conjunction with ~~the School District~~ Brevard Public Schools shall review developer proposed applications for proportionate share mitigation projects to add the school capacity necessary to satisfy the impacts of a proposed residential development. Mitigation options may include, but are not limited to:

Criteria:

- A. Contribution of land or payment for land acquisition in conjunction with the provision of additional FISH Capacity; or
- B. Mitigation banking based on the construction of a public school facility in exchange for the right to sell FISH Capacity credits; or
- C. Provision of additional student stations through the donation of buildings for use as a primary or alternative learning facility; or
- D. Provision of additional student stations through the renovation of existing buildings for use as learning facilities; or

PUBLIC SCHOOL FACILITIES ELEMENT

- E. Construction or expansion of permanent student stations; or
- F. Construction of a public school facility in advance of the time set forth in the Five-Year District Facilities Work Program; or
- G. Construction of a charter school designed in accordance with ~~the School Board~~ Brevard Public Schools standards, providing sufficient permanent capacity to ~~the District's~~ Brevard Public Schools' inventory of student stations. Use of a charter school for mitigation must include provisions for its continued existence, including but not limited to the transfer of ownership of the charter school property and/or operation of the school to ~~the School Board~~ Brevard Public Schools.

Policy PS 2.6

For mitigation measures in Policy ~~2.4~~ PS 2.5 (A) thru ~~(F)~~ (G) above, the estimated cost to construct the mitigating improvement will reflect the estimated future construction costs at the time of the anticipated construction.

Criteria:

- A. Improvements contributed by the developer shall receive school impact fee credit for that portion of the developer's educational impact used to fund the improvements on which the proportionate share mitigation is calculated.
- B. The cost difference between the developer's proportionate share mitigation costs and the impact fee credit, if greater, shall be the responsibility of the developer.

Policy PS 2.7

Brevard County and ~~the School District~~ Brevard Public Schools shall provide a 90-day negotiation period to allow for the review and negotiation of proportionate share mitigation offers proposed by a developer.

Criteria:

- A. If mitigation is approved, Brevard County and ~~the School District~~ Brevard Public Schools shall enter into an enforceable binding agreement with the developer and the improvement(s) will be included in ~~the School District's~~ Brevard Public Schools' annually adopted Five-Year District Facilities Work Program and reflected in the next update to the Capital Improvements Element.
- B. If mitigation is denied, Brevard County must deny the application based upon no available school capacity.
- C. A Local Government shall not issue any permits for a residential development until receiving confirmation of available school capacity in the form of a SCADL from ~~the School District~~ Brevard Public Schools.

PUBLIC SCHOOL FACILITIES ELEMENT

Policy PS 2.8

Brevard County shall, upon acceptance of a mitigation option identified in Policy ~~2.4~~ PS 2.5, enter into an enforceable binding agreement with ~~the School District~~ Brevard Public Schools and the developer.

Policy PS 2.9

Brevard County shall notify ~~the School District~~ Brevard Public Schools when an approved residential development has paid impact fees and when the development order for the residential development expires.

New Facilities Coordination

Objective PS 3

All new public schools built within Brevard County will be coordinated with ~~the School District~~ Brevard Public Schools to be consistent with Brevard County's Future Land Use Map designation to ensure facilities are proximate to appropriate existing and future land uses, serve as community focal points, are co-located with other appropriate public facilities, and will have needed supporting infrastructure.

Policy PS 3.1

Brevard County, in conjunction with ~~the School District~~ Brevard Public Schools, shall jointly determine the need for, and timing of, on-site and off-site improvements necessary to support a new school.

Policy PS 3.2

Brevard County shall enter into an agreement with ~~the School District~~ Brevard Public Schools identifying the timing, location, and the party or parties responsible for the planning, constructing, operating, and maintaining off- site improvements necessary to support a new school or school improvement to ensure that the necessary infrastructure is in place prior to or concurrent with construction.

Policy PS 3.3

Brevard County shall encourage the location of schools near residential areas by:

Criteria:

- A. Assisting ~~the School District~~ Brevard Public Schools in the identification of funding and/or construction opportunities (including developer participation or Local Government capital budget expenditures) for sidewalks, traffic signalization, access, water, sewer, drainage, and other infrastructure improvements.
- B. Reviewing and providing comments on all new school sites including the compatibility and integration of new schools with surrounding land uses.

PUBLIC SCHOOL FACILITIES ELEMENT

- C. Allowing schools within all residential land use categories.

Policy PS 3.4

Brevard County, in conjunction with ~~the School District~~ Brevard Public Schools, shall seek opportunities to co-locate schools with public facilities, such as parks, libraries, and community centers, as the need for these facilities is identified.

Policy PS 3.5

Brevard County, in conjunction with ~~the School District~~ Brevard Public Schools, hereby designates the Capital Outlay Committee (COC) as the monitoring group for coordinated planning and school concurrency in Brevard County.

Policy PS 3.6

Brevard County shall maintain school concurrency provisions ~~with its~~ within its Land Development Regulations (LDR) to implement school concurrency upon the effective date of this Public School Facilities Element.

Policy PS 3.7

Brevard County, in conjunction with ~~the School District~~ Brevard Public Schools and the municipalities within Brevard County shall identify issues relating to public school emergency preparedness, such as:

Criteria:

- A. The determination of evacuation zones, evacuation routes, and shelter locations.
- B. The design and use of public schools as emergency shelters.
- C. The designation of sites other than public schools as long-term shelters, to allow schools to resume normal operations following emergency events.

Annual Updates

Objective PS 4

Brevard County will include in its Capital Improvements Element (CIE), ~~the School District's~~ Brevard Public Schools' annually ~~updated~~ adopted Five-Year District Facilities Work Program ~~as adopted by the School District~~, which identifies school facility capacity projects necessary to address existing deficiencies and meet future needs based upon achieving and maintaining the adopted level of service standard for schools.

Policy PS 4.1

Brevard County shall adopt as part of its Capital Improvement Element ~~the School Board of Brevard County's~~ Brevard Public Schools Five-Year District Facilities Work Program.

PUBLIC SCHOOL FACILITIES ELEMENT

Policy PS 4.2


Brevard County shall annually coordinate review of school enrollment projections in conjunction with the ~~School District~~ Brevard Public Schools and other local governments through the Capital Outlay Committee. ~~The Public School Facilities Map Series shall depict the planned general location of schools and ancillary facilities for the five-year planning period and the long-range planning period and includes:~~

- ~~A. Existing Public School Facilities Maps - type and location of public school facilities and ancillary plants~~
- ~~B. Five-Year Planning Period Maps - generally planned public school facilities and ancillary plants~~
- ~~C. The Long Range Planning Period Map - generally planned areas of future public school facility needs~~

APPENDIX

Map Series Index

Map 1 Public School Facilities



PUBLIC SCHOOL FACILITIES ELEMENT

CHAPTER PART XV

PROPERTY RIGHTS ELEMENT

TABLE OF CONTENTS

Private Property Rights in The Local Decision Making Process1

GOALS, OBJECTIVES, AND POLICIES

GOAL PR

To ensure consideration of private property rights in the local decision making process.

Objective PR 1

Brevard County shall follow a set of policies to ensure that private property rights are considered in the local decision making process.

Policy PR 1.1

Brevard County shall consider the following in the local decision making process:

- A. The right of a property owner to physically possess and control his or her interests in the property, including easements, leases, or mineral rights.
- B. The right of a property owner to use, maintain, develop, and improve his or her property for personal use or the use of any other person, subject to state law and local ordinances.
- C. The right of the property owner to privacy and to exclude others from the property to protect the owner's possessions and property.
- D. The right of a property owner to dispose of his or her property through sale or gift.

PART XVI

BREVARD BARRIER ISLAND AREA ELEMENT

GOAL, OBJECTIVES, AND POLICIES

INTRODUCTION

The southern portion of Brevard County's barrier island was designated as an Area of Critical State Concern by the Florida Legislature in 2023, as codified in section 380.0553, F.S. The Brevard Barrier Island Area of Critical State Concern (BBIA) represents one of the most fragile and endangered coastal ecosystems and vulnerable communities in North America, due to its natural upland and marine habitats, critical sea turtle nesting grounds, nationally significant wildlife refuge conservation area, direct connection to and impacts on the nationally significant Indian River Lagoon system, economically valuable fishery, and high vulnerability of public health and safety during hurricane events. Through the implementation of this comprehensive plan, the critical functions of these natural resources are protected. Orderly and balanced growth are promoted in accordance with the existing facilities and services and the population can be safely evacuated in the event of a hurricane.

GOAL

Protect the BBIA's natural environmental and ecological resources, community character, and public health and safety.

Designation of the BBIA

Objective BBIA 1

Brevard County locally establishes and delineates the southern portion of the County's barrier island as the BBIA in compliance with section 380.0553, F.S.

BBIA Boundary

Policy BBIA 1.1

The BBIA shall be shown on the Future Land Use Map as that portion of Brevard County formed by the southern boundary of the Town of Melbourne Beach, the Indian River as the western boundary, the Atlantic Ocean as the eastern boundary, extending south to the Sebastian Inlet, specifically including lands in unincorporated Brevard County's jurisdiction within the following townships, ranges, and sections as designated by the Brevard Public Land Survey System: 28-38-17-18, 28-38-20-21, 28-38-28, 28-38-33-34, 29-38-03, 29-38-10-11, 29-38-14-15, 29-38-22-24, the barrier island portion only of 29-38-27, 29-38-25-26, 29-38-35-36, 29-39-31, 30-38-01, 30-39-06-08, 30-39-17-18, and 30-39-20. The objectives and policies contained within this local comprehensive plan apply exclusively to properties within the BBIA in unincorporated Brevard County.

Legislative Findings for the BBIA

Policy BBIA 1.2

Brevard County recognizes and affirms the below findings of the Legislature in determining the necessity of designating the BBIA:

- A. The southern barrier island of Brevard County represents one of the most fragile and endangered coastal ecosystems in North America, and the

BREVARD BARRIER ISLAND AREA

beaches, dunes, coastal scrub, and maritime hammock areas of the barrier island ecosystem represent some of the most fragile and endangered natural upland communities in the state and nation.

- B. The beaches of the region are among the most important nesting grounds for threatened and endangered sea turtles in the Western Hemisphere. The beach running the length of the southern barrier island of Brevard County is home to the largest nesting aggregation of loggerhead sea turtles in the world, and the management decisions made in the region have global impacts for the species.
- C. The Archie Carr National Wildlife Refuge is located within the barrier island of Brevard County and is a significant conservation area designated to protect habitat at the most significant area for loggerhead sea turtle nesting in the world, at the most significant area for green turtle nesting in North America, and for a diverse array of plant and animal species.
- D. The Indian River Lagoon, designated as an Estuary of National Significance by the United States Environmental Protection Agency in 1990, borders the western shore of the barrier island of Brevard County, and the natural habitats of the barrier island ecosystem protect the water quality and productivity of the Indian River Lagoon.
- E. The salt water recreational fishery of the Indian River Lagoon generates hundreds of millions of dollars per year in local economic benefit.
- F. Density limitations and natural resource protection on the barrier island of Brevard County have decreased public tax burdens associated with the provisions of services, building and maintenance of infrastructure for barrier island residential developments, and public costs for rebuilding public and private structures following severe erosion events.
- G. Protection of the primary dune system of the barrier island of Brevard County provides the only protective buffer for local development from storm surges associated with tropical storms and hurricanes.
- H. The entirety of the barrier island of Brevard County lies within a zone that is the first to be subject to mandatory evacuation protocols due to the vulnerability of the barrier island in hurricane events and the adverse impacts of such vulnerability on evacuating safely.

Legislative Intent for the BBIA

Policy BBIA 1.3

Brevard County acknowledges the intent of the Legislature, in its establishment of the BBIA, to:

BREVARD BARRIER ISLAND AREA

- A. Establish a land use management system that protects the natural environment of the BBIA;
- B. Establish a land use management system that promotes orderly and balanced growth in accordance with the capacity of existing public facilities and services;
- C. Protect and improve the Indian River Lagoon ecosystem, including improving water quality of the BBIA through federal, state, and local funding of water quality improvement projects; and
- D. Ensure that the population of the BBIA can be safely evacuated in the event of a hurricane.

Guiding Principles for Development within the BBIA

Policy BBIA 1.4

Brevard County shall develop and implement its local comprehensive plan and its associated land development regulations to ~~be consistent~~ ensure consistency with all of the guiding principles for development within the BBIA as specified in section 380.0553(5), F.S. This includes ensuring that its programs and regulatory activities are consistent with these principles. The guiding principles for development specified in section 380.0553(5), F.S., shall constitute the basis of Objectives BBIA 2, BBIA 3, BBIA 4, BBIA 5, BBIA 6, BBIA 7, BBIA 8, BBIA 9, BBIA 10, and BBIA 11.

Conflicting Policies

Policy BBIA 1.5

Where there is any conflicting policy or regulation applicable to the BBIA, the more restrictive shall apply.

Sea Turtle Habitat

Objective BBIA 2

Brevard County shall prevent the adverse impacts of development on resources critical to sea turtle habitat.

Policy BBIA 2.1

Brevard County shall prohibit new shoreline hardening structures, including rigid coastal structures as defined in Rule 62B-33, F.A.C., as amended, in accordance with Florida's Marine Turtle Protection Act, section 379.2431(1), F.S., on the Atlantic coast and develop strategies for the removal of existing structures and re-establishment of the natural dune system.

Policy BBIA 2.2

Brevard County shall continue to protect the natural beach and dune system of the Atlantic Ocean through the implementation of the following minimum criteria:

Criteria:

BREVARD BARRIER ISLAND AREA

- A. Limit development water-ward of the Brevard County Coastal Setback Line (CSL) to those structures necessary to protect the natural dune system and to provide beach access.
- B. Brevard County shall continue to maintain Florida Building Code construction standards for all development within Federal Emergency Management Agency (FEMA) Special Flood Hazard Areas and the Coastal High Hazard Area (CHHA).

Policy BBIA 2.3

Brevard County shall maintain lighting regulations in order to eliminate the visibility of artificial or otherwise man-made light to nesting female and hatchling turtles and to establish mitigation strategies for any artificial lighting that becomes visible from the sandy beach. Such regulations shall be ~~periodically~~ reviewed and updated within twelve (12) months following an update to guidelines and to reflect best practices in coordination with organizations such as as established by the Florida Fish and Wildlife Conservation Commission (FWC), the Florida Department of Environmental Protection (FDEP), and other applicable agencies and organizations. Such review shall include addressing any areas with documented impacts to nesting habitats due to artificial lights.

Policy BBIA 2.4

Beach renourishment and dune restoration plans shall continue to be designed and implemented in accordance with local, State, and federal regulations so that sea turtle nesting is not disrupted. Brevard County shall implement strategies with the best available science for coastal engineering, beach nourishment, and dune restoration projects to protect and enhance the natural dune system, maintain viable sea turtle nesting habitat, and minimize visibility of upland lights from the sandy beach while providing beach access.

Policy BBIA 2.5

The Land Development Regulations shall maintain regulations governing the location, construction, and maintenance of development adjacent to the Atlantic shoreline. Development seaward of the CSL shall be governed by the following conditions, at a minimum:

Criteria:

- A. Oceanfront development shall be required to maintain at least 50% of the native dune vegetation on site. In addition, native dune vegetation seaward of the CSL shall not be removed unless necessary for approved emergency vehicle access or coastal protection needs.
- B. In order to maintain the freshwater lens of the surficial aquifer and reduce saltwater intrusion, post-development groundwater recharge volume and rate shall equal pre-development recharge volume and rate.
- C. Reducing setbacks from State Road A1A (SR A1A) will be considered where it is necessary to maintain and maximize setback requirements from the ocean.

- D. Reconstruction or replacement of fifty (50) percent or more of a shoreline hardening structures on the Atlantic Ocean ~~that are more than fifty (50) percent destroyed~~ shall be considered new construction for purposes of Policy BBIA 2.1 above and shall be regulated as such, except for the maintenance of existing public navigational projects.
- E. Underground storage tanks or the storage of hazardous materials are not permitted.
- F. Septic tanks or septic tank drainfields shall not be permitted seaward of the CSL. Septic tanks shall be located landward of the most seaward portion of the habitable structure.

Policy BBIA 2.6

Brevard County shall ~~continue to~~ enforce development restrictions associated with the CSL and re-evaluate the effectiveness of this line ~~from time to time by December 31, 2030 and at least every ten (10) years thereafter or~~ as coastline changes dictate. ~~The County shall provide the Florida Department of Environmental Protection (FDEP) with their findings and request a review of the 1981 FDEP Coastal Construction Control Line (CCCL); if deemed appropriate.~~ In evaluating the CSL, the County shall consider data such as erosion analyses, storm surge and velocity, dune vegetation coverage, and wildlife habitat.

Policy BBIA 2.7

Outer Continental Shelf (OCS) activities such as oil and gas exploration or mining adjacent to Brevard County are discouraged for several reasons. The County's beaches are the most heavily nested beaches by sea turtles in the western Atlantic. Impacts to water quality, beach quality and fisheries could negatively impact the threatened and endangered species that nest here. Brevard County should review and comment on all OCS and offshore drilling leases proposed for waters adjacent to the County. This policy does not discourage or otherwise prohibit OCS sand and gravel mining activities conducted as part of Brevard County's shore protection and restoration strategy.

Water Quality Restoration

Objective BBIA 3

Brevard County shall prioritize water quality restoration projects for the Indian River Lagoon.

Policy BBIA 3.1

The Natural Resources Management Department shall be the lead agency for the development and implementation of the Stormwater Management Plans and shall coordinate its efforts with FDEP and St. John's River Water Management District (SJRWMD) on the Basin Management Action Plan (BMAP), Total Maximum Daily Loads (TMDLs), and the National Pollution Discharge Elimination System (NPDES) permit schedule and requirements.

Policy BBIA 3.2

_____ If during the time that the Stormwater Ordinance is being reviewed and updated, it becomes apparent that additional regulations are required in order to protect water quality in surface water bodies in Brevard County, the County will initiate protective regulations through the adoption or revision of land development regulations.

Policy BBIA 3.3

_____ No new structures (such as dams, weirs, locks, levees, or other artificial mechanisms) designed to control the stage and/or flow of waters of the State shall be constructed, except where no practical alternative exists and where such structures are necessary to protect the public safety; safeguard existing flood control structures, habitable structures, and other public investments; protect or improve water quality; or restore the function of the natural water dependent ecosystem. The use of temporary structural modifications to control the stage or flow of a water body as a part of any government sanctioned program of flood control, water quality restoration, habitat restoration or exotic plant control ~~should~~ shall be designed and operated ~~so as to minimize with the minimization of~~ harm to non-target organisms or natural ecosystems as part of the design and operation criteria.

Policy BBIA 3.4

_____ The channelization, dredging or impoundment of natural waters of the State shall be prohibited, except where no practical alternative exists for those operations necessary to correct existing threats to public health or safety, allow maintenance of existing navigational waterways, improve water quality, or provide reasonable access to water dependent shore-based facilities. All practical steps shall be taken to minimize adverse impacts to biological attributes of the water resources and water-dependent natural systems.

Policy BBIA 3.5

_____ Brevard County shall continue to participate in the development and implementation, as appropriate, of the BMAP, as developed in coordination with the FDEP and SJRWMD.

Policy BBIA 3.6

_____ Brevard County shall coordinate with the FDEP to develop and implement BMAPs to comply with NPDES permits and meet the TMDLs established for local surface waters.

Policy BBIA 3.7

_____ Brevard County shall coordinate surface water management and protection efforts with the Indian River National Estuary Program (IRLNEP), FDEP, SJRWMD and other appropriate agencies.

Policy BBIA 3.8

Brevard County shall support the SJRWMD's mapping of submerged aquatic vegetation within the Indian River Lagoon system. Evaluation results shall be made available to municipalities and other agencies or programs. Areas that show decline should be targeted for increased watershed management, including non-point source pollution control. Management strategies shall be coordinated with the municipalities and other agencies.

Policy BBIA 3.9

Brevard County shall continue to participate in the IRLNEP and other advisory committees and groups related to improving water quality in the Indian River Lagoon.

Policy BBIA 3.10

Brevard County supports the goals of the IRLNEP Comprehensive Conservation and Management Plan (CCMP) for recovery of the Lagoon. This support is reflected in the strategies identified in the County's annual submittal to the [United States Environmental Protection Agency \(EPA\)](#) Work Plan, as amended, for the CCMP.

Reducing Nutrient Contributions**Objective BBIA 4**

Brevard County shall reduce nutrient contributions from septic tanks and wastewater facilities, stormwater discharges, and agriculture nonpoint sources into the Indian River Lagoon.

Policy BBIA 4.1

Brevard County shall maintain its practice of no new direct discharges of wastewater into surface water bodies.

Policy BBIA 4.2

Untreated wastewater shall not be discharged into drainage ditches, surface waters or aquifers.

Policy BBIA 4.3

Brevard County shall continue to analyze drainage basins to identify the impact of drainage facilities on adjacent natural resources, including water quality of receiving waters. Such analysis shall be incorporated into basin prioritization in stormwater area studies.

Policy BBIA 4.4

Brevard County shall continue to identify and map both point and non-point sources of pollution within the Indian River Lagoon watershed to reduce pollutant loading sources. This program shall be coordinated with other federal, state and local agencies.

Policy BBIA 4.5

Where illegal or accidental discharges of materials, or violations of water quality standards are observed, such violations shall be reported to the appropriate federal or state regulatory agencies for further action and enforcement.

Policy BBIA 4.6

Brevard County shall review and comment, as necessary, on dredge-and-fill applications.

Policy BBIA 4.7

Brevard County should require stormwater retrofits during redevelopment for existing development that does not meet current stormwater management standards.

Policy BBIA 4.8

Brevard County shall continue to implement performance standards for marinas and marine-related facilities. Such performance standards shall comply with the Brevard County Manatee Protection Plan (MPP), as amended, and provide for the protection of water quality and include the maintenance and containment of stormwater runoff and wash-down water for dry storage areas.

Policy BBIA 4.9

Brevard County shall continue to develop and implement regulations governing live-aboard vessels. Such regulations shall include the following criteria at a minimum:

Criteria:

- A. Live-aboard vessels moored outside of marinas shall be required to utilize pump-out facilities or a municipal sewer facility if they are moored for over three (3) days.
- B. Floating structures shall be connected to pump-out facilities or a municipal sewer facility.

Policy BBIA 4.10

Retrofitting or modification of existing marina facilities shall be required to meet the criteria within the MPP, as amended, and the following minimum criteria:

Criteria:

- A. Stormwater retention/detention requirements as established by County and state stormwater management criteria.
- B. Substantially expanded marina facilities shall retain all work area runoff. For those projects with combined detention areas of five (5) acres or greater, the work area runoff shall be retained in a separate retention area. In addition, the first inch of stormwater runoff from a 10-year, 24-hour storm event shall be retained on site or shall meet the water quality standards as required by the state, whichever is more restrictive. For projects with a combined detention area of less than five (5) acres, stormwater and work area runoff may be retained in a single retention/detention area.

BREVARD BARRIER ISLAND AREA

- C. When ten (10) slips or ten (10) percent or more of the total number of slips, whichever is greater, are added, pump-out facilities shall be required, as recommended by the Marine Sanitation Study (1990), sufficient to accommodate the pump-out requirements concurrent with the total number of slips.
- D. Prior to operation of any new marina fueling facility or expansion due to an existing facility, a fuel management/spill contingency plan will be developed and provided to the Natural Resources Management Department for review. The plan shall describe methods to be used in dispensing fuel and all the procedures, methods, and materials to be used in the event of a fuel spill.

Policy BBIA 4.11

Brevard County shall coordinate with partners such as Florida Department of Agriculture and Consumer Services (FDACS) and the University of Florida Institute of Food and Agricultural Sciences to provide fertilizer ~~management~~ Best Management Practices BMP information to agricultural and golf course operators within the BBIA.

Policy BBIA 4.12

Brevard County acknowledges that FDEP will not permit the installation of new onsite sewage treatment and disposal systems (OSTDS) in the BBIA where a sewer system is available. If sewer is not available, only enhanced nutrient reducing OSTDS achieving at least 65 percent nitrogen reduction shall be authorized in compliance with section 373.469, F.S., as amended.

Policy BBIA 4.13

Brevard County will update its Code of Ordinances to include requirements that support and enforce the provisions in Policy BBIA 4.~~16~~ 12 and as required by section 373.469, F.S., as amended.

Policy BBIA 4.14

Brevard County will update its Code of Ordinances, no later than July 1, 2030, to require that any commercial or residential property with an existing OSTDS within the BBIA will connect to a sewer system if available. If sewer is unavailable, Brevard County will require that existing OSTDS be upgraded to an enhanced nutrient reduction, achieving at least 65 percent nitrogen reduction, per section 373.469, F.S., as amended.

Nature-Based Solutions

Objective BBIA 5

Brevard County shall support innovative, nature-based solutions including living shorelines, and freshwater and coastal wetland restoration.

Policy BBIA 5.1

Prior to implementing major improvements to existing structural controls within existing floodplains, Brevard County shall ~~identify structural controls within the floodplain that degrade natural systems~~ evaluate potential degradation to natural and artificial ecosystems that may result from those controls and make recommendations for alternatives to ~~mitigate impacts or~~ re-establish the natural floodplain where feasible.

Policy BBIA 5.2

Brevard County shall address modification of existing development that does not meet stormwater management standards within the Stormwater Management Criteria and should use available financial mechanisms for the modification of such development.

Criteria:

- A. During modification of existing development, stormwater management facilities within existing developments should be retrofitted to provide for treatment of runoff (including sediment removal where appropriate) prior to release to receiving waters. The Level of Service Standards for these facilities shall include the reduction of the pollutant loading as necessary to enhance or maintain the beneficial uses of the receiving water and to meet receiving water standards per Florida Administrative Code. All facilities should be maintained at design capacity.
- B. During modification of existing development, properties with bulkheads or seawalls shall be enhanced so that runoff is detained prior to release to the receiving body. This may be achieved by planting native or other appropriate vegetation along the shoreline to retain silt, sediment, and nutrients so that the quality and rate of runoff is equivalent to the pre-development state.
- C. During modification of existing development, properties with altered vegetated shorelines shall be enhanced to retain silt, sediment, and nutrients by planting native vegetation or other appropriate vegetation. A detention structure, swale, and/or berm may be used to allow sediments to settle and nutrient uptake to occur only if non-native vegetation is predominant. Runoff quality and rates should be equivalent to the pre-development state.

Policy BBIA 5.3

Brevard County shall consider innovative methods of stormwater treatment other than standard retention and detention basins, which shall include such alternatives as stormwater reuse and nature-based stormwater management systems.

Policy BBIA 5.4

Nonstructural methods of stormwater management that reduce the generation and accumulation of potential stormwater runoff contaminants ~~should~~ ~~shall~~ be utilized to the maximum extent ~~possible~~ ~~feasible~~. Nonstructural methods of stormwater management may include pesticide and herbicide control, proper fertilizer management, erosion control, and proper waste disposal. In addition, the use of wetlands and floodplains should

be utilized whenever feasible in such a manner as to maintain the natural function and biodiversity of the system.

Policy BBIA 5.5

Mosquito impoundments should be reconnected to the Indian River Lagoon where benefits can be demonstrated to increase habitat value of the impoundments and benefits to the Lagoon.

Policy BBIA 5.6

Using best available data, the County should ~~consider identifying~~ identify areas vulnerable to current and future flooding impacts that may benefit from nature-based design standards and/or Low Impact Development projects that reduce run-off; mitigate flood impacts; provide for the on-site absorption, capture, and reuse of stormwater; and preserve and restore natural drainage characteristics.

Policy BBIA 5.7

Brevard County ~~should~~ shall continue to evaluate and recommend new design and development standards for public and private infrastructure projects that consider future climate conditions and amend Land Development Regulations as necessary to reduce obstacles that hinder nature-based design standards and/or Low Impact Development. The County shall conduct this review and recommendation process at least as frequently as the regular evaluation and appraisal of this comprehensive plan.

Policy BBIA 5.8

The County ~~should~~ shall continue to encourage or require nature-based design standards and/or Low Impact Development design for development and redevelopment within areas vulnerable to current and future flooding impacts, as part of enhanced Land Development Regulations for the BBIA. Such adaptation strategies may include:

Criteria:

- A. Living shorelines
- B. Multi-use stormwater parks,
- ~~BC.~~ Bioswales as stormwater management techniques,
- ~~CD.~~ Green streets,
- ~~DE.~~ Reduced impervious areas,
- ~~EF.~~ Florida-friendly landscaping/xeriscaping, or
- ~~FG.~~ Ecological asset preservation (e.g., tree canopy, natural areas, mangroves, wetlands, dunes, aquifer recharge areas).

Policy BBIA 5.9

The County shall coordinate with organizations such as IRLNEP and the Marine Resources Council to promote the use of living shoreline design and support efforts to educate the public on the benefits of living shorelines throughout the BBIA.

Critical Assets

Objective BBIA 6

Brevard County shall safeguard against adverse economic, social, environmental, and public health and safety impacts posed by flooding and storm surge by protecting critical assets identified in section 380.093, F.S.

Policy BBIA 6.1

Public facilities should not be located within wetland areas or the 100-year estuarine floodplain unless the following apply:

Criteria:

- A. The facilities are water-dependent, such as mosquito control facilities; or,
- B. The facilities are water-related, such as boat ramps, docks or surface water management facilities; or,
- C. The facilities are not adversely affected by periodic flooding or standing water, such as highway bridges and some recreational facilities; or,
- D. The building structures are flood-proofed and located above the 100-year flood elevation, or removed from the floodplain by appropriately constructed dikes or levees; or,
- E. The facilities are found to be in the public interest and there is no feasible alternative.

Policy BBIA 6.2

Brevard County shall require hurricane plans to be submitted to the Florida Division of Emergency Management in conjunction with marina site plans for review.

Policy BBIA 6.3

Brevard County shall not support or finance new local transportation corridors that lie within the ~~coastal high hazard area~~ CHHA or areas zoned as Environmental Area, except where there are no other cost-feasible alternatives. Corresponding improvements may only be considered when the facilitation of such improvements is needed to support the existing densities programmed on the Future Land Use Map (FLUM) series of the Comprehensive Plan or for the protection of the transportation facilities from flooding and storm surge.

Policy BBIA 6.4

Brevard County should not locate sewer and water transmission lines within the ~~coastal high hazard area~~ CHHA, except where there is no practical and cost-feasible alternative due to engineering; ~~and safety~~ ~~and cost considerations~~; ~~constraints~~; where ~~there is a~~ lack of alternative existing rights-of-way; ~~;~~ or for septic to sewer conversion projects selected specifically to improve ground and surface water quality. Such transmission lines shall be designed to withstand flooding and storm surge.

Policy BBIA 6.5

_____ If County utility lines are relocated for any purpose, they should be located outside of the ~~coastal high hazard area~~ CHHA, except where there is no cost-feasible alternative and such lines are designed to withstand flooding and storm surge.

Policy BBIA 6.6

_____ Public facilities, except for recreational facilities, shall not be located by Brevard County within the ~~coastal high hazard area~~ CHHA, except where there are no other cost-feasible alternatives. Corresponding improvements may only be considered when the facilitation of such improvements is needed to support the existing densities programmed on the FLUM series of the Comprehensive Plan, to improve surface or groundwater quality, or for the protection of the public facilities from flooding and storm surge.

Policy BBIA 6.7

_____ Brevard County shall maintain acceptable hurricane evacuation times based upon the following:

Criteria:

- A. _____ The information contained in the Florida Regional Evacuation Study.
- B. _____ The goal to complete all evacuations prior to the onset of tropical storm force (39 mph) winds, as outlined in the Evacuation Concept of Operations.

Policy BBIA 6.8

_____ Brevard County shall coordinate with all appropriate agencies and manage the planning for, and implementation of, evacuations as outlined in the Evacuation Concept of Operations.

Policy BBIA 6.9

_____ Brevard County shall identify roadway and operational improvements to the hurricane evacuation network based upon capabilities, limitations, and vulnerabilities.

Criteria:

- A. _____ Priority shall be given to improvements of roadway networks serving hurricane evacuation routes with the greatest number of people.
- B. _____ Brevard County, in cooperation with the Florida Department of Transportation, shall identify key hurricane evacuation routes that are vulnerable to flooding, erosion and critical points of congestion during the established evacuation time.
- C. _____ Brevard County shall present recommended roadway, operational and maintenance improvements to the appropriate implementing and funding agencies.

Policy BBIA 6.10

_____ In those areas where citizens cannot be evacuated within the adopted evacuation clearance times outlined in the Florida Regional Evacuation Study, development orders may be deferred until such time as adequate evacuation capacity has been programmed.

BREVARD BARRIER ISLAND AREA

Policy BBIA 6.11

Brevard County shall consider hurricane evacuation times, as well as other factors including vulnerability to flooding and storm surge, in determining the timing and priority of roadway improvements that are programmed by the Board of County Commissioners.

Policy BBIA 6.12

Brevard County shall support Brevard Public Schools in their efforts to utilize enhanced emergency shelter protection standards for all reconstruction and new development as outlined in the most current Florida Statewide Emergency Shelter Plan.

Policy BBIA 6.13

Brevard County ~~should~~ shall continue to analyze those public structures within the high-risk vulnerability zone or coastal zone that are most likely to be damaged or destroyed during a hurricane, flood, or storm surge. The analysis shall occur at least every five (5) years in coordination with Emergency Management and consider the following, at a minimum:

Criteria:

- A. The cost effectiveness of relocation versus repair shall be analyzed.
- B. Alternatives shall be considered in the light of mitigative impacts, growth management consistency, impacts to the public, timeliness, legal issues, environmental impacts and cost.
- C. The following alternatives, at a minimum, shall be analyzed:
 - 1. Repair of the structure to the pre-disaster conditions.
 - 2. Repair of the structure to the pre-disaster conditions with physical protective structures, as may be legally permissible when consistent with the Conservation Element and the Coastal Management Element.
 - 3. Vertical relocation of the structure, e.g. elevating roadways with bridges.
 - 4. Relocation further inland.
- D. Reconstruction or relocation of SR A1A and other roadway segments within the ~~coastal high hazard area~~ CHHA shall be included within this study.
- E. The study shall be consistent with the East Central Florida Regional Planning Council (ECFRPC) studies. The hurricane scenarios and loss estimates shall be consistent with the Local Mitigation Strategy and shall be coordinated with other appropriate agencies.
- F. The impact of sea level rise and erosion data shall also be analyzed and considered.

Policy BBIA 6.14

In the event of a disaster, all infrastructure and other County-owned improvements that were not included within the above outlined study shall be analyzed to determine the cost effectiveness of relocation versus repair.

Policy BBIA 6.15

The County should utilize a range of sea level rise projections as recommended in the adopted East Central Florida Regional Resilience Action Plan (RRAP), as amended, for planning purposes based upon vulnerability, risk, project service life of a facility or growth management.

Policy BBIA 6.16

The County should consider designating Adaptation Action Areas (AAAs), as allowed by Florida law, as a mechanism to prioritize resilient planning, infrastructure investments, and strategies to address current and future flood impacts in areas identified as vulnerable to coastal flooding, storm surge, and sea level rise.

Policy BBIA 6.17

The County ~~should~~ shall consider the results of the Brevard County Vulnerability Analysis when planning for development, redevelopment, and improvements to critical facilities and infrastructure.

Policy BBIA 6.18

~~The County should work to reduce hazard exposure for coastal communities by coordinating with municipalities and ECFRPC to identify, scope, and recommend hazard mitigation projects as outlined in the Local Mitigation Strategy.~~ The County shall include the BBIA within its hazard mitigation project planning outlined in Coastal Management Element Policy CM 14.5.

Policy BBIA 6.19

The County should identify development and redevelopment performance standards designed to minimize or withstand permanent and/or temporary inundation from flooding, sea level rise, and storm surge. These standards may include increased freeboard elevations, the consideration of future tailwater elevations for stormwater infrastructure, and/or multi-use temporary flood storage areas.

Policy BBIA 6.20

The County ~~should~~ shall continually identify strategies and engineering solutions that minimize the loss of flood storage capacity in all floodplains and areas vulnerable to natural hazards such as flooding, storm surge, and sea level rise, and consider incorporating them into the Land Development Regulations.

Policy BBIA 6.21

The County should pursue private and public funding sources for the implementation of flood resiliency strategies – including, but not limited to, avoidance, protection, accommodation, strategic relocation - within areas identified as vulnerable to current and future flooding impacts. As funding opportunities arise, the County should consider removing real property structures from coastal FEMA flood zones through

acquisition of repetitive loss properties or properties at risk of loss, for use as green space or stormwater management.

Policy BBIA 6.22

Brevard County ~~should~~ shall continue to analyze the best available data to maintain or update relevant and current coastal hazard vulnerability projections and update maps, as applicable. The County should continue to identify and understand the risks, vulnerabilities, and opportunities for strategies within short, mid, and long-term planning horizons as established in the RRAP Formal Recommendation, as amended.

Policy BBIA 6.23

Brevard County shall coordinate with the municipalities and appropriate state agencies ~~to maintain Evacuation Zone Management Plans as described in the Coastal High Hazard section of the Coastal Management Element as well as in managing and implementing~~ the recommendations found within the Brevard County Comprehensive Emergency Management Plan, as amended.

Policy BBIA 6.24

Brevard County, in conjunction with Brevard Public Schools and the appropriate municipalities within Brevard County shall identify issues relating to public school emergency preparedness, such as the design and use of public schools as emergency shelters.

Marine Resources

Objective BBIA 7

Brevard County shall protect shoreline and marine resources, including mangroves, seagrass beds, wetlands, sea turtles, manatees, and fish and wildlife, and related habitats.

Policy BBIA 7.1

Brevard County shall continue to protect Submerged Aquatic Vegetation (SAV) from the impacts of local land development by implementing the Surface Water Protection Ordinance, as may be amended. At a minimum, the following criteria shall be addressed:

Criteria:

- A. Maintain and enhance upland vegetation within required setbacks to reduce runoff.
- B. Require proper use of turbidity screens during construction activities.
- C. Control discharge rates to promote on-site settlement of sediment loads and meet minimum retention requirements for runoff from storm events.

Policy BBIA 7.2

Brevard County shall establish in land development regulations criteria for enhanced vegetative buffering between development and marine resources, so as to

reduce the impacts of nutrient loading, shoreline erosion, and lighting on natural resources. This shall include restoration standards for properties with disturbed shorelines.

Policy BBIA 7.3

Brevard County shall preserve, protect, and replace wetlands to achieve no net loss of functional wetlands. The County shall ensure the protection of wetlands and wetland functional values by prioritizing protective activities with avoidance of impacts as the first priority, minimization of impacts as the second priority, and mitigation for impacts as the third priority. The County shall maintain regulations that promote no net loss of functional wetlands, in accordance with Conservation Element Policy CON 5.2.

Policy BBIA 7.4

Wetland regulations adopted by Brevard County should avoid duplication of wetland regulation unless regulated activities will result in the destruction and/or degradation of functional wetlands. Where the wetland degradation or destruction has been permitted by FDEP or SJRWMD based on FDEP and SJRWMD professional staff application of criteria and evaluation, the County shall apply the avoidance, minimization of impacts, and mitigation priorities and land use and density requirements of this local comprehensive plan. Any permitted wetland degradation or destruction shall provide for mitigation.

Policy BBIA 7.5

The County's mining regulations shall continue to include, at a minimum, the following provisions to minimize adverse impacts to environmental resources.

Criteria:

- A. Mining operations should not adversely impact protected wetlands or other water dependent systems and shall be set back a minimum of 100 feet from such wetlands.
- B. Mining operations shall not cause saltwater intrusion. Monitoring by the mining operator shall be required to insure this requirement.

Policy BBIA 7.6

Prior to [any alteration or](#) development of any property that, based on best available data, potentially contains wildlife habitat, wetlands, or shoreline or marine resources, an environmental assessment ~~should~~ [shall](#) be completed by an environmental professional that would analyze the impact of the proposed development on the resources. For the purposes of this policy, the term “[alteration or](#) development” excludes renovation, rehabilitation, or remodeling of any existing structure only when such activity does not include a change in the size of the structure on the land or any clearing of land as an adjunct of construction.

Policy BBIA 7.7

_____ All development and activities shall comply with the Brevard County Manatee Protection Plan, as amended. Brevard County, in coordination with applicable partners such as FWC, shall continue to monitor manatee protection measures to determine their effectiveness.

Policy BBIA 7.8

_____ ~~All existing and new marinas shall~~ Prior to issuance of Certificate of Occupancy for new or redeveloped marinas, the County shall require the applicant to erect manatee education and awareness signs that will be posted and maintained in a prominent location. Each marina operator shall establish and maintain a permanent manatee educational display at a prominent location at their marina. Brevard County shall ~~establish and continue to maintain a display displays~~ at public boat launch facilities and license tag agencies.

Policy BBIA 7.9

_____ Brevard County shall continue to maintain well-marked speed limit signs, in accordance with the uniform waterway marker program, for manatee protection and boating safety speed zones established by local ordinance only.

Policy BBIA 7.10

_____ Brevard County, or other appropriate agencies, shall develop a standardized information packet containing information regarding manatees and regulations protecting manatees for distribution by the U.S. Fish and Wildlife Service (FWS), FDEP, Brevard Marine Association, and other agencies or groups as appropriate. This will include information concerning the existing manatee slow speed or idle zones, and any additional zones that may be deemed necessary within areas frequented by manatees.

Policy BBIA 7.11

_____ Brevard County supports the use of Turtle Excluder Devices (TEDs) or other devices to protect wildlife from shrimp and other fishing nets.

Policy BBIA 7.12

_____ Brevard County's mosquito impoundment management plans shall continue to address the following criteria, at a minimum:

Criteria:

- A. _____ The primary use of mosquito control impoundments shall be to protect human health through the control of mosquito populations. Secondary uses may include stormwater management, habitat improvement, wildlife management, and other uses as appropriate. Brevard County shall encourage multiple uses of mosquito control impoundments.
- B. _____ Appropriate water management system shall be utilized.
- C. _____ Impoundments shall be restored or reconnected with the Indian River Lagoon when a public benefit can be demonstrated.

BREVARD BARRIER ISLAND AREA

- D. Any other "source reduction" mosquito control activities that also reduce the natural habitat required by freshwater or marine organisms should be prohibited.
- E. Mosquito control impoundments shall be managed in a manner that avoids adverse impacts to the water quality of receiving water bodies.

Policy BBIA 7.13

Brevard County shall [continue to](#) include seagrass protection within the MPP performance standards for marinas and marine-related facilities.

Policy BBIA 7.14

Brevard County shall continue to implement standards for marina and boat ramp siting within the coastal zone that shall address the following criteria at a minimum:

Criteria:

- A. All proposed marina siting projects in unincorporated areas of Brevard County shall come before the Board of County Commissioners for [their its](#) review. Marina development may be considered within any appropriate zoning classification, if it is consistent with the performance standards developed by the County. Uplands at the marina site shall be greater than or equal to one acre. Residential marinas shall be allowed as a permitted use, subject to the boat facility siting criteria established in the MPP, as amended, and in the policies under Objectives CON 3 and CON 9 of the Conservation Element, in all of the current conditional use zoning classifications for residential/recreational marinas, except Recreational Vehicle Park (RVP) and Government Managed Lands (GML).
- B. At the beginning of the zoning or development order application process, all marina and boat ramp development proposals must submit a conceptual plan to be reviewed by the Natural Resources Management Department for compliance with the MPP, as amended.
- C. [Brevard County shall coordinate with applicable partners including FWC on the development of new marinas and the expansion of existing marinas to ensure the project is consistent with the Brevard County MPP.](#)

Policy BBIA 7.15

Marinas shall be inspected [periodically at least every five \(5\) years](#) by Brevard County and results of these inspections shall be coordinated with other agencies. Inspections shall be coordinated with existing programs and duplication with existing inspection programs shall be avoided. Items to be inspected and reviewed may include the following.

Criteria:

- A. Pump-out facilities and marine sanitation devices, if required. Live-aboard vessels and floating structures at marinas shall be inspected to ensure that marine sanitation devices are present and operational.
- B. Compliance with power/sailboat mix, if required.

BREVARD BARRIER ISLAND AREA

- C. Spill prevention, control, containment and cleanup plans.
- D. Waste collection and disposal methods.
- E. Firefighting equipment, if required.
- F. Monitoring of marina basin water quality for bacteriological levels to ensure compliance with state and federal standards. If a water monitoring program is required, water-dependent uses shall be assessed an annual fee adequate to fund a water quality monitoring program.

Policy BBIA 7.16

Brevard County shall utilize available management plans in developing standards for marina siting and other water-dependent uses. These management plans include, but are not limited to, Aquatic Preserve Management Plans, the Surface Water Improvement Management (SWIM) Plan, and the IRLNEP CCMP.

Policy BBIA 7.17

Brevard County shall coordinate with FWC during design and modification of water control structures to prevent harm to manatees.

Upland Resources

Objective BBIA 8

Brevard County shall protect upland resources, including dune ridges, beaches, wildlife, and related habitats.

Policy BBIA 8.1

Brevard County shall maintain regulations to address premature unpermitted land clearing and revegetation, including the following minimum criteria.

Criteria:

- A. Require permitting prior to land clearing unless exempt by ordinance.
- B. Require phased clearing in conjunction with phased construction.
- C. Require permits for the removal of trees or vegetation in conjunction with land surveying unless exempt by ordinance.
- D. Require areas cleared of vegetation to be revegetated with biologically appropriate vegetation; to prevent wind or water erosion and adverse impacts to other natural resources including wildlife habitat; within ninety (90) days of initial land clearing activity where no approved landscape plan exists, or no active development order has been issued. Native vegetation should be utilized to the maximum extent possible. Require monitoring and maintenance of revegetated areas to ensure successful establishment of plantings.
- E. Require tree and canopy preservation, including root protection standards.

Policy BBIA 8.2

Brevard County should continue to utilize scientific advisory groups to investigate preservation of vegetation, particularly of upland communities. These groups are ad hoc based upon the Board direction. The Environmentally Endangered Lands Program, Selection and Management Committee (SMC) may also be used to support these investigations when consistent with policy.

Policy BBIA 8.3

Brevard County shall conserve, appropriately use and protect vegetative communities, including forests, from inappropriate development using the following minimum criteria:

Criteria:

- A. Heat Island Mitigation.
- B. Vegetative Buffering.
- C. Vegetative Loss Replacement.

Policy BBIA 8.4

Brevard County shall establish in land development regulations criteria for enhanced vegetative buffering between development and ~~the~~ [the upland resources of the Indian River Lagoon and the Atlantic Ocean, so as to reduce the impacts of nutrient loading, shoreline erosion, and lighting on natural resources. This shall include restoration standards for properties with disturbed native vegetation.](#)

Policy BBIA 8.5

Brevard County shall ~~continue to develop programs for~~ [prioritize](#) acquisition of unique vegetative communities ~~in the BBIA to~~ protect upland resources, including dune ridges, beaches, and wildlife and related habitats. This acquisition shall be voluntary and shall not include the use of eminent domain.

Policy BBIA 8.6

Brevard County shall continue to ensure removal of invasive exotics on public lands and shall educate private property owners on reasons to remove invasive exotics from private lands. This program should emphasize replacement of invasive exotics with appropriate native vegetation where feasible [at size and scale approximating the removed invasive exotics so as to reduce the impacts of nutrient loading, shoreline erosion, and lighting on natural resources.](#)

Policy BBIA 8.7

Brevard County shall continue to make available state and federal maps at the pre-application stage of all projects requiring site-plan or subdivision approval to guide future development away from crucial habitats.

Policy BBIA 8.8

Prior to ~~any alteration or~~ development of any property that, based on best available data, potentially contains wildlife habitat or upland natural resources, an environmental assessment ~~should~~ ~~shall~~ be completed by an environmental professional that would analyze the impact of the proposed development on the resources. For the purposes of this policy, the term “~~alteration or~~ development” excludes renovation, rehabilitation, or remodeling of any existing structure only when such activity does not include a change in the size of the structure on the land or any clearing of land as an adjunct of construction.

Policy BBIA 8.9

Brevard County shall continue to comply with the County-wide scrub-jay Habitat Conservation Plan as approved by ~~the US Fish and Wildlife Service~~ FWS.

Policy BBIA 8.10

~~When deemed necessary by, and in coordination with, FWC and/or FWS,~~ Brevard County shall develop and comply with management plans for other species, ~~as deemed necessary.~~

Policy BBIA 8.11

The County shall continue to implement education programs to promote the preservation of ~~crucial habitats related to Species of Greatest Conservation Need, as defined by the FWC State Wildlife Action Plan endangered and threatened species and species of special concern as well as their habitat,~~ with the assistance of ~~the FDEP, the Florida Fish and Wildlife Conservation Commission~~ FWC, ~~and the U.S. Fish and Wildlife Service~~ FWS, and other agencies or groups as appropriate.

Policy BBIA 8.12

Brevard County shall continue to adopt and enforce standards for maintenance or re-establishment of dune areas. These standards shall include, at a minimum, the following provisions:

Criteria:

- A. Native dune vegetation shall be maintained and restored on site unless removal or alteration is permitted by both Brevard County and FDEP, and other appropriate regulatory agency.
- B. Public and private beach access shall be allowed only at designated cross-over structures or historical access sites.
- C. Erosion control strategies will be utilized at unimproved public access sites until these can be improved or alternate access provided.

- D. Dune crossovers, boardwalks, walkways and other permissible structures seaward of the CSL shall be elevated above dune vegetation ~~and~~, shall be designed to allow adequate sunlight penetration for vegetation, and shall not include lighting.
- E. Shore-parallel boardwalks shall be prohibited seaward of the CSL except as required to comply with Americans with Disability Act (ADA) access.
- F. Publicly owned dunes, especially those identified for beach access sites, that have been denuded or damaged by vehicular or pedestrian traffic shall be prioritized for dune renourishment and revegetation. Improvements or erosion controls shall be implemented at the time of renourishment to prevent further site degradation.
- G. Private property owners ~~should~~ shall be encouraged to re-establish dune vegetation that has been destroyed by non-designated access activities or storm damage.
- H. Structures and impacts that are necessary for public safety or meet the best public interest shall be permitted if approved by the Board of County Commissioners.

Policy BBIA 8.13

Brevard County shall maintain an ongoing program to initiate and monitor data collection projects related to beach dynamics, sand transport and coastal processes. This program should include data generated by ~~the Florida Department of Environmental Protection~~ FDEP, the U.S. Army Corps of Engineers, the Florida Sea Grant program, universities, and other appropriate agencies.

Policy BBIA 8.14

Brevard County shall prohibit motorized vehicles on the dune and beach system except for governmental vehicles, public safety vehicles, vehicles necessary to repair utilities, or vehicles utilized during approved renourishment programs or approved scientific investigations. Pedestrian traffic within the vegetated dune areas shall be limited to emergency operations, scientific research, maintenance, cleaning or improvements as authorized by the Natural Resources Management Department and consistent with FDEP regulations.

Policy BBIA 8.15

Beach access site improvements, parking facilities, and drainage shall be secondary to improvements to the naturally functioning dune system. Brevard County shall make efforts to balance the demand for beach access with the protection of the beach and dune habitat and species. [When feasible, Brevard County shall incorporate educational signage at public beach access sites related to reducing disturbance and impacts to seabird and shorebird species listed by FWC as Species of Greatest Conservation Need.](#)

Policy BBIA 8.16

Brevard County shall continue to pursue funds for dune revegetation to be used when constructing dune crossovers as replacements for unimproved dune access.

Water Quality Protection

Objective BBIA 9

Brevard County shall limit the adverse impacts of development on the quality of water throughout the BBIA and the Indian River Lagoon.

Policy BBIA 9.1

Brevard County shall continue to make efforts to prevent negative impacts of development in and adjacent to the Indian River Lagoon and its tributaries by implementing and revising as necessary, the Surface Water Protection Ordinance, including the following minimum criteria:

Criteria:

- A. Maintain a fifty (50) foot surface water protection buffer from the ordinary high-water line, mean high water line, or safe upland line as determined or approved by the FDEP Bureau of Survey and Mapping. On bulkheaded lots, the waterward extension of the buffer is established by the bulkhead line. In lieu of an approved ordinary high-water line, mean high water line, or safe upland line, an alternative buffer establishment line that approximates the land-water interface may be approved administratively as defined in ordinance. The use of the alternative buffer establishment line shall only be applied to shorelines with a clearly defined land-water interface.
- B. Except as allowable under criteria C and D below, primary structures shall not be permitted within the surface water protection buffer. The County shall establish in land development regulations allowable uses within the surface water protection buffer. Stormwater management for all alterations associated with allowable uses shall be required to protect water quality of the receiving water body. Provisions for the alteration and/or removal of non-native invasive plants, mitigation projects, and the planting of native species shall be established by the County.
- C. For residential lots platted or established by deed on the official record books of Brevard County prior to September 8, 1988, where there is insufficient lot depth to construct a primary structure, a primary structure may be located within the surface water protection buffer at least twenty five (25) feet from the water line as outlined in Criterion A if additional measures are taken to preserve water quality and natural habitat within the adjacent surface water body. These additional measures shall, at a minimum, prevent the first inch of stormwater runoff from entering surface waters; and may include, but not be limited to, a stormwater retention system or native shoreline revegetation. Where applicable, stormwater management measures shall be consistent with Chapter 373, F.S., as amended.

- D. For residential lots located along areas of the Indian River Lagoon and its tributaries added to the State's designation of Class II Waters as of February 17, 2016, and platted or established by deed on the official record books of Brevard County prior to that date, where there is insufficient lot depth to construct a primary structure, a primary structure may be located within the surface water protection buffer at least twenty five (25) feet from the water line as outlined in Criterion A if additional measures are taken to preserve water quality and natural habitat within the adjacent surface water body. These additional measures shall, at a minimum, prevent the first inch of stormwater runoff from entering surface waters; and may include, but not be limited to, a stormwater retention system or native shoreline revegetation. Avoidance and minimization of buffer impacts shall be required. Where applicable, stormwater management measures shall be consistent with Chapter 373, F.S., as amended.
- E. Within the surface water protection buffer the maximum amount of impervious surface is thirty (30) percent, inclusive of primary structures as outlined in Criteria C and D.
- F. Prohibit shoreline alteration other than that allowed by ordinance, unless the alteration is in the public interest and does not adversely impact water quality, natural habitat, and adjacent shoreline uses.
- G. Prohibit channelization, dredging and filling, and impoundment of natural waters of the State unless the activity is clearly in the public interest and does not adversely impact water quality, natural habitat, and adjacent shoreline uses. Dredging shall not be permitted in or connected to Class II Waters, Outstanding Florida Waters (OFWs), Aquatic Preserves, areas that contain ten percent (10%) seagrass or more, and conditionally approved shellfish harvesting waters unless the activity is a federal navigation project, in the public interest, such as approved maintenance dredging of existing public or private navigational channels, or where dredging may improve water quality by removing accumulated silt or improving circulation, or for maintenance of existing structures and utility structures and utility crossings, or for shoreline alteration as allowed by this comprehensive plan.
- H. Prohibit discharges of any substances below ambient water quality standards.

Policy BBIA 9.2

Brevard County shall continue to protect the estuarine floodplains by implementing the following minimum criteria:

Criteria:

- A. Development within the one-hundred-year estuarine floodplain shall not adversely impact the drainage of adjacent properties or the quality of the receiving surface water body.

BREVARD BARRIER ISLAND AREA

B. The following specific uses are not compatible with the resource requirements of the one-hundred-year estuarine floodplain and shall not be permitted. These include, but are not limited to:

1. Placing, depositing, or dumping of solid wastes.
2. Processing and storing of threshold amounts of hazardous materials.
3. Disposal of hazardous materials.

Policy BBIA 9.3

Mining operations shall not be permitted within wetlands as protected within this comprehensive plan.

Policy BBIA 9.4

In those cases where soil erosion is of concern, especially properties along the Atlantic Ridge, projects should minimize impervious surfaces by using pervious surfaces wherever feasible, such as for overflow parking.

Policy BBIA 9.5

Brevard County ~~should~~ shall employ Best Management Practices for control of erosion and sedimentation for road construction and other County projects.

Policy BBIA 9.6

Brevard County shall utilize techniques in the installation of new facilities or improvement of existing facilities to minimize sediment accumulation within surface water bodies and wetlands.

Policy BBIA 9.7

The Brevard County Land Development Regulations shall require all new development being site planned or subdivided to provide for stormwater management that meets the following Level of Service Standards, at a minimum:

Criteria:

- A. Retention and detention requirements shall at a minimum meet SJRWMD Criteria.
- B. Retention of the first inch of runoff.
- C. Post-development rate of discharge shall not exceed pre-development rate of discharge for a 25-year, 24-hour storm event.
- D. Stormwater discharge facilities shall be designed so as to not lower receiving water quality or degrade the receiving water body below the minimum conditions necessary to assure the suitability of water for the designated use of its classification as established in Chapter 62-302, FAC.

Policy BBIA 9.8

The County shall consider and comment as necessary on the impact of new development on stormwater conveyance systems. If the stormwater impacts from

BREVARD BARRIER ISLAND AREA

proposed development are determined to cause or contribute to adverse local or downstream impacts, the developer shall be required to retain additional runoff on site or make improvements to the conveyance system equal to the impact of the new development.

Policy BBIA 9.9

Development shall not ~~negatively impact~~ result in adverse impacts to the drainage of adjacent properties or the quality of receiving surface water ~~body bodies~~ quality.

Policy BBIA 9.10

All new boat ramps should have parking areas constructed utilizing ~~permeable pavement where appropriate~~ Low Impact Development design and have the proper stormwater management system in place.

Scenic Resources

Objective BBIA 10

Brevard County shall enhance natural scenic resources to promote the aesthetic benefits of the natural environment.

Policy BBIA 10.1

Brevard County shall maintain regulations to preserve scenic vistas and establish vegetative coverage requirements for developing and redeveloping properties.

Policy BBIA 10.2

The County shall require oceanfront breezeways to permit unrestricted movement of breezes and to preserve visual access to the ocean. All developed oceanfront property except single-family residential shall have a minimum of 30 percent clear of vertical construction as breezeway/visual corridor.

Policy BBIA 10.3

The County shall require riverfront breezeways to permit unrestricted movement of breezes and to preserve visual access to the river. All developed riverfront property except single-family residential shall have a minimum of 30 percent clear of vertical construction as breezeway/visual corridor.

Policy BBIA 10.4

The County shall enhance the existing public access sites to beaches, shores, parks, and conservation lands by providing additional facilities as determined by need, the character of the land, and as funding becomes available.

Policy BBIA 10.5

SR A1A, from southern corporate limits of City of Melbourne Beach to the Indian River County Line is designated as a scenic roadway in order to preserve the adjacent natural features.

Policy BBIA 10.6

Brevard County shall encourage the protection and preservation of scenic features through implementation of the following:

Criteria:

- A. Property owners along designated roadways shall be encouraged to preserve trees and vegetation during development of these properties.
- B. Billboards and other physical barriers, such as fences, exceeding four feet in height, excluding primary and accessory structures, that interfere with or prevent visual access to the scenic qualities of the roadways designated as scenic resources, shall be prohibited. Non-conforming existing billboards and the referenced opaque physical barriers shall be amortized.
- C. Vegetation and trees growing adjacent to scenic roadways within the rights-of-way for those roads shall be protected by the land development regulations regarding land clearing activities except in those cases involving health and safety concerns or those that would deny visual access beyond the immediate area.
- D. Public or private linear projects and utility corridors developed or maintained by governmental or investor-owned regulated utilities that do not require an active development order are exempt if determined to be in the public interest as defined in the Brevard County Comprehensive Plan Glossary per Sec 62-4334 of the Brevard County Code of Ordinances.
- E. Responsible outdoor lighting that conserves energy, avoids harmful effects on wildlife, and protects the night sky, while conforming to regulatory standards including, but not limited to, lighting safety standards.

Policy BBIA 10.7

Brevard County shall investigate the feasibility of acquiring narrow strips of land along the Indian River Lagoon, where such areas could provide visual access or provide parking for passive recreation within the Lagoon.

Compatibility

Objective BBIA 11

Brevard County shall ensure that development is compatible with the unique characteristics of the BBIA.

Policy BBIA 11.1

The existence of sewer, water, roadways, or other public infrastructure shall not be considered adequate rationale for an increase in intensity.

BREVARD BARRIER ISLAND AREA

Policy BBIA 11.2

Brevard County shall review shore-line development within the coastal zone in order to maximize opportunities for water-dependent land uses. The following criteria, at a minimum, shall be utilized.

Criteria:

- A. Water-related and water-enhanced uses shall be built on uplands.
- B. Development that is feasible only through creation of land by dredging and filling of areas below the mean high-water line shall not be approved.
Exceptions may be considered where overriding public benefit to the natural resource can be demonstrated.
- C. Water-dependent commercial and industrial uses may be considered for siting adjacent to the Indian River Lagoon.

Policy BBIA 11.3

The Brevard County Land Development Regulations shall include a provision for water-enhanced commercial uses within the coastal zone.

Policy BBIA 11.4

During rezoning and other development order approval reviews, Brevard County should give immediate shoreline use priorities (in descending order of priority) to:

Criteria:

- A. Water-dependent uses such as fish, shellfish and wildlife production, recreation, water dependent industry and utilities, marinas and navigation;
- B. Water-related uses such as certain utilities, ~~commerce~~ commercial and ~~industrial~~ other uses identified in the MPP;
- C. Water-enhanced uses such as some recreation uses;
- D. Non-water dependent or related activities such as residential; and
- E. Of lowest priority are those uses that are non-water-dependent, non-water enhanced, and result in an irretrievable commitment of coastal resources.

Policy BBIA 11.5

Brevard County shall review beachfront development to ensure that it does not interfere with public access in those instances where the public has established ocean access-ways through private lands by prescription, prescriptive easement, or other legal means. The developer may improve, consolidate, or relocate such public access provided it is consistent with this Plan.

Future Land Use Categories within the BBIA

Objective BBIA 12

Pursuant to section 380.0553, F.S., the policies contained within this Part of the Comprehensive Plan do not affect any existing zoning or use of land in effect within the BBIA prior to July 1, 2023.

Policy BBIA 12.1

Consistent with Policy CM 7.1 of the Coastal Management Element, Brevard County shall not increase residential densities within the BBIA by amending the Future Land Use Map designation for such properties.

Policy BBIA 12.2

Brevard County will continue to recognize the development entitlements of nonconforming lots of record and pre-existing uses in accordance with the land development regulations.

Policy BBIA 12.3

Future Land Use Map designations shall be assigned to properties with the corresponding future land use map designations in effect prior to July 1, 2023 as shown below.

- A. Lands with ~~RES Residential~~ 1 Future Land Use Map designations shall be assigned ~~RES Residential~~ 1 – BBIA Future land Use Map designations;
- B. Lands with ~~RES Residential~~ 2 Future Land Use Map designations shall be assigned ~~RES Residential~~ 2 – BBIA Future land Use Map designations;
- C. Lands with ~~RES Residential~~ 4 ~~or RES-4 Directive~~ Future Land Use Map designations shall be assigned ~~RES Residential~~ 4 – BBIA Future land Use Map designations;
- D. Lands with Residential 4 Directive Future Land Use Map designations shall be assigned Residential 4 Directive – BBIA Future Land Use Map designations;
- ~~DE.~~ Lands with ~~RES Residential~~ 6 ~~or RES-6 Directive~~ Future Land Use Map designations shall be assigned ~~RES Residential~~ 6 – BBIA Future land Use Map designations;
- F. Lands with Residential 6 Directive Future Land Use Map designations shall be assigned Residential 6 Directive – BBIA Future Land Use Map designations;
- ~~EG.~~ Lands with ~~RES Residential~~ 8 Directive Future Land Use Map designations shall be assigned ~~RES Residential~~ 8 ~~Directive~~ – BBIA Future land Use Map designations;
- ~~FH.~~ Lands with ~~RES Residential~~ 15 Future Land Use Map designations shall be assigned ~~RES Residential~~ 15 – BBIA Future land Use Map designations;
- ~~GI.~~ Lands with Neighborhood Commercial Future Land Use Map designations shall be assigned Neighborhood Commercial – BBIA Future land Use Map designations;
- ~~HJ.~~ Lands with Community Commercial Future Land Use Map designations shall be assigned Community Commercial – BBIA Future land Use Map designations;
- ~~IK.~~ Lands with Public Facilities Future Land Use Map designations shall be assigned Public Facilities – BBIA Future land Use Map designations;

- JL. Lands with Recreation Future Land Use Map designations shall be assigned Recreation – BBIA Future land Use Map designations;
- KM. Lands with Private Conservation Future Land Use Map designations shall be assigned Private Conservation – BBIA Future land Use Map designations;
- LN. Lands with Public Conservation Future Land Use Map designations shall be assigned Public Conservation – BBIA Future land Use Map designations;
- MO. Lands without an assigned Future Land Use category shall have Future Land Use Map designations as follows:
 - 1. Privately-owned lands shall be assigned Private Conservation – BBIA;
 - 2. Publicly owned lands shall be assigned Public Conservation – BBIA.

Residential 1 – BBIA Future Land Use

Policy BBIA 12.4

The Residential 1 – BBIA land use designation permits low density residential development with a maximum density of up to one (1) unit per acre. The Residential 1 – BBIA land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan:

Criteria:

- A. Areas adjacent to existing Residential 1 land use designation; or
- B. Areas that serve as a transition between existing land uses or land use designations with density greater than one (1) unit per acre and areas with lesser density; or
- C. Unincorporated areas that are adjacent to incorporated areas and may be considered a logical transition for Residential 1.
- D. Up to a 25% density bonus to permit up to 1.25 dwelling units per acre may be considered ~~with a~~ within an existing Planned Unit Development (PUD) approved before July 1, 2023 where deemed compatible by the County with adjacent development, provided that minimum infrastructure requirements set forth in Policy FLU 1.2 are available. Such higher densities should be relegated to interior portions of the PUD tract, away from perimeters, to enhance blending with adjacent areas and to maximize the integration of open space within the development and promote inter-connectivity with surrounding uses. This density bonus shall not be utilized by PUDs approved on or after July 1, 2023 or by properties within the CHHA.

Residential 2 – BBIA Future Land Use

Policy BBIA 12.5

The Residential 2 – BBIA land use designation permits lower density residential development with a maximum density of up to two (2) units per acre. The Residential 2 – BBIA land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan:

Criteria:

- A. Areas adjacent to existing Residential 2 land use designation; or

- B. Areas that serve as a transition between existing land uses or land use designations with density greater than two (2) units per acre and areas with density of less than two (2) units per acre; or
- C. Unincorporated areas that are adjacent to incorporated areas and may be considered a logical transition for Residential 2.
- D. Up to a 25% density bonus to permit up to 2.5 dwelling units per acre may be considered ~~where the Planned Unit Development concept is utilized~~ within an existing PUD approved before July 1, 2023; where deemed compatible by the County with adjacent development, provided that minimum infrastructure requirements set forth in Policy FLU 1.2 are available. Such higher densities should be relegated to interior portions of the PUD tract, away from perimeters, to enhance blending with adjacent areas and to maximize the integration of open space within the development and promote inter-connectivity with surrounding uses. This density bonus shall not be utilized ~~for by PUDs approved on or after July 1, 2023 or by~~ properties within the CHHA.

Residential 4 – BBIA Future Land Use

Policy BBIA 12.6

The Residential 4 – BBIA land use designation affords an additional step down in density from more highly urbanized areas. This land use designation permits a maximum density of up to four (4) units per acre. The Residential 4 – BBIA land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan:

Criteria:

- A. Areas adjacent to existing Residential 4 land use designation; or
- B. Areas that serve as a transition between existing land uses or land use designations with density greater than four (4) units per acre and areas with density of less than four (4) units per acre; or
- C. Unincorporated areas that are adjacent to incorporated areas and may be considered a logical transition for Residential 4.
- D. Up to a 25% density bonus to permit up to five (5) units per acre may be considered ~~with a Planned Unit Development~~ within an existing PUD approved before July 1, 2023 where deemed compatible by the County with adjacent development, provided that minimum infrastructure requirements set forth in Policy FLU 1.2 are available. Such higher densities should be relegated to interior portions of the PUD tract, away from perimeters, to enhance blending with adjacent areas and to maximize the integration of open space within the development and promote inter-connectivity with surrounding uses. This density bonus shall not be utilized ~~for by PUDs~~ approved on or after July 1, 2023 or by properties within the CHHA

Residential 4 Directive – BBIA Future Land Use

Policy BBIA 12.7

The Residential 4 Directive – BBIA land use designation is applied to lands following the recommendation of the 1992 South Beaches Small Area Plan Study. This land use designation permits a maximum density of up to four (4) units per acre.

Residential 6 – BBIA Future Land Use

Policy BBIA 12.7 8

The Residential 6 – BBIA land use designation affords a transition in density between higher density areas and lower intensity land uses. This land use designation permits a maximum density of up to six (6) units per acre. The Residential 6 - BBIA land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan:

Criteria:

- A. Areas adjacent to existing Residential 6 land use designation; or
- B. Areas that serve as a transition between existing land uses or land use designations with density greater than six (6) units per acre and areas with density of less than six (6) units per acre; or
- C. Unincorporated areas that are adjacent to incorporated areas and may be considered a logical transition for Residential 6.
- D. Up to a 25% density bonus to permit up to 7.5 dwelling units per acre may be considered ~~where the Planned Unit Development concept is utilized; within~~ an existing PUD approved before July 1, 2023 where deemed compatible by the County with adjacent development, provided that minimum infrastructure requirements set forth in Policy FLU 1.2 are available. Such higher densities should be relegated to interior portions of the PUD tract, away from perimeters, to enhance blending with adjacent areas and to maximize the integration of open space within the development and promote inter-connectivity with surrounding uses. This density bonus shall not be utilized ~~for~~ by PUDs approved on or after July 1, 2023 or by properties within the CHHA.

Residential 6 Directive – BBIA Future Land Use

Policy BBIA 12.9

The Residential 6 Directive – BBIA land use designation is applied to lands following the recommendations of the 1992 South Beaches Small Area Plan Study. This land use designation permits a maximum density of up to six (6) units per acre.

Residential 8 Directive – BBIA Future Land Use

Policy BBIA 12.8 10

The Residential 8 ~~Directive~~ – BBIA land use designation ~~affords a transition in density between higher density areas and lower intensity residential uses~~ is applied to lands following the recommendations of the 1992 South Beaches Small Area Plan Study. This land use designation permits a maximum density of up to eight (8) units per acre.

Residential 15 – BBIA Future Land Use

Policy BBIA 12.9 11

The Residential 15 – BBIA land use designation affords the highest density allowance, permitting a maximum density of up to fifteen (15) units per acre. The Residential 15 – BBIA land use designation may be considered for lands within the following generalized locations, unless otherwise limited by this Comprehensive Plan:

Criteria:

- A. Areas located east of Interstate-95, except in instances where they are adjacent to existing or designated residential densities of an equal or higher density allowance; and
- B. Unincorporated areas that are adjacent to incorporated areas and may be considered a logical transition for Residential 15 area;
- C. Areas adjacent to an existing Residential 15 land use designation; and
- D. Areas that have access to an arterial or collector roadway, without impacting existing or designated lower density/intensity areas.
- E. Up to a 25% density bonus to permit up to 18.75 dwelling units per acre may be considered ~~where the Planned Unit Development concept is utilized;~~ within an existing PUD approved before July 1, 2023 where deemed compatible by the County with adjacent development, provided that minimum infrastructure requirements set forth in Policy FLU 1.2 are available. Such higher densities should be relegated to interior portions of the PUD tract, away from perimeters, to enhance blending with adjacent areas and to maximize the integration of open space within the development and promote inter-connectivity with surrounding uses. This density bonus shall not be utilized ~~for~~ by PUDs approved on or after July 1, 2023 or by properties within the CHHA.

Neighborhood Commercial – BBIA Future Land Use

Policy BBIA 12.10 12

Neighborhood Commercial – BBIA development activities are intended to be low impact in nature and serve the needs of the immediate residential area. Intrusion of these land uses into surrounding residential areas shall be limited. Existing BU-1-A uses that were established as of the adoption date of this provision shall be considered consistent with this policy. Minimum public facilities and services are required for commercial uses, as specified in Policy FLU 2.4 of the Future Land Use Element. Development activities that may be considered within Neighborhood Commercial Future Land Use designation, provided that listed criteria are met, include the following:

- a) Professional offices (no drive through lanes permitted);
- b) Personal Services (no drive through lanes permitted);
- c) Convenience stores (no drive through lanes permitted);
- d) Residential uses pursuant to Policy FLU 2.11 of the Future Land Use Element;
- e) Institutional uses;
- f) Recreational uses; and

BREVARD BARRIER ISLAND AREA

g) Public facilities

The zoning classifications that may be considered in Neighborhood Commercial as transitional uses are: RA-2-4, RA-2-6, RA-2-8, RA-2-10, RU-2-4, RU-2-6, RU 2-8, RU-2-10, RU-2-12, RU-2-15, RU-2-30, BU-1-A, and IN(L).

Locational and development criteria for neighborhood commercial land uses are as follows:

Criteria:

- A. Neighborhood commercial clusters should be located at collector/collector or collector/arterial intersections, except as otherwise provided for in this Comprehensive Plan.
- B. Due to the linear nature and lack of intersections along SR A1A south of Melbourne Beach, new neighborhood commercial uses may not be considered along those roadways.
- C. New neighborhood commercial land use sites should incorporate no more than two acres maximum at each corner of an intersection, as set forth in Criterion A of this policy. Neighborhood commercial land uses at such intersections should not exceed eight (8) acres total.
- D. Neighborhood commercial development clusters should be spaced at least three (3) miles apart.
- E. The gross floor area of neighborhood commercial development should not exceed a Floor Area Ratio (FAR) of 0.75 unless zoned PUD and adequate roadways, solid waste disposal, hazardous waste disposal, potable water, wastewater treatment, and drainage facilities to serve the needs of the development are available concurrent with its impacts.
- F. Recreational vehicle parks shall be located in areas which serve the needs of tourists and seasonal visitors to Brevard County. The location of recreational vehicle parks shall have access to interstate interchanges via arterial and principal collector transportation corridors or the property shall be located on a major multi-county transportation corridor.

Community Commercial – BBIA Future Land Use

Policy BBIA 12.11 13

Community Commercial - BBIA development activities are intended to serve several neighborhoods, sub-regional and regional areas and provide an array of retail, personal and professional uses. Minimum public facilities and services are required for commercial uses, as specified in Policy FLU 2.4 of the Future Land Use Element. Development activities that may be considered within the Community Commercial Future Land Use designation, provided that listed criteria are met, include the following:

- a) Existing strip commercial;
- b) Transient commercial uses;
- c) Tourist commercial uses;
- d) Professional offices;

BREVARD BARRIER ISLAND AREA

- e) Personal service establishments;
- f) Retail establishments;
- g) Non-retail commercial uses;
- h) Residential uses pursuant to Policy FLU 2.11 of the Future Land Use Element;
- i) Institutional uses;
- j) Recreational uses; and
- k) Public facilities;

Locational and development criteria for community commercial land uses are as follows:

Criteria:

- A. Community commercial clusters of up to ten (10) acres in size should be located at arterial/arterial intersections. Collector/arterial intersections are acceptable for clusters of up to ten (10) acres in size, however, the collector roadways must serve multiple residential areas. Intrusion of these land uses into the surrounding residential areas shall be limited. For community commercial clusters greater than ten (10) acres in size, they must be located at principal arterial/principal arterial intersections.
- B. Community commercial complexes should not exceed 40 acres at an intersection.
- C. Community commercial clusters up to 10 acres in size should be spaced at least 2 miles apart, and community commercial clusters up to 40 acres in size should be spaced at least five (5) miles apart.
- D. The gross floor area of community commercial complexes should not exceed 150,000 square feet for commercial clusters up to 10 acres in size and shall not exceed 400,000 square feet for commercial clusters greater than 10 acres but less than 40 acres in size unless within a ~~Planned Unit Development (PUD)~~ zoning classification. The square footage may be increased if it is located within a PUD zoning classification.
- E. The gross floor area of a community commercial development shall not exceed a FAR of 1.0 unless accompanied with a PUD zoning classification wherein the FAR may be increased up to 1.75.
- F. Recreational vehicle parks shall be located in areas which serve the needs of tourists and seasonal visitors to Brevard County. The location of recreational vehicle parks shall have access to interstate interchanges via arterial and principal collector transportation corridors or the property shall be located on a major multi-county transportation corridor.

Public Facilities – BBIA Future Land Use

Policy BBIA 12.12 14

Appropriate locations for Public Facilities - BBIA land uses should be based upon the following minimum criteria:

Criteria:

BREVARD BARRIER ISLAND AREA

- A. Public facilities are those uses that, at a minimum, relate to government-managed transportation, sanitary sewer, potable water, solid waste, drainage, conservation, education, government service systems, and other utilities such as gas, electric, telephone and cable. An exception should be made for transmission or collection facilities, rights-of-ways, and easements. Public facilities are also those uses classified as scientific research and technology development activities conducted by non-governmental organizations (NGOs) in formal partnership with governmental entities. Such NGOs shall provide economic, environmental and/or quality of life benefits to Brevard County. Specific land-use activities include either: life science research, ocean, coastal and marine research and technology development, or environmental science research. Public Facilities that are NGOs in formal partnership with governmental entities shall not exceed a FAR of 0.25
- B. Public facilities land uses may be considered for locations within all land use designations on the Future Land Use Map provided such uses are compatible with adjacent land uses consistent with this Comprehensive Plan.
- C. Following the purchase, lease or dedication of property for public facility purposes, the Comprehensive Plan shall be amended to depict the property as Public Facility on the Future Land Use Map.
- D. Brevard County shall encourage the use of common corridors for utility systems, including sanitary sewer, potable water, re-use, electricity, gas and other utilities.

In order to maximize the efficiency of public facilities and resources, Brevard County and Brevard Public Schools should strive to coordinate use of existing school facilities for public use. In addition, development of new libraries, parks and recreation facilities, children's services facilities, and other appropriate public uses on properties adjoining school sites should also be coordinated.

Recreation – BBIA Future Land Use

Policy BBIA 12.13 15

The Recreation - BBIA land use designation may be adopted as part of the Future Land Use Map to identify appropriate locations for public recreation land uses, based upon the following minimum criteria:

Criteria:

- A. Recreation land uses may be considered within all land use designations on the Future Land Use Map, provided such uses are compatible with adjacent land uses. The County shall consider compatibility parameters including, but not limited to, hours of operation, anticipated traffic volumes, and landscaping and buffering.

- B. Following acquisition by Brevard County of the property for public recreational purposes, the Future Land Use Map shall be amended to depict said property as Recreation on the Future Land Use Map.

Private Conservation – BBIA Future Land Use

Policy BBIA 12.~~14~~ 16

The Private Conservation - BBIA land use designation is related to privately owned lands with significant environmental features. The land use designation applies to privately held lands that were designated Conservation on the Future Land Use Map prior to adoption of the Future Land Use Element on May 16, 2000, regardless of their zoning classification. Any lands that are privately owned and zoned Environmental Area (EA) or so designated by an approved binding development plan after May 16, 2000 shall be designated as Private Conservation. Such privately owned parcels shall permit a maximum residential density of one (1) unit per ten (10) acres.

Public Conservation – BBIA Future Land Use

Policy BBIA 12.~~15~~ 17

The Future Land Use Map shall designate lands as public conservation to provide for the protection of publicly held environmentally sensitive areas. The Public Conservation – BBIA future land use designation is intended to accommodate lands and facilities that are managed by federal, state, and local governments within unincorporated Brevard County for conservation or preservation uses. Such uses shall conform to the following minimum criteria:

Criteria:

- A. The Public Conservation land use designation should include lands under the ownership of Brevard County, the St. Johns River Water Management District, or other such agencies, for the purpose of environmental protection, publicly owned lands within the Environmental Area (EA) zoning classification, and publicly owned areas in which it is demonstrated that the preservation of environmentally sensitive resources will provide an overriding public benefit.
- B. Development activities within lands designated as Public Conservation shall be consistent with the specific policies and intent of this comprehensive plan. Specifically, activities that are conducted on Public Conservation lands that enhance, protect, or manage such lands for nature-based recreation, conservation, or preservation purposes for the benefit of the public shall be considered as consistent with this criterion.
- C. Other environmentally sensitive lands (i.e., floodplains, wetlands, or aquifer recharge areas) that are located outside of the Public Conservation land use designation are protected through the policies of this comprehensive plan.
- D. Privately owned land shall not be designated as public conservation. If privately owned lands are acquired by state, regional, or local agencies for conservation or preservation purposes, the participating agencies should provide such information to the County so that the Future Land Use Map may

be amended pursuant to section 163.3187, F.S., as may be amended. The County shall annually request such information from the applicable agencies so that any necessary amendments can be made to the Future Land Use Map.

- E. Residential densities for public conservation lands should not exceed one (1) dwelling unit per fifty (50) acres. Dwelling units on publicly held lands, including those zoned EA that are in public ownership, are limited to accommodating park rangers or other authorized personnel as deemed appropriate in order to manage or protect such public conservation lands.

Removal of Area of Critical State Concern Designation

Objective BBIA 13

The BBIA may be recommended for de-designation by the state land planning agency, and such designation may be removed by the Administration Commission, provided certain conditions are met.

Sufficiency of Local Plan and Land Development Regulations

Policy BBIA 13.1

Brevard County acknowledges that the state land planning agency may at any time recommend the removal of the designation of the BBIA as an area of critical state concern to the Administration Commission if the agency determines that all local land development regulations and local comprehensive plans and the administration of such regulations and plans are adequate to protect the BBIA and carry out the legislative intent expressed in section 380.0553(3), F. S., and are in compliance with the principles for guiding development specified in section 380.0553(5), F.S.

Criteria for De-designation

Policy BBIA 13.2

Brevard County acknowledges that the state land planning agency must recommend removal of the designation to the administration commission if it determines that:

- A. Adequate restoration and renourishment programs are in place to preserve the beaches and dunes of the southern barrier island in Brevard County for nesting sea turtles;
- B. Seagrass replanting in the Indian River Lagoon extending the length of the BBIA is in a coverage volume that would establish recovery to scientifically defensible reference targets;
- C. Nonpoint pollution sources into the Indian River Lagoon that contribute to total phosphorus, total nitrogen, chlorophyll a, fecal coliform, and metals have been sufficiently reduced to meet water quality criteria standards

resulting in the removal of the Indian River Lagoon from the impaired waters list;

- D. The green sea turtle (*Chelonia mydas*), loggerhead sea turtle (*Caretta caretta*), and leatherback sea turtle (*Dermochelys coriacea*) have been delisted from the Florida Endangered and Threatened Species rule and the Florida Marine Turtle Protection Act under section 379.2431, F.S., as may be amended from time to time;
- E. The Brevard County local comprehensive plan, its land development regulations, and the administration of such plans and regulations are adequate to protect the BBIA, fulfill the legislative intent specified in section 380.0553(3), F.S., and are consistent with and further the principles guiding development; and
- F. The Brevard County Commission has adopted a resolution at a public hearing recommending the removal of the designation.

Timeline for De-designation


Policy BBIA 13.3

Brevard County acknowledges that the Administration Commission must initiate rulemaking to remove the BBIA area of critical state concern designation within 45 days after receipt of the recommendation from the state land planning agency, if the commission concurs with the recommendation for removal.


APPENDIX

LIST OF MAPS

<u>MAP</u>	<u>Title</u>
<u>1</u>	<u>Area of Critical State Concern</u>
<u>2</u>	<u>Future Land Use Conservation Areas (North)</u>
<u>3</u>	<u>Future Land Use Conservation Areas (Central)</u>
<u>4</u>	<u>Future Land Use Conservation Areas (South)</u>




BREVARD BARRIER ISLAND AREA




BREVARD BARRIER ISLAND AREA

LPA Adoption June 16, 2025

XVI - 43



BREVARD BARRIER ISLAND AREA




Future Land Use Conservation Areas

0 0.5 1 2 Miles

Brevard County Information Technology Department
Data Source: Planning & Development Department (FLU)

Page Index 3



BREVARD BARRIER ISLAND AREA

LPA Adoption June 16, 2025

XVI - 45

CHAPTER XVI PART XVII

GLOSSARY

GLOSSARY

Acceptable Level of Service - the minimum standard adopted in this Comprehensive Plan for a service level on public facilities and services such as roadways, sanitary sewer, potable water, drainage, public schools, solid waste, and parks.

Access - the physical attributes of a site/facility which enable a person and his attendant means of transportation, to enter a site/facility; See Public Access.

Acquire - to come into possession or control of.

Acre-foot (acre-feet) - a quantity that is equal to one acre of land covered by one foot of water.

Active Recreation - those recreational uses which require a greater degree of physical exertion and involvement and which contribute to the physical and mental well-being of an individual. Active recreation facilities typically require the alteration of land, vegetation, topography, or other natural features unless developed on a previously impacted site. Includes, but is not limited to, activities such as tennis, baseball, golf, football, etc.

Adequate - ability to satisfy a requirement.

Adequate Housing - ~~a housing unit which is suitable for human occupancy, which has working indoor plumbing, an adequate heating system, and is in safe structural condition. May have some housing code violations consisting of minor repairs and upkeep which can be corrected by relatively inexpensive means.~~

Ad valorem tax means a tax or fee based on the value of the property or item on which it is levied.

Adjusted gross income- means all wages, assets, regular cash or noncash contributions or gifts from persons outside the household, and such other resources and benefits as may be determined to be income by the ~~United States Department of Housing and Urban Development~~ Florida Department of Commerce, adjusted for family size, less deductions allowable under s. 62 of the Internal Revenue Code.

Affordable Housing - housing where monthly rents or monthly mortgage payments, including taxes, insurance, and utilities do not exceed 30 percent of that amount which represents the percentage of the median adjusted gross annual income for the following types of households or persons: Extremely-low-income persons, ~~Very-low incomes~~ Very-low-income persons, Low-income persons, and ~~Moderate-incomes~~ Moderate-income persons, as further described in section 420.0004, F.S.

Affordable Workforce Housing - means housing that is affordable to a person who earns less than 120 percent of the area median income, or less than 140 percent of the area median income if located in a county in which the median purchase price for a single-family existing home exceeds the statewide median purchase prices as determined in the Florida Sales Report, Single-Family Existing Homes, released each January by the Florida Association of Realtors and the University of Florida Real Estate Research Center. {Ref [section 380.0651\(1\)\(h\), F.S.](#)}.

Agriculture - ~~activities within land areas which are predominantly used for the cultivation of crops and livestock including: cropland, pastureland, orchards, vineyards, nurseries, ornamental horticulture areas, groves, confined feeding operations, specialty farms, and silviculture areas.~~ the science and art of production of plants and animals useful to humans, including to a variable extent the preparation of these products for human use and their disposal by marketing or otherwise, and includes aquaculture, horticulture, floriculture, viticulture, forestry, dairy, livestock, poultry, bees, and any and all forms of farm products and farm production. For the purposes of marketing and promotional activities, seafood shall also be included in this definition.

Ambient (water or air) Quality - the background quality or condition of water or air.

Amenities - attractive or positive natural, historical or cultural features such as the beaches, riverfronts, historic landmarks, museums, etc.

Aquaculture - ~~the culturing of aquatic plants and animals for human use.~~ the cultivation of aquatic organisms.

Aquatic Preserves - those sovereignty lands established by the state of Florida and managed under the provisions set forth in Chapters 253 and 258 of the Florida Statutes.

Attain - to reach an end; to arrive by effort.

Authorized Resident means any person owning a fee or leasehold interest in real property or a boating facility immediately adjacent to motorboats prohibited zone or a no entry zone.

Average Weekday Volume - average 24-hour traffic volume based upon a minimum of 48 hours of continuous counting between 12:01 a.m. Monday to 12:01 a.m. Friday.

Backlogged Facilities - infrastructure that is deficient and for which there are no planned or programmed improvements in the Capital Improvements Element.

Balanced Housing Market - a market situation where housing opportunities are equally distributed across an area according to the cost, size, type, location, and density of housing units.

Base Flood Elevation - the height, expressed in feet above sea level, of the highest level of floodwaters occurring in the regulatory base flood. The elevation of surface water resulting from a flood that has a 1% chance of equaling or exceeding that level in any given year.

Berm - a mound of sand piled by wind and waves just above the ordinary limit of waves at high tide or a manmade structure used to isolate or contain surface waters. A berm can also be defined as a man-made mound of earth, in excess of two feet in vertical height, used to shield or buffer properties from adjoining uses, highways, or noise, or to control the direction of surface water flow.

Best Evaluation Practices - the best practices relating to procedures, processes, data and information that are feasible but dependent upon the availability of resources, personnel, professional expertise, state-of-the-art equipment, and other similar components contributing to the accuracy of analytical efforts.

Best Management Practices (erosion) - erosion control methods such as those described in "Stormwater Management Manual" (1981); and the "Florida Development Manual: A Guide to Good Land and Water Management" (June, 1988), manuals adopted by the Environmental Regulation Commission pursuant to rule 1725.050 F.A.C.

Best Public Interest means public projects which clearly demonstrate a net benefit to the public, as determined by the Board of County Commissioners, and which adequately mitigate adverse environmental impacts.

Billboard Sign - any permanently affixed sign that is erected and maintained for the purpose of advertising services, accommodation, products, or activities that are not available on the premises on which the sign is located. Size limitations for billboards are contained in the zoning code.

Biological Diversity - The variety of life and its processes, including the variety of living organisms, the genetic differences among them, and the communities and ecosystems in which they occur.

Blowout - a natural or man-made hollow or pass eroded from a sand dune.

Boat Facility Siting Zones

- ~~**Zone A** - The Banana River basin south to Mathers Bridge, the Sykes Creek/Newfound Harbor basin north to the Lambert Drive bridge; that portion of the Indian River Lagoon between the NASA Causeway and the S.R. 528 Causeway; Mullet Creek (Sections 26, 35 & 36 of Township 29, Range 38); and that portion of the following tributaries lying west of the existing railroad bridges: St. Sebastian River, Turkey Creek, Crane Creek, and the Eau Gallie River.~~

- ~~**Zone B** - The Barge Canal from the west shoreline of Merritt Island to the east shoreline of Merritt Island.~~
- ~~**Zone C** - The Port Canaveral Harbor lying east of the S.R. 401 Bridge.~~
- ~~**Zone D** - The remainder of the County not under federal jurisdiction and not included in boat facility siting zones A, B, or C.~~

Boat Slip (Wet or dry slip) - an area within a boating facility which is intended for the mooring or storage of a vessel.

Boating Facility means a facility where boats are moored, stored, or launched such as a dock, pier, marina, dry storage facility with launching capability, or a boat ramp which is contiguous to the waters of the state of Florida. ~~For the purposes of this rule, boating facility shall be~~ Boating facilities are synonymous with marine facilities.

Boating Facility Siting Plan means a county-wide or locally based siting plan for determining the preferred locations for boating facility development, such as the Brevard County Manatee Protection Plan, based on an evaluation of water quality, flushing characteristics, natural resources, manatee protection needs, and recreation and economic demands.

~~**BrevCEMP**~~ **Brevard CEMP** - Brevard County Comprehensive Emergency Management Plan; mandated by Chapter 252, Florida Statutes (State Emergency Management Act), serves to integrate and coordinate comprehensive emergency management plans and programs of the state and federal governments. This document establishes a framework through which Brevard County may prepare for, respond to, recover from, and mitigate impacts resulting from a wide variety of disasters and emergency events that could adversely affect the health, safety and/or general welfare of the visitors and citizens located in Brevard County.

Buffer - open spaces, landscaped areas, fences, walls, berms, or any combination thereof used to physically separate or screen one use of property from another so as to visually separate, ameliorate, reduce, mitigate, shield, or block the adverse impacts of noise, lights, or other nuisances.

Bulkhead - a retaining wall built along a body of water behind which fill is placed.

Building - any structure that encloses a space used for sheltering any occupancy, such as residential, business, industry, or other private or public services.

Coastal Construction Line ~~CCL~~ (CCL) - ~~Brevard County Coastal Construction Control Line; the FDEP's old Coastal Control Line (CCCL) which was recorded by the State of Florida in 1975 and~~ the line adopted by Brevard County Ordinance (Ord. 85-17) to coincide with the 1981 FDEP Coastal Construction Control Line. This line was adopted by Brevard County so that the Brevard County Coastal Setback Line (CSL) could be established.

Coastal Construction Control Line ~~CCCL~~ (CCCL) - FDEP's old 1981 Coastal Construction Control Line as recorded by the State of Florida on March 21, 1975. ~~This line is also referred to as the 1981 FDEP CCCL.~~

Coastal Setback Line ~~CSL~~ (CSL) - ~~the Brevard County Coastal Construction Setback Line;~~ a line ~~designated by Brevard County set 25 foot feet~~ landward of the established Brevard County Coastal ~~Control Construction Line (CCL or CCCL).~~

Canaveral Port Authority - a distinct entity established by a state enabling act whose governing body of five elected Commissioners is responsible for the administration, development, and operation of the seaport and its supporting uplands. The Port Authority also may issue bonds and levy property taxes; they also publish their own tariffs, building regulations, and land use controls.

Capital Budget, Annual - the first year of the Capital Improvements Program serves as the current year's capital budget.

Capital Improvement - any construction, land acquisition, equipment purchase, or rental proposal that costs \$25,000 or more and has a five (5) year or longer expected service life. Projects which may cost less than \$25,000 which are considered necessary for the implementation of any long-term improvement, including implementation of the adopted Comprehensive Plan, shall also be considered a capital improvement.

Capital Improvements Program - a five (5) year program for the construction and financing of new public facilities. ~~The Brevard County Capital Improvements Program shall be consistent with the Schedule of Improvements and Funding in the Capital Improvements and Programs Element of the Brevard County Comprehensive Plan.~~ A Capital Improvement Program may also be the capital improvement program of a governing body that provides either roadway, solid waste, potable water, sanitary sewer, parks and stormwater management services to the unincorporated area of Brevard County, such as the ~~Metropolitan Planning Organizations~~ Transportation Planning Organization's Transportation Improvement Program.

Caution Zone means an area where manatees frequently inhabit on a somewhat regular basis and motorboat operators are advised to use caution so as not to strike a manatee.

Central Springs/East Coast Regional Water Supply Plan (CSEC RWSP) - recognizes the unique local challenges and resource constraints facing the central region springs and coastal areas of the St. Johns River Water Management District. The planning region encompasses three sub-regions that include Marion and north Lake counties, Volusia County and Brevard, Indian River and Okeechobee counties. The plan is updated every 5 years and is adopted by the by the St Johns River Water Management District Governing Board.

Centralized Sewer System - any collection, treatment and disposal sewer system that is not a septic tank (i.e. package plants and public sewer systems), and requires FDEP permits as opposed to HRS permits.

Channel means a marked navigation channel, unless otherwise described or designated, and is not intended to mean an access or side channel unless otherwise designated for the purpose of regulation.

Class I Waters - waters utilized as a source of potable water supply as determined by the Florida Department of Environmental Protection and defined within Chapter 62-302, F.A.C., as amended.

Class II Waters - waters utilized for shellfish propagation and harvesting as determined by the Florida Department of Environmental Protection and defined within Chapter 62-302, F.A.C., as amended.

Class III Waters - as defined within Chapter 62-302, F.A.C., all waters within Brevard County except those designated by the Florida Department of Environmental Protection as Class I, Class II, Class III shellfish areas, Outstanding Florida Waters, or Aquatic Preserves; those which are part of a designated stormwater management system; or those that are man-made waterbodies that do not have a direct surface water connection to open water.

Coastal Floodplain - ~~the area susceptible to being inundated by waters from the Atlantic Ocean from a given storm event.~~

Coastal High Hazard Area (Zone) - the area defined by Florida Statute 163.3178(2)(h).

Coastal Zone - the area within the watershed of the Atlantic Ocean and the Indian River Lagoon system. It also includes the barrier islands, Merritt Island (a remnant barrier island) and that portion of the mainland which drains into the lagoon.

Commercial Development Node - terminology for a Neighborhood Commercial (NC) activity area (see Commercial Land Use Designations). ~~A commercial development node should not exceed one acre at each corner of an intersection of collector/arterial or collector/collector roadways~~

Commercial Land Use Designations - Land use designations which permit commercial development activities of varying intensity and service radii. These are based upon factors which consider locational standards, accessibility, potential service areas for activities, compatibility with surrounding land uses, the availability of public facilities and services, and environmental constraints. ~~These land use designations include:~~

Community Commercial (CC) - a classification providing for commercial development activities which are intended to serve several neighborhoods and sub-regional areas. These activities include an array of retail, personal services, and professional uses and are appropriately located at certain intersections of principal/minor arterial intersections. ~~Collector/arterial intersections are acceptable locations provided that the said roadways serve multiple residential areas.~~

Community Commercial (CC) – BBIA - a classification specific to the BBIA providing for commercial development activities which are intended to serve several neighborhoods and sub-regional areas.

Community Commercial Cluster - an agglomeration of Community Commercial (CC) development activities of up to 10 acres in size.

Community Park - a large natural and/or landscaped area ~~preferably with a minimum of two (2) acres provided per one thousand (1,000) individuals in a planning area.~~

Concurrency - means the necessary public facilities and services to maintain the adopted level of service standards are available when development impacts occur.

Conservation Area - an area characterized by the protection, preservation, management, or restoration of wildlife and of natural resources such as forests, soil, and water.

Conserve - to keep in a safe or sound state, to avoid wasteful or destructive use of.

Consistent - compatible with; not in conflict with.

Continuing Florida Aviation System Planning Process (CFASPP) - updates the Florida Aviation System Plan, inventories existing facilities, provides an area aviation system plan describing short-, medium-, and long-term aviation system needs for nine statewide regions.

Coordinate - to work together in a common action or effort; to meet talk, and discuss in pursuit of a shared goal.

Covenant - a contractual agreement between private parties that runs with the land, thereby restricting uses that may be made of the property.

Criteria - principles, guidelines, or standards which further describe the intent of an objective or a policy.

Critical Areas ~~means portions of waters of the State of Florida as defined by subsections 370.12(2)(f), (g), (h), (i), (j), (k), (n), and (o), F.S.~~

Critical Habitat – Designated by the U.S. Fish and Wildlife Service as an area where management is required to protect endangered and threatened species, or to prevent long-term damage to their habitat.

Crucial Habitat - Habitat that is essential to ensure long-term conservation and survival of a viable population of species. Crucial habitat may include sites for breeding, foraging, and roosting; sites that provide appropriate cover and shelter; and enough surrounding suitable habitat to allow for normal behavior and to maintain the population dynamics of a listed species. Crucial habitat may be one or more geographic areas or one distinct area depending upon the distribution, home range, size, and dispersal abilities of a species.

Cultural Resources - are those resources which are expressive forms that reflect the living dimensions of an area's heritage. May be of historical or contemporary nature and would include folk crafts or skills, dance, music, visual arts, etc.

Current Weekday Volume - determined by the Brevard County Office of Traffic Management and adjusted for seasonal fluctuations prior to April, 1990.

Data and Analysis - information accumulated and evaluated to form the basis of conclusions regarding all subjects of the comprehensive plan. It shall be considered best available, unless new research using acceptable research methodology was conducted during the planning period to generate more current information. Data and analysis do not represent goals, objectives, policies, or criteria, and unless stated otherwise, represent best available data only.

Defer - to postpone; to not grant a development order or permit until a public facility or service is available at its established minimum acceptable level of service to support the impact of the development order or permits.

Deficiency - the measured impact of a development proposal which will quantitatively exceed the existing established minimum acceptable level of service for a public facility or service.

Deficient Facilities - infrastructure operating below the adopted acceptable level of service.

Demonstrated Good Cause - good cause ~~shall be as determined by the applicable permitting official or authority to be demonstrated by the existence of special conditions and circumstances preventing timely performance by the applicant, where such special conditions and circumstances occurred during a required review and comment procedure involving a governing body or agency with jurisdiction, but were not the result of any action or inaction by the applicant. The determination of whether good cause has been demonstrated shall be by the applicable permitting official or authority.~~

Desirable Level of Service - the preferred level of service for public facilities and services that may or may not be attainable even though pursued.

Develop - to set forth, to evolve the possibilities of.

Development - the term "development" means the carrying out of any ~~construction building activity or mining operation, the renovation, rehabilitation or remodeling of any structure, the alteration of land, the making of any material change in the use or appearance of any structure or land, or the dividing of land into three or more parcels, or the establishment of flag lots or access easements.~~ The following activities or uses are considered development for purposes of this Plan:

1. A reconstruction, ~~or~~ alteration of the size, or material change in the external appearance of a structure on the land.
2. A change in the intensity of use of land, such as the increase in the number of dwelling units in a structure or on land, or a material increase in the number of businesses, manufacturing establishments, offices, or dwelling units in a structure or on land.
3. Alteration of a shore or bank of a seacoast, river, stream, lake, pond, ~~wetland~~, or canal, including any "coastal construction" as defined in s.161.021, Florida Statutes.
4. Commencement of drilling, except to obtain soil samples; mining; or excavating on a parcel of land.
5. Demolition of a structure
6. Clearing of land as an adjunct of construction.
7. Deposit of refuse, solid or liquid waste, or fill on a parcel of land.

Development Deferral Zone - includes those areas in which the issuance of development orders impacts the level of service on a deficient roadway.

Development of Regional Impact (DRI) Land Use Designation - future land use designation required for projects which meet or exceed the threshold requirements established by Chapter 380, Florida Statutes and Chapter 28-24, Florida Administrative Code.

Development Order - means any order granting, denying, granting with conditions or deferring, an application for a development permit.

Development Permit - includes any building permit, zoning permit, subdivision approval, rezoning, ~~site development plan approval~~, certification, special exception, variance, or any other official action of local government having the effect of permitting the development of land.

Development Permit, Conditional - the following constitute conditional development permits. ~~For conditional development permits, Brevard County retains authority to initiate~~

~~the appropriate administrative action, such as an administrative rezoning or permit denial or deferral, considered necessary by the Board of County Commissioners, or its designee, to alleviate or prevent deficiencies on roadway, solid waste, drainage, potable water, sanitary sewer, or park facilities or services.~~

1. Existing zoning or a rezoning.
2. Any development permit, whose measured impacts would cause a deficiency to occur to a roadway, solid waste, drainage, potable water, sanitary sewer, or park facility or service.
3. Any development permit where specific conditions, standards or criteria are required by the Comprehensive Plan or element thereof, or the Land Development Regulations.

Development Permit, Final – ~~see Land Development Regulations.~~

Development, Cultural - ~~cultural development shall mean~~ any activity or development which improves or enhances the social, educational, or cultural goals of Brevard County.

Development, Economic - ~~economic development shall mean~~ any activity or development which furthers or enhances the economic goals of Brevard County.

Direct - to regulate the activities of, to dominate and determine the course of.

Directives - principals or guidelines that provide the general philosophical outlook of Brevard County with regard to the respective elements of the Comprehensive Plan. Directives do not necessarily require specific actions for implementation. However, the level of significance given to directives is commensurate with that for the goals, objectives and policies of the Comprehensive Plan.

Distressed Roadway - a roadway segment which is operating at or above 85 percent of the maximum acceptable volume of the acceptable level of service, but which has not exceeded the acceptable level of service.

Ditch means a man-made trench that was not built for navigational purposes.

Diversify - to give variety; to balance; to engage in a variety of operations.

Dock ~~means a fixed or floating structure, including moorings, used for the purpose of berthing buoyant vessels either temporarily or indefinitely.~~ means a fixed or floating structure, including access walkways, terminal platforms, catwalks, mooring pilings, lifts, davits, and other associated water-dependent structures, used for mooring and accessing vessels.

Dredging means excavation by mechanical or other methods ~~used to remove sovereign submerged land or lands beneath Class III waters in wetlands or other surface waters, or~~

[excavation by mechanical or other methods in uplands that creates wetlands or other surface waters.](#)

Easement - an acquired interest in property owned by another, and may be for overall conservation, exterior or facade, or interior preservation.

Effective - producing the desired result.

Efficient - cost effective and not wasteful of resources.

Encourage - to stimulate, spur on, inspire, advocate, give help or patronage.

Endangered Species - Species of animals and plants ~~federally so~~ listed under the jurisdiction of the U.S. Fish and Wildlife Service, Endangered Species Act of 1973, as amended (16 U.S.C. 1531 *et seq.*); ~~or the Florida Fish and Wildlife Conservation Commission, Chapter 39 and 46, Florida Administrative Code (F.A.C), Chapter 68A-27, F.A.C.; or the Florida Department of Agricultural and Consumer Services, Preservation of Native Flora of Florida, Act (s. 581.185-187, Florida Statutes) Chapter 5B-40, F.A.C.~~ These are generally any species, subspecies, or isolated population, which is in danger of extinction or extirpation from the State of Florida, throughout all or a significant portion of its range.

Enhance - to improve, to make better (in value, desirability, attractiveness).

Ensure - to make sure, certain; to guarantee.

Environmentally Sound - not contrary to the continued viability of the natural environment or detrimental to public health, safety, and welfare.

Erosion (shoreline) means the ~~gradual and imperceptible~~ wearing away of riparian or littoral land due to natural or manmade causes. ~~Artificial erosion refers to erosion caused by man-made projects and operations. Erosion on uplands means the denudation or wearing away of the upper layers of soil, such as caused by the removal of vegetation and/or the effects of wind and water.~~

Estuarine Floodplain - the area susceptible to being inundated by waters from the Indian River Lagoon System from a given storm event.

Evaluate - to determine the significance or worth of by careful appraisal and study.

Existing Boating Facilities - ~~For the purpose of the Brevard County Manatee Protection Policies as found in the Coastal Element, existing boating facilities shall be defined as those facilities which have all active and required permits or those facilities that were in operation up to ten (10) years prior to the date of the final adoption of the Plan (01/16/03).~~

~~All existing boating facilities shall be allowed to continue with the existing use and may renovate according to permitting guidelines, provided there is no change in facility size, including no increase in the number of wet or dry slips, unless the facility meets the expansion criteria as provided in the Brevard County Manatee Protection Plan. Boating facilities are generally defined as those structures or operations where boats are moored or launched, such as a dock (excluding single-family), pier, marina, dry storage facility with launching capability, or a boat ramp, which is contiguous to the waters of the state of Florida. For the purpose of this plan, boating facility shall be synonymous with “marina facility”.~~

~~**Existing Linear Shoreline** for the purpose of the Brevard County Manatee Protection Plan, means the high water line in tidally influenced areas and the ordinary high water line along waterways that are not tidally influenced. This definition shall not apply to shoreline artificially created through dredge or fill activities (such as boat basins or canals) after January 01, 1996. Such artificially created shoreline created after January 01, 1996 shall not be considered in the calculation of linear shoreline. Artificially created shoreline that was created prior to January 01, 1996 must have received the proper permitting authorization required at the time of construction. Man-made drainage ditches (such as mosquito control, flood control ditches or any non-navigable waterway) shall not qualify as linear shoreline, regardless of their date of construction. Linear shoreline shall be calculated using survey quality aerial photographs or by accurate field survey. The calculation of linear shoreline is based upon contiguous shoreline that is owned or legally controlled by the applicant. Exception to include non-contiguous shoreline within the sphere of influence of the proposed project will be considered if the federal, state, and local permitting agencies agree that inclusion of that shoreline will not result in significant adverse impacts to manatee or manatee habitat.~~

Extremely-low-income persons – [as defined in section 420.0004, F.S.](#), means one or more natural persons or a family whose total annual household income does not exceed 30 percent of the median annual adjusted gross income for households within the state. The Florida Housing Finance Corporation may adjust this amount annually by rule to provide that in lower income counties, extremely low income may exceed 30 percent of area median income and that in higher income counties, extremely low income may be less than 30 percent of area median income.

Fair Housing Market - a market situation where there is no housing discrimination based on race, sex, marital status, religion, national origin, age, or physical handicap.

Farm - is defined in Florida Statute 823.14 ~~i.e. as~~ the land, buildings, support facilities, machinery, and other appurtenances used in the production of ~~plants and animals useful to humans~~ farm or aquaculture products.

Finding - a conclusion based upon analyses of the best available data and information regarding the relationship between the use intensity of a development order or permit

proposal and the availability of public facilities or services having established minimum acceptable levels of service, to support the proposed use intensity.

Fishery Industry Fisheries - an industry which produces, harvests, processes, or markets food and other products from ocean or brackish waters.

Floating Solar Facility means a solar facility which is located on wastewater treatment ponds, abandoned limerock mine areas, stormwater treatment ponds, reclaimed water ponds, or other water storage reservoirs as provided in section 163.32051, F.S., as amended.

Floodplains - any area susceptible to being inundated by water from any source; including areas which may or may not have a direct hydrological connection to a surface water body.

Florida Department of Environmental Protection (FDEP) - the Florida Department of Environmental Protection is the state's lead agency for environmental management and stewardship, protecting our air, water and land.

Forestry - the art, application, and practice of controlling forest establishment, composition, and growth through sound management techniques, based on the owner's management objectives. See Silviculture.

~~**G1** - Critically imperiled globally because of extreme rarity (5 or fewer occurrences or very little remaining area, i.e., <2,000 acres) or because of some factor(s) making it especially vulnerable to extinction.~~

~~**G2** - Imperiled globally because of rarity (6-20 occurrences or very little remaining area, i.e., <10,000 acres) or because of some factor(s) making it very vulnerable to extinction throughout its range.~~

General Aviation Facilities - associated airport activities, which includes terminal space, based and itinerant aircraft parking and automobile parking spaces.

~~**General Contour of the Shoreline** means a line defined as the most waterward of the outside edge of emergent aquatic vegetation, if present, or a line of Mean Low Water as defined in Chapter 177, Part II, Florida Statutes, as approximated on NOAA nautical charts. Waters lying landward of this line are to be included up to the shoreline, as defined under paragraph (14), above. Emergent aquatic vegetation shall include plants rooted in the ground that extend above the surface of the water.~~

Goal - a general statement of a desired long term end toward which programs or activities are ultimately directed; may be unmeasurable or unattainable.

Green Stormwater Infrastructure (GSI) - plants, soils systems, permeable pavement or other permeable materials that filter and absorb stormwater where it falls and reduce flows of stormwater runoff to sewer systems or into surface waters.

Growth Management - the control of the location, type, intensity and rate of growth or development, in order to maximize the efficient use of public facilities and services while protecting the values and functions of the natural systems.

Hazardous Material - any material which, because of its physical, chemical, or infectious characteristics, can pose a substantial or potential hazard to human health or safety or the environment when improperly used, treated, stored, transported, or disposed of. A hazardous material generally exhibits one of four characteristics: toxic, ignitable, corrosive, or reactive. Reactive means a material may react violently and/or produce hazardous vapors or gases when exposed to water. A hazardous material can be a liquid, a solid, or a gas, or can exist in different forms dependent on the temperature and pressure of its surroundings.

Hazardous Material Incineration Unit - an incineration unit designed for the reduction or disposal of any material listed on the EPA Hazardous Substance List.

Hazardous Materials Management System - a coordinated set of programs and policies, governmental or non-governmental, whose purpose is to encourage and ensure that hazardous materials in the community are used, transported, stored, and disposed of in a manner which protects the health and safety of citizens and the environment.

Hazardous Substance - can be used interchangeably with hazardous material.

Hazardous Waste - hazardous materials which have outlived their originally intended purpose, and are ready to be disposed of, recycled, regenerated, or otherwise treated or altered.

Heavy Industrial Land Use - land uses which involve the manufacturing of products directly from raw materials. These uses may include indoor and outdoor activities such as cement and concrete production, chemicals and fertilizer processing, lumber mills, foundries and forge works, or paint and plastics production.

High Functioning Wetlands - wetlands that score 0.66 or above as determined by the Wetlands Assessment Method established in the Countywide Wetlands Study, prepared BKL, Inc. Consulting Ecologists (September 30, 2013), adopted by the Board and incorporated herein by this reference.

Highly Permeable Soils - ~~soils listed in the Brevard County Soil Survey that have a permeability rate greater than twenty inches per hour. These soils are: Astatula (As, At), Basinger (Ba), Canaveral (Ca, Cc), Galveston (Ga), Orsino (Or), Palm Beach (Pb), Paola~~

(PfB, PfD, Ph), Pomello (Ps, Pu), Pompano (Pw), Satellite (Sa), St. Johns (Sb, Sc), St. Lucie (SfB, SfD), Tavares (Ta), Valkaria (Va), ~~Welaka (We)~~. means soils which have a permeability rate greater than 20 inches per hour as identified by the Brevard County Soil Survey, 1974, and which exist to a depth of 60 inches through tests as determined by a certified soil scientist, except for urban mixes or those soils disturbed as a result of dredging or spoils deposits.

High Risk Vulnerability Zones - those areas predicted to receive sufficient flooding to require evacuation during a Category 1-2, or Category 3-5 storm, as determined by the East Central Florida Regional Planning Council.

Historic Context - an organizational framework that groups information about related historic properties based on a theme, geographical area and period of time.

Historic District - a significant concentration, linkage, or continuity of sites, buildings, structures, or objects united historically or aesthetically by plan or physical development.

Historic Property - ~~a district, site, building, structure, or object significant in American history, architecture, engineering, archaeology, and culture. It may be of value to the Nation as a whole or important only to the community in which it is located. any prehistoric or historic district, site, building, object, or other real or personal property of historical, architectural, or archaeological value, and folklife resources. These properties or resources may include, but are not limited to, monuments, memorials, Indian habitations, ceremonial sites, abandoned settlements, sunken or abandoned ships, engineering works, treasure trove, artifacts, or other objects with intrinsic historical or archaeological value, or any part thereof, relating to the history, government, and culture of the state.~~

Historic Resource - ~~any prehistoric or historic district, site, building, structure, or object included in, or eligible for inclusion in the National Register of Historic Places; such term includes artifacts, records, and remains which are related to such a district, site, building, structure, or object. see “Historic Property”.~~

Historic Site - ~~a location of a significant event, a pre-historic or historic occupation or activity, or a building or structure, whether standing, ruined, or vanished, where the location itself possesses historical, cultural, or archaeological value regardless of the value of any existing structure. see “Historic Property”.~~

HOME - the Home Investment Partnership Program that is a partnership among federal, state and local government and the for-profit and non-profit sectors who build, own, manage, finance, and support low-income housing.

Household - ~~one or more persons related by blood, adoption, or marriage, living and cooking together as a single housekeeping unit, exclusive of servants, and may include up to two unrelated persons. Also one or more persons, not exceeding four, living and~~

~~cooking together a single housekeeping unit though not related by blood, adoption or marriage. means a person or group of persons living together in a room or group of rooms as a housing unit, but the term does not include persons boarding in or renting a portion of the dwelling.~~

OR

~~A household consists of all the people who occupy a single housing unit. A household includes the related family members and all the unrelated people, if any, such as lodgers, foster children, wards, or employees who share the housing unit. A person living alone in a housing unit, or a group of unrelated people sharing a housing unit such as partners or roomers, is also counted as a household.~~

Households with Special Needs - Households which have incomes not exceeding moderate-income and, because of particular social, economic, or health related circumstances, may have greater difficulty acquiring or maintaining affordable housing. Such households may have, for example, encountered resistance to their residing in particular communities, and may have suffered increased housing costs resulting from their unique needs and high risk of institutionalization. Persons within such households may include, but are not limited to, persons with Acquired Immune Deficiency Syndrome (AIDS) and Human Immunodeficiency Virus (HIV) disease; runaway and abandoned youth; public assistance recipients; migrant and seasonal farm workers; refugees and entrants; the elderly; and disabled adults.

Housing - buildings or other structures in which people live that provide shelter, a link to the neighborhood and community, a sense of belonging, a sense of social status, and that constitutes an investment.

Housing Stock - refers to housing supply, the housing which is available for sale or rent.

Housing Unit - a house, apartment, group of rooms, or a single room occupied or intended for occupancy as separate living quarters.

Hydrologic Basin - the region or area that supplies a particular body of water or aquifer.

Hydroperiod - a means of expressing the average timing of water retention or flows through a specified area.

Identify - to establish the identity of, location or existence of.

~~**Idle Speed** means the minimum speed that will maintain the steerageway of a motorboat.~~

~~**Idle Speed Zone** means an area where vessels may not be operated at greater than Idle Speed, as defined in 62N-22.002(2), F.A.C.~~

Impervious Surface Area - the aerial extent of any impervious surface material that prevents or resists penetration by fluids and absorption of stormwater into the ground.

Implement - to carry out, to give practical effect to and ensure of actual fulfillment by concrete measures.

Implementation Strategy - the translation of management policies into operational programs.

Improve - to make more acceptable or bring nearer to some standard.

Indigenous - occurring or living naturally in an area (native).

Indian River Lagoon - the system including the Indian River, Mosquito Lagoon, the Banana River, Sykes Creek, and Newfound Harbor. Unless specifically excluded, the Indian River Lagoon shall also include the tributaries of these waters. The terms Indian River Lagoon system and Indian River Lagoon may be used interchangeably.

Indian River Lagoon Program - refers to the combined Indian River Lagoon Surface Water Improvements and Management Plan (SWIM) and National Estuary Programs.

Indian River Lagoon System - see Indian River Lagoon.

Industrial Land Use Designations - areas in which industrial land uses of varying intensities are permitted. They are designated utilizing factors which include demonstrated future need, existing industrial development and zoning trends, land use compatibility, availability of public facilities and services and environmental constraints. Industrial land use designations include the following:

Heavy/Light Industrial – future land use designation that permits light industrial activities (such as manufacturing, assembling, fabricating and warehousing which are generally conducted indoors); heavy industrial activities (which involve the manufacturing of products directly from raw materials and include both indoor and outdoor activities); and water-related/water-dependent industrial activities.

Planned Industrial – future land use designation that permits industrial development activities possessing Planned Industrial Park (PIP) and Planned Business Park (PBP) zoning classifications. Activities occur within enclosed buildings and may include manufacturing, assembling, fabricating, warehousing and retailing as well as hotel and motel accommodations that serve the travel needs of employees or clients associated with firms within this land use designation. Marinas are also permitted within this land use designation.

Intensive Historic Resource survey - systematic, detailed inventory designed to identify precisely and completely.

Interbasin Diversion - the transport or redirection of surface water from its natural hydrologic basin to a different one.

Invasive Exotic - ~~A nonindigenous species of plants or animals that out-compete native species in a specific habitat.~~ A naturalized species of plant or animal that disrupts naturally occurring native plant or animal communities by altering structure, composition, natural processes, or habitat quality.

Isolated Floodplain - the area susceptible to being inundated by waters which are not riverine, estuarine, or coastal from a given storm event.

Isolated Wetlands - wetlands which are not directly connected to open water

Joint-Use Agreement - a cooperative arrangement between two or more jurisdictions to provide for the combined use of a particular facility or service.

Land-Water Interface - a line, determined and approved by the County, clearly identifying the separation between the terrestrial and aquatic environments using among other features, vegetation and biota. This line is determined through visual observation by trained personnel as approved by the County.

Landfill - a facility for the disposal of solid wastes; the facility does not accept liquid or hazardous waste.

Landscape Level Wetlands - wetlands that are EITHER 1) five (5) acres or larger; OR 2) located within the Landscape Level Polygon depicted on Map ~~9~~ 7 of the Conservation Element, AND the U.S. Army Corps of Engineers determines the wetland is hydrologically connected to the St. Johns River or Indian River Lagoon System. Landscape Level Wetlands analyses shall be prepared by a Recognized Knowledgeable Environmental Professional.

Level of Service Management Plan - a plan providing strategies to maintain or improve the level of service on roadways while accommodating the impacts of development.

Light Industrial Land Use - land uses involving manufacturing, assembling, fabricating and warehousing activities which are generally conducted indoors, such as that found in machine shops, bottling and canning works, boat building, and freight or trucking terminals.

Linear Shoreline ~~means the mean high water line in tidally influenced areas and the ordinary high water line along waterways that are not tidally influenced. This definition shall not apply to shorelines artificially created through dredge and fill activities (such as boat basins or canals) after October 24, 1989. Such artificially created shorelines created after October 24, 1989 must have received the proper permitting authorization required at~~

~~that time. Man-made drainage ditches (such as mosquito control ditched) shall not qualify as linear shoreline regardless of their date of creation. Linear shoreline shall be calculated using survey quality aerial photographs or by field survey.~~

Listed Species - Species of animals and plants legally protected as endangered, threatened, ~~or as species of special concern~~ or commercially exploited by federal and or state laws.

Low Impact Development or Design (LID) refers to systems and practices that use or mimic natural processes that result in the infiltration, evapotranspiration or use of stormwater to protect water quality and associated aquatic habitat. LID is used to preserve, restore and create green space using soils, vegetation, and rainwater harvest techniques. LID is an approach to land development (or re-development) that works with nature to manage stormwater as close to its source as possible. LID employs principles such as preserving and recreating natural landscape features and minimizing effective imperviousness to create functional and appealing site drainage that treat stormwater as a resource rather than a waste product.

Low Income Household ~~are those households whose incomes are between 50 to 80 percent of the area's median income.~~

Low-income persons as defined in section 420.0004, F.S., means one or more natural persons or a family, the total annual adjusted gross household income of which does not exceed 80 percent of the median annual adjusted gross income for households within the state, or 80 percent of the median annual adjusted gross income for households within the metropolitan statistical area (MSA) or, if not within an MSA, within ~~the county in which the person or family resides~~ Brevard County, whichever is greater.

Main Access Dock ~~means that walkway which connects a riparian owner's property to a terminal platform.~~

Maintain - to keep in an existing state; to support or provide for; to bear the expense of.

Maintenance Dredging means mechanical or other methods used to remove sovereign submerged land in existing channels ~~or lands beneath Class III waters~~ where navigation by vessels presently occurs. ~~For the purpose of this rule, requests to dredge previously dredged areas that have regained natural characteristics due to lack of use, lack of upkeep, or other factors or requests to change the design specification of previously dredged areas shall not be considered as maintenance dredging but shall be considered new dredging.~~

Manatee Habitat Features ~~The following manatee habitat features are to be applied in Boat Facility Planning Zone D and shall be determined using the map series and data update schedule identified in Appendix 10.~~

A. Each of the following increases the number of habitat features by 1.

- ~~1. Seagrass – 5% or more seagrass present on the proposed project site is considered significant.~~
- ~~2. Manatee Abundance – Level 1 = 10 or more manatees observed/overflight within a 5-mile radius equals 1 point. Level 2 = 25 or more manatees observed/overflight within 5-mile radius equals 2 points. If more than one survey falls within the 5-mile radius, the number of manatees observed will be counted for each survey, divided by the number of overflights and then the normalized values will be summed.~~
- ~~3. Significant Manatee Mortality – Level 1 = the number of watercraft mortality within a 5-mile radius, divided by the total number of watercraft mortalities in Brevard County. A value greater than 0.05 is considered significant and is equal to 1 point. Level 2 = the number of watercraft mortalities within a 5-mile radius, divided by the total watercraft mortalities in Brevard in the last 5 years. A value greater than 0.10 is significant and is equal to 2 points.~~
- ~~4. The proposed site is in a Class II Waterbody, Outstanding Florida Waterway (OFW), or an Aquatic Preserve~~

B. Each of the following reduces the number of habitat features by 1.

- ~~1. The proposed site is presently located in a year-round “Slow Speed” or “Idle speed” manatee zone as authorized by the Florida Manatee Sanctuary Act Chapter 62N-22 F.A.C., other Federal designation or local ordinance.~~
- ~~2. The proposed site is within 3 miles of Sebastian Inlet.~~

Manatee Protection Plan means a comprehensive plan developed adopted and implemented by a county, local government, or port authority (pursuant to Chapter 315 F.S.), and approved by the Department of Environmental protection for the purpose of reducing manatee mortalities, protecting manatee habitat, promoting boating safety, and increasing public awareness. means the comprehensive long-term management plan approved by the Brevard County Board of County Commissioners on January 16, 2003, as amended, which balances resource protection, water resources uses, boating safety, and the protection of the Florida manatee in Brevard County through identification and protection of manatee habitat, boat facility siting and design standards, manatee protection boat speed zones, development of manatee awareness, educational materials and workshops, and recommendations for land acquisition, law enforcement, and intergovernmental coordination.

Marina (general) means all boating facilities with ~~2-3~~ three (3) or more wet and/or dry slips ~~(consistent with current County definition)~~. A marina is a facility or structure, which provides mooring, docking, anchorage, fueling, repairs, launching, or other related services for watercraft. Private boat docks associated with single family lots are exempt from this category.

- 1. Residential Marina** - Community docks exclusively serving subdivisions, condominiums, duplexes, or other multi-family

developments. No fueling or repair facilities ~~shall be~~ are associated with these marinas.

2. **Commercial/Recreational Marina** – Public or private facilities which provide dockage and other related amenities not exclusively associated with a subdivision, condominium, duplex, or other multi-family development.
3. **Commercial/Industrial Marina** - Facilities serving largely commercial interests, including commercial boat building, ship repairs or construction, and commercial seafood harvesting and processing.

Market - includes local, state, regional, national, and international buyers.

Maximize - to increase to the greatest quantity or extent possible.

Maximum Acceptable Volume - the greatest number of vehicles a roadway segment can carry given the level of service standard established for that segment. The traffic volume equivalent to a specific level of service standard is influenced by several roadway design and operation factors that effect average travel speed, such as traffic signal spacing, number of lanes, area type, peak hour traffic levels, and roadway type.

~~**Maximum 25MPH Speed Zone** means a controlled area within which a boat's speed made good over the bottom measured in statute miles, shall not exceed 25 miles per hour. Although it is the intention of the Department to allow those vessels capable of attaining a planing configuration at 25 MPH to do so, this speed limit shall not be construed as authorizing any vessel to travel an unsafe speed, in violation of 33 U.S.C. s. 2006, as adopted pursuant to subsection 327.33(3), F.S., by reason of:~~

- ~~a) An elevated bow which restricts visibility, and/or~~
- ~~b) An excessive wake which unreasonably or unnecessarily endangers other vessels or natural resources of the state.~~

~~**Maximum 30 MPH Speed Zone** means a controlled area within which a boat's speed made good over the bottom measured in statute miles, shall not exceed 30 miles per hour. Although it is the intention of the Department to allow those vessels capable of attaining a planing configuration at 30 MPH to do so, this speed limit shall not be construed as authorizing any vessel to travel an unsafe speed, in violation of 33 U.S.C. s. 2006, as adopted pursuant to subsection 327.33(3), F.S., by reason of:~~

- ~~a) An elevated bow which restricts visibility, and/or~~
- ~~b) An excessive wake which unreasonably or unnecessarily endangers other vessels or natural resources of the state.~~

~~**Maximum 35 MPH Speed Zone** means a controlled area within which a boat's speed made good over the bottom measured in statute miles, shall not exceed 35 miles per hour.~~

May = To have the permission to.

Mean High Water Line means the plane or local elevation of mean high water or high tides with the shore. Mean high water is the average height of the high waters over an approximate 19 year period (~~Ch. s.~~ 177.27, F.S.)

Merritt Island Redevelopment District means the area on Merritt Island bounded by Merritt Avenue to the north, Newfound Harbor to the east, Fortenberry Avenue to the south, and the Indian River Lagoon to the west. Needs updating

Miles means statute miles.

Mini-Parks - small areas intended primarily for the use of children up to the early elementary grades in high-density areas.

Minimize - to reduce to the least quantity possible.

Mining - the act or process of removing minerals or other resources from the land including mining and smelting operations, borrow pits, and commercial borrow pits ~~as defined within the Code of Brevard County.~~

Mitigation - methods used to alleviate or lessen the impact of development.

Mobile Source Emissions - a moving source of pollution such as an automobile.

Moderate Income Household ~~– are those households whose incomes are no greater than 120 percent and no less than 80 percent of the area’s median income.~~

Moderate-income persons – as defined in section 420.0004, F.S., means one or more natural persons or a family, the total annual adjusted gross household income of which is less than 120 percent of the median annual adjusted gross income for households within the state, or 120 percent of the median annual adjusted gross income for households within the metropolitan statistical area (MSA) or, if not within an MSA, within ~~the county in which the person or family resides~~ Brevard County, whichever is greater.

Mooring - a place or structure to which a vessel or aircraft can be moored.

Morphological - associated with the study of form and its development, including the study of cell structure, tissue structure, and external anatomy.

Mosquito Impoundment - a body of water confined by a dam, dike, floodgate or other barrier for the purpose of controlling the reproduction of salt marsh mosquitoes.

Motorboats Prohibited Zone means an area in which it is posted or it is apparent that because of the density of manatees or the condition of the area, motorboat activity shall be hazardous to the manatees and shall be prohibited.

Multi-Modal Transportation System - a network of transportation infrastructure that supports multiple modes of travel, including automobiles, trucks, transit, walking, and biking.

Native Vegetation - plant species that naturally occur in and are indigenous to a specified geographic area.

Natural Resources - materials that occur in nature and are essential or useful to humans, such as water, air, land, forests, fish and wildlife, topsoil, and minerals.

Natural System - the complex network of natural resources in which no resource is capable of functioning independently of the other resources in the network.

Natural Water Body - occurring normally; a water system occurring in conformity with the ordinary course of nature; not originally created through man's activities, not artificial. May include those normally occurring water bodies which have been dredged or channelized.

Neighborhood Commercial (NC) - a future land use designation providing for low impact commercial development nodes serving the needs of the immediate residential area. These activities include convenience stores and personal service establishments and are appropriately located at intersections of collector/arterial or collector/collector roadways.

Neighborhood Commercial (NC) – BBIA - [a future land use designation specific to the BBIA providing for low impact commercial development nodes serving the needs of the immediate residential area.](#)

Neighborhood Parks - designed to serve both active and passive short-term activities. Typically these parks average five (5) to fifteen (15) acres in size, with a minimum of two (2) acres of park land for every one thousand (1,000) people served in a planning area.

New Town Overlay - development standards set forth in the Comprehensive Plan for large scale mixed use projects which are at least 1,500 acres in size.

No Entry Zone means a limited area of critical importance as a safe haven for manatees to rest, feed, reproduce, give birth, nurse, or otherwise habituate undisturbed by human activity. No vessel of any kind, whether power-driven or non-motorized, as referenced in Section 1(b), Article VII, of the Florida Constitution, including every description of watercraft, barge, and airboat, shall be permitted within the designated area. No other vessel or floatation device, including but not limited to a seaplane, sailboard, surfboard, raft, or any other water toy or other like object intended for or capable of use as a means of

~~transportation of the water, shall be permitted within the designated area, nor shall other human activities including but not limited to diving, snorkeling, swimming, fishing (except by pole from an adjacent bank or bridge), and the introduction by persons of food or other objects, that involves disturbance of these waters or the manatees so inhabiting them, be permitted within such a designated area, except as provided under 62N-22.003(5), F.A.C.~~

Nonfunctional Wetland - a nonfunctional wetland is a wetland which has a water regime that has been permanently altered, either artificially or naturally, in a manner to preclude the area from maintaining surface water or hydroperiodicity necessary to sustain wetland function. This does not apply to wetlands that have had their water regime illegally altered.

Non-point Source - stormwater runoff which is not discharged through a pipe or other identified, specific conveyance mechanism.

Noxious Species - ~~undesirable plant species, including, but not limited to, plant species listed by the state that have a negative impact on endangered, threatened, or commercially exploited plant species; are naturalized plants that disrupt naturally occurring native plant communities; or pose a serious threat to agriculture. Noxious species include, but are not limited to, *Schinus terebinthifolius* (Brazilian Pepper); *Malaleuca quinquenervia* (Malaleuca, Cajeput Tree); and *Casuarina spp.* (Australian Pine); *Eucalyptus spp.* (Eucalyptus); and *Enterolobium contortisiliquum* (Ear tree).~~

Object - a construction that is primarily artistic in nature or is relatively small in scale and simply constructed. Although it may be, by nature or design, movable, an object is associated with a specific setting or environment, such as statuary in a designed landscape.

Objective - a statement that is more specific than a goal and identifies the steps necessary for the satisfactory pursuit of a goal; normally measurable and attainable.

Obtain - to gain or attain usually by planned action or effort.

Offshore Emergent Vegetation ~~--- aquatic or marine plants whose canopy continuously or frequently extends above water level.~~

One to One Hundred (1:100) ~~means one powerboat slip for every one hundred feet of contiguous linear shoreline that is owned or controlled by the applicant. Exceptions include non-contiguous shoreline within the sphere of influence of the proposed project will be considered by the Department if it can be demonstrated that inclusion of that shoreline will not result in significant adverse impacts to manatees or manatee habitat. For the purpose of calculating powerboat slips, linear shoreline footage will be rounded up to the nearest increment of 100.~~

Onsite Sewage Treatment and Disposal System (OSTDS) - any domestic sewage treatment and disposal facility, as defined by Florida Administrative Code Section 10D-6.42(29), including standard subsurface systems, gray-water systems, laundry wastewater systems, alternative systems or experimental systems, installed or proposed to be installed on land of the owner or on the land to which the owner or owners have the legal right to install a system: a system that contains a standard subsurface, filled, or mound drainfield system; an aerobic treatment unit; a graywater system tank; a laundry wastewater system tank; a septic tank; a grease interceptor; a pump tank; a solids or effluent pump; a waterless, incinerating, or organic waste-composting toilet; or a sanitary pit privy that is installed or proposed to be installed beyond the building sewer on land of the owner or on other land to which the owner has the legal right to install a system. The term includes any item placed within, or intended to be used as a part of or in conjunction with, the system. This term does not include package sewage treatment facilities and other treatment works regulated under chapter 403, F.S.

Open Space - lands and water not covered by structures including agriculture, which are suitable for passive recreation or conservation use or are in agricultural use.

Open Space System - a continuous or near-continuous network of open space areas within the pattern of development, including both public and private lands, which provide for passive recreation, conservation, and visual relief from expanses of development.

Ordinary High Water Line means the boundary between ~~uplands and submerged lands beneath non-tidal navigable natural water bodies~~ sovereign submerged lands and the adjacent uplands along nontidal waterbodies (Section 18-2.003, F.A.C.).

Outstanding Florida Waters - those water bodies afforded special protection and described within ~~Chapter 62-303, F.A.C., Chapter 62-302, F.A.C.,~~ as amended.

Overcrowded Housing - are those housing units which contain more than 1.00 person per room.

Overriding public benefit means the result of a development action by a private property owner that substantially preserves, restores, or enhances those natural functions which define areas of critical concern, environmentally sensitive areas, shorelines, or water bodies identified by the Comprehensive Plan, the Natural Resources Management Department, or state or federal agencies. Overriding public benefits include, but are not limited to, proposals which preserve, restore, or enhance floodplain, wetland, shoreline, or prime aquifer recharge functions and provide for the dedication of associated lands to the County or other acceptable public entity or agency.

Package Treatment Plant - a sewage treatment facility that is prefabricated off-site and assembled on-site.

Parallel Roadways - a roadway or group of roadways of a lower classification that provide alternate routes for a primary roadway, and which serve similar origin and destination points.

Passive Recreation - recreation uses where very minimum alteration of vegetation, topography or other native feature is necessary, for the enjoyment of the site amenities. Activities which are considered passive include, but are not limited to, hiking, bicycling, nature observation, camping, non-motorized boating, rowing, swimming, picnicking, archaeological or historic preservation.

Pedestrian Way - a transportation facility designed for use by pedestrians which may be used by other forms of non-motorized transportation.

Percent (%) Seagrass Coverage Seagrass coverage shall be determined on a project site during the months of May through October. The percent coverage of seagrass is determined by counting short shoots in a one square meter (1m²) plot frame that has been evenly subdivided into one hundred square cells. The plot is placed every five meters (5m) along a minimum of three (3) transect lines perpendicular to the shoreline and extending to the end of the project site. The transect lines are to be evenly spaced along the project site shoreline with one transect located at the middle of the site and one at each end of the project site. Transects shall be no greater than fifty meters (50m) apart. If the project site is greater than one hundred meters (100m) in width, additional transects shall be added at a rate of one for every fifty meters (50m) of shoreline. If ten of the sample plot frames contain ten percent (10%) or more seagrass, then the final coverage for the site is greater than or equal to ten percent (10%). The project site is defined as that area within which boats will be docked. If the project site and the shoreline are not contiguous then the first plot frame shall be placed at the intersection of the project site and the transect line.

Person - any corporation, individual, partnership, association, or other entity.

Planing means riding on or near the water's surface as a result of the hydrodynamic forces on a vessel's hull, sponsons, foils or other surfaces. A vessel is considered "on plane" when it is being operated at or above the speed necessary to keep the vessel planing.

Planned Industrial Park Land Use Designation - future land use designation intended for the location of light, clean industrial land uses in "clusters". These uses may include indoor activities such as manufacturing, assembling, fabricating, warehousing and retailing. Hotel and motel accommodations that serve the travel needs of employees for clients associated with firms within the planned industrial parks would also be appropriate. Marinas could also be considered for location within this land use designation.

Planned Unit Development - a development, usually phased and of a large scale, which provides a mixture of land uses and densities, incorporates open space through the clustering of land uses, and permits flexibility in the development design.

Point Source - a source, such as a pipe, from which stormwater or wastewater is discharged.

Policy - a statement that is more detailed than an objective and provides guidelines for specific actions which will satisfy particular objectives.

Population - The total number of people inhabiting a specified area or the total number of inhabitants of a particular race, class, or group in a specified area. For biological purposes, the definition of population is a collection of individuals belonging to the same species and living in the same area.

Powerboat ~~Any vessel which is primarily propelled or powered by an internal combustion engine and which is used or is capable of being used as a means of navigation or transportation on water. Sailboats with auxiliary engines are not considered powerboats for the purpose of this plan. For the purpose of this plan powerboat and motorboat are synonymous.~~

Private Residential Single-family Dock ~~means a dock, which is used for private, recreational, or leisure purposes for a single family residence, cottage, or other such single dwelling unit.~~

Preserve - to keep intact.

Prime Farmlands - those lands which, due to the combination of physical and chemical conditions, consistently produce a high level of output with minimal fertilizer, labor, and energy requirements.

Private Conservation - [a future land use designation intended to accommodate privately-held conservation areas with significant environmental features.](#)

Private Conservation – BBIA - [a future land use designation specific to the BBIA intended to accommodate privately-held conservation areas with significant environmental features.](#)

Private Wastewater Treatment Plant - a wastewater treatment plant of small capacity, usually between five thousand and one million gallons per day. Private treatment plants are those facilities that provide wastewater services to a localized community because of the absence of a publicly owned facility. These may be purchased as a package from a vendor and assembled from prefabricated components on the site. Private wastewater

treatment plants with capacities of fewer than one hundred thousand gallons per day may be purchased pre-assembled.

Privatization - the transfer of public sector services and responsibilities to the private sector.

Promote - to contribute to the growth or prosperity of; to help bring into being; to present for public acceptance.

Protect - to shield from injury or destruction.

Provide - to supply what is needed for sustenance or support; to supply for use.

Public Access - the ability of the public to physically reach, enter or use public sites, facilities and activities and shores.

Public Conservation - a future land use designation intended to accommodate conservation areas and facilities that are managed by federal, state and local governments. ~~Residential uses to accommodate park rangers or other authorized personnel to manage or protect conservation lands are permitted at a maximum density not to exceed 1 dwelling unit per 50 acres.~~

Public Conservation – BBIA - [a future land use designation specific to the BBIA intended to accommodate conservation areas and facilities that are managed by federal, state and local governments.](#)

Public Facilities - transportation, sewer, solid waste, drainage, potable water, fire and police protection, emergency medical, educational, parks and recreation, and public health systems and facilities.

Public Facilities Land Use Designation - future land use designation which permits activities and improvements which relate to government-managed transportation, sanitary sewer, potable water, solid waste, drainage, conservation, education, government service systems and other utilities such as gas, electric, telephone and cable.

Public Facilities – BBIA Land Use Designation - [future land use designation specific to the BBIA which permits activities and improvements which relate to government-managed transportation, sanitary sewer, potable water, solid waste, drainage, conservation, education, government service systems and other utilities such as gas, electric, telephone and cable.](#)

Public Interest means demonstrable environmental, social, and economic benefits which would accrue to the public at large as a result of a proposed action, and which would clearly exceed all demonstrable environmental, social, and economic costs of the

proposed action. ~~In determining the public interest in a request for use, sale, lease, or transfer of interest in sovereignty lands or severance of materials from sovereignty lands, the board shall consider the ultimate project and purpose to be served by said use, sale, lease, or transfer of lands or materials.~~

Public Navigation Project means a project primarily for the purpose of navigation which is authorized and funded, by the United States Congress or by port authorities as defined in Section 315.02(2), F.S.

Public Services - the programs and employees determined necessary by local government to provide adequate operation and maintenance of public systems and facilities.

Public Utilities means those services, provided by persons requested by the Public Service Commission, or which are provided by rural cooperatives, municipalities, or other governmental agencies, including electricity, telephone, public water and wastewater services, and structures necessary for the provision of these services.

Pursue - to find or employ measures to obtain or accomplish.

Recognized Knowledgeable Environmental Professional - XXX

Reconnaissance Survey - a cursory inspection of an area, most useful for characterizing its historic or other resources in general and for developing a basis for deciding how to organize and orient more detailed historic or other resource survey efforts.

Recreation - the pursuit of leisure time activities occurring in an indoor or outdoor setting.

Recreation~~at~~ Land Use Designation - land use designation which permits public recreation activities.

Recreation – BBIA Land Use Designation - land use designation specific to the BBIA which permits public recreation activities.

Recreational Vehicle Parks - activities intended to serve the needs of tourists and seasonal ~~(up to six months)~~ residents and provide lodging for visitors with recreational vehicles, travel trailers, and camping equipment as well as supportive facilities such as laundries, bathing facilities, and recreation areas. ~~Activities are located in Community Commercial (CC) land use designations. Densities for Recreational Vehicle Parks shall not exceed 10 units per acre.~~

OR

means a place set aside and offered by a person, for either direct or indirect remuneration of the owner, lessor, or operator of such place, for the parking, accommodation, or rental

of five or more recreational vehicles or tents; and the term also includes buildings and sites set aside for group camping and similar recreational facilities.

Recycling - the reuse of materials and/or wastes.

~~**Redevelopment** – activities or projects in an area to eliminate and prevent the development or spread of slums and blight, or to provide affordable housing, whether for rent or sale, to low and moderate income households; or to generate renewed economic activity and development.~~

means undertakings, activities, or projects of a county, municipality, or community redevelopment agency in a community redevelopment area for the elimination and prevention of the development or spread of slums and blight, or for the reduction or prevention of crime, or for the provision of affordable housing, whether for rent or for sale, to residents of low or moderate income, including the elderly, and may include slum clearance and redevelopment in a community redevelopment area or rehabilitation and revitalization of coastal resort and tourist areas that are deteriorating and economically distressed, or rehabilitation or conservation in a community redevelopment area, or any combination or part thereof, in accordance with a community redevelopment plan and may include the preparation of such a plan.

~~**Regional Park** - ideally, there should be a minimum of twenty (20) acres per one thousand (1,000) individuals or a minimum of one park per County wide area. The regional park is usually the largest of all parks and typically serves an area encompassing one county or region of adjacent counties, depending on population concentrations of the counties, size, and location generally resource-oriented and designed to blend highly specialized recreational facilities with the natural environment.~~

Regulatory Discharge - discharges of water from canals in order to regulate the water level of lands within the drainage basin of the canal.

Rehabilitation - the process of returning a property to a state of utility, through repair or alteration, which makes possible an efficient contemporary use while preserving those portions and features of the property which are significant to its historic, architectural, and cultural values.

~~**Reliever Aviation Facilities** – general aviation airports designated by the Federal Aviation Administration as alternatives to busy commercial service airports for business and cargo aircraft traffic.~~

Relocation Housing - those dwellings made available to households displaced by public programs, provided that such dwellings are sound, safe and sanitary and within the financial means of the households displaced.

Resident - a person who makes his/her home in a particular place, may be of permanent or temporary status and would include both existing and future residents and special populations.

Residential Land Use Designations - areas designated on the Future Land Use Map for use in providing housing including single-family, multi-family, and mobile home dwelling units. Residential land use designations stipulate varying density allowances which are based upon various factors, including the availability of public facilities and services, compatibility with surrounding land uses, and environmental constraints. These land use classifications are defined as follows:

Residential 30 Directive - a classification providing for a maximum residential density of thirty (30) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 15 - a classification providing for a maximum residential density of fifteen (15) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 15 – BBIA - [a classification specific to the BBIA providing for a maximum residential density of fifteen \(15\) dwelling units per acre, unless otherwise established by the Comprehensive Plan.](#)

Residential 12 Directive – a classification providing for a maximum residential density of twelve (12) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 10 – a classification providing for a maximum residential density of ten (10) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 8 Directive – a classification providing for a maximum residential density of eight (8) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 8 Directive – BBIA – [a classification specific to the BBIA providing for a maximum residential density of eight \(8\) dwelling units per acre, unless otherwise established by the Comprehensive Plan.](#)

Residential 6 - a classification providing for a maximum residential density of six (6) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 6 – BBIA - [a classification specific to the BBIA providing for a maximum residential density of six \(6\) dwelling units per acre, unless otherwise established by the Comprehensive Plan.](#)

Residential 6 Directive - a classification providing for a maximum residential density of six (6) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 6 Directive – BBIA - [a classification specific to the BBIA providing for a maximum residential density of six \(6\) dwelling units per acre, unless otherwise established by the Comprehensive Plan.](#)

Residential 5 Directive – a classification providing for a maximum residential density of five (5) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 4 - a classification providing for a maximum residential density of four (4) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 4 – BBIA - a classification specific to the BBIA providing for a maximum residential density of four (4) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 4 Directive - a classification providing for a maximum residential density of four (4) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 4 Directive – BBIA - a classification specific to the BBIA providing for a maximum residential density of four (4) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 3 Directive – a classification providing for a maximum residential density of three (3) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 2 - a classification providing for a maximum residential density of two (2) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 2 – BBIA - a classification specific to the BBIA providing for a maximum residential density of two (2) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 2 Directive - a classification providing for a maximum residential density of two (2) dwelling units per acre, unless otherwise established by the Comprehensive Plan.

Residential 1 - a classification providing for a maximum residential density of one (1) dwelling unit per acre, unless otherwise established by the Comprehensive Plan.

Residential 1 – BBIA - a classification specific to the BBIA providing for a maximum residential density of one (1) dwelling unit per acre, unless otherwise established by the Comprehensive Plan.

Residential 1:2.5 - a classification providing for a maximum residential density of one (1) dwelling unit per two and one-half (2.5) acres, unless otherwise established by the Comprehensive Plan.

Resiliency facility means a facility owned and operated by a public utility for the purposes of assembling, creating, holding, securing, or deploying natural gas reserves for temporary use during a system outage or natural disaster, per section 163.3210, F.S., as amended.

Resource Recovery - the process of obtaining materials or energy from wastes; recycling.

Retention (surface water) - a drainage technique that retards or detains runoff or discharge to enhance groundwater recharge and reduce erosion and surface water

pollution, such as a retention basin, parking lot storage, porous pavement, dry well, or any combination thereof.

Reverter Clause - a clause in a deed which stipulates that unless certain conditions are followed, ownership of the property involved will return to the conveyor or to a designated third party.

Rights of Boaters, Fishermen, and Waterskiers (as they apply under 370.12(2)(k), F.S.) means that boaters, fisherpersons, and waterskiers have the right to use the waters of the State of Florida for recreational or commercial purposes in a manner consistent with all applicable federal, state, and local laws and regulations. Such laws and regulations include, but are not limited to, those governing the operation and safety of vessels on the water to promote public safety, environmental/natural resource protection, and/or responsible use of the waters of the State.

Riverine Floodplain - the area susceptible to being inundated by waters from the St. Johns River, freshwater Lakes, and freshwater tributaries to the Indian River Lagoon System from a given storm event.

Roadway Network - the vehicular and pedestrian traffic circulation system including roads, bicycle paths and lanes, sidewalks, and traffic control devices.

Runoff (surface runoff) - (aka surface runoff) the portion of precipitation or irrigation on an area that flows across the ground surface as sheet or stream flow to natural or manmade catchment basins without returning to the atmosphere nor infiltrating the soil to recharge groundwater.

S1 - Critically imperiled in state because of extreme rarity (5 or fewer occurrences or very little remaining area) or because of some factor(s) making it especially vulnerable to extinction.

S2 - Imperiled in state because of rarity (6-20 occurrences or little remaining area) or because of some factor(s) making it very vulnerable to extinction throughout its range.

Schedule of Improvements and Funding - that schedule prioritizing capital facilities and services adopted as part of the Capital Improvements and Programs element of the Brevard County Comprehensive Plan.

Seagrass Coverage (%) - Seagrass coverage shall be determined on a project site during the months of May through October. The percent coverage of seagrass is determined by counting short shoots in a one square meter (1m²) plot frame that has been evenly subdivided into one hundred square cells. The plot is placed every five meters (5m) along a minimum of three (3) transect lines perpendicular to the shoreline and extending to the end of the project site. The transect lines are to be evenly spaced along the project site

~~shoreline with one transect located at the middle of the site and one at each end of the project site. Transects shall be no greater than fifty meters (50m) apart. If the project site is greater than one hundred meters (100m) in width, additional transects shall be added at a rate of one for every fifty meters (50m) of shoreline. If ten of the sample plot frames contain ten percent (10%) or more seagrass, then the final coverage for the site is greater than or equal to ten percent (10%). The project site is defined as that area within which boats will be docked. If the project site and the shoreline are not contiguous then the first plot frame shall be placed at the intersection of the project site and the transect line.~~

Seawall means a vertical structure built along a portion of a coast, retaining earth against its landward face and designed to prevent erosion and other damage by wave action; means a manmade wall or encroachment, except riprap, which is made to break the force of waves and to protect the shore from erosion.

Setback - the distance between development, activity, and/or a structure and any a lot line, water line, or control line.

Sewerage system means pipelines or conduits, pumping stations, and force mains and all other structures, devices, appurtenances, and facilities used for collecting or conducting wastes to an ultimate point for treatment or disposal.

Shall - expresses a command, must express what is mandatory, to be done at all times without deviation.

Shelter Space - facilities usable for the purpose of providing safe sheltering for “at risk” population. Public shelters must be able to provide protection from surge inundation, flooding and high winds. Shelter space is considered to ~~be~~ include both public and private facilities. Public shelters are identified by two categories; ~~;~~ general population and special needs. Private shelters consist of structures privately owned.

Shoreline means the point where the water meets the land at any point in time.

Shoreline Protection Buffer ~~- a setback established from the mean or ordinary high water line or safe upland line whichever the applicant chooses. Within the shoreline protection buffer, passive recreation, hunting, fish and wildlife management open space, nature trails and limited amounts and types of shoreline access facilities shall be allowed. The amounts and types of development allowed within the shoreline protection buffer and other development restrictions are found in Conservation Element Policies 3.3, 3.4, and 3.5.~~

Short Shoot ~~- The area between the rhizome (root) and the blade of a seagrass.~~

Should - expresses obligation; mandatory action necessary unless it can be clearly demonstrated that:

- a. Strict application will be contrary to the public interest;
- b. The public values being protected are insignificant and strict application will result in an excessive hardship to the project;
- c. Strict application will place an excessive hardship on the project, and an alternative action is available which is equal to or superior than the original requirements in reaching the policy's objective, ~~and; or;~~
- d. The activity is not financially feasible for the local government.

Significant Adverse Impacts ~~means that within the sphere of influence of a proposed boating facility, death or injury to manatees or destruction of manatee habitat can be reasonably expected to occur as a result of the construction, expansion, or increase in powerboat densities and activities associated with boating facility.~~

Significant Manatee Habitat Features ~~- each of the following five habitat features is considered significant as described:~~

1. ~~Seagrass - 5% or more seagrass present on the proposed project site is considered significant.~~
2. ~~Manatee Abundance - five (5) or more observations/overflight within a 5 mile radius of the site. If more than one survey falls within the 5-mile radius, the number of manatees observed will be counted for each survey, divided by the number of overflights and then the normalized values will be summed.~~
3. ~~Significant Manatee Mortality - the number of watercraft mortality within a 5 mile radius, divided by the total number of watercraft mortalities in Brevard County, A value of 0.03 or larger is considered significant.~~
4. ~~Manatee Freshwater Source/Calving/Cavorting/Feeding/Resting Area is within a 1/2 mile of the proposed site.~~
5. ~~The proposed site is in a Class II Waterbody, Outstanding Florida Waterway (OFW), or an Aquatic Preserve.~~

Silviculture ~~- the art, application, and practice of controlling forest establishment, composition, and growth through sound management techniques, based on the owners management objectives. See Forestry: the art of producing and tending forest stands, or the application of the knowledge of silvics, the branch of forestry that provides the scientific basis for the cultural treatment of forest stands, or the bringing together of biological and economic concepts to prescribe and apply treatments to help reach land management objectives.~~

Slip, Wet Slip, or Dry Slip means an area within a boating facility which is intended for the mooring, storage, or launching of a vessel.

Slow Speed means the speed at which a vessel proceeds when it is fully off plane and completely settled into the water. ~~Vessels shall not be operated a speed that creates an excessive wake or other hazardous condition, which is unreasonably or unnecessarily, endangers other vessels under the existing circumstances. This requiring level of~~

protection for the safety of vessels and vessel operators is also intended to provide adequate protection for manatees and is therefore adopted because of its familiarity to vessel operators. Due to the different speeds at which vessels of different sizes and configurations may travel while in compliance with this definition, there is no specific numerical speed assigned to Slow Speed.

A vessel is not proceeding at Slow Speed if it is:

- 1.—On a plane;
- 2.—in the process of coming off plane and settling into the water or coming up onto plane;
- 3.—creating an excessive wake or other hazardous condition which unreasonably or unnecessarily endangers other vessels.

A vessel is proceeding at Slow Speed if it is fully off plane and completely settled into the water and not creating an excessive wake or other hazardous condition which unreasonably or unnecessarily endangers other vessels

Slow Speed Zone means an area where vessels may not be operated at greater than Slow Speed, as defined above and in 62N-22.002(7), F.A.C.

Solar Facility means a production facility for electric power that uses photovoltaic modules to convert solar energy to electricity that may be stored on site, delivered to a transmission system, and consumed primarily offsite; consists principally of photovoltaic modules, a mounting or racking system, power inverters, transformers, collection systems, battery systems, fire suppression equipment, and associated components; and may include accessory administration or maintenance buildings, electric transmission lines, substations, energy storage equipment, and related accessory uses and structures, as defined in section 163.3205, F.S., as amended.

Solid Waste - sludge from a waste treatment works, water supply treatment plant, or air pollution control facility; or, garbage, rubbish, refuse, derelict vessels, junk vehicles, and other discarded material, including solid, liquid, semisolid, and contained gaseous material resulting from domestic, industrial, commercial, mining, agricultural, or governmental operations.

Source Reduction - the practice of reducing the generation of waste at the source of production. Potential source reduction methods include redesign of processes to minimize waste production and the use of safer substitute materials in manufacturing process.

Sovereignty Lands means those lands including, but not limited to, tidal lands, islands, sandbars, shallow banks, and lands waterward of the ordinary or mean high water line, to which the State of Florida acquired title on March 3, 1845, by virtue of statehood, and of which it has not since divested its title interest. For the purposes of this rule sovereignty lands shall include all submerged lands within the boundaries of the preserve, title to which is held by the Board.

Sovereignty submerged lands means those lands including but not limited to, tidal lands, islands, sand bars, shallow banks, and lands waterward of the ordinary or mean high water line, beneath navigable fresh water or beneath tidally-influenced waters, to which the State of Florida acquired title on March 3, 1845, by virtue of statehood, and which have not been heretofore conveyed or alienated, and all submerged lands to which title is held by the Board of Trustees of the Florida Internal Improvement Trust Fund. Also referred to as sovereign submerged lands.

Special Populations - a subset of the resident population which includes those persons with special housing needs such as the elderly, single parent families, handicapped, transients, and family-deprived.

Special Use Parks - there are parks and recreational facilities which do not conform to existent standards and have special uses including recreational vehicle parks, nature trails, golf courses, conservation areas, airport parks and wildlife sanctuaries.

Specialized Incineration Unit - an incineration unit designed for the reduction or disposal of material that poses a threat to the environment when it is left untreated (e.g., bio-hazardous material).

Species - a group of individuals that potentially breed among themselves and do not breed with other groups (biological definition) or a group of individuals that are morphologically, physiologically, or biochemically distinct from other groups in some important characteristic (morphological definition of species).

~~**Species of Special Concern**—Species of animals listed under the jurisdiction of the Florida Fish, Game and Wildlife Conservation Commission, Chapters 39 and 46 F.A.C. These are generally any species, subspecies, or isolated population that is likely to become a threatened species, or a species that meets certain criteria for threatened status but where conclusive data is limited or lacking.~~

~~**Sphere of Influence** means those waters where powerboats from a boating facility are reasonably expected to operate.~~

Spoil Islands - dirt, rock, or waste material that has been removed from its prior location, often the bottoms of waterways, and deposited as emergent mounds.

St. Johns River Water Management District (SJRWMD) - an environmental regulatory agency of the state of Florida whose work is focused on ensuring a long-term supply of drinking water, and to protect and restore the health of water bodies in the district's 18 counties in northeast and east-central Florida. While the district works closely with utilities on water supply issues, the district is not a water supplier. SJRWMD was established in

1972 by the state Legislature through passage of the Water Resources Act (Chapter 373, Florida Statutes, as it may be amended from time to time).

Standard - a rule set up and established by authority for the measure of quantity, weight, extent, value or quality; a criterion on which a judgment or decision may be based.

Strive - to endeavor; to devote serious effort or energy.

Structure - anything constructed or erected, the use of which requires rigid location on the ground or attachment to something having a permanent location on the ground.

~~Substandard Housing Suitable for Rehabilitation~~ - ~~a housing unit which is suitable for human occupancy but which has some degree of hazardous conditions to the health or safety of the occupants. Also, a housing unit which is structurally sound but has visible degrees of deterioration and several housing code violations but all of which are economically feasible to correct.~~

~~Substandard Housing not Suitable for Rehabilitation~~ - ~~a housing unit which is structurally unsound and which possesses a serious and immediate threat to the health and safety of the occupants. Also, a housing unit which is not suitable for occupancy and the conditions or code violations are not economically feasible to correct. Would include units damaged by fire, storm, or other natural causes.~~

Substandard (Housing) - Any unit lacking complete plumbing or sanitary facilities for the exclusive use of the occupants; a unit which is in violation of one or more major sections of an applicable housing code and where such violation poses a serious threat to the health of the occupant; or a unit that has been declared unfit for human habitation but that could be rehabilitated for less than 50 percent of the property value.

~~Substantially Surrounded~~ - ~~when a parcel of land is bordered on two sides by land developed as commercial or industrial. Such commercial or industrial development should abut the subject land.~~

Suitability - Means the degree to which the existing characteristics and limitations of land and water are compatible with a proposed use or development. ~~(Form 9J-5.003(134)).~~

Support - to promote the interests or causes of; to uphold or defend as valid or right, advocate; to argue or vote for; to pay the costs of; to favor actively in the face of opposition.

Surface Water - water on the earth's surface exposed to the atmosphere as rivers, lakes, streams, and oceans.

Surface Water Protection Buffer - a setback established from the mean or ordinary high water line or safe upland line ~~whichever the applicant chooses. Within the surface water~~

~~protection buffer, passive recreation, hunting, fish and wildlife management open space, nature trails and limited amounts and types of shoreline access facilities shall be allowed. The amounts and types of development allowed within the surface water protection buffer and other development restrictions are found in Conservation Element Objective 3: where activities, uses, and development are regulated.~~

Terminal Platform means that part of a dock or pier, including finger piers that are connected to the access walkway, is located at the terminus of the facility, and is designed, to secure and load or unload a vessel or conduct other water dependent activities.

Threatened Species - Species of animals and plants ~~federally so listed under the jurisdiction of the U.S. Fish and Wildlife Service, Endangered Species Act of 1973, as amended (16 U.S.C. 1531 et seq.), or ; the Florida Fish and Wildlife Conservation Commission, Chapters 39 and 46, Florida Administrative Code (F.A.C.); Chapter 68A-27, F.A.C.; or the Florida Department of Agricultural and Consumer Services, Preservation of Native Flora of Florida, Act (s. 581.185-187, Florida Statutes) Chapter 5B-40, F.A.C. These are generally any species, subspecies, or isolated population, which are likely to become an endangered species within the foreseeable future throughout all or a significant portion of its range.~~

Tourist Commercial Development Activities - activities intended to serve the needs of tourists and seasonal residents and include hotels, motels and support activities such as restaurants, gas stations and souvenir shops. ~~Varying densities for hotel/motel activities are set forth within the Comprehensive Plan. Such activities are located in Community Commercial (CC) land use designations, unless otherwise provided in the Comprehensive Plan.~~

Toxic Material - a type of hazardous waste that causes harm to humans or other organisms by entering the organism and interfering with normal life functions, as opposed to corrosive, ignitable, or reactive materials which cause damage by physical proximity or contact.

Transfer Station - a facility for the temporary collection of solid waste prior to transport to the processing facility.

Transient Commercial Development Activities - activities intended to serve the needs of the overnight visitor ~~and are located in Community Commercial (CC) land use designations.~~

Transitional Level of Service - a temporary acceptable level of service for a specific facility or service ~~not to exceed 12 years, but which shall~~ which realistically reflect reflects the minimum timeframe necessary to establish a funding source and/or remove affecting obstacles and proceed with an appropriate improvement effort.

Tributary - a natural stream or other natural water body that flows, falls, or empties into another water body. This definition is not to include non-point sources.

Turbidity - a thick, hazy condition of air or water due to the presence of suspended particulates or other pollutants.

Turning Basin ~~means the area of sovereign submerged land which is required to maneuver a vessel into or out of a facility.~~

Type 1 Aquifer Recharge Areas - those areas which are within the City of Titusville's Area of Critical Concern, or are within five hundred (500) feet of a public water supply well or within the boundaries of a development that proposes a public water supply well provided that this area serves to recharge the aquifer from which the well draws and which have highly permeable soils.

Type 2 Aquifer Recharge Areas - those areas which are not classified as Type 1 aquifer recharge areas and are above 30 feet mean sea level and have highly permeable soils.

Type 3 Aquifer Recharge Areas - those areas which have highly permeable soils and are below 30 feet mean sea level.

Unique Farmlands - those lands which possess a special complement of location, soil characteristics, growing season and moisture supply that result in high productivity for specialty crops such as fruits, vegetables and vineyards.

Units Per Acre - the number of residential units allowed as a maximum per acre, calculated as the total number of residential units divided by the total site acreage. This term may describe an aggregate density over a large tract or a building lot size.

Urban Sprawl ~~= a land development pattern characterized by the location of development in areas where public facilities and services cannot be provided efficiently.~~ means a development pattern characterized by low density, automobile-dependent development with either a single use or multiple uses that are not functionally related, requiring the extension of public facilities and services in an inefficient manner, and failing to provide a clear separation between urban and rural uses.

Urban-District Park - generally contain 100 to 499 acres and serve several communities in the metropolitan area.

Utility Corridor - an inter-county corridor established for rail transportation of persons and/or cargo and one or more of the following: the location of lines for the transmission of water, electricity, communications, petroleum products, products of a public utility (including new technologies of a public utility nature), or materials.

Very-Low-Income Household - a household which possesses a household income of less than 50 percent of the median income.

Very-low-income persons- [as defined in section 420.0004, F.S.](#), means one or more natural persons or a family, not including students, the total annual adjusted gross household income of which does not exceed 50 percent of the median annual adjusted gross income for households within the state, or 50 percent of the median annual adjusted gross income for households within the metropolitan statistical area (MSA) or, if not within an MSA, within ~~the county in which the person or family resides~~ [Brevard County](#), whichever is greater.

Wake means ~~all change in the vertical height of the water's surface caused by the passage of a vessel including, but not limited to, a vessel's bow wave, stern wave, and propeller wash.~~

Water Dependent Uses - activities which can be carried out only on, in, or adjacent to water areas because the use requires access to the water body for waterborne transportation including ports and marinas, recreation, electrical generating facilities, or water supply.

Water Enhanced Uses - activities which are not water dependent but whose value is increased due to location along the water. This increased value is not related to the increased property values of water-front property. Water enhanced uses include restaurants, some upland recreational areas and tourist attractions.

Water Quality - a measure of the levels of pollutants occurring within a specified area of a waterbody.

Water Related Uses - activities which are not directly dependent upon access to a water body, but which provide goods and services that are directly associated with water-dependent or waterway uses. These land uses include bait and tackle shops, and boat sales and rentals.

Water Supply Facilities Work Plan (WSFWP) - a plan to establish future water demands and potential water sources and facilities to meet those demands for a 10-year planning horizon. This plan is developed in collaboration with SJRWMD, adopted by reference in the Brevard County Comprehensive Plan and must be updated within 18 months after the SJRWMD approves an update to the Regional Water Supply Plan (RWSP) affecting Brevard County.

Watershed - the region or area of land that drains water, sediment, and dissolved materials to a common outlet or body of water.

Water's Edge Wetlands – wetlands which are a transitional area between dry land and open water.

Wetland Functionality - is determined by the ability of the wetland to provide a diversity of habitat and food sources for aquatic and wetland-dependent species, and for threatened and endangered species and species of special concern; to provide flood storage capacity; to provide for the protection of downstream and offshore water resources from siltation and pollution; or to provide for the stabilization of the water table. ~~(from Chapter 62-3691, Brevard County Code of Ordinances). In considering the functional value of wetlands, the degree of alteration, uniqueness, landscape diversity, and proximity to water bodies should be considered.~~

Wetlands - as defined in Florida Statute ~~373.019(25)~~ 373.019(27).

Wildlife and Open Space Corridor - a widespread, continuous or near-continuous system of wildlife habitat that is established by linking wildlife preserves, sanctuaries, refuges, parks or open space areas to provide a pathway for wildlife movement.

Wildlife Habitat – an area that provides an animal with food, water, and shelter and that also provides the spatial requirements that facilitate breeding, foraging, roosting, and resting.

Acronyms

BBIA	<u>Brevard Barrier Island Area of Critical State Concern</u>
BCC	<u>Brevard County Board of County Commissioners</u>
BMAP	<u>Basin Management Action Plan</u>
BMP	<u>Best Management Practices</u>
CON	<u>Conservation Element</u>
CCL	<u>Brevard County Coastal Control Construction Line (Ord. 85-17).</u>
CCCL	<u>FDEP's old 1981 Coastal Construction Control Line (1975).</u>
CSL	<u>Brevard County Coastal Setback Line</u>
CEMP	<u>Comprehensive Emergency Management Plan</u>
CHHA	<u>Coastal High Hazard Area</u>
CI	<u>Capital Improvements Element</u>
CIP	<u>Capital Improvements Plan</u>
CM	<u>Coastal Management Element</u>
CSL	<u>Brevard County Coastal Setback Line</u>
CCMP	<u>Coastal Conservation and Management Plan</u>
DEO	<u>Department of Economic Opportunity</u>
DRI	<u>Development of Regional Impact</u>
ECFRPC	<u>East Central Florida Regional Planning Council</u>
EEL	<u>Environmentally Endangered Lands Program</u>
EPA	<u>United States</u> Environmental Protection Agency

GLOSSARY

F.A.C.	Florida Administrative Code
FDACS	Florida Department of Agriculture and Consumer Services
FDEP	Florida Department of Environmental Protection
FDOT	Florida Department of Transportation
FLU	Future Land Use Element
FLUM	Future Land Use Map
F.S.	Florida Statutes
FWC	Florida Fish and Wildlife Conservation Commission
FWS	United States Fish and Wildlife Service
HOU	Housing Element
HP	Historic Preservation Element
IC	Intergovernmental Coordination Element
IRL	Indian River Lagoon
IRLNEP	Indian River Lagoon National Estuary Program
LOS	Level of Service
LPA	Local Planning Agency
MPP	Brevard County Manatee Protection Plan
NEP	National Estuary Program
NRCS	Natural Resources and Conservation Service (previously the Soil and Water Conservation District)
OSTDS	Onsite Sewage Treatment and Disposal System
PR	Property Rights Element
PLRG	Pollution Load Reduction Goals
PS	Public School Facilities Element
PSFB	Patrick Space Force Base
PUD	Planned Unit Development
PW	Potable Water Element
ROS	Recreation and Open Space Element
RWSP	Regional Water Supply Plan
SAV	Submerged Aquatic Vegetation
SJRWMD	St. Johns River Water Management District
SOIRL	Save Our Indian River Lagoon Program
SR A1A	State Road A1A
SS	Sanitary Sewer Element
SWH	Solid Waste and Hazardous Materials Element
SWIM	Surface Water Improvement and Management
SW	Surface Water Element
SACOE	United States Army Corps of Engineers
TMDL	Total Maximum Daily Load
TPO	Space Coast Transportation Planning Organization
TRA	Transportation Element
USACE	United States Army Corps of Engineers
WSFWP	Water Supply Facilities Work Plan

GLOSSARY